HTI CONTRACTING LLC
PO Box :390737
506 - Binary Tower , Business bay
Dubai , United Arab Emirates
www.hashtaginteriors.com

COMMERCIAL PROPOSAL
FOR
(ARCHITECTURAL WORKS)

Paradym.io

1202 B, 12th FLOOR, OPUS TOWER
BUSINESSBAY, DUBAI - UAE

To:
Mr. Halen Rodda
Project Lead
Dubai -United Arab Emirates
halen@projectpeople.ae

Date:
October 31, 2024
Reference No.:
QTN-058/SU-105

HTI CONTRACTING LLC
PO Box :390737
506 - Binary Tower , Business bay
Dubai , United Arab Emirates
www.hashtaginteriors.com

General Terms & Conditions

Payment Terms: 50 % Advance Payment against order confirmation and release of purchase order.
30% 1st progressive payment upon completion of 40% of works.
15% 2nd progressive payment upon completion of 70% of works.
5% 2upon completion and handover to client.
Performa invoice must be approved by client within 7 days from submission.

Project Timeline: Documents and Drawings Preparation: 7 Days from the date of order confirmation.
Approval from omniyat: 2 weeks, 2 weeks from the receipt of NOC from DDA and DCD.
Site Works: 7-8 Weeks from the date of receipt of fit-out permit.
Total : 11-12 Weeks from the date of receipt of order confirmation.

Validity: Our quote is valid for a period of 30 days from hereof.

Warranty: As per manufacturer and 365 days DLP from the date of occupancy handing over of the phases.
Note: Damages due to Natural calamities/War etc. are excluded.

Insurance: Project insurance to be obtain as per company policy if required by any party.

We trust that you will find the attached quotation in line with your requirements, and shall look forward to your earliest response.

Yours faithfully
For HTI Contracting LLC

Suraj Roy
roy@hashtaginteriors.com
054 585 0779

Special Note and Exclusion:

- ***a.*** *Scope is limited to BOQ*
- ***b.*** *Any additional works will be charged as variation.*
- ***c.*** *Feel/Charges to approval authorities/mall management to be paid by client on actuals,*
- ***d.*** *PABX, active components, laptop, PC, white goods etc. are excluded.*
- ***e.*** *HVAC, Fire fighting, Fire Alarm works are as per building approved contractor.*
- ***f.*** *BTU meter, BMS, new thermostats etc. are excluded.*
- ***g.*** *Upright sprinklers, void smoke detector, fire pump etc. are excluded.*
- ***h.*** *Any specific requirements arise after project award by any statutory authority/client will be charged as variation.*
- ***i.*** *Variation to be approved prior to start of works and 100% payment to be cleared by the client upon confirmation.*
- ***j.*** *Incase of cancellation of project the client will be charged a fee of 10% of the project value.*
- ***k.*** *Delay in work by any 3rd party appointed by consultant/building management/client. HTI will not be held responsible.*
- ***l.*** *Any delay in payment, finishes approval, from approval authority or due to natural calamities HTI will not be held responsible.*
- ***m.*** *Any white goods, printer, coffee machine etc. are excluded.*
- ***n.*** *All materials & installations should be of approved types in compliance with the government a uthority and Civil Defense , health & safety, mechanical, electrical and ergonomic standards.*
- ***o.*** *24x7 & appliances by client*

HASHTAG
INTERIORS & CONTRACTING

HTI CONTRACTING LLC
PO Box :390737
506 - Binary Tower , Business bay
Dubai , United Arab Emirates
www.hashtaginteriors.com

SL NO.	MAIN SUMMARY DESCRIPTION OF WORKS	AMOUNT AED
A.	ARCHITECTURAL WORKS:	
1	PREAMBLE/GENERAL WORKS:	AED 47,185.00
2	DEMOLITION WORKS:	AED 16,860.00
3	GLAZING WORKS:	AED 36,760.00
4	PARTITION WORKS:	AED 41,460.00
5	FINISHING WORKS:	AED 31,656.00
6	FLOORING WORKS:	AED 40,280.00
7	CEILING WORKS:	AED 50,560.00
8	INTERNAL SIGNAGE/BRANDING WORKS:	AED 27,595.00
9	JOINERY / WOOD WORKS:	AED 132,440.00
10	ELECTRICAL AND LIGHTING WORKS:	AED 68,570.00
11	FIRE FIGHTING AND FIRE ALARM WORKS :	AED 63,468.00
12	HVAC WORKS:	AED 56,170.00
13	SANITARY & PLUMBING WORKS:	AED 3,175.00
14	IT WORKS :	AED 110,567.00
15	FURNITURE	AED 226,018.00
	TOTAL AMOUNT FOR ARCHITECTURAL WORKS	AED 952,764.00
	LESS SPECIAL DISCOUNT	AED 72,764.00
	NET TOTAL PROJECT VALUE	AED 880,000.00
	5% VALUE ADDED TAX	AED 44,000.00

HTI CONTRACTING LLC
PO Box :390737
506 - Binary Tower , Business bay
Dubai , United Arab Emirates
www.hashtaginteriors.com

ARCHITECTURAL WORKS:			QTY	UNIT	RATE	AMOUNT
ITEM	DESCRIPTION OF WORKS				AED	AED
1.00	PREAMBLE/GENERAL WORKS:					
1.01	**SITE MANAGEMENT** Provision for site management, including staff and facilities necessary for the efficient execution and supervision of the works.		1	Job	3,000.00	3,000.00
1.02	**MOBILIZATION** Allow sum for mobilization & demobilization		1	Ls	2,500.00	2,500.00
1.03	**HEALTH & SAFETY PROTECTION** Implementation of health and safety measures, including site inductions, provision of personal protective equipment (PPE), first aid facilities, fire prevention equipment, and site security measures in accordance with applicable regulations		1	Ls	500.00	500.00
1.04	Allow sum for covering and protection of entrance area, lobby, corridor, service lifts and finished products to prevent any damages due to the on-going fit-out works as per the building management.		1	Job	3,750.00	3,750.00
1.05	Allow for charges of arranging permit/access for labors pick-ups and material delivery.		1	Job	3,500.00	3,500.00
1.06	**DESIGN & SHOP DRAWING:** Preparation of construction/workshop drawings for approval of local authorities (Municipality, Civil defense department and DEWA) and joinery workshop drawings and as-build drawings.		1	Job	6,000.00	6,000.00
1.07	**PROJECT INSURANCES:** Insurance policies for the project as per building management standard. Contractor/ Erection All Risks (CAR) and Third-Party Liability Insurance Cover (TPL) for AED 5,000,000		1	Job	7,685.00	7,685.00
1.08	**CLEANING :** Allow sum for removal of debris and daily general site cleaning for the entire project duration.		1	Job	2,000.00	2,000.00
	SERVICES					
1.09	Temporary DB for the duration of the construction of the project as per the building management guidelines.		1	Job	7,500.00	7,500.00
1.10	Washroom Upkeep charges for the entire project duration as per the building management guidelines.		1	Job	3,750.00	3,750.00
	APPROVAL PROCESS (AUTHORITIES AND BUILDING MANAGEMENT)					
	AUTHORITY APPROVAL (FOR 1 LEASE)					
1.11	Contractors coordination charges to liaise with local authorities such as DDA, Civil defense and DEWA to obtain complete approval.		1	Job	7,000.00	7,000.00
1.12	Deposits and fees for local authority approvals to complete the approval process from DDA, Civil defense and DEWA.		1	Job		BY CLIENT

HTI CONTRACTING LLC
PO Box :390737
506 - Binary Tower , Business bay
Dubai , United Arab Emirates
www.hashtaginteriors.com

1.13	Allow sum for building management approval - fees for drawing approvals. Fit Out fee payable to "Clarity Owners Association Management LLC" (5 AED per Sq.Ft + VAT)		1	Ps	15,650.00		BY CLIENT
					TOTAL AMOUNT FOR PREAMBLE/GENERAL WORKS	**AED**	**47,185.00**
2.00	**DEMOLITION WORKS:**						
2.01	As per the site condition to suit provision of the new approved layout. Carting Away debris to the approved municipal dumpsite.		1	Ls	16,860.00	AED	16,860.00
2.02	Removal of existing vinyl, carpet flooring, gypsum partition, glass partition & doors, gypsum ceiling, pantry counter & mep services.						
					TOTAL AMOUNT FOR FINISHING WORKS	**AED**	**16,860.00**
3.00	**GLAZING WORKS:**						
3.01	**<u>Glass Partition:</u>** Supply and installation of 12 mm thick clear toughened (tempered) glass partition from floor to false ceiling height. Glass partitions to be fixed onto a 25 mm thick aluminium channel. Glass to glass joints will be sealed off with clear silicon sealant. **Glass Partition Height : 2600 mm** **Location : As per design.**		59	Sqm	390.00	AED	23,010.00
3.02	**<u>New Glass Doors</u>** Supply and installation of 12 mm thick clear frameless glass doors (single leaf, swing type), size 90 x 260 cm (Upto false ceiling height) , complete with dorma or equivalent floor mechanism, standard lock, and standard SS (brushed finished) handles. Type: Single Leaf **Location :** Closed Cabins		5	Nos.	2,750.00	AED	13,750.00
3.03	**<u>Glass Partition:</u>** Supply and installation of 13.52 (6+1.52 Eva lamination +6 mm thick) laminated clear tempered glass partitions from floor to 2600 mm height. Glass partitions to be fixed on to 42 series aluminium powder coated sections. **Glass Partition Height : 2600 mm** **Location : As per design.**		59	Sqm	740.00		**Optional**
3.04	**<u>New Glass Doors</u>** Supply and installation of 13.52 (6+1.52 Eva lamination +6 mm thick) laminated clear tempered Framed glass swing door, size 900 x 2600 mm, complete with handle and lockset in black powder coated finish accessories. Type: Single Leaf **Location :** Closed Cabins		5	Nos.	4,860.00		**Optional**
					TOTAL AMOUNT FOR GLAZING WORKS	**AED**	**36,760.00**

HTI CONTRACTING LLC
PO Box :390737
506 - Binary Tower , Business bay
Dubai , United Arab Emirates
www.hashtaginteriors.com

4.00	**PARTITION WORKS:**						
4.01	**Gypsum Partitions.** Supply and installation of 125 mm thick Double skinned 12.5mm thick NFR gypsum board (on both sides)partition consisting of 72mm galvanized iron tracks and 75mm galvanized iron studs, mineral rockwool of 30 kg/m3 density and 4 nos. of 12.5 mm thick gypsum boards with joints filled and smoothly sanded-ready to receive final finishes, from finished floor to soffit/slab. **Make : Gypsum Boards / Joint Compound / Corner Tape / Fiber Tape : USG or equivalent**	 	170	Sqm	170.00	AED	28,900.00
4.02	**Fire Rated Gypsum Partitions.** Supply and installation of 125 mm thick Double skinned 12.5mm thick FR gypsum board (on both sides)partition consisting of 72mm galvanized iron tracks and 75mm galvanized iron studs, mineral rockwool of 30 kg/m3 density and 4 nos. of 12.5 mm thick gypsumboardswith joints filled and smoothly sanded-ready to receive final finishes, from finished floor to soffit/slab. **Location: Server Room** **Make : Gypsum Boards / Joint Compound / Corner Tape / Fiber Tape : USG or equivalent**	 	20	Sqm	185.00	AED	3,700.00
4.02	**Baffle Wall Partitions:.** Supply and installation of baffle drywall partitions 125 mm thick Double skinned 12.5mm thick FR gypsum board (on both sides) partition consisting of 72mm galvanized iron tracks and 75mm galvanized iron studs, mineral rockwool of 30 kg/m3 density and 4 nos. of 12.5 mm thick gypsum boards with joints filled and smoothly sanded-ready to receive final finishes, from finished floor to soffit/slab. **Make : Gypsum Boards / Joint Compound / Corner Tape / Fiber Tape : Boral or equivalent**		23	LM	170.00	AED	3,910.00
4.03	**GYPSUM LINING :** Supply and installation of straight gypsum cladding - single layer,12mm non fire-rated gypsum boards on one side, including furring channels up to the false ceiling. Location - Informal seating area & closed office 2 pax		55	Sqm	90.00	AED	4,950.00
					TOTAL AMOUNT FOR PARTITION WORKS	**AED**	**41,460.00**
5.00	**FINISHING WORKS:**						
5.01	**New Gypsum Partitions & Existing Walls.** Supply and Application of Paint on Partitions etc. as per site requirements. The rate shall be inclusive of Preparing the surface to receive the paint + stucco + 2 Coats of primer + 2 Coats of Painting. **Brand : Jotun or Berger**	 	352	Sqm	28.00	AED	9,856.00
5.02	Supply and apply of texture paint as per the design.		10	Sqm	150.00	AED	1,500.00

HTI CONTRACTING LLC
PO Box :390737
506 - Binary Tower , Business bay
Dubai , United Arab Emirates
www.hashtaginteriors.com

5.03	Supply and installation of Wall Cladding. Proposed Product: DECOPANEL Composition: 100% PET (60% Recycled) Thickness : 10mm Size: 500mm x 500mm (Joint lines will be visible) Acoustic insulation: 25mm thick low density fibre glass insulation Colour : To be selected Flammability: B-s1, d0 as per EN-13501 Size:50x50 cm **Location: Conference, Meeting & Focus Rooms**		53	Sqm	350.00	AED	18,550.00
5.04	Supply and installation of brick Wall Cladding with glue & grout as per the design **Location: Pantry**		5	Sqm	350.00	AED	1,750.00
					TOTAL AMOUNT FOR FINISHING WORKS	**AED**	**31,656.00**
6.00	**FLOORING WORKS:**						
6.01	Supply and installation of 50x50 contract ID carpet tile flooring with felt backing, anti static, fire retardant from Belgium or equivalent as per proposed design scheme with 5 years commercial warranty. **Location : As per the design** Sample and Specification Sheet to be Submitted for approvals.		145	Sqm	90.00	AED	13,050.00
6.02	Supply and installation of spc plank type flooring size: 18.2 cm x 122cm thickness 5mm color to be selected. Location : As per the design		137	Sqm	140.00	AED	19,180.00
6.03	Supply and installation of anti-static flooring. Location Server Room		7	Sqm	140.00	AED	980.00
6.04	Supply and installation of metal termination strip between the different flooring.		34	Lm	80.00	AED	2,720.00
6.05	Opening and closing of the existing raised flooring to facilitate the MEP related works.		1	Job	2,850.00	AED	2,850.00
6.06	Cutting of the raised floor to accommodate the proposed new floor service boxes.		1	Lumpsum	1,500.00	AED	1,500.00
					TOTAL AMOUNT FOR FLOORING WORKS	**AED**	**40,280.00**
7.00	**CEILING WORKS:**						
7.01	Supply and installation of plain gypsum board ceiling with necessary support and GI channel as per the design ready to receive finish. Make : Gypsum Boards Boral or equivalent		221	Sqm	115.00	AED	25,415.00
7.02	Supply and installation of FR plain gypsum board ceiling with necessary support and GI channel as per the design ready to receive finish. Make : Gypsum Boards Boral or equivalent		7	Sqm	130.00	AED	910.00

7.03	Supply and installation of plain gypsum board ceiling drop 900 mm with necessary support and GI channel as per the design ready to receive finish. Make : Gypsum Boards Boral or equivalent		30	Sqm	110.00	AED	3,300.00
7.04	**Ceiling Painting.** Supply and Application of Paint : RAL : 9010, on Ceiling. **Brand : Jotun or Berger**		283	Sqm	30.00	AED	8,490.00
7.05	**<u>OPEN AREA PAINTING</u>** Supply and application of fenomastic spray paint on slab with necessary base coats (Including MEP services) Location: Corridor area		49	Sqm	45.00	AED	2,205.00
7.06	Supply and installation of upto 100 mm high cove bulkhead.		73	Lm	75.00	AED	5,475.00
7.07	**Ceiling Painting.** Supply and Application of Paint : RAL : 9010, on cove. **Brand : Jotun or Berger**		73	Lm	25.00	AED	1,825.00
7.08	Supply and installation of 600x600 ceiling access panel. **Location: Closed cabins**		14	Nos.	210.00	AED	2,940.00
					TOTAL AMOUNT FOR CEILING WORKS	**AED**	**50,560.00**
8.00	**INTERNAL SIGNAGE/BRANDING WORKS:**						
8.01	**Main door signage** Fabrication and installation of office name sign reading "Paradym.io" In both English & Arabic Letters. The letters made of 3mm thick matte finish acrylic laser cut letters of height 50mm. The letters will be fixed directly on the existing Glass background with VHB tape and suitable adhesive.		1	Nos.	1,070.00	AED	1,070.00
8.02	Supply and installation of COMPANY LOGO in acrylic/mdf black letters with logo & without backlit. Size: 1200L x 600H mm **Location :Informal Seating** **Brands : Customized Locally**		1	Nos.	6,500.00	AED	6,500.00
8.03	Supply and installation of COMPANY LOGO in acrylic/MDF finish without backlit. Size: 1800L x 250H mm **Location : Reception** **Brands : Customized Locally**		1	Nos.	8,500.00	AED	8,500.00
8.04	Supply and installation of COMPANY LOGO in acrylic/MDF finish without backlit. Size: 1200L x 1200H mm **Location : Reception** **Brands : Customized Locally**		1	Nos.	7,500.00	AED	7,500.00
8.05	Supply and installation of only grey color frosting as per client's guidelines upto 1500 mm coverage. **Location : Glass partitions** **Brands : Customized Locally** EPS file to be provided by client.		35	Sqm	115.00	AED	4,025.00

8.06	Supply and installation of switchable smart glass film pasted on glass partition & doors. **Location : Glass partitions**		1	Job	61,000.00		Rate only
	TOTAL AMOUNT FOR SIGANGE/BRANDING WORKS					**AED**	**27,595.00**
9.00	**JOINERY / WOOD WORKS:**						
9.01	Supply and installation 50 mm high PU painted MDF skirting around the wall as per design.		109	LM	45.00	AED	4,905.00
9.02	Wooden Wall Cladding : Supply and installation of plain wooden cladding in laminate finish as per proposed design scheme. Location: Entrance wall Manufacture : Joinery Item		15	Sqm	950.00	AED	14,250.00
9.03	Bench Seating: Supply and installation of locally customized bench seating with cushion in fabric & laminate finish as per proposed design scheme. Size: 8100L x 650D x 750H mm Location: Informal Seating Manufacture : Joinery Item		1	Item	25,025.00	AED	25,025.00
9.04	Supply and installation of locally customized high table made with MR MDF wooden legs in texture paint finish with quartz/marble top as per the design. Size: 3700L x 800D x 1100H mm Location: Bar Area **Manufacture : Joinery Item**		1	Set	22,770.00	AED	22,770.00
9.05	Coffee Station: Low height unit: Supply and installation of locally customized wet pantry counter fabricated inside laminate outside painted MR mdf underneath storage with shutter, shelves & quartz/marble top & backsplash. overhead unit: Supply and installation of kitchen overhead cabinet made with MR mdf inside laminated outside laminate finish doors with shutters & shelves. Low height unit Size: 3100L x 600D x 900H mm Overhead unit Size: 3100L x 400D x 800H mm Location: Bar Area Manufacture : Joinery Item		1	Set	13,500.00	AED	13,500.00
9.06	Supply and installation of locally customized high table made with MR MDF laminate finish top with metal legs as per the design. Size: 2700L x 600D x 1100H mm Location: Bar Area **Manufacture : Joinery Item**		1	Set	7,250.00	AED	7,250.00
9.07	Supply and installation of locally customized full height storage cabinet fabricated in mdf laminate finish with shutter & shelves as per proposed design theme. size 1200 x 600 x 2400 mm Location: Printer Room Manufacture : Joinery Item		1	Item	7,440.00	AED	7,440.00

HTI CONTRACTING LLC
PO Box :390737
506 - Binary Tower , Business bay
Dubai , United Arab Emirates
www.hashtaginteriors.com

9.08	Supply and installation of locally customized full height storage cabinet fabricated in mdf laminate finish with shutter & shelves as per proposed design theme. size 1300 x 400 x 2600 mm Location: Byron's Room Manufacture : Joinery Item		1	Item	7,740.00	AED	7,740.00
9.09	Supply and installation of locally customized full height display cabinet fabricated in mdf laminate finish with shutter & shelves as per proposed design theme. size 1400 x 400 x 2600 mm Location: Byron's Room Manufacture : Joinery Item		1	Item	8,550.00	AED	8,550.00
9.10	Supply and installation of locally customized high table made with MR MDF laminate finish top with metal legs as per the design. Size: 3700L x 500D x 1100H mm Location: Hot Desk Area **Manufacture : Joinery Item**		1	Set	9,310.00	AED	9,310.00
9.11	Supply and installation mdf backing support for the tv's		6	No's	250.00	AED	1,500.00
9.11	Supply and installation of 60 Min fire rated wooden single leaf swing door with door frame & architraves made in mdf with pu paint finish with vision panel, standard door locks, ironmongery and handles. Size: 900x2100 mm **Location: Server Room**		1	No's	5,200.00	AED	5,200.00
9.12	Allow sum for the supply and installation of artificial plants		1	Ps	5,000.00	AED	5,000.00
					TOTAL AMOUNT FOR JOINERY WORKS	**AED**	**132,440.00**
10.00	**ELECTRICAL AND LIGHTING WORKS:**						
10.01	Modification of the existing electrical supply with new MCCB and circuit brakers in DBs to suit the ratings and new load schedule. Relocation of existing DB.		1	No	3,500.00	AED	3,500.00
10.02	Supply and installation of conduiting & wiring for the light points		64	No's	150.00	AED	9,600.00
10.03	Supply and installation of conduiting & wiring for the cove lights		90	Lm	45.00	AED	4,050.00
10.04	Supply & fixing of 1 Gang 1 way white PVC switch (Make: Schneider or equivalent)		10	No's	130.00	AED	1,300.00
10.05	Supply & fixing of 2 Gang 1 way white PVC switch (Make: Schneider or equivalent)		7	No's	150.00	AED	1,050.00
10.06	Supply & fixing of 3 Gang 1 way White PVC switch (Make: MK & Schneider)		4	No's	180.00	AED	720.00
10.07	Supply and installation of 13 Amp Double power socket with necessary conduiting, wiring as per the design(Conduit: PVC, Wire: Ducab, Switch & Socket: MK White Logic) .		29	No's	285.00	AED	8,265.00

HTI CONTRACTING LLC
PO Box :390737
506 - Binary Tower , Business bay
Dubai , United Arab Emirates
www.hashtaginteriors.com

10.08	Supply and installation of 13 Amp single power socket with necessary conduiting, wiring as per the design(Conduit: PVC, Wire: Ducab, Switch & Socket: MK White Logic) .		11	No's	275.00	AED	3,025.00
10.09	Supply and installation of 16A Industrial Socket for the Server Rack including conduiting and wiring.		1	Nos.	550.00	AED	550.00
10.10	Charges for Relocation of existing floor box		19	No's	250.00	AED	4,750.00
10.11	Testing and commissioning of Electrical system.		1	Ls	1,000.00	AED	1,000.00
	Note: 1) We consider that there is enough available load at site to suit the proposed design, if additional load is required it will require an NOC from the landlord and DEWA. It would also incur an additional cost. 2) Existing electrical DEWA approved load schedule to be provided by client.						
	LIGHTING:						
10.12	Supply and Installation of twin spot lights		12	Nos.	350.00	AED	4,200.00
10.13	Supply & fixing of light LED Directional Spotlight Material : Die Cast Aluminium Finish : White Reflector : Anodized Aluminium Diffuser : Clear Glass Light Source : Cree Power consumption : 10WCCT : To be confirmed CRI : 90+ | Beam Angle : 45°Power Supply : Constant Current LED DriverDimmable : No | Size : D104 x H94 x C92 mm Protection : IP40		31	Nos.	210.00	AED	6,510.00
10.14	Supply and installation of decorative pendant circular light 600 dia for meeting room & focus room		2	Nos.	1,450.00	AED	2,900.00
10.15	Supply and installation of linear led light Location: Meeting Room		1	No	3,500.00	AED	3,500.00
10.16	Supply and installation of decorative pendant circular light 600 dia for bar area		3	No's	1,250.00	AED	3,750.00
10.17	Supply and installation of led strip light		90	Lm	65.00	AED	5,850.00
10.18	Relocation of existing linear light as per the site requirement.		18	No's	50.00	AED	900.00
	IT STRUCTURE:						
10.19	Supply and installation of 25mm Pvc conduiting and wiring back box fixing. for thermostat.		6	No's	75.00	AED	450.00
10.20	Supply installation of 25mm Pvc Conduiting for WIFI		4	No's	75.00	AED	300.00

10.21	Supply installation of 25mm Pvc Conduiting for CCTV.		6	No's	75.00	AED	450.00
10.22	Supply installation of 50mm Pvc Conduiting for HDMI.		6	No's	100.00	AED	600.00
10.23	Supply and installation of 25mm Pvc conduiting and back box fixing for Data /Telephone		18	No's	75.00	AED	1,350.00
	TOTAL AMOUNT FOR ELECTRICAL AND LIGHTING WORKS					**AED**	**68,570.00**
11.00	**FIRE FIGHTING AND FIRE ALARM WORKS :**						
	FIRE FIGHTING						
11.01	Relocation of Existing Concealed Pendent Sprinkler with Necessary Pipe and Fittings Include New Sprinkler Head		19	No's			
11.02	Supply of 5 Kg Co2 Fire Extinguisher		2	No's			
11.03	Supply of 6 Kg DCP Fire Extinguisher		2	No's			
11.04	Isolation of Zone Control Valve including draining & refilling		1	Lot			
11.05	Supply of 2 Kg DCP Fire Extinguisher		1	No's			
11.06	Testing and Commissioning Charges(Pressure Test)		1	No's			
11.07	CD Certificate charges (Supply,Installation,Warranty)		1	Lot			
	FIRE ALARM WORKS						
11.08	Relocation of existing Smoke detectors including cabling works		12	No's			
11.09	Relocation of existing Heat detectors including cabling works		1	No's	63,468.00	AED	63,468.00
11.10	Relocation of existing Manual Call Point including cabling works		1	No's			
11.11	Relocation of Sounder including cabling works		1	No's			
11.12	Supply & Installation of Addressable IFU modules (24x7-1nos, Main FACP-1nos, access door-1nos.)		3	No's			
11.13	Programming, Testing and Commissioning		1	No's			
	EMERGENCY & EXIT LIGHTING SYSTEM						
11.14	Relocation of Self Contained Emergency Light, w/cabling works.		9	No's			
11.15	Supply & Installation of directional Exit Light,1W,wall/hanging mounted w/cabling works.		2	No's			
	TOTAL AMOUNT FOR FIRE FIGHTING AND FIRE ALARM WORKS					**AED**	**63,468.00**
12.00	**HVAC WORKS:**						
12.01	Fabrication and installation of new branch PI ducting, complete with insulation to be connected to the existing main duct.						
12.02	Supply and Install plenum boxes and connected to the supply grills and diffusers to suit the new design requirements.						
12.03	Supply and installation of additional linear supply air and return air diffusers as per the layout.						
12.04	Supply and installation of new VCD as per the requirements. Make: Danko.		1	Lump sum	56,170.00	AED	56,170.00
12.05	Supply and installation of extract duct fan for the pantry						
12.06	To do the Air balancing, adjusting with Report (3rd party report is excluded).						

12.07	As per your requirement, for the closed cabins, supply and fixing of cross talk sound attenuators,						
12.08	As per your requirement, for the closed cabins, supply and fixing of sound attenuators Normal Type,						
	Note : New FCUs are excluded, Air Balancing Reports, Warranties etc. Shall be provided.						
	TOTAL AMOUNT FOR HVAC WORKS					**AED**	**56,170.00**
13.00	**SANITARY & PLUMBING WORKS:**						
13.01	Supply and installation of single bowl Sink with bottle trap		1	No's	860.00	AED	860.00
13.02	Supply and installation of Sink Mixer with angle valve & hose pipes.		1	No's	640.00	AED	640.00
13.03	Supply and installation of floor trap		1	No's	175.00	AED	175.00
13.04	Charges for modification of water supply and drainage line as per the new requirement.		1	Ls	1,500.00	AED	1,500.00
	TOTAL AMOUNT FOR SANITARY & PLUMBING WORKS					**AED**	**3,175.00**
14.00	**IT WORKS :**						
	STRUCTURE CABLING						
14.01	Service charge of installation, testing, and labeling of Cat6 CCTV Cable Pulling without PVC Containment, both end terminations with RJ45 Module/connector per point. Printer points - 1nos TV points - 6nos ACS points - 1nos WiFi points - 4nos CCTV points - 6nos		18	No's	200.00	AED	3,600.00
14.02	Cat6 UTP cable roll 305meters		3	No's	535.00	AED	1,605.00
14.03	Cat6 24-port Patch panel with keystones		1	No's	315.00	AED	315.00
14.04	Cable Manager		1	No's	60.00	AED	60.00
14.05	Cat6 1meter Patch Cord Server side including patching		18	No's	24.00	AED	432.00
14.06	42U Network Server Cabinet with glass front door, height 42U, width 800mm, depth 1000mm		1	No's	3,865.00	AED	3,865.00
14.07	Service charges for Fiber optic cable pulling from existing ONU to rack location and Splicing -20 mtr		1	Job	800.00	AED	800.00
	TV & VC						
14.08	Logitech for Conference Room 960-001312 -Logitech Rally Bar Graphite UK-ME 952-000085 Logitech TAP IP 989-000430-LOGITECH RALLY MIC POD USB BLACK 952-000041-TV MOUNT FOR VIDEO BARS - WW - TV MOUNT 952-000047-RALLY MIC POD EXTENSION CABLE - OFF-WHITE - USB - N /A - WW - 10M EXTENSION CABLE		1	No's	25,065.00	AED	25,065.00
14.09	Logitech for Meeting Room VIDEO CONFERENCE LOGITECH 960-001340 Logitech Rally Bar Mini 952-000085 Logitech TAP IP		1	No's	17,680.00	AED	17,680.00
14.10	Service Charge for installation of VC devices.		2	No's	1,330.00	AED	2,660.00
14.11	Supply and installation of Samsung 65inch UA65CU7000UXZN TV with brackets		6	No's	3,390.00	AED	20,340.00
14.12	Supply and installation of movable tv stand		1	No's	400.00	AED	400.00

HTI CONTRACTING LLC
PO Box :390737
506 - Binary Tower , Business bay
Dubai , United Arab Emirates
www.hashtaginteriors.com

14.13	Supply and installation of 15meters HDMI cable		6	No's	335.00	AED	2,010.00
	WIFI			No's			
14.14	Unifi Wifi Access Point WiFi6 Pro		4	No's	1,050.00	AED	4,200.00
14.15	Installation and configuration charges		4	No's	265.00	AED	1,060.00
	CCTV						
14.16	Hikvision 8-channel NVR with POE Ports		1	No's	1,000.00	AED	1,000.00
14.17	WD Purple surveillance hard drive 2TB internal for CCTV Encoding Mode - H.265 Resolution - 1080P(1920×1080) Frame Rate(fps) - 10 Recordings - 40days		1	No's	465.00	AED	465.00
14.18	Hikvision 2MP Fixed Dome Network Camera 2.8mm Lens		6	No's	280.00	AED	1,680.00
14.19	Installation and configuration charges for cameras		6	No's	200.00	AED	1,200.00
14.20	Supply and installation of Hikvision 22inch Monitor with brackets		1	No's	600.00	AED	600.00
	Printer						
14.21	Canon imageRUNNER C3326i Multifunction Laser Printer, Print, Copy, Scan, Send, Optional Fax, 7" TFT LCD WVGA Color Touch Panel, 26 ppm Print Speed, Up to 1200 x 1200 DPI Resolution, White C3326i		1	No's	15,680.00	AED	15,680.00
14.22	Installation charges		1	No's	930.00	AED	930.00
14.23	**ACCESS CONTROL WORKS:** Supply and installation of access control. RFID- BLE Neo cylinder WIFT IQ - to connect locks over cloud Key fob -pack of 5 Maintenance card SALTO KS L SUBSCRIPTION VOUCHER-For system USER upto 50 users (per year license) Programming charges		1	Set	4,920.00	AED	4,920.00
	TOTAL AMOUNT FOR IT WORKS					**AED**	**110,567.00**
	TOTAL AMOUNT FOR ARCHITECTURAL WORKS					**AED**	**723,746.00**

HTI CONTRACTING LLC
PO Box :390737
506 - Binary Tower , Business bay
Dubai , United Arab Emirates
www.hashtaginteriors.com

14	FURNITURES:	QTY	UNIT	RATE	AMOUNT	PRODUCT IMAGE
ITEM	DESCRIPTION OF WORKS			AED	AED	
1	**BYRON'S OFFICE :**					
1.01	Free standing Rectangular shape white table with HPL finish MFC table top, wooden frame with size 1800*800*750mm with flip cover and modesty panel, built in cable tray. - HPL white finish table top WARRANTY - 5 YEARS	1	nos.	4,945.00	4,945.00	
1.02	**Executive Chair;** *High back chair; High density mold foam with plastic frame inside *2D mechanism height adjustable; 5-stars aluminum base &PU castors; *Aluminum armrest; WARRANTY - 5 YEARS	1	nos.	1,435.00	1,435.00	
1.03	Executive Visitor chair PU upholstery; Aluminum alloy frame; High density sponge; Aluminum alloy base with castors; WARRANTY - 5 YEARS	2	nos.	1,332.00	2,664.00	
1.04	Executive Sofa 2 seater Size/mm: 1560W*840D*720H, premium quality PU finish with imported New Zealand pine, 45 density high elastic sponge cushion, with powder coated high-quality steel legs WARRANTY - 5 YEARS	1	nos.	4,075.00	4,075.00	
2	**COLLAB / HOTDESK AREA :**					
2.01	Executive Sofa 3 seater Size/mm: 2060W*840D*720H, premium quality fabric finish with imported New Zealand pine, 45 density high elastic sponge cushion, with powder coated high-quality steel legs WARRANTY - 5 YEARS	1	nos.	5,370.00	5,370.00	
2.02	Esy lounge sofa chair Sturdy solid timber frame; High density foam; PU upholstery; powder coated metal legs. WARRANTY - 5 YEARS	1	nos.	1,477.00	1,477.00	
2.03	Round shape coffee table on metal base and laminate marble finish top size1010*460H WARRANTY - 5 YEARS	1	nos.	1,250.00	1,250.00	
2.04	Coffee table in 18mm MDF table top ·Black painted steel frame WARRANTY - 5 YEARS	1	nos.	1,210.00	1,210.00	

HTI CONTRACTING LLC
PO Box :390737
506 - Binary Tower , Business bay
Dubai , United Arab Emirates
www.hashtaginteriors.com

2.05	**Breakout Area,** Bar height stool Seat : Polypropylene seat and wooden legs. WARRANTY - 5 YEARS	5	nos.	1,020.00	5,100.00	
3	**STAFF AND RECEPTION AREA :**					
3.01	InterAction B2B sit standing workstation Size/mm: 1400W*1500D*640-1290H Top: 25mm thickness laminated with scallop cut Frame:metal with powder coat; Leg Orientation:Square/Rectangle column; Height Range:640~1290mm; Speed:40mm/s; / Max Loading: 150kg; With Timotion Dual motor; SAA/UL/CE approved;with cable duct WARRANTY - 5 YEARS	10	nos.	6,770.00	Optional item	
3.02	CLUSTER OF 2 : Rectangular shape Main table: 1200*700*750 mm in Laminate finish table top fixed height desk. - Metal legs with side panels. Location : Closed office 2 pax WARRANTY - 5 YEARS	1	nos.	2,195.00	2,195.00	
3.03	CLUSTER OF 6: Rectangular shape Main table: 1200*700*750 mm in Laminate finish table top fixed height desk. - Metal legs with side panels. Location : Open Staff Area WARRANTY - 5 YEARS	3	nos.	5,210.00	15,630.00	
3.04	Desk mounted fabric finish side acoustic screen non pinnable board with floor brackets and connector with desk size 1100x30 fabric to be approved by client. WARRANTY - 5 YEARS	10	nos.	225.00	2,250.00	
3.05	Cable tray for cable management in powder coated metal finish accessable from table top.700*170*80H WARRANTY - 5 YEARS	20	nos.	135.00	2,700.00	
3.06	3 drawer mobile pedestal with lock in white powder coated metal finish. WARRANTY - 5 YEARS	20	nos.	660.00	13,200.00	
3.07	Filing storage with shutter and open shelves in laminted finish with lock in approved finish size 1600 x 400 x 1200 Location : Closed office 2 pax WARRANTY - 5 YEARS	1	nos.	1,310.00	1,310.00	

HTI CONTRACTING LLC
PO Box :390737
506 - Binary Tower , Business bay
Dubai , United Arab Emirates
www.hashtaginteriors.com

3.08	Dining area chair 730*740*820mm high density foam with fabric upholstery, solid wood legs Location : Closed office 2 pax WARRANTY - 5 YEARS	2	nos.	1,590.00	3,180.00	
3.09	Disc Powder coated metal disc frame/Fixed height; 25mm melamine top dia 800*370 Location : Closed office 2 pax WARRANTY - 5 YEARS	1	nos.	890.00	890.00	
3.10	**Executive Chair;** - Fabric Seat and Mesh Back - Aluminium chrome base with castors - Back lock mechanism - Fixed Arm Rest **Model: CH203** WARRANTY - 5 YEARS	20	nos.	790.00	15,800.00	
3.11	**Executive Chair;** - Fabric Seat and Mesh Back - Aluminium chrome base with castors - Back lock mechanism - Fixed Arm Rest **Model: CH203** WARRANTY - 5 YEARS	20	nos.	1,210.00	Optional item	
3.12	**Open Lounge Chair: sleek** with wooden structure in approved fabric finish. WARRANTY - 5 YEARS	9	nos.	1,620.00	14,580.00	
3.13	Round shape coffee table on metal base and laminate marble finish top size dia 600*370 Model: ARC070 WARRANTY - 5 YEARS	3	nos.	998.00	2,994.00	

HTI CONTRACTING LLC
PO Box :390737
506 - Binary Tower , Business bay
Dubai , United Arab Emirates
www.hashtaginteriors.com

4	**CONFERENCE/MEETING/FOCUS ROOM :**					
4.01	8 PAX meeting table size 3000*1200*750, in Wood texture laminate finish table top, with metal type table legs with cable management with flip top box and cutout.Base with MDF painting finish . **Model: MTB-3212** WARRANTY - 5 YEARS	1	nos.	9,210.00	9,210.00	
4.02	6 PAX meeting table size dia 1600*750, in Wood texture laminate finish table top, with metal type table legs with cable management with flip top box and cutout.Base with MDF painting finish . **Model: MTB-0016** WARRANTY - 5 YEARS	1	nos.	2,945.00	2,945.00	
4.03	**Conference Room Chair;** 560W*680D*1100H PU upholstery; High density cutting foam; Plywood with PU upholstery; Aluminum base & PU castors; WARRANTY - 5 years	16	nos.	1,080.00	17,280.00	
4.04	Power module with 2 universal socket, 2 data, 1HDMI and 1 VGA point including cable manager cord for each table with flip cover.	2	nos.	1,050.00	2,100.00	
4.05	Esy lounge sofa chair Size/mm: 840Q*820D*700H Sturdy solid timber frame; High density foam; Fabric upholstery; Adjustable feet; WARRANTY - 5 YEARS	4	nos.	2,980.00	11,920.00	
4.06	Round shape coffee table on metal base and laminate marble finish top size dia 600*370 Model: ARC070 WARRANTY - 5 YEARS	1	nos.	998.00	998.00	
5	**BAR AREA :**					
5.01	**Breakout Area,** Bar height stool Seat : Polypropylene 100% Sinopec brand PP+5%GF plastic； Metal frame； Add surcharge by USD 6.5 for seat pad; WARRANTY - 5 YEARS	4	nos.	900.00	3,600.00	
6	**HOLDING / INFORMAL SEATING AREA :**					
6.01	**Open Lounge Chair: sleek** with wooden structure in approved fabric finish. WARRANTY - 5 YEARS	2	nos.	1,620.00	3,240.00	

HTI CONTRACTING LLC
PO Box :390737
506 - Binary Tower , Business bay
Dubai , United Arab Emirates
www.hashtaginteriors.com

6.02	Round shape coffee table on metal base and laminate marble finish top size1010*460H WARRANTY - 5 YEARS	2	nos.	1,415.00	2,830.00	
6.03	Esy lounge sofa chair Size/mm: 840Q*820D*700H Sturdy solid timber frame; High density foam; Fabric upholstery; Adjustable feet; WARRANTY - 5 YEARS	2	nos.	1,330.00	2,660.00	
7	**DINING AREA :**					
7.01	Dining area chair 730*740*820mm high density foam with fabric upholstery, solid wood legs WARRANTY - 5 YEARS	8	nos.	1,590.00	12,720.00	
7.02	Disc Powder coated metal disc frame/Fixed height; 25mm melamine top dia 800*370 WARRANTY - 5 YEARS	2	nos.	890.00	1,780.00	
7.03	**Breakout Area,** Bar height stool Seat : Polypropylene seat and wooden legs. WARRANTY - 5 YEARS	4	nos.	1,020.00	4,080.00	
8	**PHONE BOOTH :**					
8.01	IWORKPOD Size/mm: 1200W*1000D*2200H Exterior: Cold rolled steel plate electrostatic sprayed coat; Interior: Steel plate+9mm acoustic panel; Floor:Particle board+ carpet tile; Door: Alu frame+ 6mm tempered glass; Rear Glass:10mm tempered glass; Table: 800W*350D*750H Sensor: 900RPM/130CFM Fan(Silent); Light: LED strip Light; Furniture Excluded;	2	nos.	24,200.00	48,400.00	
				TOTAL AMOUNT FOR FURNITURE	**AED 226,018.00**	