Electrolux

FORTUNE TOWER, JLT

COMMERCIAL SUBMISSION

04.08.2025

VERSION 01

JTCPL™ DESIGNS

www.jtcpldesigns.com

Date: 04 August 2025

Electrolux Middle East
Level 40, Mazaya Business Avenue BB1
Jumeriah Lake Towers Dubai United Arab Emirates

Project: Electroux Middle East Office Relocation, Unit 2904-2905-2906, 29th Floor, Fortune Tower, Jumeriah Lake Towers, Dubai.

Subject: Interior Fit-out works - Design & Build Services Proposal

Dear Eloisa,

This has reference to the RFP for Interior Fit-out Design and Build Services for **Electrolux ME's** office relocation in Dubai. We are pleased to submit our proposal in line with the scope outlined.

At **JTCPL Designs,** we are eager to be a part of this journey and contribute towards project success. Our approach is rooted in a deep understanding of **Electrolux ME's** business goals, and we remain committed through thoughtful, effective design-build.

While the enclosed proposal reflects our best understanding, we remain open to your suggestions in refining the commercial framework and jointly evolving a solution that aligns seamlessly with your best expectations.

We are deeply grateful to you for this opportunity and for the trust extended to us. You have our assurance on the highest levels of commitment and our best services at all times.

Thank you and Best Regards,

PREETHI SREEDHARA
STUDIO HEAD, JTCPL DESIGNS

1. SCOPE OF SERVICES:

Interior Design & Build Services including ID & MEP fit-out works for Electrolux Middle East Office relocation, JLT for an approx. area of 427 sqm. (4,600 Sq.ft)

2. CLIENT RESPONSIBILITIES:

- The client shall issue detailed Design brief regarding the project and appropriate sign-off for the duration of the project.
- The client shall provide all the necessary as -built drawings, including structures, service and utility lines.
- The client shall pay the fees, levies, tax, security deposits and all other expenses related to the Local Authority Approvals.
- Any amendments / changes to the Design provided by JTCPL Designs, shall be only after mutual discussion and consent of JTCPL Designs.
- The client shall give effect to the professional advice of JTCPL Designs and cause no changes in the drawings and documents without the consent of JTCPL Designs.
- The client shall furnish any other information, documents, assistance etc which may be required for the smooth progress of the project.

3. PROJECT BUDGET ESTIMATE:

- Interior Fit out Works (ID & MEP Works): **AED 2,192,952.00** (exclusive of 5% VAT)

- Please see attached Budget Summary for a detailed breakdown of the estimate.
- Our offer is based on our preliminary assessment of the scope of works outlined in the RFP and subject to change upon approval of Concept design and material specifications upon appointment.

4. COMMERICAL CLARIFICATIONS:

In the absence of Contract Terms and Conditions, we have based our submission on the use of our standard Short Form of Contract, a copy of which can be provided for your review upon request.

5. PAYMENT TERMS:

Sr. No	Milestone Payments	Payable Percentage
1	Advance Payment (upon award of project)	30%
2	Upon Concept Design Sign-off	20%
3	Site Mobilization	20%
4	Progress Payment _01 (Completion of MEP 1st fix)	15%
5	Progress Payment _02 (Closure of Ceilings)	10%
6	Practical Completion (incl. Inspections & Approvals)	5%

Notes:

- 30% Advance Payment; payable within 7 days of the Contract Agreement (less any upfront payment received against the Letter of Award).
- Subsequent milestone payments payable within 15 days of submission of Invoice.

6. CONDITIONS:

- This document and all other documents submitted along with proposals are prepared by JTCPL Designs; the execution of this proposal is dependent on entering into an Agreement with JTCPL Designs.
- All documents and drawings prepared by JTCPL Designs will be in English.
- Offer valid for 15 days from submission date.
- Our offer is based on prelim assessment of scope of works and subject to change upon approval of Concept and detailed design and measurement validation upon appointment.
- Not subject to Retention.
- This scope of works does not include any specialist design services such as Structural, Kitchen, Specialist Lighting, Landscape, IT & AV, Music,
- In the event of any force majeure or early closure of services of the project, the Client is to pay the due amounts for all the delivered services by that date carried by JTCPL Designs, until the date of the notice of early closure of works.
- All exclusion items are listed in the Quotation summary attached along with this document.
- Client supplied goods and any Variation items will be priced at Cost plus Ten (10%) percent.

7. OWNERSHIP OF COPYRIGHT:

- All design decks, drawings, documents and models prepared by JTCPL Designs are proprietary instruments of service and constitute the intellectual property of JTCPL Designs. These materials remain the exclusive property of JTCPL Designs, regardless of whether the specific project for which they were developed is ultimately executed.

- The Client may retain copies of drawings, specifications and related documents solely for reference and use in connection with the designated project, provided the project is formally awarded to JTCPL Designs. These materials shall not be reproduced, disclosed or used by the Client or any third party for any other purpose or project without the prior written consent of JTCPL Designs.

ELECTROLUX MIDDLE EAST_ FIT OUT WORKS

29th Floor, Fortune Tower, Cluster C, Jumeriah Lake Towers, Dubai

BUDGET SUMMARY_V01

Date: 04 August 2025

SL.NO	ITEM DESCRIPTION	Amount (AED)
1	PRELIMINARIES AND GENERAL FEES	32,000.00
2	DEMOLITION WORKS	26,195.00
3	CIVIL WORKS	66,635.00
4	WALLS & PARTITION WORKS	200,961.00
5	DOORS	83,000.00
6	CEILING WORKS	227,630.00
7	FLOORING WORKS	118,525.00
8	WALL FINISHES	170,365.00
9	JOINERY	377,120.00
10	MISCELLANEOUS	42,700.00
11	ELECTRICAL WORKS	256,459.00
12	HVAC WORKS	193,360.00
13	FIRE FIGHTING & FIRE ALARM WORKS (Provisional Sum)	127,075.00
14	EMERGENCY AND EXIT LIGHT WORKS	20,500.00
15	PLUMBING & DRAINAGE	69,545.00
A	**SUB TOTAL**	**2,012,070.00**
B	**FURNITURE**	180,882.00
C	**TOTAL (A + B)**	**2,192,952.00**
		VAT Extra
D	**OPTIONAL WORKS AS PER BELOW**	
1	ACCESS CONTROL SYSTEM	21,026.00
2	ROOM BOOKING SYSTEM	39,862.00
3	CCTV WORKS	21,070.00
		VAT Extra

ELECTROLUX MIDDLE EAST_ FIT OUT WORKS
29th Floor, Fortune Tower, Cluster C, Jumeriah Lake Towers, Dubai
BILL OF QUANTITIES
Date: 04 August 2025

SR NO	DESCRIPTION	QUANTITY	UNIT	RATE (AED)	AMOUNT (AED)
1.0	**PRELIMINARIES AND GENERAL FEES**				
1.01	Allow coordination charges for taking Authority approval. (Concordia) Allow charges for preparation of Shop drawings, sample approvals, As built Allow cost for mobilization and demobilization of scaffolding, temporary lighting and water supply, fire extinguisher, first aid kit, protection of landlords/mall management property etc. Allow for insurances Please note- The mentioned CAR policy is quoted based on standard terms and conditions. Any special requirement or higher Value of insurance by the client or Building management will be charged additional. Allow charges for site supervision and site management Allow charges for protection of works Allow charges for Site cleaning , Waste Management during fit out and after completion of works. Allow charges for Site cleaning , Waste Management during fit out and after completion of works. QA / QC & HSE: Fire extinguisher H & S Board. PPE's Site access control Availability of safety officer. Sample Boards : Preparation of Sample boards for client approvals Allow charges for temporary hoarding during main entrance door replacement	1.00	Ls	22,000.00	22,000.00
1.02	Allowance for Concordia & Building Management Fees Note: Budgetary charges have been considered. The client shall bear the cost based on actual invoices from Concordia and building management.	1.00	Ls	10,000.00	10,000.00
	NOTES:				
	All kind of landlord fees and deposit to be paid by the client as per actual.				
	Temporary Services(Power & Water) - Building Management will Charge according to usage to be paid by the client				
	Specialist Consultant charges for Authority approval, Authority exemption fees are excluded.				
	Security deposits of Authority, Security deposit of Building management ,specialist consultant fees shall be paid directly by the client.				
	TOTAL FOR PRELIMINARIES & GENERAL FEES				**32,000.00**
2.0	**DEMOLITION WORKS**				
2.01	Removal of the Existing Floor tiles (proposed reception area, proposed toilet, existing pantry and toilet), 60x60 tile Ceiling finishes, Wall Tiles, Gypsum Partitions, Block Partitions, doors, sanitary fittings, light, blinds, joinery items and cart away debries in the approved dump yard Note: Removal of existing floor tiles has not been considered for the entire area. It is only considered for the proposed reception area, passage infront of toilet, proposed toilet, existing pantry and existing toilet.	**1.00**	**Ls**	**26,195.00**	**26,195.00**
	TOTAL FOR DEMOLITION WORKS				**26,195.00**
3.0	**CIVIL WORKS**				
3.01	Cement Sand Screed: Supply and installation of 50mm high pre mix pre bag cement-sand screed as per the requirement to receive final floor finishes. Location: Reception, Passage infront of toilet, Existing Toilet, Pantry Area	115.00	Sqm	100.00	11,500.00
3.02	Membrane Waterproofing Supply and application of one layer of membrane waterproofing on floors and 300mm high on walls.	53.00	Sqm	105.00	5,565.00
3.03	Supply and installation of 300 mm high light weight cement sand screed - 200 mm styrofoam + 100 mm cement sand screed	27.00	Sqm	275.00	7,425.00
3.04	Protection Screed: Supply and installation of 20 mm thick protection screed above waterproofing	33.00	Sqm	50.00	1,650.00
3.05	Upstand for Waterproofing: Allow charges for creating upstand for waterproofing using concrete block.	1.00	Ls	1,000.00	1,000.00

ELECTROLUX MIDDLE EAST_ FIT OUT WORKS
29th Floor, Fortune Tower, Cluster C, Jumeriah Lake Towers, Dubai
BILL OF QUANTITIES
Date: 04 August 2025

SR NO	DESCRIPTION	QUANTITY	UNIT	RATE (AED)	AMOUNT (AED)
3.06	60x120 cm Tile flooring Supply and installation of 600x1200 mm tile flooring with with necessary adhesive and cementitious grouting.	40.00	Sqm	350.00	14,000.00
3.07	Porcelain Tile Flooring: Supply and installation of 600x1200 mm porcelain tile flooring with necessary adhesive and cementitious grouting.	27.00	Sqm	225.00	6,075.00
3.08	Transition Profile: Supply and installation of transition profile between different floor types. Note: Transition profiles have been considered only for the reception area & server room.	12.00	Lm	100.00	1,200.00
3.09	Threshold: Supply and installation of 20 mm thick crema marfil marble threshold with necessary adhesives. Size: 1000 mm L x 100 mm W x20 mm thick.	2.00	Nos	500.00	1,000.00
3.09	PU Paint Finish MDF Skirting: Supply and installation of 50x12 mm PU paint finish MDF Skirting.	237.00	Lm	60.00	14,220.00
3.10	PU Paint Finish MDF Skirting to Curved Column: Supply and installation of 50x12 mm PU paint finish MDF Skirting to Curved Column.	15.00	Lm	200.00	3,000.00
	NOTES:				-
	New screed is considered for the proposed toilet, reception, existing toilet, and pantry areas at units 2904 and 2905. In all other areas, the floor finish will be installed over the existing tiles, including 5-6 mm self-leveling.				-
	Raising of the floor in the toilet area is subject to approval from the building management.				-
	TOTAL FOR CIVIL WORKS				**66,635.00**
4.0	**WALLS & PARTITION WORKS**				
4.01	Double Layer Regular Gypsum Board Partition: Supply and installation of 122 mm thick double layer Gypsum drywall Partition comprising of 2x12.5 mm regular gypsum board to each side of 70 mm stud at every 600mm c/c & 72 mm track on top & bottom with 30kg/m3 rockwool insulation, complete with jointing, taping and ready to receive final finish.	134.00	Sqm	200.00	26,800.00
4.02	Gypsum Partition – Single Layer Regular Gypsum Board: Supply and installation of 100 mm thick single layer gypsum drywall partition comprising of 1x12.5 mm regular gypsum board to each side of 70 mm Stud at every 600mm c/c & 72 mm Track on top & bottom with 30kg/m3 rock wool insulation, complete with jointing, taping and ready to receive final finish.	113.00	Sqm	150.00	16,950.00
4.03	Double Layer Baffle Wall: Supply and installation of 122 mm thick double layer Gypsum Baffle Wall comprising of 2x12.5 mm regular gypsum board to each side of 70 mm stud at every 600mm c/c & 72 mm track on top & bottom with 30kg/m3 rockwool insulation, complete with jointing, taping and ready to receive final finish.	23.00	Lm	175.00	4,025.00
4.04	Gypsum Cladding Supply and installation of gypsum cladding using 1x12.5 mm regular gypsum board with furring channel/stud. Height: 320 mm	33.00	Lm	130.00	4,290.00
4.04	Gypsum Niche for TV Allow charges for creating niche for TV using 1x12.5 mm regular gypsum board with furring channel/stud.	6.00	Nos	1,950.00	11,700.00
4.05	Cistern Wall – Single Layer Calcium Silicate Board: Supply and installation of cistern wall comprising of 1x12 mm calcium silicate board to one side of stud at every 600mm c/c & complete with jointing, taping and ready to receive final finish including support for concealed cistern.	5.00	Nos	200.00	1,000.00
4.06	Cistern Top: Supply and installation of crema marfil marble cistern top for cistern walls.	6.00	LM	410.00	2,460.00

ELECTROLUX MIDDLE EAST_ FIT OUT WORKS
29th Floor, Fortune Tower, Cluster C, Jumeriah Lake Towers, Dubai
BILL OF QUANTITIES
Date: 04 August 2025

SR NO	DESCRIPTION	QUANTITY	UNIT	RATE (AED)	AMOUNT (AED)
4.07	Solid Block Wall: Supply and installation of 150 mm thick solid block wall including lintel	68.00	Sqm	350.00	23,800.00
4.08	Cement Sand Plastering: Supply and installation of cement sand plastering to the block wall.	198.00	Sqm	80.00	15,840.00
4.09	DB Enclosure Allow charges for creating gypsum enclosure using 1x12 mm fire rated gypsum board and GI frame work for DB	1.00	Nos	800.00	800.00
4.10	Supply and installation of MDF Support for joinery items & TV backing.	22.00	Sqm	200.00	4,400.00
4.11	Supply and installation of single glazed partition. System - Single glaze partition System thickness Upto -35mm Profiles Upto - 35mm (Walls, floor and ceiling) Finish - Powder coated RAL 9011z colour Glass - 1x12 mm tempered glass Glass to glass joint with dry polyplast Acoustic Rating - 32dB Fire rating - Nil	34.00	Sqm	650.00	22,100.00
4.12	Supply and installation of Manually operated foldable Partition. Paired/Hinged Panels	1.00	Nos	40,000.00	40,000.00
4.13	Allow charges for metal support for foldable partiton.	1.00	Nos	7,500.00	7,500.00
4.14	Gents & Ladies area HPL toilet cubicles as per design Panel Thickness : 12mm	5.00	Nos	3,702.00	18,510.00
4.15	HPL Urinal Divider Size: 450 mm L x 1200 mm H	1.00	Nos	786.00	786.00
	TOTAL FOR WALLS & PARTITION WORKS				**200,961.00**
5.0	**CEILING WORKS**				
5.01	Regular Plain Gypsum Ceiling: Supply & Installation of regular plain gypsum ceiling using single layer of 12.5 mm thick regular gypsum boards, suspended with main channel @900 c/c, furring channel @400 mm c/c fixed with screws and accessories with jointing, taping and ready to receive final finish. Quantity 3 Sqm	1.00	Ls	650.00	650.00
5.02	60x60 cm Tile Ceiling: Supply and installation of 600x600x15 mm Acoustic Tile Ceiling including T15 suspension system.	39.00	Sqm	190.00	7,410.00
5.03	750 mm high Vertical Bulkhead : Supply and installation of 750 mm high regular gypsum bulkhead including suspension complete with jointing, taping and ready to receive final finish	86.00	Lm	145.00	12,470.00
5.04	Gypsum Pelmet: Supply and installation of 150 mm x 150 mm Gypsum Pelmet using 1x12.5 mm regular gypsum board and GI Frame Work Locations: Window Area	54.00	Lm	125.00	6,750.00
5.05	Soffit Painting: Supply and application of white paint finish for the open ceiling area including painting of all the MEP services.	483.00	Sqm	55.00	26,565.00
5.06	Ceiling Painting: Supply and apply of painting with one coat primer, one coat stucco and two coat jotun fenomastic white paint to the gypsum ceiling, bulkhead, Pelmet.	115.00	Sqm	34.00	3,910.00
5.07	Supply & Installation Of Acoustic Linear Baffle Acoustic Polyester Ceiling Baffles: • FELT Acoustic Linear baffle- Suspended Vertically • Baffle Thickness: 12mm • Baffle sizes: 200mm(H),Length-Max 2800 mm • Color: to be confirmed • Including fixing accessories –metal wire& adjustable Hanger hook • Application: To control the echo & reverberation time				
5.07	GM Room 4100 mm L x 200 mm H, Spacing 100 mm	32.00	Nos	750.00	24,000.00

ELECTROLUX MIDDLE EAST_ FIT OUT WORKS
29th Floor, Fortune Tower, Cluster C, Jumeriah Lake Towers, Dubai
BILL OF QUANTITIES
Date: 04 August 2025

SR NO	DESCRIPTION	QUANTITY	UNIT	RATE (AED)	AMOUNT (AED)
5.08	Corridor near workstation area 1 1550 mm L x 200 mm H, Spacing 100 mm	168.00	Nos	500.00	84,000.00
5.09	Corridor near workstation area 2 1550 mm L x 200 mm H, Spacing 100 mm	94.00	Nos	500.00	47,000.00
5.10	Supply and installation of 600 x 1200 mm white powder coated Galvanized Steel Mesh ceiling with T24 exposed grid system fixed with hanging wire.	35.00	Sqm	425.00	14,875.00
	Note: Baffle ceiling not considered in the corridor infront of Focus POD				
	TOTAL FOR CEILING WORKS				**227,630.00**
6.0	**FLOORING WORKS**				
6.01	HPL Finish Raised Access Floor: Supply and installation of 600 x600 mm HPL finish cementitious raised access floor with pedestals. Location: Server Room	8.00	Sqm	475.00	3,800.00
6.02	Area : CP-01 (Ex-Stock) Range: Connected Ethos Collection - CE100 Colour: 4314006 Consider Size : 50cm x 50cm	165.00	m2	200.00	33,000.00
6.03	Area : CP-02 (Ex-Stock) Range: Connected Ethos Collection - CE100 Colour: 4314019 Sustain Size : 50cm x 50cm 	90.00	m2	200.00	18,000.00
6.04	Area : LVT -01 LVT (Ex-Stock) Range: Level Set Collection - Textured Woodgrains Colour: A00406 Antique Light Oak Size : 25cm x 1m Installation : Ashlar	140.00	m2	160.00	22,400.00
6.05	Supply and Installation of Self Leveling Thickness: Upto 5mm * To Install on screed only * Cost will increase in case of self levelling thickness more than 5mm	395.00	m2	75.00	29,625.00
6.06	Supply and Installation of Stair Nosing	27.00	m	140.00	3,780.00
6.07	Supply and Installation of Profile	34.00	m2	125.00	4,250.00
6.08	Floor protection using 500 micron thick polythene sheet- for new flooring	367.00	m2	10.00	3,670.00
	TOTAL FOR FLOORING WORKS				**118,525.00**
7.0	**WALL FINISHES WORK**				
7.01	Fenomastic Paint: Supply and apply of painting with one coat primer, one coat stucco and two coat jotun fenomastic white paint.	253.00	Sqm	50.00	12,650.00
7.02	Wall Paper: Supply and Installation of Wallpaper with necessary fixing material including necessary surface preparation.	99.00	Sqm	100.00	9,900.00
7.03	Wall Paper: Supply and Installation of Wallpaper with necessary fixing material including necessary surface preparation.	48.00	Sqm	100.00	4,800.00
7.04	Digital Printed Wall Paper: Supply and Installation of Digital Printed Wallpaper with necessary fixing material including necessary surface preparation.	75.00	Sqm	200.00	15,000.00
7.05	Digital Printed Wall Paper: Supply and Installation of Digital Printed Wallpaper with necessary fixing material including necessary surface preparation.	21.00	Sqm	200.00	4,200.00
7.06	Digital Printed Wall Paper: Supply and Installation of Digital Printed Wallpaper with necessary fixing material including necessary surface preparation.	3.00	Sqm	200.00	600.00

ELECTROLUX MIDDLE EAST_ FIT OUT WORKS
29th Floor, Fortune Tower, Cluster C, Jumeriah Lake Towers, Dubai
BILL OF QUANTITIES
Date: 04 August 2025

SR NO	DESCRIPTION	QUANTITY	UNIT	RATE (AED)	AMOUNT (AED)
7.07	Acoustic PET Panels with Groove Design: PET Panels with Grooved design as per Project requirement Panel Thickness: 12mm Panel Size: 1200(W) x 2800(H) mm Fixing with Silicon directly on wall Color: to be selected from our range Height considered - 2400 mm	21.00	Sqm	550.00	11,550.00
7.08	Vinyl Frosted Stickers: Supply and installation of vinyl frosted stickers to the glass partition. Note - No color or graphics considered in our scope.	40.00	Sqm	200.00	8,000.00
7.09	Porcelain Wall Tiles: Supply and installation of 600x1200 mm porcelain wall tiles with necessary adhesive and cementitious grouting.	99.00	Sqm	210.00	20,790.00
7.10	Supply and installation of Ribbed wooden panelling Fabricated with laminate finish MDF.	11.00	Sqm	650.00	7,150.00
7.11	Supply and installation of Ribbed wooden panelling Fabricated with laminate finish MDF.	8.00	Sqm	650.00	5,200.00
7.12	Supply and installation of Laminate finish MDF panelling with groove.	13.00	Sqm	650.00	8,450.00
7.13	Supply and installation of Laminate finish MDF panelling with groove.	17.00	Sqm	650.00	11,050.00
7.14	Supply and installation of PU Paint finish MDF panelling with groove.	19.00	Sqm	975.00	18,525.00
7.15	Supply and installation of Laminate finish MDF panelling with groove.	24.00	Sqm	650.00	15,600.00
7.16	Supply and installation of crystal clear back painted glass cladding including mdf backing.	2.00	Nos	5,175.00	10,350.00
7.17	Supply and installation of crystal clear back painted glass cladding including mdf backing.	2.00	Nos	2,075.00	4,150.00
7.18	Supply and installation of crystal clear back painted glass cladding including mdf backing.	1.00	Nos	2,400.00	2,400.00
	TOTAL FOR WALL FINISHES WORKS				**170,365.00**
8.0	**DOORS**				
8.01	Single Leaf Timber Swing Door - Non Fire Rated - Hidden door Supply and installation of Single leaf semi solid swing door in Laminate finish with frame and architrave in Laminate finish mdf with necessary ironmongery.	3.00	Nos	5,000.00	15,000.00
8.02	60 min Fire Rated Timber Door Supply and installation of 60mm fire rated single leaf solid swing door in approved laminate finish with solid wood frame and architrave with necessary ironmongery. Size: 900 mm (L) x 2400 mm (H)	2.00	Nos	7,000.00	14,000.00
8.03	Manual Sliding wooden Door Supply and installation of Single leaf semi solid Manual Sliding wooden Door in Laminate finish with frame and architrave in laminate finish mdf with necessary ironmongery. Size: 1000 mm (L) x 2400 mm (H)	1.00	Nos	4,000.00	4,000.00
8.04	Single Leaf Timber Swing Door - Non Fire Rated Supply and installation of Single leaf semi solid swing door in PU paint finish with frame and architrave in laminate finish mdf with necessary ironmongery. Size: 1000 mm (L) x 2400 mm (H) Note: Door Closer is excluded.	2.00	Nos	3,750.00	7,500.00
8.03	Double Leaf Door Shutter: Supply and installation of double leaf MDF door shutter made of 18 mm thick laminate finish MDF. Size: 1400 mm (L) x 2400 mm (H)	1.00	Nos	6,500.00	6,500.00

ELECTROLUX MIDDLE EAST_ FIT OUT WORKS
29th Floor, Fortune Tower, Cluster C, Jumeriah Lake Towers, Dubai
BILL OF QUANTITIES
Date: 04 August 2025

SR NO	DESCRIPTION	QUANTITY	UNIT	RATE (AED)	AMOUNT (AED)
8.04	Supply and installation of frameless single glazed door System thickness -50mm Door frame - 50mm Aluminium door frame Finish - Powder coated RAL 9011z colour Door - 1x12mm Acoustic Laminated glass door Lock + Lever handle + Hinges + Cylinder + door stopper + drop seal Master key excluded Exposed door closer excluded Acoustic Rating - 35dB Fire rating – Nil Size: 900 mm x 2400 mm	6.00	Nos	6,000.00	36,000.00
	TOTAL FOR DOORS				**83,000.00**
9.0	**JOINERY WORKS**				
9.01	JY 01: Reception Counter Supply and Installation of custom made Reception Counter fabricated in PU painted finish MDF with corian finish fascia, counter top and worktop and interior carcass in melamine finish mdf. Size: 2100mm(L) x 800mm(W) x 1100mm(H).	1.00	Nos	15,860.00	15,860.00
9.02	JN 02: Ribbed pattern Wall Cladding Supply and installation Ribbed pattern Wall Cladding fabricated with laminate finish mdf including 50 mm SS strip at both end and bottom side Size: 2700 mm L x 2400 mm H	1.00	Nos	10,960.00	10,960.00
9.03	JY 03a Display Unit Supply and installation of display Unit fabricated with laminate finish mdf with white artificial white stone finish counter top. Size: 2200 mm L x 850 mm W x 2400 mm H	1.00	Nos	14,540.00	14,540.00
9.04	JY03b Display Pantry Cabinet Supply and installation of Display Pantry Cabinet fabricated with shutters, fascia in laminated finish mdf, interior carcass in melamine finish mdf and base cabinet top in white artificial white stone finish. Base Cabinet - Size: 1000 mm L x 600 mm D x 900 H mm Overhead Cabinet: Size: 1000 mm L x 450 mm D x 900 H mm Full height Cabinet size: 800 mm L x 600 mm D x 2400 H mm Supply and installation of digital printed wall paper at back splash. Size: 1000 mm L x 700 mm H	1.00	Nos	11,875.00	11,875.00
9.05	JY 04a Planter Box, Wooden ceiling & Bulkhead Supply and installation of planter box fabricated in laminate finish mdf with GRP Lining/ waterproofing. Size: 1200 mm L x 850 mm D x 300 H mm Supply and installation laminate finish MDF Wall Cladding, ceiling & bulkhead- 8 Sqm	1.00	Nos	12,575.00	12,575.00
9.06	JY 05: Full height Storage Cabinet + DB Shutter Supply and installation of full height Storage Cabinet fabricated with shutters, fascia in laminated finish mdf, interior carcass in melamine finish mdf. Including Planter box at bottom. Size: 2750 mm L x 500 mm D x 2400 H mm Supply and installation of DB cabinet fabricated with Laminate finish MDF. Size: 2760 mm L x 500 mm D x 2400 H mm	1.00	Nos	27,975.00	27,975.00
9.07	JY 06a: Full height Storage Cabinet & Open Shelf above printer Supply and installation of full height Storage Cabinet fabricated with shutters, fascia in laminated finish mdf, interior carcass in melamine finish mdf. Size: 650 mm L x 600 mm D x 2400 H mm Open Shelf Supply and installation of Open Shelf fabricated with laminated finish mdf. Size: 1000 mm L x 500 mm D x 2400 H mm	1.00	Nos	6,825.00	6,825.00
9.08	JY 06b: Open Shelf Supply and installation of Open Shelf fabricated with laminated finish mdf. Size: 1000 mm L x 500 mm D x 2400 H mm	1.00	Nos	3,815.00	3,815.00

ELECTROLUX MIDDLE EAST_ FIT OUT WORKS
29th Floor, Fortune Tower, Cluster C, Jumeriah Lake Towers, Dubai
BILL OF QUANTITIES
Date: 04 August 2025

SR NO	DESCRIPTION	QUANTITY	UNIT	RATE (AED)	AMOUNT (AED)
9.09	JY 07a: Hot Desk Supply and installation of Hot Desk fabricated with laminated finish mdf. Size: 4200 mm L x 500 mm W x 1100 mm H	1.00	Nos	12,670.00	12,670.00
9.10	JY 07b: Hot Desk Supply and installation of Hot Desk fabricate with laminated finish mdf. Size: 6550 mm L x 500 mm W x 1100 mm H	1.00	Nos	19,605.00	19,605.00
9.11	JY 08 Pantry Cabinet Supply and installation of Pantry Cabinet fabricated with shutters, fascia in PU painted finish mdf, interior carcass in melamine finish mdf and base cabinet top in artificial white stone finish Full height cabinet shutter - glass Base Cabinet - Size: 5250 mm L x 600 mm D x 900 H mm Overhead Cabinet: Size: 5250 mm L x 450 mm D x 900 H mm Shelf: 5250 mm L x 450 mm W Full height Cabinet size: 2200 mm L x 600 mm D x 2400 H mm Supply and installation of crystal clear back painted glass back splash including mdf backing. Size: 5250 mm L x 700 mm H	1.00	Nos	53,815.00	53,815.00
9.12	JY 08a: Water dispense door shutter Supply and installation of Water dispense shutter fabricated with laminated finish mdf. Size: 450 mm L x 500 mm D x 2400 H mm	1.00	Nos	2,360.00	2,360.00
9.13	JY 09a: Step Seating Supply and installation of step seating fabricated with PU painted finish MDF. Seat in upholstered finish including storage below, interior carcass in melamine finish mdf. Fabric from our standard range Size: 4500 mm L x 1800 mm D x 900 H mm	1.00	Nos	29,620.00	29,620.00
9.14	JY 09b: Planter box Supply and installation of planter box fabricated in laminate finish mdf with GRP Lining/ waterproofing, interior carcass in melamine finish mdf. Size: 1800 mm L x 465 mm D x 900 H mm	1.00	Nos	4,630.00	4,630.00
9.15	JY 10a: Vanity Counter Supply and installation of vanity counter fabricated with shutters, fascia in laminated finish mdf, interior carcass in melamine finish mdf and counter top and back splash in crema marfil marble finish. Size: 2700 mm L x 600 mm W x 900 mm H	1.00	Nos	11,450.00	11,450.00
9.16	JY 10b: Vanity Counter Supply and installation of vanity counter fabricated with shutters, fascia in laminated finish mdf, interior carcass in melamine finish mdf and counter top and back splash in crema marfil marble finish.. Size: 1650 mm L x 600 mm W x 900 mm H	1.00	Nos	7,000.00	7,000.00
9.17	JY 10c: Bench Supply and installation of bench fabricated with in Laminate finish mdf. Size: 800 mm L x 600 mm W x 600 mm H	1.00	Nos	1,825.00	1,825.00
9.18	JY 10d: Bench Supply and installation of bench fabricated with in laminate finish mdf. Size: 1200 mm L x 600 mm W x 600 mm H	1.00	Nos	2,750.00	2,750.00
9.19	JY 10e: Mirror Supply and installation of full height mirror including mdf backing Size: 900 m L x 2400 mm H	1.00	Nos	2,725.00	2,725.00
9.20	JY 10f: Mirror Supply and installation of full height mirror including mdf backing Size: Size: 2700 mm L x 1000 mm H	1.00	Nos	3,075.00	3,075.00
9.21	JY 10g: Mirror Supply and installation of full height mirror including mdf backing Size: 1650 mm L x 1000 mm H	1.00	Nos	1,875.00	1,875.00

ELECTROLUX MIDDLE EAST_ FIT OUT WORKS
29th Floor, Fortune Tower, Cluster C, Jumeriah Lake Towers, Dubai
BILL OF QUANTITIES
Date: 04 August 2025

SR NO	DESCRIPTION	QUANTITY	UNIT	RATE (AED)	AMOUNT (AED)
9.22	JY 11a: TV Unit Supply and installation of TV Unit fabricated with shutters, fascia in laminated finish mdf, interior carcass in melamine finish mdf. Size: 3900 mm L x 600 mm D x 2400 H mm Laminate finish wall cladding 3900 mm L x 750 mm H	2.00	Nos	17,300.00	34,600.00
9.23	JY 11b: Back Painted Glass Supply and installation of crystal clear back painted glass back splash including mdf backing. Size: 800 mm L x 1200 mm H	4.00	Nos	1,095.00	4,380.00
9.24	JY 12: Wooden cladding to window upstand Supply and installation of Wooden cladding fabricated with laminate finish mdf. Size: 320 mm W x 100 mm High Location: Window upstand Installation considered above existing finish Note: Sill Level cladding is excluded.	52.00	Lm	495.00	25,740.00
9.25	JY 13: Full height Storage Cabinet Supply and installation of full height Storage Cabinet fabricated with shutters, fascia in laminated finish mdf, interior carcass in melamine finish mdf. Size: 5600 mm L x 600 mm D x 2400 H mm	1.00	Nos	24,100.00	24,100.00
9.26	JY 14: Janitor Cabinet Supply and installation of full height Storage Cabinet fabricated with shutters, fascia in laminated finish mdf, interior carcass in melamine finish mdf. Size: 1000 mm L x 600 mm D x 2400 H mm	1.00	Nos	4,350.00	4,350.00
9.27	JY 15 Wooden Feature Wall Supply and installation of wooden feature wall fabricated with PU painted finish mdf. size: 3000 mm L x 150 mm W x 2400 mm H	1.00	Nos	26,125.00	26,125.00
	TOTAL FOR JOINERY WORKS				**377,120.00**
10.0	**PLUMBING WORKS**				
10.01	Supply and installation of water line for toilets and pantry with necessary PPR pipes and fittings as per new layout	1.00	Ls	10,000.00	10,000.00
10.02	Supply and installation of drainage line for toilets and pantry with necessary PVC pipes and fittings as per new layout	1.00	Ls	9,000.00	9,000.00
10.03	Supply and installation of 50 litres water heater	2.00	Nos	1,750.00	3,500.00
10.04	Wall Mounted water closet including concealed cistern	5.00	Nos	2,675.00	13,375.00
10.05	Shataff	5.00	Nos	350.00	1,750.00
10.06	Toilet Roll Holder	5.00	Nos	300.00	1,500.00
10.07	Robe Hook	5.00	Nos	125.00	625.00
10.08	Under counter wash basin	5.00	Nos	900.00	4,500.00
10.09	Wash basin mixer - sensor operated	5.00	Nos	1,400.00	7,000.00
10.10	Inbuilt soap dispensor	5.00	Nos	525.00	2,625.00
10.11	Paper dispensor	2.00	Nos	400.00	800.00
10.12	Urinals- sensor operated	2.00	Nos	4,500.00	9,000.00
10.13	Single bowl Sink , No Drainboard- Pantry	1.00	Nos	1,000.00	1,000.00
10.14	Sink Mixer -Pantry	1.00	Nos	700.00	700.00
10.15	Pedal bin, stainless steel, 50 L	3.00	Nos	550.00	1,650.00

ELECTROLUX MIDDLE EAST_ FIT OUT WORKS
29th Floor, Fortune Tower, Cluster C, Jumeriah Lake Towers, Dubai
BILL OF QUANTITIES
Date: 04 August 2025

SR NO	DESCRIPTION	QUANTITY	UNIT	RATE (AED)	AMOUNT (AED)
10.16	Supply and installation of SS floor Trap	8.00	Nos.	315.00	2,520.00
	TOTAL FOR PLUMBING WORKS				**69,545.00**
11.0	**ELECTRICAL WORKS**				
11.01	Supply of Light Fittings	1.00	Ls	65,138.00	65,138.00
11.02	Installation of below light fittings including PVC conduiting and PVC insulated normal wiring.				
11.02a	Linear Pendant Light 1200 mm	23.00	Nos	190.00	4,370.00
11.02b	Linear Pendant Light 1800 mm	2.00	Nos	234.00	468.00
11.02c	Linear Pendant Light 2100 mm	1.00	Nos	234.00	234.00
11.02d	Linear Pendant Light 2400 mm	1.00	Nos	280.00	280.00
11.02e	Linear Pendant Light 3000 mm	4.00	Nos	315.00	1,260.00
11.02f	Linear Pendant Light 3600 mm	4.00	Nos	315.00	1,260.00
11.02g	Linear Pendant Light 6000 mm	4.00	Nos	385.00	1,540.00
11.02h	Cylindrical Pendant Light	58.00	Nos	190.00	11,020.00
11.02i	Pendant Light at Pantry ceiling	12.00	Nos	190.00	2,280.00
11.02j	Pendant Light at Hot Desks	9.00	Nos	190.00	1,710.00
11.02k	60x60 Light/ Down Light	24.00	Nos	190.00	4,560.00
11.02l	Strip Light at joinery items	40.00	Lm	52.00	2,080.00
11.03	Supply and installation of Light switches 1 Gang with Necessary PVC conduiting and Wiring.	11.00	Nos	234.00	2,574.00
11.04	Supply and installation of Light switches 2 Gang with Necessary PVC conduiting and Wiring.	5.00	Nos	430.00	2,150.00
11.05	Supply and installation of Light switches 3 Gang with Necessary PVC conduiting and Wiring.	7.00	Nos	630.00	4,410.00
11.06	Supply and installation of Floor box with Twin Power Socket 2 Nos including normal wiring and PVC conduiting	34.00	Nos	1,140.00	38,760.00
11.07	Supply and installation of Floor box with Twin Power Socket 1 Nos including normal wiring and PVC conduiting	4.00	Nos	860.00	3,440.00
11.08	Supply and installation of 13 AMP single power sockets with Necessary PVC conduiting and Wiring.	6.00	Nos	370.00	2,220.00
11.09	Supply and installation of 13 AMP twin power sockets with Necessary PVC conduiting and Wiring.	40.00	Nos	416.00	16,640.00
11.10	Supply and installation of 15 AMP single power sockets with Necessary PVC conduiting and Wiring. Location: Pantry	1.00	Nos	535.00	535.00
11.11	Supply and installation of 20 AMP power point with Necessary PVC conduiting and Wiring with 20A DP Switch for water heater	2.00	Nos	660.00	1,320.00
11.12	Supply and installation of 20 AMP power point with Necessary PVC conduiting and Wiring with 20A DP Switch for FCU	8.00	Nos	660.00	5,280.00
11.13	Supply and installation of 13 AMP power point with Necessary PVC conduiting and Wiring for VAV	5.00	Nos	325.00	1,625.00
11.14	Supply and installation of 13 AMP power point with Necessary PVC conduiting and Wiring for FACP	1.00	Nos	360.00	360.00
11.15	Supply and installation of PVC Conduit for thermostat	13.00	Nos	160.00	2,080.00
11.16	Supply and installation of 13Amp Power with Necessary PVC conduiting and Wiring for signage.	1.00	Nos	385.00	385.00
11.17	Supply and installation of new DB with all related enclosure and additional breakers	3.00	Nos	4,350.00	13,050.00

ELECTROLUX MIDDLE EAST_ FIT OUT WORKS
29th Floor, Fortune Tower, Cluster C, Jumeriah Lake Towers, Dubai
BILL OF QUANTITIES
Date: 04 August 2025

SR NO	DESCRIPTION	QUANTITY	UNIT	RATE (AED)	AMOUNT (AED)
11.18	Supply and installation of 2X1C X 35 XLPE/SWA/PVC +1X 1C X 25 ECC with all related accessories for 2 Nos DB	50.00	Lm	165.00	8,250.00
11.19	Supply and installation of 100x50 mm cable tray bend, elbow and support fixing	45.00	m	85.00	3,825.00
11.20	Supply and installation of 100x100mm GI trunking, bend, elbow, support fixing above ceiling for lighting and power.	100.00	Meter	85.00	8,500.00
11.21	Modification of existing SMDB in the electrical room as per DEWA standard	1.00	Nos	1,840.00	1,840.00
11.22	Testing & commissioning of electrical works	1.00	Ls	2,295.00	2,295.00
11.23	Allow charges for civil works related to electrical works including cutting & chipping	1.00	Ls	6,125.00	6,125.00
	POWER AND CONDUIT FOR IT WORKS				
11.24	Supply and installation of 20 AMP industrial socket with Necessary PVC conduiting and Wiring for server rack	3.00	Nos	925.00	2,775.00
11.25	Supply and installation of PVC Conduit for data/voice/ CCTV	120.00	Nos	160.00	19,200.00
11.26	Supply and installation of PVC Conduit for wifi	5.00	Nos	160.00	800.00
11.27	Supply and installation of 13A power with Necessary PVC conduiting and Wiring for Access control, Conference system , meeting scheduler	11.00	Nos	385.00	4,235.00
11.28	Supply and installation of PVC Conduit for Access control	3.00	Nos	280.00	840.00
11.29	Supply and installation of PVC Conduit for fiber cabling	1.00	Nos	385.00	385.00
11.30	Supply and installation of 50 mm PVC Conduit for TV.	6.00	Nos	280.00	1,680.00
11.31	Supply and installation of 100x50mm Gi cable tray for IT works above ceiling.	60.00	Meter	78.00	4,680.00
	Note: We have considered PVC conduit & White PVC Switches / Lighting controls / Thermostat If GI conduit or metallic switches and sockets are required, it will be treated as additional.				
	Note: DEWA approval is excluded. DEWA security deposit shall be paid directly by the client.				
	TOTAL FOR ELECTRICAL WORKS				**256,459.00**
12.0	**HVAC WORKS**				
12.01	Supply and Installation of Pre-Insulated ducting (Modification) as per new layout for existing A/c units -7 Nos and Fresh air Pre-Insulated ducting	1.00	Item	45,000.00	45,000.00
12.02	Relocation of existing 3 nos FCU including modification of chilled water pipes	1.00	Item	9,200.00	9,200.00
12.03	Supply & installation of acoustic liner for duct	1.00	Item	12,850.00	12,850.00
12.04	Supply & installation of foster cloth with antifungal coating	1.00	Item	13,000.00	13,000.00
12.05	Supply and installation of flexible ducting, GI Ring and VCD	1.00	Item	7,700.00	7,700.00
12.06	Supply and installation of linear grills and diffuser Grills and Diffuser	1.00	Item	8,035.00	8,035.00
12.07	Supply and Installation of Pre-Insulated ducting for toilet and pantry extract. (Male & Female)	1.00	Item	6,275.00	6,275.00
12.08	Performance Testing of existing A/c system	1.00	Item	6,125.00	6,125.00
12.09	Commissioning of existing A/c system	1.00	Item	6,125.00	6,125.00
12.1	Supply and installation of Bypass type VAV with thermostat.	5.00	nos	3,060.00	15,300.00
12.11	Supply and installation of sound attenuator	7.00	nos	1,840.00	12,880.00
12.12	Relocation of existing thermostat	7.00	nos	540.00	3,780.00
12.13	Supply and Installation of humidifier	1.00	nos	2,295.00	2,295.00
12.14	Supply and Installation of fragrance diffuser	1.00	nos	2,295.00	2,295.00
12.15	Supply and installation of MSFD	2.00	nos	2,900.00	5,800.00
12.16	Servicing of A/c units along with strainer cleaning	Rate Only/ Nos If Required	nos	1,600.00	
12.17	Allow charges for third party chilled water flushing	1.00	Ls	18,350.00	18,350.00

ELECTROLUX MIDDLE EAST_ FIT OUT WORKS
29th Floor, Fortune Tower, Cluster C, Jumeriah Lake Towers, Dubai
BILL OF QUANTITIES
Date: 04 August 2025

SR NO	DESCRIPTION	QUANTITY	UNIT	RATE (AED)	AMOUNT (AED)
12.18	Deducated FCU for server room Supply and Installation of Separate chilled water FCU for Server room with required valve package, Duct Note: Subject to the availability of chilled water and approval from the building management.	1.00	Nos	18,350.00	18,350.00
	Notes:				
	We have assumed that all existing HVAC units are in working condition. We have not considered any relocation or replacement for the same.				
	BMS related works (If any) is excluded from our scope.				
	BTU meter are excluded.				
	We have considered pre insulated duct works for HVAC.				
	VAV (Individual AC control) considered for GM room, Meeting room 6 Pax, meeting room 4 pax only				
	TOTAL FOR HVAC WORKS				**193,360.00**
13.0	**CIVIL DEFENCE WORKS - Provisional Sum**				
13.01	Civil Defence Works Provisional Sum Considered	1.00	Psum	127,075.00	127,075.00
	Note: We have considered provisional sum for fire fighting & fire alarm works. The works will be carried out by the Civil Defence-approved contractor nominated by the building. JTCPL Designs will charge 15% coordination fee on the actual quotation from building nominated contractor.				
	TOTAL FOR CIVIL DEFENCE WORKS (Provisional Sum)				**127,075.00**
14.0	**MISCELLANEOUS ITEMS**				
14.01	Manually Operated Sunscreen Roller Blinds: Supply and Installation of manually operated sunscreen roller blinds on the existing glass windows. Height: 2200 mm	120.00	Sqm	150.00	18,000.00
14.02	Manually Operated Blackout Roller Blinds: Supply and Installation of manually operated blackout roller blinds on the existing glass windows. Height: 2200 mm	Optional Rate Only/ Sqm	Sqm	200.00	
14.03	Reception Signage Supply and installation of Illuminated Reception Signage fabricated with 3mm stainless steel brush finish and 20mm frosted acrylic with led light Length 2000 mm	1.00	Nos	15,000.00	15,000.00
14.04	LOGO- Non Illuminated - Townhall backdrop Made of brush finish SS Size - 400 mm x 400 mm	1.00	Nos	3,000.00	3,000.00
14.05	Supply and installation way finding signage, Door Signage made of SS Size: 30 cm L x 10 cm H	13.00	Nos	200.00	2,600.00
14.06	Supply and installation Toilet signage made of SS Size: 10 cm L x 15 cm H	2.00	Nos	300.00	600.00
14.07	Supply and installation of Artificial olive Tree height 1500 mm	1.00	Nos	3,500.00	3,500.00
	Note: New Loose Plants, Pots are excluded				
	TOTAL FOR MISCELLANEOUS ITEMS				**42,700.00**

ELECTROLUX MIDDLE EAST_ FIT OUT WORKS
29th Floor, Fortune Tower, Cluster C, Jumeriah Lake Towers, Dubai
FURNITURE BOQ - V.01
Date: 04 August 2025

TAG	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
TB-01a	**Height Adjustable Workstation Desk- 1200 x 600** **Twin desk** White Table top White legs Custom Fabric Finish for Acoustic divider panel **Location:** Open Office	25	NOS	4,245.00	106,125.00
TB-01b	**Height Adjustable Workstation Desk- 1200 x 600** **Single desk** White Table top White legs Custom Fabric Finish for Acoustic divider panel **Location:** Open Office	9	NOS	1,950.00	17,550.00
TB-01c	**Height Adjustable Workstation Desk- 1500 x 600** **Single desk** White Table top White legs Custom Fabric Finish for Acoustic divider panel **Location:** Focus Room	2	NOS	2,150.00	4,300.00
TB-01d	**2x User Under-Desk Cable Management System** Power Access and Cable Management Solution including Under Desk Cable Tray 4-way extended socket Power cable	25	NOS	570.00	14,250.00
TB-01e	**Single User Under-Desk Interlink** Power Access and Cable Management Solution including Under Desk Cable Tray 3-way extended socket Power cable	10	NOS	380.00	3,800.00
TB-02-EX	**GM CABIN DESK:** Height Adjustable Workstation Desk-1400 x 400 **Location:** GM Cabin **Existing desk to be relocated**	1	NOS	N/A	N/A

ELECTROLUX MIDDLE EAST_ FIT OUT WORKS
29th Floor, Fortune Tower, Cluster C, Jumeriah Lake Towers, Dubai
FURNITURE BOQ - V.01
Date: 04 August 2025

TAG	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
TB-03	**MEETING TABLE - 1800 x 1000** White Table top with powder coated Metal Legs with cable management system, cable tray, snake cable, 2 Mts PDU **Location:** 4P Meeting Room	2	NOS	1,680.00	3,360.00
TB-04	**MEETING TABLE - 2400 x 1200** White Table top with powder coated Metal Legs with cable management system, cable tray, snake cable, 2 Mts PDU **Location:** 6P Meeting Room	2	NOS	2,100.00	4,200.00
TB-04a	**Power Data and HDMI Module** Technical Features:2x Universal Outlet, 2x USB Hub (A+C PD20W), 2x CAT6, 1 HDMI including Power Cable **Location:** Meeting tables	4	NOS	860.00	3,440.00
TB-04b	**Flexi Spine Cable Management** Underdesk round cable management solution **Location:** Meeting tables	4	NOS	145.00	580.00
TB-04c	**Under Desk Cable Tray** Cable holder for organizing power sockets and cords - measures 65cm x 11cm **Location**: Meeting tables	4	NOS	122.00	488.00
TB-05-EX	**MEETING TABLE - 3 Person** Existing round table **Location:** GM Cabin **Existing table to be relocated** 	1	NOS	N/A	N/A

ELECTROLUX MIDDLE EAST_ FIT OUT WORKS
29th Floor, Fortune Tower, Cluster C, Jumeriah Lake Towers, Dubai
FURNITURE BOQ - V.01
Date: 04 August 2025

TAG	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
TB-06	**DINING TABLE- 700mm dia** Table top - Starke Pro White Frame - Powdercoated white **Location:** Pantry	2	NOS	860.00	1,720.00
TB-07	**COFFEE TABLE** Rectangular Coffee Table Table Top - Starke Black Legs - Black **Location:** Reception Waiting Area **Budgetary Amount considered**	1	NOS	985.00	985.00
ST-01-EX	**STORAGE CABINETS** Existing Cabinets **Location**: Open Office Reuse existing as is	7	NOS	N/A	N/A
ST-02-EX	**PEDESTAL CABINETS** Existing Metal Cabinets **Location**: Workstation Desks Reuse existing as is	59	NOS	N/A	N/A
CH - 01 - EX	**TASK CHAIR:** Herman Miller - Mirra Chair - Existing **Location:** Workstations, GM Cabin, Reception, Meeting Rooms **Existing Chairs to be relocated**	81	NOS	N/A	N/A
CH-03	**VISITOR CHAIR** Frame: Grey plastic+ glass fiber frame Arm: Seat-back linked fixed armrest Mechanism: Single lock, cable control mechanism Gas lift: 85mm extended length, Class-3 gas lift Base: 340mm nylon base+60mm PU caster" **Location:** GM Cabin	3	NOS	652.00	1,956.00
CH-04	**HIGH CHAIR** Upholstered seat with mould foam with black metal leg. **Location:** Hot Desk, Pantry	13	NOS	760.00	9,880.00

ELECTROLUX MIDDLE EAST_ FIT OUT WORKS
29th Floor, Fortune Tower, Cluster C, Jumeriah Lake Towers, Dubai
FURNITURE BOQ - V.01
Date: 04 August 2025

TAG	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
CH-05	**DINING CHAIR** Multi-Purpose Designer Chair- White **Location:** Pantry	4	NOS	430.00	1,720.00
SF-01	**SOFA - 1 SEATER** Single seater upholstered sofa with wooden legs **Location:** Reception Waiting area	1	NOS	1,785.00	1,785.00
SF-02	**SOFA - 2 SEATER** Two seater upholstered sofa with wooden legs **Location:** Reception Waiting area	1	NOS	3,171.00	3,171.00
SF-03	**POUF** Small Leisure Stool - Upholstered Stool **Location:** Focus Rooms	2	NOS	786.00	1,572.00
	BASIC TOTAL FURNITURE				**180,882.00**
					VAT Extra

Notes & Exclusions:

(A) Furniture color will be based on available fabric/leather as approved and signed-off by Client before the manufacturing.

(B) Price includes standard packaging as per manufacturing standard. Does not include any special packaging and/or drop test packaging

(C) Cost provided is for items listed out in this Furniture schedule only.

(D) Products strictly follow party A's quality standards

(E) Price does not include any White Goods. To be supplied by Client

(F) Price does not include preparation of any Inventory of existing Furniture and / or transportation,relocation,installation of any existing Plants / planters, existing furniture or any other items from Client's current Office.

(G) Price does not include refinishing of any existing furniture. Additional charges to apply in case of any refurbishments / resizing required.

(H) Validity: 15 days upon issuance of this quotation. Stock levels and prices are subject to change without notification.

(I) Payment Terms: 60% advance, 40% balance before delivery

ELECTROLUX MIDDLE EAST_ FIT OUT WORKS
29th Floor, Fortune Tower, Cluster C, Jumeriah Lake Towers, Dubai
OPTIONAL WORKS
Date: 04 August 2025

Sr No	Item Description	Qty	Unit	Rate	Amount (AED)
1.00	**ACCESS CONTROL SYSTEM**				
	ZKTECO STAND ALONE ACCESS CONTROL SYSTEM				
1.01	**SpeedFace H5L(P)** Linux-Based Hybrid Biometric Access Control and Time & Attendance Terminal with Visible Light Facial Recognition Features · Visible Light Facial Recognition · Anti-spoofing algorithm against print attack (laser, color and B / W photos), videos attack and 3D mask attack · Multiple verification methods: Face / Fingerprint / Card / Palm · Available card modules: 125kHz ID card (EM) / 13.56MHz IC card · Supplement lighting with adjustable brightness · Capacity of 6,000 face templates	3	Nos	3,375.00	10,125.00
1.02	Supply of DOOR EXIT BUTTON (NO TOUCH)	3	Nos	266.00	798.00
1.03	Supply of ADAPTER PLUS POWER SUPPLY	3	Nos	150.00	450.00
1.04	Supply of ELOCL -Magnetic Door Lock	3	Nos	611.00	1,833.00
1.05	Supply of ELOCL Glass U/LZ Bracket	3	Nos	150.00	450.00
1.06	Supply of Emergency Reusable Break Glass	3	Nos	150.00	450.00
1.07	Supply and Pulling of **Cat6 UTP Cable**, FOR device to magnetic lock and device to push button with connector cables and necessary Accessories	3	Nos	165.00	495.00
1.07	Installation of access control device, magnetic lock with all Necessary Accessories	1	Ls	1,175.00	1,175.00
1.08	INBIO security software with license	1	Ls	3,685.00	3,685.00
1.09	Testing & Commissioning Charges User training of access control device	1	Ls	1,565.00	1,565.00
	TOTAL AMOUNT FOR ACCESS CONTROL SYSTEM			**AED.**	**21,026.00**
2.00	**ROOM BOOKING SYSTEM**				
2.01	Supply of Evoko Liso -Room booking system.	4	Nos	8,230.00	32,920.00
2.02	Configuration Charges	1	Ls	5,486.00	5,486.00
2.03	Supply & Pulling Cat6a UTP Cables, Termination & Testing With all necessary accessories.	4	Nos	364.00	1,456.00
	TOTAL AMOUNT FOR ROOM BOOKING SYSTEM			**AED.**	**39,862.00**

ELECTROLUX MIDDLE EAST_ FIT OUT WORKS
29th Floor, Fortune Tower, Cluster C, Jumeriah Lake Towers, Dubai
OPTIONAL WORKS
Date: 04 August 2025

Sr No	Item Description	Qty	Unit	Rate	Amount (AED)
3.00	**CCTV - NVR & IP CAMERA**				
	Brand:Hanwha (Samsung)				
3.01	Supply of (Samsung)Hanwha Wisenet - 16CH 8MP NVR without PoE. Features • Up to 16CH 8MP resolution • H.265, H.264, MJPEG codec • WiseStream support • 128Mbps network camera recording • Plug & play by 16 PoE port	1	Nos	7,332.00	7,332.00
3.02	Supply of (Samsung) Wisenet LND-6012R 2MP IR Dome Camera, Indoor, 30fps, 2.8mm Fixed Focal Lens, Double Codec, 120dB WDR, PoE, White for indoor use as per proposed drawing.	7	Nos	611.00	4,277.00
3.03	Supply of WD Purple 6 TB Surveillance Hard Disk Drive	1	Nos	1,242.00	1,242.00
3.04	Supply of 16 Port POE Switch	1	Nos	1,200.00	1,200.00
3.05	Supply & Pulling Cat6A UTP Cables, Termination & Testing With all necessary accessories.	7	Nos	364.00	2,548.00
3.06	Camera Installation, Focusing with all necessary accessories.	1	Nos	1,410.00	1,410.00
3.07	Supply of UNV 27inch Monitor with wall mount bracket	1	Nos	1,020.00	1,020.00
3.08	Supply of HDMI 4K Cable 10 Mtrs	1	Nos	468.00	468.00
3.09	Testing & Commissioning Charges	1	Nos	1,573.00	1,573.00
	Note: SIRA building charges are not included in this quotation.				-
	TOTAL AMOUNT FOR CCTV			**AED.**	**21,070.00**

ELECTROLUX MIDDLE EAST_ FIT OUT WORKS
29th Floor, Fortune Tower, Cluster C, Jumeriah Lake Towers, Dubai
NOTES & EXCLUSIONS
Date: 04 August 2025

1	**Payment Terms**	: As per Cover letter submitted
2	**Duration**	: As per Project Program submitted
3	**Validity**	: 15 days from the quote date
4	Any Items which are not mentioned in the attached BOQ reference will be a variation work.	JTCPL_Electrolux_QTN-V01
5	Our offer is based on the BOQ . Any changes in quantity/specification/size will have additional cost implications. The 3D renders and drawings are provided for reference only and should be read alongside the BOQ, which shall prevail as the definitive scope of works and deliverables.	
6	We will not take responsibilities on any changes in drawings or specification commented or instructed by the authorities, while it has been submitted for approvals. All the cost resulting from this changes if any, will be added to the contract as a variation. Which needs to be agreed upon before starting such works.	
7	The client shall provide and bear the costs for the following facilities and services. - All government statutory fees/deposits. - Landlord fees/review fees. - Water & Electricity for construction works - Secured storage spaces for materials - Permits /Access/Passes for workers - Mess & toilet facility for our workers	
8	Specialist Consultant charges for Authority approval, Authority exemption fees are excluded. Specialist works such as Structural consultant, Core cutting RC Slab scanning etc are not considered.	
9	The mentioned CAR policy is quoted based on standard terms and conditions. Any special requirement or higher Value of insurance by the client or building management will be charged additional.	
10	All the materials delivered on site for Installation will be the property of JTCPL Designs Interior Decoration LLC until the Taking over Certificate of the project signed by the Client. JTCPL will have all rights to take it back if the Contractual terms are not honored by any party.	
11	All documents required for authority submissions shall be provided by the client.	
12	We have considered Locally available materials such as laminate, Solid Surface, Carpet, Lights, Glazed partitions, Acoustic ceiling & wall products.	
13	Manually operated perimeter blinds (non-blackout) have been considered.	
14	We have considered provisional sum for fire fighting & fire alarm works. The works will be executed by the Civil Defence-approved contractor nominated by the building (Eurofire). JTCPL Designs will apply a 15% coordination fee on the contractor's actual quotation.	
15	We have considered PVC conduit and white PVC sockets and switches. If GI conduit or metallic switches and sockets are required, it will be treated as additional. No fire proof / LSF cables are considered.	
16	We have considered pre insulated duct works for HVAC.	
17	It is assumed that the existing electrical load is sufficient; hence, no power upgrade has been considered. Subject to approval, existing DEWA meters are to be retained, and the client shall provide an NOC from the landlord.	
18	Designing of branding graphics \ creation of art work is excluded. Supply of Plants & Planters, Décor, Loose rugs, Art Works, White goods, Appliances Artifacts are excluded.	
19	Door closers are excluded	
20	Attic Stock on Flooring tiles is excluded	
21	Janitor Sink is excluded, Smart / Switchable glass not included.	
22	Third party testing & commissioning of electrical works. (Live Test & Megger Test) is not considered in the scope.	
23	DB merging is not considered in the scope	
24	LEED certification, Green Building, WELL related works are excluded.	
25	We have assumed that all existing HVAC units are in working condition and sufficient for the space. We have not considered any relocation or replacement for the same. We have not considered any additional FCU's or dedicated FCU for Server room. Air Freshener or dehumidified inside AC ducts are not included.	
26	All works related to IT passive & active works including structured cabling, server racks and relocation, FM 200, Leak detection system, Security System, UPS works, AV System, 24/7 Direct alarm systems,Wi-Fi, TV, Video Conferencing System & PA System, HDMI cable are not considered in the scope	
27	BTU meter, Water Meter, combining of Dewa meters and related works, Lighting control system, Dali Dimmable, Motion sensors, Central battery System are excluded.	

ELECTROLUX MIDDLE EAST_ FIT OUT WORKS
29th Floor, Fortune Tower, Cluster C, Jumeriah Lake Towers, Dubai
NOTES & EXCLUSIONS
Date: 04 August 2025

28	Chlorination for water supply is excluded.
29	Third party air balancing & third party testing and commissioning are excluded from our scope.
30	BMS related works (If any) is excluded from our scope.
31	Annual maintenance contract for plants are excluded
32	Preparation of Inventory , Shifting of existing furniture, AV equipment, Server Racks, Light fittings, loose plants or any other existing items from Mazaya Tower to Fortune Tower is not consider in the scope.
33	All long lead items included in the proposal are based on availability, subject to timely client approvals. In the event of delays in approval, readily available alternates will be considered.
34	**AS PER UAE LAW, 5% VAT WOULD BE APPLICABLE FOR ANY SUPPLY OF GOODS AND SERVICES AND WOULD BE ADDED TO THE FINAL VALUE OF EACH INVOICE**

I/ We hereby confirm that I/ We have read all the terms and conditions as well as the product details such as finished /dimension/quantities proposed in the quotation and give our approval for the same.

Client's Signature/ Company Stamp	Client's Full Name	Date

Continual growth and improvement by creating an ecosystem of like-minded individuals to change the language of workspace design-build by Client-centricity and Team-centricity with Passion, Integrity and Discipline thus enriching the lives we touch.

JTCPL™
DESIGNS

www.jtcpldesigns.com