Pinnacle
Interiors

NSATS Office - Fit Out Works
Dubai

COST PROPOSAL

Pinnacle Interiors LLC
Dubai UAE
PO Box 47743
Tel: 04 346 6051
Fax: 04 346 6059

Name of project: NSATS Office, Office C 202 - Fit Out Works

Ref: PI/QTN - 180/2023

Date: 20/07/2023

Dear Sir,
We are submitting herewith our proposal for the above mentioned job as per the BOQ given below,

SUMMARY

	Description				Amount
A	Fit Out Works	Item	1		1,234,470.00
B	Loose Furniture	Item	1		214,030.00
	SUM TOTAL (Dhs One Million Four Hundred Forty Eight Thousand and Five Hundred Only)				AED 1,448,500.00

5% UAE VAT applicable on the Invoice Value

Payment Terms :

50% Advance Payment
40% Progress Payment
10% upon Final completion
Note: All invoices to be payable within 7 working days of the Invoice submission.

Validity : 30 days

Completion : To be Discussed

We hope this is in line with your requirements and looking forward to your earliest favourable response .

Regards
Joseph Charles
Managing Director
Pinnacle Interiors LLC, Dubai.

Pinnacle Interiors LLC
Dubai UAE
PO Box 47743
Tel: 04 346 6051
Fax: 04 346 6059

Name of project: NSATS Office, Office C 202 - Fit Out Works

Ref: PI/QTN - 180 A/2023

Date: 20/07/2023

Dear Sir,
We are submitting herewith our proposal for the above mentioned job as per the BOQ given below,

COST PROPOSAL

Sl no.	Description	Item	Qty	Unit Rate	Amount
	A. Preliminaries				
A.1	Charges for preparation and submission of drawings and documents to Landlord and Local Authorities	Item	1		2,500.00
A.2	Charges to be paid to authorities for approvals / Third Party Consultancy Charges / Utilities Connection Charges	Item	Actuals to be paid by the client		EXCLUDED
A.3	Contractor All Risk Insurance Policy	Item	1		2,000.00
A.4	Mobilization charges of the project and Site Protection charges	Item	1		3,500.00
A.5	Scaffolding Charges	Item	1		2,500.00
A.6	Regular Cleaning Charges	Item	1		1,800.00
A.7	Final Site Cleaning Charges	Item	1		2,000.00
A.8	Design Charges (Includes 8 No.s 3D renders)	Item	Shall be waived off if Project is awarded to Pinnacle		8,500.00
	Total for Preliminaries				**22,800.00**
	B. Demolition				
B.1	Dismantling and removing existing 1 entrance door and cart away the debris as per Dubai Municipality norms	LS	1	600.00	600.00
B.2	Demolition of existing partition for making opening for entrance door and cart away the debris as per Dubai Municipality norms	LS	1	1,000.00	1,000.00
	Total for Demolition				**1,600.00**
	C. Partitions				
C.1	Supply and installation of single layer plain gypsum cladding to existing columns and walls up to false ceiling level as per proposed layout	msq	125	110.00	13,750.00
C.2	Supply and installation of 100mm thick plain gypsum partition up to false ceiling level with both sides gypsum boards with necessary supports. Location: Reception, Director 1 & 2, Meeting and Lounge, Sr. Executive 1 & 2, Open workstation area, Demo/ Presentation, Storage	msq	140	130.00	18,200.00
C.3	Supply and installation of 100mm thick MR gypsum partition up to false ceiling level with both sides gypsum boards with necessary supports. Location: Powder room	msq	45	140.00	6,300.00
C.4	Supply and installation of 100mm thick FR gypsum partition up to false ceiling level with both sides gypsum boards with necessary supports. Location: Server	msq	15	140.00	2,100.00
C.5	Supply and installation of 10mm thick clear tempered glass partition with 20*30mm black powder coated aluminium black powder coated U-channel, glass to glass silicone joints. Ht 2.8mH Location: Director 1 & 2, Meeting and Lounge, Sr. Executive 1 & 2, Open workstation area	msq	51	550.00	28,050.00
C.6	Supply and installation of support baffle above proposed glass partitions and doors	RM	24	120.00	2,880.00
	NOTE: Assumed Existing corridor area partitions are in line with the proposed layout & hence existing partitions are retained. Modification to corridor partitions, ceiling, flooring - Excluded				-
	Total for Partitions				**71,280.00**
	D. Wall Finishes & Doors				
D.1	Supply & apply primer, stucco and two top coats of fenomastic paint finish to the existing and proposed walls & partitions. Location: Storage, Powder, Server, Corridor, Open workstation, Pantry, columns	msq	420	35.00	14,700.00
D.2	Supply and installation of texture paint finish to the partitions as per proposed wall finishes layout. Location: Director 1, Entrance, Corridor, Lounge, Reception	msq	90	170.00	15,300.00

Pinnacle Interiors LLC
Dubai UAE
PO Box 47743
Tel: 04 346 6051
Fax: 04 346 6059

Name of project: NSATS Office, Office C 202 - Fit Out Works

Ref: PI/QTN - 180 A/2023

Date: 20/07/2023

D.3	Supply & installation of wooden wall cladding with vertical strips made in MDF with veneer finish. Ht: 2.9mH Location: Director 1, Director 2, Meeting and Lounge, Reception, Demo/ Presentation room	msq	89	1,500.00	133,500.00
D.4	OPTION 2: Supply & installation of fluted wall cladding made in 18mm thick MDF with paint finish. Ht: 2.9mH Location: Director 1, Director 2, Meeting and Lounge, Reception, Demo/ Presentation room	msq	89	1,235.00	RATE ONLY
D.5	Supply and installation of 100 x 50mm wooden slats made in MDF with wood veneer finish. Size: 100 x 50 x 2900mmH Location: Reception Back wall	Nos	20	700.00	14,000.00
D.6	Supply and installation of Grooved Acoustic wall paneling 12mm Acoustic PET panel. Make: Local make. Size : 1200x2400mm (max)	msq	28	475.00	13,300.00
D.7	Supply and installation of additional supports for installation of TV Location: Director 2, Meeting	Nos	2	1,200.00	2,400.00
D.8	Supply & Installation of MDF skirting in painted finish	RM	235	60.00	14,100.00
D.9	Supply & installation of 45mm thick semi solid hidden swing door made with one side vertical strips in veneer finish with door frame and architrave in MDF with veneer finish and necessary ironmongery Size: 800 x 2200mm Location: Director 1 Storage, Powder room	Nos	2	3,900.00	7,800.00
D.10	Supply & installation of 45mm thick semi solid hidden swing door made with one side vertical strips in veneer finish with door frame and architrave in MDF with veneer finish and necessary ironmongery Size: 900 x 2200mm Location: Presentation Storage	Nos	1	4,000.00	4,000.00
D.11	Supply & installation of 45mm thick semi solid hidden swing door made with both sides vertical strips in veneer finish with door frame and architrave in MDF with veneer finish and necessary ironmongery Size: 900 x 2200mm Location: Door between Director 2 and Meeting room	Nos	1	4,700.00	4,700.00
D.12	Supply and installation of 45mm thick semi solid hidden 1 Hour Fire rated wooden swing door with door frame and architrave in MDF with paint finish Size: 800 x 2200mm Location: Server room	Nos	1	6,750.00	6,750.00
D.13	Supply and installation of 45mm thick semi solid wooden swing door with door frame and architrave in MDF with paint finish Size: 900 x 2200mm Location: Pantry	Nos	1	3,300.00	3,300.00
D.14	Supply and fixing of 12 mm clear tempered glass Single leaf frameless manual sliding glass door with all around straight polished edges fixing by top track system and 1000 *800 mm long H type straight handle. Size: 1000 x 2800mm Location: Director 1, 2, Sr. Executive 1, 2	Nos	4	2,900.00	11,600.00
D.15	Supply and fixing of 12 mm clear tempered glass Double leaf frameless manual sliding glass door with all around straight polished edges fixing by top track system and 1000 *800 mm long H type straight handle. Size: 2200 x 2800 Location: Meeting and Lounge	Nos	1	5,200.00	5,200.00
D.16	Supply and fixing of 12 mm clear tempered double leaf frame less swing glass door with all around straight polished edges fixing with Dorma BTS65 floor machine and 800*600mm H type handle Size: 1700 x 2400 Location: Entrance	Nos	1	5,200.00	5,200.00
D.17	Supply and installation of manual roller blinds at façade area Location: Director 1, 2, Meeting and Lounge, Demo/ Presentation	msq	93	120.00	11,160.00
D.18	3D Letters Signage (Backlit) : Fabrication & installation of letters made of 30mm embossed 3D Aluminum powder coated letters with 6mm Opal white acrylic inner base. Back lit cool white LED lights illuminations and high quality transformers. Logo fixing with 2cm spacers & screws. Size: 1800 x 450mmH (Size & Design To be confirmed)	PS	1	11,500.00	11,500.00
	Total for Wall Finishes & Doors				**278,510.00**
	E. Flooring				

Pinnacle Interiors LLC
Dubai UAE
PO Box 47743
Pinnacle Interiors
Tel: 04 346 6051
Fax: 04 346 6059

Name of project: NSATS Office, Office C 202 - Fit Out Works

Ref: PI/QTN - 180 A/2023

Date: 20/07/2023

E.1	Supply and installation of 6mm cement board on top of existing raised flooring to accept proposed tile floor finishes (Considered for Item E.4 & E.13)	msq	53	65.00	3,445.00
E.2	Minor Modification to existing raised flooring for installation of proposed floor finishes. Note: New pedestals/ panels - Excluded.	LS	1	7,850.00	7,850.00
E.3	Supply and installation of waterproofing below floor finishes and up to 80cm upstand. Location: Pantry, Powder room	LS	1	2,300.00	2,300.00
E.4	Supply and installation of neolith flooring (1500 x 1500mm x 6mm thick) as per proposed flooring layout. Color - Beige Location: Reception, Pantry, Corridor	msq	50	1,100.00	55,000.00
E.5	Option 2: Supply and installation of microtopping as per proposed flooring layout. Location: Reception, Pantry, Corridor	msq	50	320.00	RATE ONLY
E.6	Option 3: Supply and installation of concrete LVT flooring as per proposed flooring layout. Make: VOX LVT. Location: Reception, Pantry, Corridor	msq	50	210.00	RATE ONLY
E.7	Supply and installation of carpet tile flooring (Type 1) as per proposed flooring layout. Make: Shaw Living System or equivalent. Location: Director 1's Lounge, Director 2, Sr. Executive 1 & 2, Demo/ Presentation	msq	117	300.00	35,100.00
E.8	Supply & installation of carpet tile flooring (Type 2) as per proposed flooring layout. Make: Shaw Canopy or equivalent. Location: Open Workstation	msq	15	275.00	4,125.00
E.9	Supply & installation of carpet tile flooring (Type 3) as per proposed flooring layout. Make: Standard carpet or equivalent. Location: Server, Storage	msq	12	215.00	2,580.00
E.10	Supply and installation of Parquet flooring as per proposed flooring layout. Make: Parqwood Collection Dune Oak 1-Strip, Plank Size: L: 1900 mm x W: 190mm x 14 mm/3 mm. Location: Director 1, Storage, Reception	msq	78	395.00	30,810.00
E.11	OPTION 2: Supply & installation of LVT flooring as per proposed flooring layout. Make: Shaw Unite or Equivalent. Location: Director 1, Storage, Reception	msq	78	350.00	RATE ONLY
E.12	Supply and installation of area rug as per flooring layout. Make: Ege or equivalent. Size: 3485 x 2328mm Location: Meeting and Lounge	Nos	1	3,500.00	3,500.00
E.13	Supply and installation of anti slip porcelain floor tiles for powder room Make: RAK or equivalent. Location: Powder room	LS	1	2,050.00	2,050.00
E.14	Supply and installation of Marble Threshold Location: Powder	Nos	1	350.00	350.00
E.15	Supply and installation of SS floor transition profile in black powder coated finish between different floor finishes	RM	42	140.00	5,880.00
	Total for Flooring				**152,990.00**
	F. Ceiling & Ceiling Finishes				
F.1	Supply and installation of plain gypsum ceiling as per proposed ceiling layout with necessary suspension system. Ht 2.9mH	msq	250	120.00	30,000.00
F.2	Supply and installation of plain gypsum ceiling as per proposed ceiling layout with necessary suspension system. Ht 2.7mH	msq	14	120.00	1,680.00
F.3	Supply and installation of wooden ceiling with slats as per proposed ceiling design. Location: Reception	msq	10	1,400.00	14,000.00
F.4	Supply and installation of gypsum bulkhead at drop ceiling as per proposed ceiling layout	RM	34	90.00	3,060.00
F.5	Supply and installation of gypsum cove ceiling as per proposed ceiling layout	RM	34	85.00	2,890.00
F.6	Supply and installation of Acoustic gypsum board ceiling. (Gyproc sound bloc board considered) Location: Demo/ Presentation room	msq	63	135.00	RATE ONLY
F.7	Supply and installation of 60x60 grid ceiling as per proposed ceiling layout with necessary suspension system	LS	1	1,200.00	1,200.00
F.8	Supply & installation of MDF boxing (recessed) in painted finish for installing ceiling down lights & AC grills. Size: 10cm W x 20cmH	RM	47	345.00	16,215.00
F.9	Supply and installation of gypsum pelmet for blinds in painted finish Location: Director 1, 2, Meeting and Lounge, Demo/ Presentation	RM	33	120.00	3,960.00
F.10	Supply and installation of access panel	Nos	20	250.00	5,000.00
	Total for Ceiling & Ceiling Finishes				**78,005.00**
	G. Light Fittings				

Pinnacle Interiors LLC
Dubai UAE
PO Box 47743
Tel: 04 346 6051
Fax: 04 346 6059

Name of project: NSATS Office, Office C 202 - Fit Out Works

Ref: PI/QTN - 180 A/2023

Date: 20/07/2023

G.1	Supply of Spotlights Description : Adj LED Downlight Material : Die cast Aluminum Finish :White | Light Source : LED Wattage : 12W Efficiency : 100lm/W CRI : 85+|Beam Angle : 40° Power Supply : Constant Current led Driver|Dimmable : No Size : D120xH87mm Protection : IP20	Nos	88	150.00	13,200.00
G.2	Supply of suspended linear light Description :Suspended Linear Light Material : Extruded Aluminum Finish : Black Diffuser : Opal Light Source : LED Wattage : 26W/Mtr | Efficacy : 110 lm/W CRI : 80+ | Beam Angle : 100° CCT : 3000K Power Supply : Constant Current Driver Dimmable : No Dimension: W35 x H37 x L1200mm Protection : IP20	Nos	8	325.00	2,600.00
G.3	Supply of suspended linear light Description :Suspended Linear Light Material : Extruded Aluminum Finish : Black Diffuser : Opal Light Source : LED Wattage : 26W/Mtr | Efficacy : 110 lm/W CRI : 80+ | Beam Angle : 100° CCT : 3000K Power Supply : Constant Current Driver Dimmable : No Dimension: W35 x H37 x L1400mm Protection : IP20	Nos	1	385.00	385.00
G.4	Supply of suspended linear light Description :Suspended Linear Light Material : Extruded Aluminum Finish : Black Diffuser : Opal Light Source : LED Wattage : 26W/Mtr | Efficacy : 110 lm/W CRI : 80+ | Beam Angle : 100° CCT : 3000K Power Supply : Constant Current Driver Dimmable : No Dimension: W35 x H37 x L2400mm Protection : IP20	Nos	3	660.00	1,980.00
G.5	Supply of Track mounted Spotlight with track & hanging kit Description:LED Track mounted spotlight Material: Extruded Aluminium Finish: Black | Diffuser: Clear glass Wattage: 10W CRI: 85+ | Beam angle: 36° Light Source: Luminus USA Power Supply : Constant CurrentLED Driver Dimmable:No Size: D75XH195mm IP:20 Description : 4 WIRE 3 Phase Track Finish : Black. L: 1000mm	Nos	24	445.00	10,680.00

Pinnacle Interiors LLC
Dubai UAE
PO Box 47743
Tel: 04 346 6051
Fax: 04 346 6059

Name of project: NSATS Office, Office C 202 - Fit Out Works

Ref: PI/QTN - 180 A/2023

Date: 20/07/2023

G.6	Supply of reception area pendant light Decorative Pendant Light Material : Metal + Acrylic Finish : Gold + Black Light Source: LED Wattage : 6W CCT: To Be Confirmed Power Supply : Constant Current LED Driver Dimmable : No Dimension : D60xH400mm	Nos	4	475.00	1,900.00
G.7	Supply of circular pendant light Suspended Round Light Material : Die cast Aluminum Finish : White Diffuser :Opal Diffuser Light Source : Samsung Wattage : 48W | Efficiency : 90lm/W CRI : 85+ | Beam Angle : 120° CCT : 4000k Power Supply : Constant Current Dimmable : No Size : D600mm | Protection : IP20	Nos	3	875.00	2,625.00
G.8	Supply of Decorative chandelier Decorative Pendant Material : Iron Light Source : E27x6 Wattage:6x 8W CCT : To Be Confirmed Dimension : D134xH44cm	Nos	1	2,450.00	2,450.00
G.9	Supply of 60x60 LED panel lights LED Panel Light Material : Die Cast Aluminum Diffuser : Opal Diffuser Finish : White | CCT : TBC Light Source : Samsung Wattage :40W | Efficacy : 90lm/W CRI : 85+ | Beam Angle : 120° Power Supply : Constant Current LED Driver |Dimmable : No Size : 595x595mm Protection : IP44	Nos	3	140.00	420.00
G.10	Supply of LED strip light LED Striplight Wattage : 14.4W/Mtr 24v | LED Qty : 120LED Efficiency :60lm/W|CRI : >85 CCT :3000K Light Source : Bridgelux Size : 5 Mtr/Roll | Protection : IP20	RM	71	95.00	6,745.00
	Total for Light Fittings				**42,985.00**
	H. Electrical Works				
H.1	Point wiring of Lighting fixtures including PVC conduit and cabling	Pts	147	150.00	22,050.00
H.2	Installation of Down and Spot Light Fittings.	Nos	111	55.00	6,105.00
H.3	Installation of 60x60 Light Fittings	Nos	3	55.00	165.00
H.4	Installation of Pendant Light Fittings.	Nos	17	75.00	1,275.00
H.5	Installation of Chandelier Light Fittings.	Nos	1	295.00	295.00
H.6	Installation of Cove Light Fittings.	Mtr	71	55.00	3,905.00
H.7	Supply and Installation of Light switches with PVC wiring and PVC conduiting	Nos	16	130.00	2,080.00
H.8	Supply and installation of Grid switches with pvc wiring and PVC conduiting	Nos	1	885.00	885.00
H.9	Supply & Installation of 13 Amps Single Switched Socket mounted including PVC conduiting and wiring.	Nos	5	270.00	1,350.00

Pinnacle Interiors LLC
Dubai UAE
PO Box 47743
Tel: 04 346 6051
Fax: 04 346 6059

Name of project: NSATS Office, Office C 202 - Fit Out Works

Ref: PI/QTN - 180 A/2023

Date: 20/07/2023

H.10	Supply & Installation of 13 Amps Double Switched Socket mounted including PVC conduiting and wiring	Nos	31	295.00	9,145.00
H.11	Supply and installation of Floor Box including cabling for sockets. (1 No-13A twin socket, 1-Data & 1-Voice)	Nos	3	1,000.00	3,000.00
H.12	Supply &Installation of 15 Amps Single switched socket mounted including PVC conduiting for Microwave Oven in Pantry.	Nos	1	565.00	565.00
H.13	Supply & Installation of 15 Amps Single switched socket including PVC conduiting and wiring for Coffee Machine in Coffee Bar and Pantry.	Nos	2	530.00	1,060.00
H.14	Supply & Installation of 20 Amps SPN Isolator including PVC conduiting and wiring for Signage.	Nos	1	885.00	885.00
H.15	Supply & Installation of 20 Amps SPN Isolator including PVC conduiting and wiring for Server.	Nos	1	885.00	885.00
H.16	Supply conduiting, wiring & installation of 20 A DP switch with flux outlet for Water Heater.	Nos	1	650.00	650.00
H.17	Supply & Installation of Power Point for ONTC.	Nos	1	415.00	415.00
H.18	Supply & Installation of Power Point for FACP & 24x7	Nos	2	415.00	830.00
H.19	Supply & Installation of Power Point for Access Control.	Nos	5	415.00	2,075.00
H.20	Supply & Installation of Power Point for Time attendance.	Nos	1	415.00	415.00
H.21	Supply & Installation of Power Point for Logo.	Nos	1	415.00	415.00
H.22	Supply & Installation of Power Point for Sliding Door.	Nos	5	415.00	2,075.00
H.23	Supply & Installation of Power Point for Exhaust Fan	Nos	1	415.00	415.00
H.24	Supply & Installation of Power Point for screen	Nos	1	415.00	415.00
H.25	Supply & Installation of Power Point for FTU.	Nos	17	415.00	7,055.00
H.26	Supply & Installation of Containment for Thermostat	Pts	17	120.00	2,040.00
H.27	Supply and Installation of necessary cable trunking works for Lighting works with supports	Mtr	26	120.00	3,120.00
H.28	Supply and Installation of necessary cable trunking works for Power works with supports	Mtr	26	120.00	3,120.00
H.29	Supply & Installation of Necessary cable tray works for Data/Voice.	Mtr	26	120.00	3,120.00
H.30	Supply & Installation of PVC Conduit for Data, Voice	Pts	32	120.00	3,840.00
H.31	Supply & Installation of PVC Conduit for Camera, Wifi, Speaker, Time attendance and Access Control	Nos	16	120.00	1,920.00
H.32	Supply & Installation of 32 mm PVC Conduit for HDMI/VGI for TV/Screen	Nos	4	470.00	1,880.00
H.33	Modification of Existing Building SMDB including dressing as per new Requirements. (Cable from MDB or LV Panel to SMDB Excluded) (Note: Considered SMDB in existing location with same allotted Load & Work will be Executed Subjected to Building Management & Authority Approval. Power Upgrade related works is Excluded. If Replacement/Relocation required, will be charged additionally)	Nos	1	11,175.00	11,175.00
H.34	Supply and installation of CT meter cabinet (200A) inside electrical room (Considered single meter for proposed unit as per site) Note: Undertaking for 24-hours access to electrical room from landlord need to be provided to DEWA	Nos	1	5,000.00	RATE ONLY
H.35	Supply & Installation of New DB-01 including DB dressing and labeling	Nos	1	6,120.00	6,120.00
H.36	Supply and Laying of 4Cx 35 SQ MM XLPE/SWA/PVC/CU cable + ECC from SMDB to Meter Cabinet and to New DB	Mtr	35	260.00	9,100.00
H.37	Termination of 4CX 35 Sqmm	Nos	8	120.00	960.00
H.38	Megger test, Testing and commissioning. (Note: Third Party Excluded)	LS	1	1,765.00	1,765.00
H.39	Preparation of load schedule.	LS	1	2,355.00	2,355.00
H.40	DEWA inspection & approval charges. (Note: Power Upgrade Excluded, Power upgrade & related works subjected to Building Management Approval & power availability, Estimation & Security Deposit Charges by Client)	LS	1	8,235.00	8,235.00
	NOTE: Power Upgradation, Electrical Room modification - Excluded				-
	Total for Electrical Works				**127,160.00**
	I. HVAC Works				

Pinnacle Interiors LLC
Dubai UAE
PO Box 47743
Tel: 04 346 6051
Fax: 04 346 6059

Name of project: NSATS Office, Office C 202 - Fit Out Works

Ref: PI/QTN - 180 A/2023

Date: 20/07/2023

I.1	Supply of Floor Terminal Unit (TU4) inclusive of two centrifugal fans, motorized damper, multifunctional electronic controller with "bus" communication card, air discharge and intake floor grills, 5m power connection cable with British Standard fused plug. This unit has an LCD Screen for reading all necessary data and easily changing them if required. Manufacturer: AET, UK	Nos	17	9,270.00	157,590.00
I.2	Installation of Floor Unit (TU4) inside the Raised Access Floor, supply & installation of all necessary data (bus communication) cabling & RJ45.	Nos	17	470.00	7,990.00
I.3	Supply of floor grille	Nos	5	815.00	4,075.00
I.4	Supply and installation of return linear grills in each room as per the proposed layout (Note: As per the discussion, considered partition from floor level to false ceiling only. If partition goes upto the slab above false ceiling return dusting to be provided.)	Item	1	8,355.00	8,355.00
I.5	Supply and installation of return ducting, plenum boxes, VCD, FLEXIBLES With all necessary supports and fittings	Item	1	17,650.00	RATE ONLY. To be included if partitions are up to Slab
I.6	Coordination for Rerouting of voids (for supply air) below floor level according to the proposed layout. (Assuming supply air diffusers are existing at the site)	Item	1	4,120.00	RATE ONLY
I.7	Supply and installation of extract air ducting for toilet and wet pantry and connection to the duct existing inside the corridor toilet with necessary supports and fittings (Corridor ceiling need to be demolished for the connection)	Item	1	8,000.00	8,000.00
I.8	Supply and installation of Extract air fan and NRD.	Item	1	3,095.00	3,095.00
	Total for HVAC Works				**189,105.00**
	J. Plumbing Works				
J.1	Supply & Installation of Pantry Sink with Mixer. Inset Square Sink Single Hole Kitchen Sink Mixer	Nos	1	3,220.00	3,220.00
J.2	Supply & Installation of Water Closet with fixing kit. Back to Wall WC	Nos	1	3,245.00	3,245.00
J.3	Supply of Bidet Spray Kit, Toilet roll holder, Waste Bin Universal Bidet Spray Kit Toilet Roll Holder with Cover	Set	1	680.00	680.00
J.4	Supply & Installation of Wash basin with Mixer for Toilet. Countertop Wash Basin Mono Basin Mixer	Nos	1	2,705.00	2,705.00
J.5	Supply and Installation of Water Heater. (50 liters) - Brand : Ariston.	Nos	1	1,000.00	1,000.00
J.6	Supply & Installation of PPR piping for water supply, including necessary PPR fittings for PS - 1 No, WC - 1 No, WB - 1 No, including Water Heater - 1 No.	LS	1	4,235.00	4,235.00
J.7	Supply & Installation of UPVC piping for Drainage including necessary UPVC fittings for PS - 1 No, WC - 1 No, WB - 1 No, including Water Heater - 1 No.	LS	1	5,180.00	5,180.00
J.8	Supply & Installation of Floor Trap (Note: Floor Trap cover Excluded)	Nos	2	475.00	950.00

Pinnacle Interiors LLC
Dubai UAE
PO Box 47743
Tel: 04 346 6051
Fax: 04 346 6059

Name of project: NSATS Office, Office C 202 - Fit Out Works

Ref: PI/QTN - 180 A/2023

Date: 20/07/2023

J.9	Conducting Gravity Test, Pressure Test and Provide reports. (Third Party Excluded)	LS	1	1,180.00	1,180.00
	Total for Plumbing Works				**22,395.00**
	K. FF & FA Works				
K.1	Supply of fire alarm control panel (4007 ES)	Nos	1		
K.2	Network card (1 No.) & Wired media card (2 No.)	Nos	1		
K.3	Supply of control module (new panel loop) For Interfacing of FACP to building	Nos	2		
K.4	Supply of control moduleFor Interfacing of FACP to 24X7	Nos	2		
K.5	Supply of monitor module (Building panel loop) For Interfacing of FACP to building	Nos	2		
K.6	Supply of smoke detector with base	Nos	12		
K.7	Supply of heat detector with base	Nos	2		
K.8	Supply of manual call point with back box	Nos	2		
K.9	Supply of sounder with back box	Nos	2		
K.10	Supply of control module with back box (ACS)	Nos	1		
K.11	Installation & configuration of FACP	Nos	1		93,295.00
K.12	Installation of FAS devices with cable & accessories	Nos	29		
K.13	Relocation of existing FAS devices with cable & accessories (SD-3)	Nos	3		
K.14	Network cabling charges	Nos	1		
K.15	Network Programming, graphics updation, testing & commissioning of FACP	Nos	1		
K.16	Supply and installation of pendant sprinkler with pipes and accessories	Nos	1		
K.17	Relocation of existing concealed pendent sprinkler with pipes & accessories	Nos	28		
K.18	Supply & installation of fire extinguisher set (5kg CO2 +4 Kg DCP)	Nos	2		
K.19	Draining & recharging of FFS	LS	1		
K.20	Certificate charges	LS	1		
K.21	EMERGENCY & EXIT LIGHT SYSTEM				
K.22	Supply & Installation of Emergency Light Concealed	Nos	17		
K.23	Supply & Installation of Exit Light Hanging	Nos	6		12,240.00
K.24	Supply & Installation of Cables & accessories	LS	1		
	Total for FF & FA Works				**105,535.00**
	L. Joinery Works				
L.1	Supply and installation of reception desk with front and side with fluted solid wood in polished finish and counter top in corian finish with LED strip lighting. Size: 1800 x 600 x 1100mmH Location: Reception 	Nos	1	11,950.00	11,950.00
L.2	Supply and installation of Pantry Counter with overhead cabinet made in 18mm thick MDF with wood veneer finish with counter top and 600mm backsplash in quartz finish. Location: Pantry Counter Size: 1990 x 600 x 900mm Back splash: 1990 x 600mmH OH Size: 1990 x 450 x 1000mmH	Nos	1	13,485.00	13,485.00

Pinnacle Interiors LLC
Dubai UAE
PO Box 47743
Tel: 04 346 6051
Fax: 04 346 6059

Name of project: NSATS Office, Office C 202 - Fit Out Works

Ref: PI/QTN - 180 A/2023

Date: 20/07/2023

L.3	Supply and installation of Coffee bar counter with overhead cabinets made in 18mm thick MDF with wood veneer finish with counter top and 600mm backsplash in quartz finish. Location: Lounge Counter Size: 3220 x 650 x 900mm Back splash: 3220 x 600mmH OH Size: 3220 x 450 x 1000mmH	Nos	1	20,610.00	20,610.00
L.4	Supply and installation of customized curved wooden Desk with top and legs made in MDF with veneer finish. Location: Demo/ Presentation room Size: 2452 x 676 x 750mmH	Nos	1	7,445.00	7,445.00
L.5	Supply and installation of customized curved wooden Desk with top and legs made in MDF with veneer finish. Location: Demo/ Presentation room Size: 8566 mm L x 570 W x 900mmH	Nos	1	20,100.00	20,100.00
L.6	Supply and installation of customized curved wooden Desk with top and legs made in MDF with veneer finish. Location: Demo/ Presentation room Size: 3827 mm L x 570 W x 1100mmH	Nos	1	10,800.00	10,800.00
L.7	Supply and installation of customized Working Desk with top and legs made in MDF with veneer finish. Location: Director 1 Size: 3220 x 700 x 750mmH	Nos	2	12,700.00	25,400.00
L.8	Supply and installation of full height Storage made in 18mm thick MDF with inside laminate and outside wood veneer finish. Location: Director 1 Storage Size: 3910 x 600 x 2400mm	Nos	1	21,450.00	21,450.00
L.9	Supply & installation of Powder Counter made in 18mm thick MDF with wood veneer finish with counter top in quartz finish. Location: Powder room Counter Size: 1445 x 500 x 500mm	Nos	1	8,000.00	8,000.00
L.10	Supply and installation of 6mm thick mirror with MDF backing and all around LED strip lighting. Location: Powder room Size: 1445 x 1500mm	Nos	1	2,865.00	2,865.00
	Total for Joinery				**142,105.00**
	TOTAL (Dhs One Million Two Hundred Thirty Four Thousand Four Hundred and Seventy Only)				AED 1,234,470.00

5% UAE VAT applicable on the Invoice Value

Notes :

1. This quote is limited to above scope of work and is a lump sum BOQ
2. Approval Fees/deposit for any Government and Non-Government Authority are excluded.
3. The power is calculated assuming that the load at site is sufficient and additional power requirement is subject to DEWA & Landlord approval.
4. Temporary Power & Water Charges - Excluded
5. Partitions considered only up to false ceiling
6. CAT6 Cabling/ CCTV/ ACS/ Telephone/ AV/ Screen/ Projector/ Video Conferencing/ Speaker - Excluded
7. The replacement or relocation of existing Building SMDB and associated cable works is not included. Considered SMDB in the same location with the same load.
8. Electrical room related Works, Cable from MDB to SMDB, DB Relocations are Excluded
9. Power Upgrade or Degrade, Meter Provision, New Meter installation, Estimation & Security Deposit Charges - Excluded
10. Server rack/ FM200 - Excluded
11. Dimmable Lights/ Dimming System/ Lighting Control panel/ Motion Sensors - Excluded
12. Grease Trap, Water Filtration system, Chlorination - Excluded
13. Dimmable Lights/ Lighting Control system - Excluded. BMS Integration - Excluded
14. Supply & Installation of Booster Pump, Circulation Pump, Drainage Pump, Water Storage Tank related Works are excluded
15. Light Fittings - Subject to approval
16. Sanitary Fittings - Subject to approval
17. Corridor area modification - Excluded
18. Pantry Appliances - Excluded
19. FORCE MAJEURE: In the event of war, earthquakes, any natural disasters or any circumstances beyond the control of Contractor, the Contractor and Client shall terminate this contract and dues will be paid in accordance with the amount of work carried out at site and/or the orders the contractor has placed incurring the cost involved.

Pinnacle Interiors LLC
Dubai UAE
PO Box 47743
Tel: 04 346 6051
Fax: 04 346 6059

Name of project: NSATS Office, Office C 202 - Fit Out Works

Ref: PI/QTN - 180 A/2023

Date: 20/07/2023

Payment Terms :

50% Advance Payment
40% Progress Payment
10% upon Final completion
Note: All invoices to be payable within 7 working days of the Invoice submission.

Validity : 30 days

Completion : To be Discussed

We hope this is in line with your requirements and looking forward to your earliest favourable response .

Regards
Joseph Charles
Managing Director
Pinnacle Interiors LLC, Dubai.

Pinnacle Interiors LLC
Dubai UAE
PO Box 47743
Tel: 04 346 6051
Fax: 04 346 6059

Name of project: NSATS Office, Office C 202 - Loose Furniture

Ref: PI/QTN - 180 B/2023

Date: 20/07/2023

Dear Sir,
We are submitting herewith our proposal for the above mentioned job as per the BOQ given below,

COST PROPOSAL

Sl no.	Description	Item	Qty	Unit Rate	Amount
	A. Partitions				
A.1	**DIRECTOR 1**				-
A.2	ELITE Executive desk with extension, wooden top & wooden panel base, polyurethane desk pad, front modesty panel, undertop storage cabinet, cable-way beam with 2 charger USB. 250x218x75cmH LAS MOBILI - ITALY	Nos	1	13,060.00	13,060.00
A.3	JERA Executive chair high backrest, with headrest, upholstered seat & back, integrated armrests, pneumatic height adjustment & tilt mechanism, aluminium base on wheels LAS MOBILI - ITALY	Nos	1	4,410.00	4,410.00
A.4	JERA Executive chair low backrest, upholstered seat & back, integrated armrests, swivel, pyramidal base LAS MOBILI - ITALY	Nos	2	3,140.00	6,280.00
A.5	ELITE Round meeting table, wooden top & metal base. 120Øx75cmH LAS MOBILI - ITALY	Nos	1	2,740.00	2,740.00
A.6	JERA Executive chair low backrest, upholstered seat & quilted back, integrated armrests, pneumatic height adjustment, aluminium base on wheels LAS MOBILI - ITALY	Nos	4	3,550.00	14,200.00

Pinnacle Interiors LLC
Dubai UAE
PO Box 47743
Tel: 04 346 6051
Fax: 04 346 6059

Name of project: NSATS Office, Office C 202 - Loose Furniture

Ref: PI/QTN - 180 B/2023

Date: 20/07/2023

A.7	TRUKA Swivel armchair, upholstered seat & back, with armrest, polyurethane foam padding and 4 star glossy aluminium base LAS MOBILI - ITALY	Nos	2	2,980.00	5,960.00
A.8	PODIO Round coffee table, wooden top & metal base with powder coated finish. 60diamx45cmH LAS MOBILI - ITALY	Nos	1	1,010.00	1,010.00
A.9	EVERY Swivel chair, upholstered seat and mesh back, 2D adjustable armrests, multilevel weight adjustment, synchronous mechanism, seat depth and lumbar support adjustment, 5 star black polyamide base on wheels. INTERSTUHL - GERMANY	Nos	4	2,550.00	10,200.00
A.10	**DIRECTOR 2**				-
A.11	IULIO Executive desk 218x100x75cmH, wooden top and wooden base with aluminium frame, front modesty panel, side service unit 140x45x62cmH, with 2 sliding doors & lock + soft-close. LAS MOBILI - ITALY	Nos	1	10,090.00	10,090.00
A.12	JOYCE JC113 High backrest swivel chair, with integrated headrest, upholstered seat & back, 3D T adjustable armrests, lockable synchronous mechanism, weight adjustment, back height adjustment, seat depth and inclination, 5 star aluminium polished base on wheels INTERSTUHL - GERMANY	Nos	1	4,230.00	4,230.00
A.13	BUDDY Visitor chair, upholstered seat & mesh back, tubular steel frame, black polyamide structure,fixed polypropylene armrest, cantilever black painted metal base, stackable upto 4 high INTERSTUHL - GERMANY	Nos	2	1,760.00	3,520.00

Pinnacle Interiors LLC
Dubai UAE
PO Box 47743
Tel: 04 346 6051
Fax: 04 346 6059

Name of project: NSATS Office, Office C 202 - Loose Furniture

Ref: PI/QTN - 180 B/2023

Date: 20/07/2023

A.14	TRUKA Swivel armchair, upholstered seat & back, with armrest, polyurethane foam padding and 4 star aluminium base LAS MOBILI - ITALY	Nos	2	2,980.00	5,960.00
A.15	PODIO Round coffee table, wooden top & metal base with powder coated finish. 60diamx45cmH LAS MOBILI - ITALY	Nos	1	1,010.00	1,010.00
A.16	**MEETING & LOUNGE**				-
A.17	OXI Round meeting table, wooden top & central metal base. 120Diax73cmH LAS MOBILI - ITALY	Nos	1	2,340.00	2,340.00
A.18	F04 Task swivel chair, upholstered padded seat, polypropylene seat and backrest, penumatic height adjustment, black base on wheels LAS MOBILI - ITALY	Nos	5	1,580.00	7,900.00
A.19	JET SET Three seater sofa, upholstered seat & back, Internal frame in poplar plywood & MDF panels, fire retardent polyurethane foam padding, powder coated metal base. 218x73x76cmH LAS MOBILI - ITALY	Nos	1	9,290.00	9,290.00
A.20	JET SET Single seater sofa, upholstered seat & back, Internal frame in poplar plywood & MDF panels, fire retardent polyurethane foam padding, powder coated metal base. LAS MOBILI - ITALY	Nos	2	5,470.00	10,940.00

Pinnacle Interiors LLC
Dubai UAE
PO Box 47743
Tel: 04 346 6051
Fax: 04 346 6059

Name of project: NSATS Office, Office C 202 - Loose Furniture

Ref: PI/QTN - 180 B/2023

Date: 20/07/2023

A.21	TRUKA Swivel armchair, upholstered seat & back, with armrest, polyurethane foam padding, 4 star glossy aluminium base. LAS MOBILI - ITALY	Nos	2	4,680.00	9,360.00
A.22	KYOTO Round coffee table, painted metal top & base. Size: 60 Dia x 37.2cmH LAS MOBILI - ITALY	Nos	2	830.00	1,660.00
A.23	**OPEN WORKSTATION**				-
A.24	OXI R Single desk Workstation Composed of 1 rectangular desk, Wooden top, metal base Pedestal included Top access & cable tray, management wire Desk:140 (L) x 70(W) x 73.6 (H)cm LAS MOBILI - ITALY 	Nos	6	3,610.00	21,660.00
A.25	EVERY Swivel chair, upholstered seat and mesh back, 2D adjustable armrests, multilevel weight adjustment, synchronous mechanism, seat depth and lumbar support adjustment, 5 star black polyamide base on wheels. INTERSTUHL - GERMANY	Nos	6	2,550.00	15,300.00
A.26	**SR. EXECUTIVE 1 & 2**				-
A.27	OXI R Executive desk, wooden top & metal base, front modesty panel, 3 drawers mobile pedestal + lock 140x80x75cmH LAS MOBILI - ITALY	Nos	2	2,900.00	5,800.00
A.28	EVERY Swivel chair, upholstered seat and mesh back, 2D adjustable armrests, multilevel weight adjustment, synchronous mechanism, seat depth and lumbar support adjustment, 5 star black polyamide base on wheels. INTERSTUHL - GERMANY	Nos	2	2,550.00	5,100.00

Pinnacle Interiors LLC
Dubai UAE
PO Box 47743
Tel: 04 346 6051
Fax: 04 346 6059

Name of project: NSATS Office, Office C 202 - Loose Furniture

Ref: PI/QTN - 180 B/2023

Date: 20/07/2023

A.29	BUDDY Visitor chair, upholstered seat & mesh back, tubular steel frame, black polyamide structure,fixed polypropylene armrest, cantilever black painted metal base, stackable upto 4 high INTERSTUHL - GERMANY	Nos	2	1,760.00	3,520.00
A.30	**DEMO/ PRESENTATION ROOM**				-
A.31	F03 Task chair, upholstered padded seat and mesh backrest, fixed armrests, polypropylene, pneumatic height adjustment, black base on wheels LAS MOBILI - ITALY	Nos	16	1,220.00	19,520.00
A.32	**RECEPTION & WAITING AREA**				-
A.33	EVERY Swivel chair, upholstered seat and mesh back, 2D adjustable armrests, multilevel weight adjustment, synchronous mechanishm, seat depth and lumbar support adjustment, 5 star black polyamide base on wheels. INTERSTUHL - GERMANY	Nos	1	2,550.00	2,550.00
A.34	TRUKA High back lounge chair, upholstered seat & back, with armrest, polyurethane foam padding, 4 wooden leg base. LAS MOBILI - ITALY	Nos	2	4,730.00	9,460.00
A.35	KYOTO Round coffee table, painted metal top & base. Size: 60Diax37.2cmH LAS MOBILI - ITALY	Nos	2	830.00	1,660.00
A.36	**PANTRY AREA**				-
A.37	OXI Round meeting table, wooden top & central metal base. 80Diax73cmH LAS MOBILI - ITALY	Nos	2	1,830.00	3,660.00

Pinnacle Interiors LLC
Dubai UAE
PO Box 47743
Tel: 04 346 6051
Fax: 04 346 6059

Name of project: NSATS Office, Office C 202 - Loose Furniture

Ref: PI/QTN - 180 B/2023

Date: 20/07/2023

A.38	F02 Four legs chair, polypropylene seat and backrest, metal tubular chromed finish, stackable MAX 8 PCS. LAS MOBILI - ITALY	Nos	4	410.00	1,640.00
	Total for Loose Furniture				**214,030.00**
	TOTAL (Dhs Two Hundred Fourteen Thousand and Thirty Only)				AED 214,030.00

5% UAE VAT applicable on the Invoice Value

Notes :

1. This quote is limited to above scope of work and is a lump sum BOQ
2. Lead Time: 75 TO 100 DAYS
3. Demo/ Presentation room Tables - Considered in Joinery scope
4. Working Desk - Considered in Joinery Scope
5. FORCE MAJEURE: In the event of war, earthquakes, any natural disasters or any circumstances beyond the control of Contractor, the Contractor and Client shall terminate this contract and dues will be paid in accordance with the amount of work carried out at site and/or the orders the contractor has placed incurring the cost involved.

Payment Terms :

50% Advance Payment
40% Upon Delivery
10% upon Installation
Note: All invoices to be payable within 7 working days of the Invoice submission.

Validity : 30 days

Completion : To be Discussed

We hope this is in line with your requirements and looking forward to your earliest favourable response .

Regards
Joseph Charles
Managing Director
Pinnacle Interiors LLC, Dubai.