AL HASHEMI - Lift Lobby

VARIATION ORDER

MDID 2575- VO 03 REV05

Project Manager: SAHDEV BHADRECHA
Project QS : UDITHA FERNANDO

Original Submission Date : **7/Mar/2025**
Revised Submission Date : **29/Jul/2025**

Contractor Details	Employer Details
Motif Interiors Mazaya Business Avenue Tower AA1 - 25th floor - Dubai,	Al Hashemi - Lift Lobby Area

VARIATION SUMMARY EXCLUDING VAT

Additonal MEP Works at Common Areas	**AED**	**216,714.00**

IMPACT ON THE CONTRACT VALUE EXCLUDING VAT

Original Contract Value	AED	950,000.00
Previously Approved Variations	AED	7,000.00
Value of this Variation	AED	216,714.00
Potential revised Contract Value	AED	1,173,714.00

ANNEXURES

Annexure 1 : Updated Variation Tracking Schedule

TIME IMPACT

Anticipated Program Impact Notification as per the contract Sub-clause 10.3 (including Product & On-Site Installation): Estimated timeframe starts from the approval of variations, samples, or drawings, whichever is later. Revised drawings and a detailed program will be issued following VO approval and acceptance..

Estimated Time Impact: 08 Weeks

APPROVED AND ACCEPTED BY

On Behalf of the Client	On Behalf of the Contractor
Date:	Date:

Additonal MEP Works at Common Areas

MDID 2575- VO 03 REV05

	DESCRIPTION	QTY.	UNIT	RATE	ADDITION	OMISSION	REMARKS
1.00	**Omission**						
1.01	Installation of light fixtures supplied by client.	(1.00)	L/s	4,455.00		(4,455.00)	
1.02	installation of Client Supplied 13A Single switched socket including pvc conduiting and wiring. (Conduit: pvc, Wire: Oman/NCI)	(5.00)	Nos	270.00		(1,350.00)	
1.03	installation of Client Supplied 13A Twinswitched socket including pvc conduiting and wiring. (Conduit: pvc, Wire: Oman/NCI)	(5.00)	Nos	270.00		(1,350.00)	
1.04	Supply and installation of Floor box with 1 No.of client supplied 13A double power socket outlet. (Conduit: PVC, Wire: Oman/NCI , Floor box: MK Ega/Davis) Note:Power modules for work station excluded.	(2.00)	Nos	713.00		(1,426.00)	
1.05	Modification of existing DB Note : Relocation is possible within the cable limit	(1.00)	Nos	600.00		(600.00)	
	Addition						
	Electrical Works						
1.00	**Basement Floors**	-					
1.01	Installation of light fixtures supplied by client.	1.00	L/s	1,035.00	1,035.00		
1.02	Supply and Installation of Light control switch	1.00	LS	1,380.00	1,380.00		
1.03	Supply and installation of 5A Single switched socket (Socket -MK/Legrand PVC white finish)	12.00	Nos	150.00	1,800.00		
1.04	Supply and installation of 13A Twin switched socket (Socket - MK/Legrand PVC white finish)	6.00	Item	200.00	1,200.00		BOQ Rate - electrical Item E.05
	Ground Floor	-					
1.05	PVC Conduiting and wiring for the light points as per new design. (Conduit:PVC , Wire: Oman/NCI) Note : All light to be supplied by client.	1.00	Nos	156.00	Rate only		BOQ Rate - electrical Item E.01
1.06	Installation of light fixtures supplied by client.	1.00	L/s	2,818.00	2,818.00		
1.07	Supply and Installation of Light control switch	1.00	LS	1,725.00	1,725.00		
1.08	Supply and installation of 5A Single switched socket (Socket -MK/Legrand PVC white finish)	10.00	Nos	150.00	1,500.00		
1.09	Supply and installation of 13A Twin switched socket (Socket - MK/Legrand PVC white finish)	3.00	Nos	200.00	600.00		
1.10	Installation of 13A Single switched socket faceplate. Note: Existing conduiting and wiring to be retained. Socket -MK/Legrand PVC white finish	1.00	Nos	120.00	120.00		
1.11	Installation of 13A Twin switched socket faceplate. Note: Existing conduiting and wiring to be retained. Socket -MK/Legrand PVC white finish	1.00	Nos	180.00	180.00		
1.12	Supply and installation of standalone type occupancy sensor	6.00	Nos	633.00	3,798.00		
1.13	PVC Containment for the thermostat.	2.00	Nos	120.00	240.00		BOQ Rate - electrical Item E.17
1.14	Modification of existing DB. Note : Relocation is possible within the cable limit	1.00	Nos	1,800.00	1,800.00		
	First Floor						
1.18	PVC Conduiting and wiring for the light points as per new design. (Conduit:PVC , Wire: Oman/NCI) Note : All light to be supplied by client.	82.00	Nos	156.00	Rate only		BOQ Rate - electrical Item E.01
1.19	Installation of light fixtures supplied by client.	1.00	L/s	4,715.00	4,715.00		
1.20	Supply and Installation of Light control switch	1.00	L/s	2,875.00	2,875.00		
1.21	Supply and installation of 5A Single switched socket (Conduit: pvc, Wire: Oman/NCI , Socket -MK/Legrand PVC white finish)	5.00	Nos	150.00	750.00		
1.22	Supply and installation of 13A Single switched socket (Conduit: pvc, Wire: Oman/NCI , Socket -MK/Legrand PVC white finish)	5.00	Nos	200.00	1,000.00		BOQ Rate - electrical Item E.04
1.23	Installation of 13A Twin switched socket faceplate. Note: Existing conduiting and wiring to be retained. Socket -MK/Legrand PVC white finish	1.00	Nos	120.00	120.00		
1.24	PVC Containment for the thermostat.	2.00	Nos	120.00	240.00		BOQ Rate - electrical Item E.17
1.25	Modification of existing DB. Note : Relocation is possible within the cable limit	1.00	Nos	1,800.00	1,800.00		
	Sub Total - Electrical Works				**29,696.00**		

Additonal MEP Works at Common Areas

MDID 2575- VO 03 REV05

	DESCRIPTION	QTY.	UNIT	RATE	ADDITION	OMISSION	REMARKS
	HVAC Works						
2.00	**Basement, Ground Floor & First Floor**						
2.01	Installation of Client supplied Thermostat and Controller.	1.00	Nos	403.00	Rate only		
2.02	Supply and Installation of factory fabricated GI duct works, 13mm thick aluminum faced polyolifin foam insulation AC Duct works,plenum boxes etc.	58.00	m2	252.00	14,616.00		BOQ Rate - HVAC Item H.11
2.03	Supply installation of 25mm thick with 16 KG/M³ density insulated flexible ducts.	12.00	BOX	222.00	2,664.00		BOQ Rate - HVAC Item H.12
2.04	Supply and installation of 38 mm width flow bar grill.	160.00	Rm	258.00	41,280.00		BOQ Rate - HVAC Item H.16
2.05	Air balancing by third party.	1.00	Item	5,175.00	5,175.00		
2.06	Final Connections , handover , Testing & Commissioning of installed system.	1.00	Nos	6,728.00	6,728.00		
	Sub Total - HVAC Works				**70,463.00**		
	FAFF Works						
3.00	**Basement, Ground Floor & First Floor**						
3.01	Relocation of existing pendant sprinkler.	37.00	Nos	780.00	28,860.00		BOQ Rate - FAFF Item FAFF.01
3.02	Supply and installation of new pendant sprinkler.	3.00	Nos	863.00	2,589.00		
3.03	Supply and installation of new upright sprinkler.	31.00	Nos	805.00	24,955.00		
3.04	Cancellation of existing pendant sprinkler.	1.00	Nos	345.00	345.00		
3.05	Testing and commissioning charges for the fire fighting system	1.00	L/s	5,750.00	5,750.00		
3.06	Certification charges for the fire fighting devices.	1.00	L/s	1,150.00	1,150.00		
3.07	Shutdown and draining charges for the fire fighting system.	1.00	Nos	3,450.00	3,450.00		
3.08	Removing and refixing of smoke detector.	16.00	Nos	518.00	8,288.00		
3.09	Supply and installation of new void smoke detector with LED indicator	13.00	Nos	1,265.00	16,445.00		
3.10	Relocation of heat detector with base.	3.00	Nos	518.00	1,554.00		
3.11	Relocation of break glass with base.	4.00	Nos	540.00	2,160.00		BOQ Rate - FAFF Item FAFF.08
3.12	Relocation of sounder with base.	4.00	Nos	540.00	2,160.00		BOQ Rate - FAFF Item FAFF.09
3.13	Isolation/ De-Isolation of fire alarm devices.	1.00	L/s	1,150.00	1,150.00		
3.14	Programming, Testing and commissioning charges for the fire alarm system	1.00	L/s	9,775.00	9,775.00		
3.15	Certification charges for the fire alarm devices.	1.00	L/s	1,150.00	1,150.00		
3.16	Removing and re fixing of emergency light.	16.00	Nos	345.00	5,520.00		
3.17	Removing and re fixing of exit light.	11.00	Nos	345.00	3,795.00		
3.18	Supply and installation of Fire extinguisher sets	6.00	Nos	690.00	4,140.00		
	Sub Total - FAFF Works				**123,236.00**		
	Civil Works						
3.19	Necessary Civil Works related to MEP works	1.00	Item	2,500.00	2,500.00		
	Sub Total - Electrical Works/HVAC Works & FAFF Works				**225,895.00**	**(9,181.00)**	
		Difference (AED) - Excl. VAT			**216,714.00**		

Payment Terms and Conditions

1 **100% Advance Payment upon Approval of this Variation**

Terms and Conditions

1 The scope of work does not include PVC conduit installation or wiring for the light points, nor any modifications to the distribution board (DB). Should the existing cables be deemed unsuitable for reuse, this will be considered as a new variation and subject to additional costs

2 We reserve the right to re-quote in the event of material change, size, quantity or specification changes.

3 This offer is valid for 30 days.

4 Pricing is based on the understanding that the work will be completed within the contract period. If work extends beyond this period, separate preliminaries will be charged as additional costs for the scope.

5 5% VAT will be added to the invoice.

AL HASHEMI - Lift Lobby

MDID 2575- VO 03 REV05

Annexure 1 : Updated Variation Tracking Schedule

Presented By:

Motif Interiors
Mazaya Business Avenue
Tower AA1 - 25th Floor - Dubai

VARIATION ORDER TRACKING SCHEDULE

Project Ref :	MDID 2575
Project Name :	AL HASHEMI - COMMON AREAS
Contractor :	MOTIF INTERIOR DECORATION LLC

Date: 30-Jul-2025

Variation No.	Description:	Rev.	First Submission Date	Revision Submission Date	Previous Submitted Value	Submitted Value	Commercial Status				Instruction Status		Time Implication (Weeks)	Status	Remarks
							Rejected Value	Pending Value	Approved Value	Payment Claims	Instructed Date	Approved Date			
1	MEP Design Charges	0	20-Feb-25			9,000.00			7,000.00				02 Weeks	Approved	
2	Metal Thresholds	0	28-Feb-25		6,348.00										
		1		4-Mar-25	5,040.00										
		2		3-Apr-25	4,485.00										
		3		21-May-25		5,658.00		5,658.00					06 Weeks	Pending	
3	Additional MEP works at lift lobby area	0	7-Mar-25		280,163.00										
		1		8-Apr-25	205,066.00										
		2		11-Jun-25	139,963.00										
		3		25-Jun-25	127,524.00										
		4		17-Jul-25	8-Jun-23										
	Additional MEP works at lift lobby area including 1st Fix	5		30-Jul-25		216,714.00		216,714.00					08 Weeks	Pending	
4	Waterproofing in common area washrooms	0	18-Mar-25			9,540.00			9,540.00			19-Mar-25	02 Weeks	Approved	
5	Glass Doors - Removing & Refixing	0	9-Apr-25		10,440.00										
		1		10-Apr-25	8,100.00										
		2		24-Apr-25		8,460.00	8,460.00							Cancelled	
6	Additinal Gypsum Cladding - Private Lift lobbies	0	17-Apr-25			11,656.00			11,656.00			5-May-25	01 Week	Approved	
7	Lux Calculation	0	23-Jul-25			5,750.00		5,750.00						Pending	
						266,778.00	**8,460.00**	**228,122.00**	**28,196.00**	**-**					

Main Contract Value	**950,000.00**
Approved Variations	28,196.00
Pending Variations	228,122.00
Anticipated Final Contract Value	**1,206,318.00**

Total No of VOs	**6.00**
Approved VOs	**3.00**
Instructed VOs	**-**
Pending VOs	**3.00**