PROPOSED INTERIOR FITOUT WORKS AT

AMALGAMA MANAGEMENT SERVICES DMCC, JUMEIRAH TOWERS

DUBAI, UAE

Interiors

16.12.2024

DATE : 16/12/2024

Subject : Commercial Proposal for Interior Fit-out works

PROJECT : AMALGAMA MANAGEMENT SERVICES DMCC, JUMEIRAH TOWERS - DUBAI, UAE

We are pleased to present our proposal for your review against the Fit-out works for **AMALGAMA MANAGEMENT SERVICES DMCC, JUMEIRAH TOWERS - DUBAI, UAE.** Please find herewith our competitive offer as per the attached bill of quantities amounting as below.

GRAND TOTAL FROM SUMMARY		**1,125,458.00**
	VAT 5%	56,272.90

GRAND TOTAL FROM SUMMARY - VALUE ENGINEERING OPTION		**1,020,334.00**
	VAT 5%	51,016.70

Completion : to be discussed.

Validity : 20 days from the date above.

Payment terms :
50% Advance against LPO,
40% Progressive Progress payment.
10% on Completion.

Notes & exclusion –As per Notes and exclusions sheet.

Thank you for the opportunity to participate in this tender. If you have any questions, please don't hesitate to get in contact with us. we hope our offer is in line with your requirement and look forward to working with you directly.

Thank you and best regards,

Chris Service
Managing Director | CS Interiors

DATE : 16/12/2024

Subject : Commercial Proposal for Interior Fit-out works

PROJECT :AMALGAMA MANAGEMENT SERVICES DMCC, JUMEIRAH TOWERS - DUBAI, UAE

NOTES AND EXCLUSIONS

General Notes

1 Submitted BOQ is based on the layout, site visit & instructions

2 Any changes to the work, pertaining to the instructions from mall management/authorities/employer will have an additional cost implication and to be agreed upon finalizing of details.

Exclusions

1 Any scope related to non scope of areas.

2 Any scope not mentioned in BOQ

3 Printer

FITOUT WORK AT AMALGAMA MANAGEMENT SERVICES DMCC, JUMEIRAH TOWERS
DUBAI, UAE

		16/12/2024
Sl NO.	**DESCRIPTION**	**AMOUNT**
1	PRELIMINARIES	65,500.00
2	DEMOLITION AND CIVIL WORKS	4,470.00
3	FLOOR WORKS	79,156.00
4	WALLS AND WALL FINISHES	59,151.00
5	CEILING WORKS	69,943.00
6	DOORS	13,755.00
7	GLASS WORKS	57,110.00
8	TV AND VIDEO CONFERENCING SYSTEM	16,652.00
9	LIGHT FITTINGS	30,000.00
10	BLINDS	12,198.00
11	PANTRY APPLIANCES	6,374.00
12	TOILET SANITARY WARES	6,480.00
13	LOGO AND SIGNAGE	12,000.00
14	ARTIFICIAL PLANTS	10,000.00
15	IT WORKS	20,000.00
16	LOOSE FURNITURE	119,769.00
17	JOINERY WORKS	310,070.00
18	MEP WORKS	232,830.00
	Total Amount (Excluding VAT)	**1,125,458.00**
	VAT 5%	**56,272.90**

Interiors

FITOUT WORK AT AMALGAMA MANAGEMENT SERVICES DMCC, JUMEIRAH TOWERS DUBAI, UAE

					16/12/2024
Sl NO.	**DESCRIPTION**	**QTY**	**UNIT**	**RATE**	**AMOUNT**
1.00	**PRELIMINARIES**				
1.01	**SITE MANAGEMENT** Provision for site management, including staff and facilities necessary for the efficient execution and supervision of the works.	1	Item	18,000.00	18,000.00
1.02	**MOBILIZATION & DEMOBILIZATION** Allow sum for mobilization & demobilization including supply and installation of temporary DB,Hoarding, adequate lighting, fire fighting equipment / extinguishers, cleaning / clearing of site on daily basis & upon project completion and provision for protection of finished goods, site safety, First Aid kits as well as security.	1	Item	8,500.00	8,500.00
1.03	**AUTHORITY APPROVALS** Obtaining and maintaining necessary permits, licenses, and approvals from the Developer and other deposits .	1	Item	12,000.00	12,000.00
a	Fees for local authority approvals for complete approval process from Civil defence, Tecom, DEWA and Dubai municipality.	1	Item	-	**Actual By Client**
b	Payment and Deposit	1	Item	-	**Actual By Client**
c	Allow sum for building management approval-fees for drawing approvals as listed in the tenants manual.	1	Item	-	**Actual By Client**
1.04	**INSURANCE** Provision of all required insurance policies, including but not limited to public liability, employer's liability, and contract works insurance, as per the contract requirements.	1	Item	3,500.00	3,500.00
1.05	**HEALTH & SAFETY PROTECTION** Implementation of health and safety measures, including site inductions, provision of personal protective equipment (PPE), first aid facilities, fire prevention equipment, and site security measures in accordance with applicable regulations and standards.	1	Item	4,000.00	4,000.00
1.06	**SITE CLEARANCE** Clearing and removal of all debris, vegetation, and existing structures from the site, including the disposal of waste materials in accordance with legal requirements and best practices.	1	Item	3,000.00	3,000.00
1.07	**TEMPORARY WATER & ELECTRICITY** Provision and maintenance of temporary water and electricity supplies for the site, including connections, distribution, and metering, as required for the construction works.	1	Item	-	**By Client**

1.08	**SHOP DRAWING** Preparation, submission, and coordination of detailed architectural and MEP shop drawings in accordance with the design specifications and applicable standards, incorporating any revisions and obtaining necessary approvals from the relevant authorities and consultants.	1	Item	8,000.00	8,000.00
1.09	**SCAFFOLDING** Permanent scaffolding provided for this project.	1	Item	6,000.00	6,000.00
1.10	**FINAL CLEANING** Carrying out a thorough final cleaning of the entire project site, including the removal of construction debris, dust, and any leftover materials. The cleaning process should cover all internal and external areas, ensuring that the completed facility is in a clean and presentable condition, ready for handover to the client.	1	Item	2,500.00	2,500.00
				SUB TOTAL CARRIED TO SUMMARY	**65,500.00**
2.00	**DEMOLITION AND CIVIL WORKS**				
2.01	**DEMOLITION** Demolish and cart away of existing interior elements including Existing floor tiles in Toilets and Pantry area joinery elements.	1	Psum	4,470.00	4,470.00
				SUB TOTAL CARRIED TO SUMMARY	**4,470.00**

3.00	**FLOOR WORKS**				
3.01	**SCREED** Supply and installation of 100mm ht Concrete screed to receive final floor finishes. Location: All area except the Toilet and Pantry	238	Sqm	94.00	22,372.00
3.02	**SELF LEVELING** Provision for the modifiction of existing floor substate and self leveling to receive floor finish. Location: All area except the Toilet and Pantry	238	Sqm	75.00	17,850.00
3.03	**CARPET FLOOR** Supply and installation of 50 X 50 carpet tile flooring including underlay, adhesives, and other fixing accessories as per the requirement. Location: Workstations, MD Cabin, Meeting Room, Cabin 01 & 02, Conference Room, Server room and POD.	172	Sqm	140.00	24,080.00
3.04	**LVT FLOOR** Supply and installation of LVT flooring including the glue or other fixing materials as per requirement. Location: Corridor, Pantry and Waiting area	66	Sqm	147.00	9,702.00
3.05	**PORCELAIN TILE** Supply and installation of 60 X 60 porcelain tile flooring including the glue or other fixing materials as per requirement. Location: Toilets	7	Sqm	212.00	1,484.00
3.06	**WATERPROOFING** Supply and installation of Cementitious Water proofing. Location: Toilet and Pantry	16	Sqm	74.00	1,184.00
3.07	**FLOOR TRIM** Supply and installation of metal floor installation profiles at various floor finishes. All work will be executed in compliance with industry standards and manufacturer's recommendation.	25	Rm	78.00	1,950.00
3.08	**THRESHOLDS** Supply and install polished marble thresholds at specified locations for seamless transitions between different flooring materials. Location: Toilet area	2	Nos	267.00	534.00
				SUB TOTAL CARRIED TO SUMMARY	**79,156.00**

4.00	**WALLS AND WALL FINISHES**				
4.01	**WATERPROOF COMPOSITE SKIRTING** Supply and installation of 100mm thick Waterproof composite skirting, PU painted to the desired color. All work will be executed in compliance with industry standards and manufacturer's recommendations.	95	Rm	47.00	4,465.00
4.02	**GYPSUM PARTITION** Supply and installation of Gypsum wall partition - 15cm thick - GI stud and track framing system. Height: 3m Location: As per the proposed layout	75	Sqm	154.00	11,550.00
4.03	**GYPSUM BAFFLE** Supply & installation of gypsum Baffle over glass (300mm) partition with necessary fittings. Location: Above the glass partition	6	Rm	107.00	642.00
4.04	**GYPSUM WALL STRUCTURE WITH ARCH SHAPE NICHE** Provision for Supply and installation of Gypsum wall Structurre including the Arch shape niche as per the requirements. Size : 2500mm L x 2700mm H Location : Waiting area	1	Item	9,168.00	9,168.00
4.05	**GPSUM WALL STRUCTURE** Provision for supply and installation of Gpsum wall structure. Size : 1000mm L x 100mm x 2700mm H Location : Conference Room	1	Item	3,600.00	3,600.00
4.06	**FENOMASTIC PAINT** Supply and apply of Jotun fenomastic Wall paint inlcuding the base coats. Location : All rooms except the Conference room and meeting room	341	Sqm	38.00	12,958.00
4.07	**TEXTURE PAINT** Supply and Apply two coats of concrete texutre paint with all necessary base coats to Walls. Location: As per the proposed layout	17	Sqm	38.00	646.00
4.08	**WRITABLE GLASS** Supply and Installation of Writable glass as per the requirements. Height: 1.5m H Location: Conference room	10	Sqm	1,167.00	11,670.00
4.09	**WALL TILE** Supply and installation of 60 X 60 porcelain tile on the wall including the glue or other fixing materials as per requirement. Height considered: 1.5m Location: Toilets	21	Sqm	212.00	4,452.00
				SUB TOTAL CARRIED TO SUMMARY	**59,151.00**

5.00	**CEILING WORKS**				
5.01	**GYPSUM CEILING** Supply and installation of 12.5mm thick regular gypsum board ceiling on GI suspension system. Location : All area	250	Sqm	140.00	35,000.00
5.02	**CEILING PAINT:** Supply and application of Jotun fenomastic Ceiling paint inlcuding the base coats. Location: Gypsum ceiling	250	Sqm	38.00	9,500.00
5.03	**BULKHEAD** Supply and Installation of bulkhead including as per requirements. Location: Corridor, Conference room and Waiting area	39	Rm	127.00	4,953.00
5.03	**CEILING COVE** Supply and Installation of ceiling cove as per requirements. Location: Workstation	36	Rm	120.00	4,320.00
5.04	**CEILING COVE LIGHT** Supply and Installation of LED light on the ceiling area as per requirements. Location: Workstation, Conference room and Waiting area	110	Rm	147.00	16,170.00
				SUB TOTAL CARRIED	**69,943.00**
6.00	**DOORS**				
6.01	**FR DOORS INCLUDING IRONMONGERY** Supply and installation of Fire Rated double door, 1.2mm thick galvanized steel sheets, 45mm thick doors honeycomb infill and 1.5mm thick galvanized steel sheets frame up to 200mm jamb depth. Plyester polyester coating - Non Mertallic colour. Size: 1.8m L x 2.2m H Location :Main entrance door	1	Nos	5,715.00	5,715.00
6.02	**WOODEN DOOR** Fabrication, Supply and installation of single leaf single swing door made of semi solid shutter with all laminate finish. Door frame and architrave solid wood with PU polish finish including ironmongery. Size: 0.9m L x 2.4m H Location: Server room	1	Nos	3,770.00	3,770.00
6.03	**GLASS DOOR WITH WOODEN FRAME** Supply and installation of single leaf single swing glass door with wooden frame including ironmongeries and handle. Size: 0.9m L x 2.4m H Location: Conference room	1	Nos	4,270.00	4,270.00
				SUB TOTAL CARRIED TO SUMMARY	**13,755.00**

7.00	**GLASS WORKS**				
7.01	**ACOUSTIC SINGLE GLAZED PARTITIONS** Supply and installation of Single glazed partitions using 12mm thick normal clear tempered glass panel in Silicone glass to glass joints. channels: 26x26mm top, bottom and wall aluminium channels. All aluminium sections are in Standard Powder Coated Finish. (Upto 33 dB) Height: 2.7m Location **:** Meeting room, Conference room, MD Cabin, Cabin 1 & 2 and POD	33	Sqm	670.00	22,110.00
7.02	**ACOUSTIC GLASS DOOR** Supply and installation of Framed Axile Clarity single glazed swing door in 12mm thick normal clear tempered glass door panel with complete ironmongeries and accessories; top & bottom quad pivot, Standard 90 degree hold open floor spring, threshold plate, Standard 600mm long non lockable H type pull handle, Slimline profile and Oval door stop. All aluminium door frame and hardware's are in Standard Powder Coated Finish. (Upto 32 dB) Size: 0.9m L X 2.7m H Location : Office, meeting, conference rooms	5	Nos	7,000.00	35,000.00
				SUB TOTAL CARRIED TO SUMMARY	**57,110.00**

8.00	**TV AND VIDEO CONFERENCING SYSTEM**				
8.01	Supply and Installation of 85" TV Brand: Samsung Location: Meeting room and Conference room	2	Nos	4,473.00	8,946.00
OPTION	Supply and Installation of 65" TV Brand: Samsung Location: Manager cabins (The added cost is for a one TV)	3	Nos	3,449.00	**OPTION**
8.02	Supply and Installation of Group Video conferencing system with Expansion Mics. Brand: Logitech Location: Meeting room and Conference room	2	Nos	3,853.00	7,706.00
				SUB TOTAL CARRIED TO SUMMARY	**16,652.00**
9.00	**LIGHT FITTINGS**				
9.01	Provision for new light fittings.	1	Psum	30,000.00	30,000.00
				SUB TOTAL CARRIED TO SUMMARY	**30,000.00**
10.00	**BLINDS**				
10.01	**MANUAL BLINDS** Supply and installation of manual window Blinds as per the requirements.	114	Sqm	107.00	12,198.00
OPTION	Supply and installation of Motorized window Blinds as per the requirements. Location: Conference room	1	Item	5,000.00	**OPTION**
				SUB TOTAL CARRIED TO SUMMARY	**12,198.00**
11.00	**PANTRY APPLIANCES**				
11.01	Provision for supply of pantry area appliances Including: **Microwave oven - 1 Nos** **Fridge - 1 Nos** **Coffee machine - 1 Nos** **Sink and Tap - 2 Nos**	1	Item	6,374.00	6,374.00
				SUB TOTAL CARRIED TO SUMMARY	**6,374.00**

12.00	**TOILET SANITARY WARES**				
12.01	WC with seat cover - White	2	Nos	1,682.00	3,364.00
12.02	Shattaf - Chrome	2	Nos	107.00	214.00
12.03	Toilet roll holder - Chrome	2	Nos	150.00	300.00
12.04	Wash basin - White	2	Nos	488.00	976.00
12.05	Wash basin mixer - Chrome	2	Nos	813.00	1,626.00
				SUB TOTAL CARRIED TO SUMMARY	**6,480.00**
13.00	**LOGO AND SIGNAGE**				
13.01	**SIGNAGE** Provision for required any signage works. (Please Note, This price considered only as a psum. Need more details for actual price. Price will vary when the design finalized	1	Psum	12,000.00	12,000.00
				SUB TOTAL CARRIED TO SUMMARY	**12,000.00**
14.00	**ARTIFICIAL PLANTS**				
14.01	Provision for the required Artificial planting works. (Not including planter box)	1	Psum	10,000.00	10,000.00
				SUB TOTAL CARRIED TO SUMMARY	**10,000.00**
15.00	**IT WORKS**				
15.01	Provision for the IT Works including Data, Wifi, Access control and Finger print	1	Psum	20,000.00	20,000.00
				SUB TOTAL CARRIED TO SUMMARY	**20,000.00**
				TOTAL	**462,789.00**

Interiors

FITOUT WORK AT AMALGAMA MANAGEMENT SERVICES DMCC, JUMEIRAH TOWERS
DUBAI, UAE

						16/12/2024
Sl NO.	**DESCRIPTION**	**IMAGES**	**QTY**	**UNIT**	**RATE**	**AMOUNT**
	LOOSE FURNITURE	**UNIT -01**				
	MEETINE ROOM					
1.00	customize manager desk 180x160 MDF laminated top and leg 36mm with side table with drawers and shelves modesty panal with wire box and cable management color : as agree		1	Nos	822.00	822.00
2.00	**Marics White Task Chair** Award winning lightweight task chair with a fully integrated reclining mechanism. The chair has a 19° reclining mechanism, nylon arms and frame, wintex fabric back and seat, and height-adjustable mechanism. Warranty: 3 Years Size: W59 x D54 x H85-105 cm Frame: Light Gray		4	Nos	843.00	3,372.00
	WAITING AREA					
3.00	**Lounge Chair** Minimalist rounded design, ideal office seating in lounge area. With soft materials and cushioned seat, this chair provides comfort and relaxed atmosphere in the office. It has black powdered coated base that gives the chair a contemporary character, quite the opposite of its generous padding that invites you to sit back and relax .Color: (Color to be confirmed) Base: Black Size: W73 x D52 x H62 cm		1	Nos	1,215.00	1,215.00
4.00	**Vino Round Coffee Table** Aesthetic chamfered veneer coffee table with a design of simple lines steel tube base with full round seamless end caps. The table top diameter is 50cm made up of plywood red oak veneer, oiled finished with natural color and the height is 50.5cm. Size: Dia 50 x H50.5cm Table Top: Starke® Pro Black		1	Nos	786.00	786.00
5.00	**Back task chair** Product Code- JUN90HA - Mesh Back Task Chair on a Synchronised Mechanism with Height Adjustable Arms Arm Pad- ST - Standard Fabric Price Band- C1+ - Class 1+ Frame Finish- BLK - Black Castor/Glide Type- HWC - Hard Wheel Castors Mesh Back Finish- BLK - Black Seat Depth Adjustment- 50S - 50mm Seat Depth AdjustmentSize- 590mm L x 540mm W x 900mm H		1	Nos	629.00	629.00

	WORKSTATIONS					
6.00	**PYRAMID - CLUSTER OF 6 FACE TO FACE :** Product Features: - Top Made Of 25mm thick (MDF MELAMINE FINISH) - Durable table legs manufactured in powder coated steel in white and silver finish. - Mobile pedistal 3Drawer - Colour: ANY COLOR W140 x D60 x H75 cm.		1	Nos	9,272.00	9,272.00
7.00	**PYRAMID - CLUSTER OF 4 FACE TO FACE :** Product Features: - Top Made Of 25mm thick (MDF MELAMINE FINISH) - Modesty Panel Wood or Metal - Durable table legs manufactured in powder coated steel in white and silver finish. - Mobile pedistal 3Drawer - Colour: ANY COLOR W140 x D60 x H75 cm.		3	Nos	6,443.00	19,329.00
8.00	**MEDIUM BACK CHAIR:** Black frame, Seat fabric and back mesh, adjustable armrest, aluminium base & nylon castors		18	Nos	600.00	10,800.00
9.00	**Lounge Stool** Fashionable and playful designer stool with different sizes that can be adapted to multiple uses. It can be scattered freely in the office space or placed in groups of three or two. Size: Medium W60 x H43 cm Fabric Color:(Color to be confirmed)		2	Nos	800.00	1,600.00
10.00	**ECO Planter Cabinet Black with Lockable Push Open Doors** ECO Planter Cabinets are the perfect alternative for traditional storage solutions in office spaces. Providing a large storage capacity in independent lockable compartments with adjustable shelves, ECO cabinets can be also used as green space seperators in open office plans. Finish: Starke® Germany Natural Pacific Walnut Body: Black Cabinet Doors: Swing Doors Size: W150 x D35 x H122 cm		4	Nos	2,719.00	10,876.00

	MD CABIN					
11.00	customize manager desk 180x160 MDF laminated top and leg 36mm with side table with drawers and shelves modesty panal with wire box and cable management color : as agree		1	Nos	3,536.00	3,536.00
12.00	HIGH BACK CHAIR,BLACK PU UPH,ALUMARMREST WITH PU PAD,ALU-BASE+PU CASTERSBLACK, MEC-UP AND DOWN TITLTING/LOCKABLE FUNCATION		1	Nos	1,136.00	1,136.00
13.00	VISITOR CHAIR,BLACK PU UPH,CHORMARMREST WITH PU PAD,CHROME CNDLRBASE, BLACK		2	Nos	1,072.00	2,144.00
14.00	**KOZE THREE SEATER** Frame :Plywood and Flexible Woods, Chrome legs Seat & Back:Upholstered seat & back Finish : Available in multiple stain colours size: L187(+/-) x D71(+/-) x H88(+/-)		1	Nos	2,436.00	2,436.00
15.00	**Single Seater SOFA**		1	Nos	1,215.00	1,215.00
16.00	**coffee table 60DIA with 45 H**		2	Nos	1,000.00	2,000.00

	CABIN 01					
17.00	customize manager desk 180x160 MDF laminated top and leg 36mm with side table with drawers and shelves modesty panal with wire box and cable management color : as agree		1	Nos	3,536.00	3,536.00
18.00	HIGH BACK CHAIR,BLACK PU UPH,ALUMARMREST WITH PU PAD,ALU-BASE+PU CASTERSBLACK, MEC-UP AND DOWN TITLTING/LOCKABLE FUNCATION		1	Nos	1,136.00	1,136.00
19.00	VISITOR CHAIR,BLACK PU UPH,CHORMARMREST WITH PU PAD,CHROME CNDLRBASE, BLACK		2	Nos	1,072.00	2,144.00
	CABIN 02					
20.00	customize manager desk 180x160 MDF laminated top and leg 36mm with side table with drawers and shelves modesty panal with wire box and cable management color : as agree		1	Nos	3,536.00	3,536.00
21.00	HIGH BACK CHAIR,BLACK PU UPH,ALUMARMREST WITH PU PAD,ALU-BASE+PU CASTERSBLACK, MEC-UP AND DOWN TITLTING/LOCKABLE FUNCATION		1	Nos	1,136.00	1,136.00
22.00	VISITOR CHAIR,BLACK PU UPH,CHORMARMREST WITH PU PAD,CHROME CNDLRBASE, BLACK		2	Nos	1,072.00	2,144.00

	CONFERENCE ROOM					
23.00	**Diamond Modern Meeting Table** Contemporary conference table with an unconventional steel base, powder coated in white or black color. The tabletop is Rectangular or Oval-shaped, produced with high-quality 36mm MFC boards and available in a wide range of finishes. This meeting table includes a Brushed aluminum rectangular grommet, a Horizontal underdeck cable management tray with a Double channel cable management spine. Worktop Finish: Starke® Germany Natural Pacific Walnut Frame Color: Powder Coated Black Cable Management: Rectangular Grommet Dimension: W420 x D120 cm		1	Nos	11,290.00	11,290.00
24.00	**Marics White Task Chair** Award winning lightweight task chair with a fully integrated reclining mechanism. The chair has a 19° reclining mechanism, nylon arms and frame, wintex fabric back and seat, and height-adjustable mechanism. Warranty: 3 Years Size: W59 x D54 x H85-105 cm Frame: Light Gray		12	Nos	843.00	10,116.00
	DRY PANTRY					
25.00	**coffee table 60DIA with 45 H**		1	Nos	1,000.00	1,000.00
26.00	**Shell Padded Modern Bar Stool** Fully Upholstered Bentwood Seat Structure. Black Powder Coated Steel Frame. Padded Leather Seat. Upholstery Material: Genuine Leather LeatherColor: Black BlackFrame Base: Black Powder Coated Size-450mm L x 450mm w x1035mm H		3	Nos	772.00	2,316.00
27.00	**plastic dining chair black color with fabric seat**		3	Nos	315.00	945.00
	PH POD					
28.00	**KOZE THREE SEATER** Frame :Plywood and Flexible Woods, Chrome legs Seat & Back:Upholstered seat & back Finish : Available in multiple stain colours size: L187(+/-) x D71(+/-) x H88(+/-)		2	Nos	2,436.00	4,872.00
29.00	**coffee table 60DIA with 45 H**		1	Nos	1,000.00	1,000.00

	CORRIDOR					
30.00	**Lounge Chair** Minimalist rounded design, ideal office seating in lounge area. With soft materials and cushioned seat, this chair provides comfort and relaxed atmosphere in the office. It has black powdered coated base that gives the chair a contemporary character, quite the opposite of its generous padding that invites you to sit back and relax .Color: (Color to be confirmed) Base: Black Size: W73 x D52 x H62 cm		2	Nos	1,215.00	2,430.00
31.00	**coffee table 60DIA with 45 H**		1	Nos	1,000.00	1,000.00
					SUB TOTAL CARRIED TO SUMMARY	**119,769.00**

Interiors

FITOUT WORK AT AMALGAMA MANAGEMENT SERVICES DMCC, JUMEIRAH TOWERS DUBAI, UAE

					16/12/2024
Sl No	**Item Description**	**Qty**	**Unit**	**Rate**	**Amount**
1	**JOINERY WORKS**				
	LOUNGE/WAITING AREA				
1.01	**Supply and installation of Reception Counter-** Structure in plywood and Solid White Wood. Carcass, Shelf in 18mm thick White Melamine MDF with PVC edge Lipping. Shutters in 18mm thick MDF with Oak Veneer Natural / Stained Finish as per approved sample. Front Side in Superior Polyurethane Product. Top in Quartz Stone. Size- 2000mm L x 900mm D x 750/1100 mm H.	1	Nos	8,620.00	8,620.00
1.02	**Wooden Wall Cladding-** Supply and installation of Wooden Wall Cladding in 18mm thick MDF with Oak Veneer Natural / Stained Finish as per approved sample. Including Necessary Split Battens. Size- 3300+2000mm L x 2700mm H.	15	Sqm	925.00	13,875.00
1.03	**Ribbed Wooden Wall Cladding and CNC Cut MDF Design-** Supply and installation of Wooden Wall Cladding in 18mm thick MDF with Oak Veneer Natural / Stained Finish as per approved sample. Including Necessary Split Battens. Size- 3000mm L x 2700mm H.	9	Sqm	1,155.00	10,395.00
1.04	**CNC Cut MDF Design with Back Light-** Supply and installation of CNC Cut MDF Design with PU Paint Finish as per approved sample. Including Necessary Split Battens and LED Strip Lights.	1	Item	8,620.00	8,620.00
	SERVER/STORAGE				
1.05	**Supply and installation of Storage Shelving Unit-** Carcass, Shelf in 18mm thick White Melamine MDF with PVC edge Lipping. Shutters in 18mm thick MDF with Oak Veneer Natural / Stained Finish as per approved sample. Size- 1900mm L x 2700mm H x 600 mm D.	1	Nos	7,105.00	7,105.00
	CONFERENCE ROOM 12 PAX				
1.06	**Column Wooden Wall Cladding-** Supply and installation of Wooden Wall Cladding in 18mm thick MDF with Oak Veneer Natural / Stained Finish as per approved sample. Including Necessary Split Battens. Size- 1000mm L x 2700mm H.	5	Nos	2,700.00	13,500.00
1.07	**Wooden TV Wall-** Supply and installation of Wooden TV Wall. Structure in White Wood and Ply Wood. Panel in 18mm thick MDF with Oak Veneer Natural / Stained Finish as per approved sample. Including Necessary Supports. Size- 2000mm L x 2700mm H.	1	Nos	11,220.00	11,220.00
1.08	**Wooden Planter Box-** Supply and installation of Wooden Planter Box. In 18mm thick MDF with Oak Veneer Natural / Stained Finish as per approved sample. Including Necessary Supports. Excluding Plant. Size- 1300mm L x 450mm W x 1200mm H.	1	Nos	3,800.00	3,800.00
1.09	**Wooden Ceiling Cladding-** Supply and installation of Wooden Wall Cladding in 12mm thick MDF with Oak Veneer Natural / Stained Finish as per approved sample. Including Necessary Supports. Size- 4000mm L x 2400mm W.	1	Nos	16,985.00	16,985.00
	PH POD				

1.10	**Supply and installation of Wall Fabric Cladding-** Supply and installation of fabric wall cladding panels. We have considered 10mm thick foam cladded on MDF with Fabric Finish. Acoustic requirements not considered. Color- as per selection from Catalog.	21	Sqm	650.00	13,650.00
	CABIN 01 & 02				
1.11	**Supply and installation of Wooden Low Height Storage Cabinet -** Carcass, Shelf in White Melamine MDF with PVC Lipping on exposed areas and Shutters in 18mm thick MDF with Oak Veneer Natural / Stained Finish as per approved sample. Size-2200mm L x 1200mm H x 450mm D.	2	Nos	4,910.00	9,820.00
	MEETING ROOM				
1.12	**Wooden TV Wall-** Supply and installation of Wooden TV Wall. Structure in White Wood and Ply Wood. Panel in 18mm thick MDF with Oak Veneer Natural / Stained Finish as per approved sample. Including Necessary Supports. Size- 3600mm L x 2700mm H.	1	Nos	19,145.00	19,145.00
	MD CABIN				
1.13	**Supply and installation of Wooden Full Height Display/Storage Cabinet -** Carcass, Shelf and Shutters in 18mm thick MDF with Oak Veneer Natural / Stained Finish as per approved sample. Including jumbo size Porcelain Tile Cladding on Back Wall. Size-2200mm L x 2700mm H x 450mm D.	1	Nos	19,555.00	19,555.00
	DRY PANTRY				
1.14	**Supply and installation of Pantry unit-** Carcass, shelf and Drawer Box in White MR Melamine MDF with PVC edge Lipping. Shutters, Drawer Fascia, Open Shelf in MR MDF with PU Paint or Oak Veneer Natural/Stained as per approved sample. including LED Strip Light, Including Porcelain Tile Counter top. Excluding all appliance. Base Unit Size- 2100mm L x 600mm D x 900mm H Wall Unit Size- 2100mm L x 300mm D x 1000mm H	1	Nos	14,245.00	14,245.00
1.15	**Supply and installation of Ledge Table-** In Plywood and Metal angle supports. Top in Porcelain Tile Counter top. Size- 2100mm L x 600mm D x 750mm H.	1	Nos	6,215.00	6,215.00
1.16	**Supply and installation of Wooden Slates Screen-** In 18mm thick MDF with Oak Veneer Natural/Stained as per approved sample. Total 10 slats of Size 50 x 100mm. Height 2700mm. Including Base & top Metal Support.	1	Nos	14,125.00	14,125.00
	EX PANTRY				
1.17	**Supply and installation of Pantry unit-** Supply and installation of Pantry unit Carcass, shelf and Drawer Box in White MR Melamine MDF with PVC edge Lipping. Shutters, Drawer Fascia, Open Shelf in MR MDF with PU Paint or Oak Veneer Natural/Stained as per approved sample. including LED Strip Light, Including Porcelain Tile Counter top. Excluding all appliance. Base Unit Size- 1500mm L x 600mm D x 900mm H Wall Unit Size- 1500mm L x 300mm D x 1000mm H	1	Nos	12,045.00	12,045.00
	EX TOILET				
1.18	**Vanity Counter-** Supply and installation of vanity counter made of 18 mm MDF with necessary metal support and Porcelain Tile Counter top. Bottom shelve MR MDF with Oak Veneer Natural/Stained as per approved sample. Size: 800 mm L x 600mmD x 600mm H	2	Nos	3,970.00	7,940.00
1.19	**Vanity Mirror-** Supply and installation of 6mm thick mirror with 18mm MDF Backing and SS Metal Trim. Size: 800mm L x 1500 mm H	2	Nos	1,925.00	3,850.00
	WORK STATIONS AREA				

1.20	**Supply and installation of Wooden Slates Screen and Ceiling-** In 18mm thick MDF with Oak Veneer Natural/Stained as per approved sample. Total 18 slats of Size 50 x 100mm. Height 2700mm. Including Base & top Metal Support.	1	Nos	26,920.00	26,920.00
1.21	**Wooden Planter Box with Storage-** Supply and installation of Wooden Planter Box. Carcass, Shelf in White Melamine MDF with PVC Lipping on Exposed edges. Shutters and exposed area in 18mm thick MDF with Oak Veneer Natural / Stained Finish as per approved sample. Including Necessary Supports. Excluding Plant. Size- 1600mm L x 450mm W x 1200mm H.	4	Nos	5,910.00	23,640.00
1.22	**Supply and installation of Over Head Cabinet (Above Printer)-** Carcass, shelf and Shutter in 18mm thick MDF with Oak Veneer Natural/Stained as per approved sample. Size- 1500mm L x 600mm D x 1200mm H.	1	Nos	2,635.00	2,635.00
1.23	**Supply and installation of Wooden Storage Cabinet -** Carcass, Shelf in White Melamine MDF with PVC Lipping on exposed areas and Shutters and exposed area in 18mm thick MDF with Oak Veneer Natural / Stained Finish as per approved sample. Size- 4200mm L x 2700mm H x 500mm D.	1	Nos	20,065.00	20,065.00
	CORRIDOR				
1.24	**Wooden Ceiling Slates-** Supply and installation of Wooden Slates Ceiling Fixed with Suspended Metal Rod- In 12mm MDF made to size 40 x 100mm with BODAQ wrapping Finish. Maximum Length will be 2400mm Length. (Acoustic requirements not considered).	26	Sqm	850.00	22,100.00
	TOTAL CARRIED TO SUMMARY				**310,070.00**

Interiors

PROPOSED MEP WORKS FOR AMALGAMA MANAGEMENT SERVICES DMCC, JUMEIRAH TOWERS DUBAI, UAE

16/12/2024

SI NO.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	MEP WORKS				
1.00	**ELECTRICAL WORK**				
	Sub Main Distribution Boards (MDB/SMDB/DB)				
1.001	Modification of DBs	1	Nos.	4,546.00	4,546.00
1.002	Temporary power service and lights for construction Note:- Any additional charge from DEWA / FM team to be paid by client	1	Item	1,949.00	1,949.00
1.003	Approval Note:- Any additional charge from the DEWA / FM team is to be paid by the client We have assumed that DEWA approval is not required if required we have add in the cost	1	Item	5,845.00	Rate Only
	Note: We have excluded the Power upgradation Additional payment by the client Main armoured cable				
	Containment				
1.004	**HDGI Cable tray and trunking including necessary supports, accessories etc. all in accordance with the drawings** H/L and L/L Cable trunking for Lighting & Power	1	Item	4,676.00	4,676.00
	Supply and Install power points with PVC Conduits, PVC Wiring, containment & accessories including final termination for the following as per the drawings, specification and regulations.				
1.005	13A Switch socket, Twin white PVC	8	Nos.	377.00	3,016.00
1.006	13A Switch socket, Single white PVC	6	Nos.	286.00	1,716.00
1.007	Floor box (2 Twin socket and 4 data)	14	Nos.	650.00	9,100.00
1.008	HDMI point for TV point	3	Nos.	325.00	975.00
1.009	Power for server rack	2	Nos.	390.00	780.00
1.010	power isolator for Coffice machine	1	Nos.	520.00	520.00
1.011	Power for Dry Pantry equipments	6	Nos.	520.00	3,120.00
1.012	Power for Wet Pantry equipments	2	Nos.	521.00	1,042.00
1.013	16A SPN isolator with Timer for Signages	2	Nos.	520.00	1,040.00
	Supply and install Lighting power points with Wiring, PVC Conduiting & final circuit PVC wiring including termination for the followings - (Supply of Light Fixture Excluded in this price)				
1.014	Install Light fixture with containment, cabling and termination hanging and spot lights and wall light power points	80	Nos.	186.00	14,880.00
1.015	Install Light fixture with containment, cabling and termination liner light power points	15	Nos.	208.00	3,120.00
1.016	Install Light fixture with containment, cabling and termination LED light power points (Ceilling cove,Curtains and joinerys)	10	Nos.	156.00	1,560.00
1.017	Supply and installation of Lighting Switches (MK)	18	Nos.	260.00	4,680.00
	Supply and Installation of only PVC conduits, containments and Cat 6 cable pulling for the MEP Services as per the design requirements (Final confirmation subject to cofirmation on scope)				
1.018	Data/Voice Twin outlet (RJ-45)				
1.019	Security System(Access Control)	1	Items	4,676.00	4,676.00
1.02	Wi Fi system				
	Testing & commissioning				
1.021	Testing & commissioning of Electrical System	1	Items	4,546.00	4,546.00
				SUB TOTAL CARRIED TO SUMMARY	**65,942.00**

Interiors

PROPOSED MEP WORKS FOR AMALGAMA MANAGEMENT SERVICES DMCC, JUMEIRAH TOWERS DUBAI, UAE

16/12/2024

Sl NO.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
2.00	**FIRE PROTECTION WORKS**				
	Fire Alarm Works				
	Supply and installation of Fire alarm Devices with necessary fire rated cables, clips and other accessories as per the drawings and specifications as per the new design requirement.				
2.01	Supply and Installation of Addressable Smoke Detector	6	Nos.	975.00	5,850.00
0.01	Supply and Installation of Addressable heat Detector	2	Nos.	976.00	1,952.00
2.02	Relocation of existing Smoke	3	Nos.	390.00	1,170.00
2.03	Relocation of Break Glass Unit	1	Nos.	455.00	455.00
2.04	Relocation of Fire Alarm Sounder	1	Nos.	455.00	455.00
2.05	Supply and Installation of Inter Face Unit control module	3	Nos.	1,039.00	3,117.00
2.06	Supply and Installation of FA cables 1.5mmx2C red colour	1	Items	2,338.00	2,338.00
2.07	Supply and installation of fire alram panel FACP	1	Nos.	14,286.00	14,286.00
2.08	Testing and commissioning of Fire Alarm System	1	Item	6,884.00	6,884.00
	Emergency Lighting System				
2.09	Supply and Installation of Emergency Light self contained	9	Nos.	585.00	5,265.00
2.10	Supply and Installation of Emergency Exit Light	5	Nos.	585.00	2,925.00
2.11	Allow sum for testing, addressing, programming and commissioning of Emergency Lighting System	1	Item	1,299.00	1,299.00
	Fire Fightings system				
2.11	Supply and installtion of springkler in ceilling area	11	Nos.	715.00	7,865.00
2.12	Relocation of sprinkler and change the sprinkler head	22	Nos.	390.00	8,580.00
2.13	CO2 fire extinguishers (5 kg)	2	Nos.	333.00	666.00
2.14	Dry Chemical powder extinguisher (6 kg)	2	Nos.	276.00	552.00
2.15	Fire Blanket	1	Nos.	192.00	192.00
	FF isolation charge				
2.16	Isolation of FA and FF system charge to paid for FLS maintenance team	1	Item	2,598.00	2,598.00
2.17	Charge for DCD inspection certificate	1	Item	1,039.00	1,039.00
2.18	Testing and commissioning of Fire Fighting System	1	Item	1,949.00	1,949.00
				SUB TOTAL CARRIED TO SUMMARY	**69,437.00**

Interiors

PROPOSED MEP WORKS FOR AMALGAMA MANAGEMENT SERVICES DMCC, JUMEIRAH TOWERS
DUBAI, UAE

16/12/2024

SI NO.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
3.00	**HVAC WORKS**				
3.01	Service the existing AC	3	Nos.	455.00	1,365.00
3.02	Supply and installation of By pass Type VAV	8	Nos.	2,338.00	18,704.00
3.03	Relocation of thermostat FCUs	3	Nos.	260.00	780.00
3.04	Supply and installation of By pass VAV thermosart	8	Nos.	455.00	3,640.00
3.05	Supply and installation of cross stock	6	Nos.	585.00	3,510.00
3.06	Supply and installation of normal type Fire Damaper for server room	2	Nos.	884.00	1,768.00
	Duct work including Plenum Boxes, elbows, bends, tees, junctions, belmouths, access doors, connection to equipments and air out lets as per the drawings and specifications.				
3.06	Fabrication, and installation of Supply Air Duct (PI Ducting) for FCUs based on proposed drawings.	1	Items	25,169.00	25,169.00
3.07	Flexible duct (consider each 1.5m) with round damper, rings & jubilee clips as per design	1	Item	4,546.00	4,546.00
3.08	Supply & installation of Volume Control Dampers control the air flow	1	Item	3,507.00	3,507.00
3.09	Supply & installation of acoustic insulation control the airflow noise	1	Item	4,286.00	4,286.00
	Grilles and Diffusers				
3.10	Supply and installation of Grills and Diffusers including fittings, supports, and other materials required to complete installation as specified and shown on the drawing. Grills Type:Flow Bar diffuser for linear grills	1	Item	15,195.00	15,195.00
	Testing & Commissioning				
3.11	Testing, commissioning & air balancing	1	Item	3,897.00	3,897.00
				SUB TOTAL CARRIED TO SUMMARY	**86,367.00**
4.00	**PLUMBING WORKS**				
4.01	Sanitary fitting installtion	1	Item	1,949.00	1,949.00
4.02	Supply and installation of PPR domestic Cold and Hot water pipes including fittings, accessories, hangers, and support; scope up to the building line. Pipe line for water heater changing and relocation	1	Item	1,949.00	1,949.00
4.03	All hot and cold water pipes vertical drops concealed in block work walls below ceiling in cross linked polyethylene piping (PEX) complete with connectors and accessories	1	Item	650.00	650.00
4.04	Supply and Installation of Water hammer Arrestor	2	Nos.	325.00	650.00
4.05	Cold and Hot water gate valve	3	Nos.	195.00	585.00
4.06	Supply and installation of water heater 30lit	1	Nos.	1,013.00	1,013.00
4.07	Supply and installation of UPVC waste pipes including hangers, supports, fittings and accessories bathrooms waste pipes	1	Items.	1,949.00	1,949.00
4.08	Supply and Installation of Floor Trap	3	Nos.	260.00	780.00
4.09	Supply and Installation of Clean Outs	1	Nos.	260.00	260.00
4.10	Testing and Commissioning Plumbing system (Pressure test , Gravity and slope test)	1	Item	1,299.00	1,299.00
				SUB TOTAL CARRIED TO SUMMARY	**11,084.00**

Interiors

PROPOSED MEP WORKS FOR AMALGAMA MANAGEMENT SERVICES DMCC, JUMEIRAH TOWERS
DUBAI, UAE

					16/12/2024
Sl NO.	**DESCRIPTION**	**QTY**	**UNIT**	**RATE**	**AMOUNT**
	1. We have excluded Power upgradation and DEWA approval				
	2. We have excluded the Lighting control system,we have consider ON/ OFF switches				
	3. We have excluded the BMS system				
	4. We have excluded the FM200 for sever room				
	5. We have assumed that the existing AC is in working condition				
				TOTAL MEP	**232,830.00**