INTERIORS
HAPPINESS TO SPACES

3105 HUSPY OFFICE - AUH

Reference No: 3105 - R6

Commercial Proposal

HTS Interiors

27th of February 2026

Project :	**3105 HUSPY OFFICE- AUH**
Subject :	**DETAILED COST PLAN**
Qtn Ref.:	**HTS/INT/QN/2026/3105- R6**

Item	Description	VALUE R6
1	PRELIMINARIES & GENERAL REQUIREMENTS	184,746.00
2	AUTHORITY FEES & LANDLORD FEES	43,011.00
3	DESIGN REQUIREMENTS	Included
	ID & MEP WORKS	
4	DEMOLITION WORKS	795.00
5	CIVIL WORKS	58,388.00
6	FLOOR WORKS	355,778.00
7	DRY WALL PARTITIONS	135,311.00
8	GLASS & DOOR WORKS	209,123.00
9	WALL FINISHES	45,759.00
10	CEILING WORKS	241,034.00
11	JOINERY WORKS	116,395.00
12	LIGHT FIXTURES	239,874.00
13	MEP WORKS + FIRE LIFE SAFETY + BMS WORKS	
A	HVAC WORKS	395,963.00
B	ELECTRICAL WORKS	509,231.00
C	PLUMBING WORKS	N/A
D	FIRE ALARM WORKS	103,479.00
E	EMERGENCY LIGHT SYSTEM	80,136.00
F	FIRE FIGHTING WORKS	117,670.00
G	BMS WORKS	N/A
14	BUILDERS WORKS	59,970.00
15	DATA CONTAINMENT WORKS	52,397.00
16	LOOSE FURNITURE	By Client
17	ROLLER BLINDS/ SIGNAGES/ WHITE GOODS/ PLANTS	
A	ROLLER BLINDS	39,618.00
B	SIGNAGES	16,182.00
C	PLANTS	Excluded
	GRAND TOTAL (EXCLUSIVE OF 5% VAT)	**3,004,860.00**
	ADDITIONAL ITEMS EXCLUDED FROM THE SCOPE OF WORK	-

Project :	3105 HUSPY OFFICE- AUH
Subject :	DETAILED COST PLAN
Qtn Ref.:	HTS/INT/QN/2026/3105- R6

Changed items

Item	Description	QUANTITY	UNIT	RATE	R06 - VALUE	IMAGE
1	**PRELIMINARIES & GENERAL REQUIREMENTS**					
A	Management and Staff	1	Item	184,746.00	184,746.00	
B	Site Establishment	1	Item		Included	
C	Consumables and services	1	Item		Included	
D	Samples and Mood Board	1	Item		Included	
E	Site Protection (Internal works)	1	Item		Included	
F	Safety, health and welfare of workpeople	1	Item		Included	
G	Site Security	1	Item		Included	
H	Construction Plants and Tools	1	Item		Excluded	
I	Water for the works (Connection and Meter by HTS)	1	Item		by Client	
J	Lighting and power for the works (Connection and Meter by HTS)	1	Item		by Client	
K	Personal Protective Equipment (PPE)	1	Item		Included	
L	Temporary Toilets and Ablutions (to be provided on site)	1	Item		by Client	
M	First Aid	1	Item		Included	
N	As Built and Construction Drawings	1	Item		Included	
O	Clearing Away Rubbish	1	Item		Included	
P	Insurances	1	Item		Included	
Q	Bonds (Advance Payment and Performance Bond)	1	Item		Included	
R	Programme and Progress of Work	1	Item		Included	
	SUB TOTAL				**184,746.00**	
2	**AUTHORITY FEES & LANDLORD FEES**					
A	Landlord Design Review Fee	1	Item	17,011.00	17,011.00	
B	ADCD Consultant Fee	1	Item	16,000.00	16,000.00	
C	ADCD Initial FLS drawing & FLS Shop drawing Review Fee	1	Item		Included	
D	Municipality Fee	1	Item		Included	
E	TAQA consultant and drawings preparation charges	1	PS	10,000.00	10,000.00	Budgetary, subject to actual authority fees
F	Refundable Security Deposit	1	Item		Included	
	SUB TOTAL				**43,011.00**	
3	**DESIGN REQUIREMENTS**					
A	Allowance for the design and engineering for complete fit-out in accordance with the employer's requirements	1	Item	-	Included	
	SUB TOTAL				**Included**	
	ID & MEP WORKS					
4	**DEMOLITION WORKS**					
A	Removal of existing doors including wrapping and hand it over to the bldg. management. Location: Main Entrance	1	set	795.00	795.00	
B	Demolition of existing block wall for door opening including removal of masonry, plaster, and debris, and making the opening ready for new door installation including door lintel. Location: Main Entrance/ Exit doors	1	ls	-	Ommited	N/A, Not required
	SUB TOTAL				**795.00**	
5	**CIVIL WORKS**					
	Wet Area Waterproofing				**N/A**	
A	Allow for waterproofing to wet area floors/ walls. Location: To all wet areas				**N/A**	
	Self leveling/ underlay					
B	Supply and application of 2-3 mm thick self levelling compound to receive proposed carpet and LVT flooring. Location : Proposed carpet, LVT flooring area.	859	m2	51.00	43,809.00	

Project :	**3105 HUSPY OFFICE- AUH**		
Subject :	**DETAILED COST PLAN**		
Qtn Ref.:	**HTS/INT/QN/2026/3105- R6**		

Changed items

Item	Description	QUANTITY	UNIT	RATE	R06 - VALUE	IMAGE
C	Associated floor build-up (i.e. underlay) for all raised floor areas with porcelain tiles.	61	m2	239.00	14,579.00	
	SUB TOTAL				**58,388.00**	
6	**FLOOR WORKS**					
	Raised access floor					
A	RAF1: Supply & installation of 100-150mm H raised access flooring. Spec: TBC, Locally sourced product. Dimension: 600mm x 600mm x 33.80 mm Location: Throughout	907	m2	175.00	158,725.00	
B	RAF2: Supply & installation of 300mm H raised access flooring. Spec: TBC, Locally sourced product. Dimension: 600mm x 600mm x 33.80 mm Location: Townhall area	7	m2	375.00	2,625.00	
C	RAF3: Supply & installation of 200mm H Anti-static raised access flooring. Spec: TBC, Locally sourced product. Dimension: 600mm x 600mm x 33.80 mm Location: Server room	6	m2	497.00	2,982.00	
D	floor cut-outs for power and data cables.	98	nr	39.00	3,822.00	
E	Door Machine cut-out.	10	nr	39.00	390.00	
	Carpet					
F	FF-02: Carpet Tile Specification: TBC, locally sourced Size : 500x500mm Location: Open workstations, Meeting rooms & Podcast room	532	m2	71.00	37,772.00	**A provisional sum has been calculated at a PC rate for 532 m2 of carpet, totaling AED 22,000 as per Clients instruction, + Installation, OH&P @ 15%, excluding wastage. Note: Awaiitng official quotation from Client**
	LVT flooring					
G	FF-03: Concrete-Effect LVT flooring Specification: LVT, locally sourced. Size : 60x90cm/ 5mm thick or equal/equivalent Location: Townhall, Pantry area, Collab, Hot desking & Printing areas, Passage/ Corridor	327	m2	142.00	46,434.00	
	Porcelain tiles					
H	FF-01: Porcelain Tiles Specification: Marble-effect porcelain tiles- Clayark or equivalent. Size : TBC Location: Reception area	61	m2	353.00	21,533.00	
	Accessories and Edge Details					
	Floor Profile					
K	TR-01: Floor trims to separate different floor type Specification: TBC, locally source. Location: Between carpet and tiles, between tiles and LVT	140	m	96.00	13,440.00	
	Skirting					
M	SK01: MDF skirting Specification: 12 mm thick, 50mm high MDF skirting with PU paint finish. Location: Throughout	391	m	72.00	28,152.00	**Additional Qty. as per revised requirements**
N	150mm H Ply Box skirting Specification: 12 mm thick, 150mm high ply skirting with paint finish. Location: Throughout window perimeter	147	m	239.00	35,133.00	**Revised cost as per revised propose detail**

Project :	**3105 HUSPY OFFICE- AUH**		
Subject :	**DETAILED COST PLAN**		
Qtn Ref.:	**HTS/INT/QN/2026/3105- R6**		

Changed items

Item	Description	QUANTITY	UNIT	RATE	R06 - VALUE	IMAGE
P	300mm H MDF skirting Specification: 12 mm thick, 300mm high laminated wood MDF skiting. Location: Platform	10	m	477.00	4,770.00	
	SUB TOTAL				**355,778.00**	
7	**DRY WALL PARTITIONS**					
A	**120mm Thick Drywall Partitions with Mineral Rockwool Insulation** Supply and installation of 120mm thick straight drywall partitions, constructed with (Knauf or equivalent) CW70 metal studs at 600mm stud spacing, covered on both faces with 12.5mm thick gypsum boards (Knauf or equivalent), filled with 16 kg/m³ mineral rockwool insulation, including all jointing, taping, and finishing, prepared to receive the final surface finish, in the areas specified below. **Height:** From Slab to Slab, 3976mmH (Approx) **Location:** Throughout meeting rooms, podcast room, & Reception area	269	m2	231.00	62,139.00	**Additional qty. as per additional Pod cast and offices & pantry**
B	**120mm Thick Curved Drywall Partitions with Mineral Rockwool Insulation** Supply and installation of 120mm thick straight drywall partitions, constructed with (Knauf or equivalent) CW70 metal studs at 600mm stud spacing, covered on both faces with 12.5mm thick gypsum boards (Knauf or equivalent), filled with 16 kg/m³ mineral rockwool insulation, including all jointing, taping, and finishing, prepared to receive the final surface finish, in the areas specified below. **Height:** From Slab to Slab, 3976mmH (Approx) **Location:** Throughout meeting rooms, podcast room, & Reception area	38	m2	287.00	10,906.00	**Additional qty. as per additional Pod cast and offices**
C	**100mm Thick 60-Minute Fire-Rated Drywall Partitions with Mineral Rockwool Insulation** Supply and installation of 100mm thick straight drywall partitions up to the false/slab ceiling, constructed with (Knauf or equivalent) CW70 metal studs at 600mm stud spacing, covered on both faces with 15mm thick 60-minute fire-rated gypsum boards (Knauf or equivalent), filled with 16 kg/m³ mineral rockwool insulation, including all jointing, taping, and finishing, prepared to receive the final surface finish, in the areas specified below. **Height:** From Slab to Slab, 3976mmH (Approx) **Location:** Server room	18	m2	263.00	4,734.00	
D	**65mm Thick Fire-Rated Gypsum Board Lining (Without Rockwool Insulation)** Supply and installation of 65mm thick straight drywall partitions, constructed using Knauf CW50 metal studs at 600mm stud spacing, covered with one layer of 15mm thick fire-rated gypsum board (Knauf or equivalent) on one face, without rockwool insulation, rising up to 200mm above the false ceiling level,, provision for LED light, including all jointing, taping, and finishing, prepared to receive the final surface finish, in the locations indicated below. **Height:** From Slab to 200mm above the FCL, 3200mmH (Approx) **Location:** Core/ corridor wall	83	m2	144.00	11,952.00	**Qty. adjusted as per requirement, outside corridor quantities, removed**
E	**100mm Thick Fire-Rated Gypsum Board Lining (Without Rockwool Insulation)** Supply and installation of 100mm thick straight drywall partitions, constructed using Knauf CW70 metal studs at 600mm stud spacing, covered with one layer of 15mm thick fire-rated gypsum board (Knauf or equivalent) on one face, without rockwool insulation, rising up to 200mm above the false ceiling level, including all jointing, taping, and finishing, prepared to receive the final surface finish, in the locations indicated below. **Height:** From Slab to 200mm above the FCL, 3200mmH (Approx) **Location:** Core/ corridor wall- with niche	212	m2	215.00	45,580.00	**Qty. adjusted as per Corridor niche requirements**
	SUB TOTAL				**135,311.00**	
8	**GLASS & DOOR WORKS**					
	Glass partition					

Project :	**3105 HUSPY OFFICE- AUH**		
Subject :	**DETAILED COST PLAN**		
Qtn Ref.:	**HTS/INT/QN/2026/3105- R6**		

Changed items

Item	Description	QUANTITY	UNIT	RATE	R06 - VALUE	IMAGE
A	**12mm thk. Clear tempered glass partition (Framed)** Specifications: Single glazing system comprising of 1x12mm Clear tempered glass partition. Acoustic rating: 32dB Partition height: FFL to FCL H3000 mm Type: Single glazed Location: Meeting rooms	78	m2	741.00	57,798.00	**Additional qty. as per additional Pod cast and offices**
	Doors					
B	**Single glazed single leaf swing door (Frameless)** Specification: Supply and install Single glazed single leaf, comprising of 1x12mm Clear tempered glass. Fire Rating: Non - Fire rated Door Hardware: Round H-Type Pull Handle 1500 mm L Floor Spring (Door Closer) Pivot Clamps Lockset & Cylinder (Non-Master Key) Door Stopper Dimension: L1000mm x H3000mm Location: Meeting rooms	5	nr	6,440.00	Rate only	**Cancelled item & replaced with framed door**
C	**Single glazed single leaf swing door (Framed with drop seal)** Specification: Supply and install Single glazed single leaf, comprising of 1x12mm Clear tempered glass. Door Hardware: Offset Round H-Type Pull Handle 1500 mm L Floor Spring (Door Closer) Pivot Arms Lockset & Cylinder (Non-Master Key) Door Stopper Door Size: 1094 mm x 3000 mm H Door Type: n/a Rw: 34 dBLocation: Meeting rooms/ Podcast & offices	12	nr	8,904.00	106,848.00	**Additional quantities are required for the new podcast studio and office, including the provision and installation of new access doors at the Reception area.**
D	**Supply and Install of Aluminum Tech Panel beside Glass Door for access door.** Size: 300x3000mm H	3	nr	2,703.00	8,109.00	**Added Item required for access control**
E	**Single glazed double leaf sliding doors with fixed glass panels (Automatic)** Specification: Supply and install automatic Single glazed double leaf sliding door with fixed panel, comprising of 1x12mm Clear tempered glass in RAL 9005 Black Powder Coated finish. Fire Rating: Non - Fire rated Dimension: L1400mm x H2325mm Location: Main entrance/ exit	1	set	28,620.00	28,620.00	**Qty. reduced, To retain existing door**
F	Single Leaf 60 mins. FR Timber Swing Door Specification: Single leaf semi-solid core swing door in FR MDF Veneer finish, door frame in solid wood stained finish and architraves in MDF veneer finish. Door Hardware: Lockable lever handle and concealed door closer powder coated finish. Fire Rating: 60mins. FR Dimension: L1000mm x H2500mm Location: Server room	1	nr	7,748.00	7,748.00	**Reduced cost**
	SUB TOTAL				**209,123.00**	
9	**WALL FINISHES**					
	Painting works					
A	**Paint Finish** Specification: Jotun Fenomastic Colour: White Finish: Matt Location: Throughout	802	m2	42.00	33,684.00	**Added**
B	**Textured Paint Finish** Specification: Jotun Lady design Colour: Cementitious effect Location: Reception and Corridor Niches	150	m2	207.00	Rate only	**Cancelled and replaced with wallpaper and paint finish**

Project :	**3105 HUSPY OFFICE- AUH**
Subject :	**DETAILED COST PLAN**
Qtn Ref.:	**HTS/INT/QN/2026/3105- R6**

Changed items

Item	Description	QUANTITY	UNIT	RATE	R06 - VALUE	IMAGE
C	**Wallpaper** Specification: NGC Nafees or equivalent Colour: Textured paint- effect wallpaper Location: Reception, Townhall area & Podcast room	63	m2	111.00	6,993.00	
	Back painted glass					
D	Back painted glass (Backsplash) Supply & installation of back painted glass. Specification: TBC, locally source. Location: Pantry	6	m2	847.00	5,082.00	
	Wooden slats/ cladding					
E	Supply & installation of wood laminate cladding. Specification: TBC Location: Meeting room 8pax		m2	1,118.00	Rate only	
F	Supply & installation of wooden slats in wood laminate finish. Specification: TBC Location: Printing area		m2	1,788.00	Rate only	
	SUB TOTAL				**45,759.00**	
10	**CEILING WORKS**					
	Suspended Ceiling					
	Flat Gypsum Ceiling					
A	Flat Gypsum Board Ceiling Specification:12.5mm Knauf Or Equivalent Regular Gypsum Board In Standard GI Metal Frames, Supports And Hangers, Filled, Skimmed, Finish and Painted (measured separately) in White RAL 9010 Matt Finish Location: Throughout	388	m2	207.00	80,316.00	**Additional Qty from acoustic panel**
B	60x60 FR Gypsum ceiling tiles Supply and installation of 60×60 cm fire-rated gypsum ceiling tiles on suspended metal framework with necessary hangers, perimeter trims, and fixings. Location: Server room	6	m2	255.00	1,530.00	
C	Acoustic ceiling panels Supply and installation of acoustic ceiling panels on suspended metal framework with necessary hangers, perimeter trims, and fixings, finished flush and sound-absorbing. Panel size: 1600x650x20mm Location: Meeting rooms	9	nr	1,352.00	12,168.00	
	Ceiling Accessories					
	Blind Niche, Bulkhead and light cove					
D	BH-01: 100mm H Vertical Gypsum Bulkhead Specification: 12.5mm thick Knauf or equivalent regular gypsum board (RG) in standard GI metal frames, supports and hangers, filled, skimmed, finish and painted (measured separately) in RAL TBC finish. Location: Meeting rooms- 14pax	40	m	120.00	4,800.00	
E	BH-01: 200mm H Vertical Gypsum Bulkhead Specification: 12.5mm thick Knauf or equivalent regular gypsum board (RG) in standard GI metal frames, supports and hangers, filled, skimmed, finish and painted (measured separately) in RAL TBC finish. Location: Townhall, printing area and Pantry	28	m	144.00	4,032.00	

Project :	**3105 HUSPY OFFICE- AUH**	
Subject :	**DETAILED COST PLAN**	
Qtn Ref.:	**HTS/INT/QN/2026/3105- R6**	

Changed items

Item	Description	QUANTITY	UNIT	RATE	R06 - VALUE	IMAGE
F	BH-03: 1176mm H Vertical Gypsum Bulkhead Specification: 12.5mm thick Knauf or equivalent regular gypsum board (RG) in standard GI metal frames, supports and hangers, filled, skimmed, finish and painted (measured separately) in RAL TBC finish. Location: Corridor	84	m	223.00	18,732.00	
G	BH-04: 50+100+100H light cove Specification: 12.5mm thick Knauf or equivalent regular gypsum board (RG) in standard GI metal frames, supports and hangers, filled, skimmed, finish and painted (measured separately) in RAL TBC matt finish. Location: Throughout corridor	123	m	215.00	Rate only	
H	BH-05: 200mm + 200mm width curtain cove Specification: 12.5mm thick Knauf or equivalent regular gypsum board (RG) in standard GI metal frames, supports and hangers, filled, skimmed, finish and painted (measured separately) in RAL TBC matt finish.	148	m	215.00	31,820.00	
	Access Panel					
J	AP01: Standard Access Ceiling Panel Specification: TBC Size: 600 x 600mm Location: Throughout	64	nr	287.00	18,368.00	**Approx. number**
	Ceiling Finishes					
K	Paint finish to flat gypsum ceiling Specification: Application of 2 coats of skim coat followed by 2 coats of off-white Fenomastic Emulsion paint finish. RAL: TBC Location: Meeting rooms, Reception area Pantry & Printing area	388	m2	42.00	16,296.00	
M	Spray paint to exposed concrete/slab ceiling including MEP services Surface preparation and spray painting of exposed concrete/slab ceiling, including MEP services, cleaning, priming, and application of two coats of approved paint. RAL: TBC Location: Throughout- Exposed ceiling	566	m2	72.00	40,752.00	
N	Paint finish to 100mm H bulkhead and niche Specification: Application of 2 coats of skim coat followed by 2 coats of off-white Fenomastic Emulsion paint finish. RAL: TBC Location: Meeting rooms & Reception area	40	m	29.00	1,160.00	
P	Paint finish to 200mm H bulkhead and niche Specification: Application of 2 coats of skim coat followed by 2 coats of off-white Fenomastic Emulsion paint finish. RAL: TBC Location: Townhall, printing area and Pantry	28	m	29.00	812.00	**Additional item as per new paint for bulkhead as per new proposal**
Q	Paint finish to 1176mm H bulkhead and niche Specification: Application of 2 coats of skim coat followed by 2 coats of off-white Fenomastic Emulsion paint finish. RAL: TBC Location: Between open ceiling and gypsum ceiling including Townhall	84	m	48.00	4,032.00	
R	Paint finish to light cove Specification: Application of 2 coats of skim coat followed by 2 coats of off-white Fenomastic Emulsion paint finish. RAL: TBC Location: Window perimeter	123	m	-	Rate only	**Cancelled item as per new proposal**
S	Paint finish to curtain cove Specification: Application of 2 coats of skim coat followed by 2 coats of off-white Fenomastic Emulsion paint finish. RAL: TBC Location: Window perimeter	148	m	42.00	6,216.00	
	SUB TOTAL				**241,034.00**	

Project :	**3105 HUSPY OFFICE- AUH**
Subject :	**DETAILED COST PLAN**
Qtn Ref.:	**HTS/INT/QN/2026/3105- R6**

Changed items

Item	Description	QUANTITY	UNIT	RATE	R06 - VALUE	IMAGE
11	**JOINERY WORKS**					
	Supply, fabricate, and install fixed joinery including all framing, finishes fixtures, hardware, MEP provisions, electrical switch and sockets, provision for storage and equipment space all complete in accordance with drawings and specifications					
A	**Reception counter** Specification: Supply and installation of wooden reception counter with textured paint finish, solid surface countertop, and MDF melamine for internal drawers and carcass, including all materials, labor, and accessories. Dimension: L=2900mm x D=900mm x H=750-1200mm; Location: Reception area	1	nr	24,019.00	24,019.00	
C	**Pantry base cabinet** Specification: Supply and installation of dry pantry base cabinet made of MDF with laminate and solid surface countertop. Size: L=12200mm x D=600mm x H=900mmm Note: **Supply of white goods, supply & installation of LED strip light, sockets & any MEP works are excluded.	1	nr	54,534.00	Rate only	**Cancelled item, replaced wall with wallpaper & skirting only, cabinet will be under furniture**
D	**Pantry base cabinet** Specification: Supply and installation of dry pantry base cabinet made of MDF with laminate and solid surface countertop. Size: L=2360mm x D=600mm x H=900mmm Location: Pantry Note: **Supply of white goods, supply & installation of LED strip light, sockets & any MEP works are excluded.	1	nr	10,550.00	10,550.00	**New item as per new pantry location**
E	**Reception wall** Specification: Supply and installation of reception wall with wooden cladding integrated with wooden slats, prepared to receive company signage, finished with textured paint; including all necessary framing, fixings, grooves as per design, and accessories. Size : L=6000mm x H=3000mmm Location: Reception area	1	nr	16,539.00	16,539.00	
F	**300mm thick standalone MDF divider** Specification: Supply and installation of a 300mm thick standalone MDF divider on raised platform, securely bolted to the slab floor, including side fascia, all framing, finishes, fixings, and necessary accessories. Platform height: 300mm. Size : L=3200mm x W=300mm x H=2800mmm Location: Raised Platform Note: **Raised access flooring (300mm H) to be quoted, supplied and installed separately." **Supply & installation of screens are by Client.	1	nr	45,407.00	45,407.00	
G	**Bar Counter** Specification: Supply and installation of bar counter with solid surface countertop, including MDF wood laminate front and side panels and internal carcass as required, complete with all fixings, hardware, and necessary accessories. Size : L=3900mm x W=600mm x H=1200mmm Location: Pantry/ Townhall	1	nr	22,619.00	Rate only	**Cancelled Item, part of Loose furniture**
H	**DB cabinet** Specification: Supply and installation of FR DB cabinet in FR MDF laminate finish. Size: L=1200mm x D=200mm x H=2800mm; Location: Hallway	4	nr	4,970.00	19,880.00	
	SUB TOTAL				**116,395.00**	

Project :	3105 HUSPY OFFICE- AUH
Subject :	DETAILED COST PLAN
Qtn Ref.:	HTS/INT/QN/2026/3105- R6

Changed items

Item	Description	QUANTITY	UNIT	RATE	R06 - VALUE	IMAGE
12	**LIGHT FIXTURES**					
A	LIGHT FIXTURES (Architectural & Decorative).					
A.1	Allowance for supply of light fixtures (architectural & decorative). Location: Throughout					
A.1.1	**Suspended Cylinder Light.**	90	nr	549.00	49,410.00	
A.1.2	**Recessed spotlight**	36	nr	162.00	5,832.00	
A.1.3	**Recessed downlight**	18	nr	173.00	3,114.00	
A.1.4	**Suspended linear light (1.13m)**	89	Set	1,024.00	91,136.00	
A.1.5	**Suspended Oblong light (10m)**	4	Set	11,137.00	44,548.00	
A.1.6	**Suspended linear light**	2	nr	2,302.00	4,604.00	
A.1.7	**Pendant light (80cm dia.)**	4	nr	3,089.00	12,356.00	
A.1.8	**Surface magnertic light with track**	24	nr	608.00	14,592.00	
A.1.9	**Surface linear light**	8	nr	1,516.00	12,128.00	
A.1.10	**60X60 Panel Light**	2	nr	132.00	264.00	
A.1.11	**LED Strip light**	10	lm	189.00	1,890.00	
B	SANITARY FITTINGS					
B.1	Allowance for supply of sanitary fittings. Location: Pantry		ls	-	**N/A**	
	SUB TOTAL				**239,874.00**	
13	**MEP WORKS + FIRE LIFE SAFETY + BMS WORKS**					
A	**HVAC WORKS**					
	Supply, and installation, of all items listed according to the indicated specifications and design guidelines					
A.1	Allowance for HVAC works as follow,	1	ls	380,483.00	380,483.00	
A.1.01	Supply & Installation of Pre Insulated ducts for FCUs.	615	Item		Included	
A.1.02	Supply & Installation of Volume control Damper (VCD).	57	Item		Included	
A.1.03	Supply & Installation of 300mmx300mm square diffusers.	98	Item		Included	
A.1.04	Supply & Installation of 300mmx300mm Return square diffusers.	15	Item		Included	
A.1.05	Supply & Installation of air grills as per proposal.	25	Item		Included	
A.1.06	Supply & Installation of plenum box for linear slot diffuser.	25	Item		Included	
A.1.07	Supply & installation of Thermostat for FCUs including control wiring and conduiting, Make Honeywell/ equivalent.	14	Item		Included	
A.1.08	HVAC Machines air balancing, testing, commissioning. Note: Third party excluded)	1	ls		Included	
A.1.09	Chemical flushing.	1	ls	15,480.00	15,480.00	Additional item
	Note: *It is assumed that the existing BTU meter is available on site and in good working condition. *Individual AC control for enclosed rooms is not included in this scope. *Chilled water flushing is excluded from this scope. *The offer is based on the GA layout. Any changes in the final approved layout shall be treated as a variation. *Relocation of existing FCUs is not included. *No new FCVs are considered; only new FCUs are included. *Existing FCUs will be reused, assuming they are in good condition.					
	SUB TOTAL				**395,963.00**	

Project :	3105 HUSPY OFFICE- AUH
Subject :	DETAILED COST PLAN
Qtn Ref.:	HTS/INT/QN/2026/3105- R6

Changed items

Item	Description	QUANTITY	UNIT	RATE	R06 - VALUE	IMAGE
B	**ELECTRICAL WORKS**					
B.1	Allowance for electrical works as follow,	1	ls	509,231.00	509,231.00	
B.1.01	Supply and installation of PVC Conduiting and wiring for the light points as per new design.	300	nr	-	Included	
B.1.02	Installation of light fixtures	1	ls	-	Included	
B.1.03	Supply and installation of Light switch including PVC conduiting and wiring.	12	nr	-	Included	
B.1.04	Supply and installation of Grid switch including PVC conduiting and wiring.	4	nr	-	Included	
B.1.05	Supply and installation of 13A Single switched socket including pvc conduiting and wiring.	20	nr	-	Included	
B.1.06	Supply and installation of 13A Twin switched socket including pvc conduiting and wiring.	25	nr	-	Included	
B.1.07	Supply and installation of commando socket including pvc conduiting and wiring.	2	nr	-	Included	
B.1.08	Supply and installation of 20A DP switched socket including pvc conduiting and wiring.	4	nr	-	Included	
B.1.09	Supply and Installation Floor box with 2 No.of 13A double power socket outlet and data points	94	nr	-	Included	
B.1.10	Supply and installation of 13A switch + flex outlet for FCU/VAV including pvc conduiting and wiring.	14	nr	-	Included	
B.1.11	Supply and installation of Spur outlet for FACP/ONU including pvc conduiting and wiring.	4	nr	-	Included	
B.1.12	Supply and installation of single phase isolator conduiting and wiring. (coffee Machine, dish washer)	2	nr	-	Included	
B.1.13	Supply and installation of 3phase phase isolator conduiting and wiring.(server room)	1	nr	-	Included	
B.1.14	Supply and installation of GI Trunking at high level for lighting & power circuits	1	ls	-	Included	
B.1.15	Supply and installation of GI Tray at main cable for new DB and Modification of existing tray as required	1	ls	-	Included	
B.1.16	Supply and installation of new DB as per the new load schedule.	4	nr	-	Included	
B.1.17	Modification of existing SMDB as per the new proposal	1	nr	-	Included	
B.1.18	Supply and installation of new 4Cx35mm2 xlpe cable + 1Cx16mm2 ECC from existing SMDB to DB's	1	ls	-	Included	
B.1.19	Testing and Commissioning (Third party Excluded)	1	ls	-	Included	
	SUB TOTAL				**509,231.00**	
C	**PLUMBING WORKS**					
C.1	Allowance for plumbing works.		ls		**N/A**	**N/A- Considering Dry pantry**
	SUB TOTAL				**N/A**	
D	**FIRE ALARM SYSTEM**					
D.1	Allowance for fire alarm system.	1	ls	103,479.00	103,479.00	
D.1.01	Supply, Cabling and Installation of One Loop Addressable Fire Alarm Control panel.	1	nr	-	Included	
D.1.02	Supply, Cabling and Installation of Addressable Smoke detector with base.	31	nr	-	Included	
D.1.03	Supply, Cabling and Installation of Addressable Heat detector with base.	1	nr	-	Included	
D.1.04	Supply, Cabling and Installation of Addressable Void Smoke detector with remote Indicator. Note: If Required more qty, it will be quoted separately	7	nr	-	Included	

Project :	3105 HUSPY OFFICE- AUH
Subject :	DETAILED COST PLAN
Qtn Ref.:	HTS/INT/QN/2026/3105- R6

Changed items

Item	Description	QUANTITY	UNIT	RATE	R06 - VALUE	IMAGE
D.1.05	Supply, Cabling and Installation of Addressable Manual Call points.	6	nr	-	Included	
D.1.06	Supply, Cabling and Installation of Sounder.	6	nr	-	Included	
D.1.07	Supply, Cabling and Installation of Addressable Input/output Modules for Interfacing Work.ZCV_ 6 Nos, Hassantuk_2 Nos,Access Control_2 Nos, Building FACP Interface_2 Nos, (Note: If required more qty, it will be quoted separately	12	nr	-	Included	
D.1.08	Programming of proposed Office Fire Alarm control panel.	1	ls	-	Included	
D.1.09	Cabling & Fixing of power supply socket from the Proposed FACP.	1	ls	-	Included	
D.1.10	Supply, Cabling and Installation of Addressable Interface Module for Building FACP.(Fire and Fault) Brand: Simplex	2	nr	-	Included	
D.1.11	Isolation of Existing FA Devices and Adding Modules with Reprogramming of Building Panel. Addressable: Simplex	1	ls	-	Included	
	SUB TOTAL				**103,479.00**	
E	**EMERGENCY LIGHT WORKS**					
E.1	Allowance for emergency light works.	1	ls	80,136.00	80,136.00	
E.1.01	Supply, Cabling and Installation of Emergency Light Monitoring Panel	1	ls	-	Included	
E.1.02	Supply, Cabling and Installation of Emergency Light-Surface/Ceiling Mount-Monitoring type.	25	nr	-	Included	
E.1.03	Supply, Cabling and Installation of Exit Light - Directional Type-Monitoring Type.	9	nr	-	Included	
E.1.04	Programming Charges for the proposed EM/EXIT Light Monitoring panel.	1	nr	-	Included	
E.1.05	Removing of Existing CBS(Inotec) Emergency light and deletion of Program Charges.	1	ls	-	Included	
	SUB TOTAL				**80,136.00**	
F	**FIRE FIGHTING WORKS**					
G.1	Allowance for fire fighting works.	1	ls	117,670.00	117,670.00	
G.1.01	Modification of Existing Upright Sprinkler Piping Network with required pipe and fittings.	102	nr	-	Included	
G.1.02	Supply and Installation of Quick Response Concealed Pendent Sprinkler Head with required Pipe and Fittings accessories, 68 Deg. (Ceiling Area Only considered as per Ceiling Drawing)	60	nr	-	Included	
G.1.03	Supply & installation of 5 kg CO2 Fire Extinguisher.	6	nr	-	Included	
G.1.04	Supply and Installation of 6 Kg DCP Fire Extinguisher.	6	nr	-	Included	
G.1.05	Supply & Installation of fire blanket in pantry area	1	nr	-	Included	
G.1.06	Supply and Installation of 2"& 2 1/2" New butterfly valve.	6	nr	-	Included	
G.1.07	Draining, Repressurization, Pressure Test & Certificate for fire fighting system. (28th Floor)	1	ls	-	Included	
	Note: *AMC proposal is excluded our proposal, once drawing approved will share the proposal separately. *FM - 200 clean agent system is excluded.					
	SUB TOTAL				**117,670.00**	

Project :	**3105 HUSPY OFFICE- AUH**
Subject :	**DETAILED COST PLAN**
Qtn Ref.:	**HTS/INT/QN/2026/3105- R6**

Changed items

Item	Description	QUANTITY	UNIT	RATE	R06 - VALUE	IMAGE
G	**BMS**					
H.1	Allowance for BMS works.	1	ls	-	N/A	**N/A**
H.1.01	Supply & installation of Thermostat compatible with BMS connection. Lobbing cable shield between FCUs to BMS point.	46	nr	-	Included	
	Note: *New FCVs, BMS controllers, BMS PC, DDC panel upgrades, and BMS cable looping works are excluded.					
	SUB TOTAL				**N/A**	
14	**BUILDERS WORKS**					
A	Allowance for MEP builders works (Cutting/ chasing, coring & etc.)	1	Item	59,970.00	59,970.00	
	SUB TOTAL				**59,970.00**	
15	**DATA CONTAINMENT WORKS**					
A	Allowance for data containment works.	1	ls	52,397.00	52,397.00	**Additional cost for containment works associated with 3 additional access control systems.**
	SUB TOTAL				**52,397.00**	
16	**LOOSE FURNITURE**				**Excluded**	
17	**ROLLER BLINDS/ SIGNAGES/ WHITE GOODS/ PLANTS**					
A	Roller Blinds & Curtains					
A.1	WT-01: Manually Operated Roller Blinds Specification: TBC Location: Window perimeter	330	m2	105.00	34,650.00	
A.2	Side guide channel.	684	m	82.00	Rate only	**Cancelled item**
A.3	Supply & installation of black-out curtain with tracks.	12	m2	414.00	4,968.00	
	SUB TOTAL				**39,618.00**	
B	Signages & Branding					
B.1	Supply and Installation of Illuminated Signage. Spec: 3D backlit "Huspy™" wall signage made from matte black acrylic with warm white LED halo lighting. Installed using stud fixing with hidden wiring. Size: L=1000mm x H=200mm	1	ls	11,712.00	11,712.00	
B.2	Company front entrance door logo	2	ls	2,235.00	4,470.00	
	SUB TOTAL				**16,182.00**	
C	White goods					
C.1	Supply of White Goods @ Pantry (Fridge, Microwave, Kettle & Coffee machine)		ls	-	Excluded	**By Client**
	SUB TOTAL				**Excluded**	
D	Plants				**Excluded**	
	SUB TOTAL				**Excluded**	
	Grand Total (Exclusive of 5% VAT)				**3,004,860.00**	

GENERAL TERMS & CONDITIONS

Project	3105 HUSPY OFFICE- AUH
Subject	DETAILED COST PLAN
Date:	27 February 2026
Qtn Ref.:	HTS/INT/QN/2026/3105- R6

GENERAL NOTES:	
1	Sufficient electrical load is assumed to be available at the site to meet the design requirements.
2	ADCD/ Certificate is considered only for new items and a single application.
3	A Provisional Sum has been considered for the following works:
a	All lighting fixtures are included under a Provisional Sum. Costs may vary depending on the approved specifications.
b	MEP + FLS works: final design and locations may vary as per site conditions.
c	Signage cost may vary depending on the final design and specifications to be confirmed by the Client.
4	A new SMDB is proposed to accommodate the new lighting DB and UPS DB.
5	Six existing double leaf doors are to be removed and closed with fire-rated gypsum lining.
6	Non-FR automatic double leaf sliding doors are considered at both entrances.
7	Marble-effect porcelain tiles are considered for the Reception area.
8	It is assumed that the existing BTU meter is available on site and in good working condition.
9	We have considered re-using of existing FCUs and no relocation will be done, assuming that all units are working in a good condition.
10	We considered new thermostats that will be compatible on the existing landlord BMS.
EXCLUSIONS :	
1	Plumbing works are excluded; no wet areas are considered.
2	Electrical load/power upgradation works are excluded.
3	Lighting control and related works are excluded.
4	Structured cabling, Wi-Fi points, and all works related to IT, Data, Security, and AV shall be provided by the Client.
5	Leak detection panels and related works are excluded.
6	Coordination/payment for DU/Etisalat connections by the Client is excluded.
7	New fibre cabling works are excluded.
8	FM - 200 clean agent system is excluded.
9	Any additional requirements or changes during approvals by Civil Defence, Local Authority, Building Management, or Building Nominated Vendor shall be carried out by the Client. Existing devices in the modified area will be connected to the new FACP.
10	Relocation of existing FHR is not included in the scope of work.
11	Individual AC control for enclosed rooms is not included in this scope.
12	Chilled water flushing is excluded from this scope.
13	New FCVs, BMS controllers, BMS PC, DDC panel upgrades, and BMS cable looping works are excluded.
14	White goods, artworks, rugs, and sculptures are excluded.
15	Loose furniture shall be provided by the Client.
PAYMENT TERMS & PROJECT COMPLETION SCHEDULE :	
*	40% Advance Payment upon the issuance of Invoice
*	10% Mobilisation to Site & protection of the Landlord Area
*	25% On Completion of MEP 1st fix
*	20% On Completion of floor and ceiling works
*	5% On Completion of the Woks / Handover (TOC/Beneficial Occupancy)
	Payment Terms:
	1. All milestone payments shall be invoiced by the Contractor and released by the Client within 7 calendar days of invoice receipt.
	2. Any disputes regarding milestone completion must be notified within 5 working days and the undisputed amounts shall be paid as scheduled.
VAT (VALUE ADDED TAX)	
*	An additional amount of 5% (Or any % specified by the government) will be charged with invoice, according to the government rules and regulations.
VALIDITY :	
*	This offer is valid only for 90 days upon issue. HTS reserve the rights to revise the rates accordingly after this period