Design Infinity *Beyond Imagination …*

Date: 16/12/2024

REF : DI/GN/530/2024

Kind Attention: Mr. Halen Rodda
Partner & Project Lead
halen@projectpeople.ae

Dear Sir,

PROJECT : Amalgama MS 3604 JBC 4 DMCC – Design & Build RFP No. (AMALG-2024-RFP-01)

We thank you for allowing us to offer our commercial proposal forAmalgama MS 3604 JBC 4, Dubai, UAE.

Please find herewith our competitive offer as per the attached bill of quantities amounting as below.

SUB TOTAL: 1,219,241.00

VAT 5%: 60,962.05

Completion: AS PER SCHEDULE

Validity: 30 days from the above date.

Payment Terms ID Works :25% Advance payment,65% Progressive payment,5% on completion &
5% retention payment to be released against security cheque
All paymets to be certified and paid within 10 calendar days

Payment Terms Loose furniture :50% advance along with order confirmation, 40% on material delivery to site and 10% on installation.

We look forward to establishing a constructive dialogue with you at all stages of your evaluation process. Assuring you of our best services at all times.

We hope our offer is in line with your requirement and look forward to working with you.

Thank you and best regards,

Geetha Nayak
Managing Partner
Mobile No: +971 501467608

Design Infinity *Beyond Imagination …*

Date: 16/12/2024

REF : DI/GN/530/2024

PROJECT : Amalgama MS 3604 JBC 4 DMCC – Design & Build RFP No. (AMALG-2024-RFP-01)

NOTES

1. Any changes to the work, pertaining to the instructions from Landlord /authorities/employer will have an additional cost implication and to be agreed upon finalizing of details.
2. MEP is predesigned by considering to reuse all existing MEP services.
3. All Existing MEP system are considered to be in good working conditions.
4. All incoming power cables to DBs and SMDBs are considered to be reused without any modifications.
5. FCUS to be reused in place as same existing,
6. We assumed that existing FCU's are in a good condition with enough cooling and will remain same place without any relocation

EXCLUSIONS

7. VAT
8. Any modification works for existing FAHUs/AHUs
9. Upgradation on existing MEP services-Power upgradation, Chilled water upgradation and Fire pumps
10. Light control system
11. CCTV & ACCESS CONTROL SYSTEM
12. Toilet/Pantry area works.

Design Infinity *Beyond Imagination …*

PROJECT : Amalgama MS 3604 JBC 4 DMCC – Design & Build RFP No. (AMALG-2024-RFP-01)		
REF : DI/GN/530/2024		Date: 16/12/2024
SUMMARY		
1	**PRELIMINARIES**	**72,771.00**
2	**PARTITIONS**	**52,175.00**
3	**FLOOR WORKS**	**106,566.00**
4	**CEILING WORKS**	**54,769.00**
5	**WALL FINISHES**	**121,696.00**
6	**DOOR WORKS**	**61,298.00**
7	**JOINERY WORKS**	**73,338.00**
8	**LOGO**	**2,778.00**
9	**PLANTS**	**46,208.00**
10	**WHITE GOODS**	**3,189.00**
11	**BLINDS**	**10,925.00**
12	**LIGHT FIXTURES**	**49,314.00**
13	**ELECTRICAL WORKS**	**80,319.00**
14	**HVAC WORKS**	**166,532.00**
15	**CIVIL DEFENSE WORKS**	**92,753.00**
16	**IT/AV WORKS**	**69,535.00**
17	**LOOSE FURNITURE**	**155,075.00**
	GRAND TOTAL (AED)	**1,219,241.00**

PROJECT : Amalgama MS 3604 JBC 4 DMCC – Design & Build RFP No. (AMALG-2024-RFP-01)

ID WORKS Date: 16/12/2024

Sl NO.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT	REFERENCE
1.00	**PRELIMINARIES**					
1.01	General- Contractor's preliminaries for mobilization, site preparation	1	Item	3,500.00	3,500.00	
1.02	Charges for setting out transportations to/from site, material deliveries, small tools and equipment's, protection of finished products in on-going site, site attendance and call out attendance.	1	Item		INCLUDED	
1.03	Charges for Preparation of Technical drawings (Architectural & MEP) to execute works at the site.	1	Item	5,000.00	5,000.00	
1.04	Allow provision of Insurance for entire fit out period. Contractors all Risk Insurance (As per UAE Law).	1	Item	5,000.00	5,000.00	
1.05	Charges for Project management, site supervision & coordination.	1	Item	15,000.00	15,000.00	
1.06	Allow for coordination with government/authorities along with submission of proposed designs and obtaining completion certificate.	1	Item	5,000.00	5,000.00	
1.07	Charges for scaffolding.	1	Item	1,500.00	1,500.00	
1.08	Health, Safety and Environmental Procedures.	1	Item	500.00	500.00	
1.09	Regular cleaning of site during construction period and after completion professional deep cleaning and made ready to occupy. Including carting away the debris to Municipal dumping area.	1	Item	6,944.00	6,944.00	
1.10	Access Workers passes	1	Item	6,944.00	6,944.00	
1.11	Advance payment bond guarantee	1	Item	3,000.00	3,000.00	
1.12	Performance bond guarantee	1	Item	6,900.00	6,900.00	
1.13	JBC management DMCC Fitout fee	1	Item	13,483.00	13,483.00	
	Note - *1. Authority Fees to be paid by the client as per the actuals.*					
				TOTAL PRELIMINARIES	**72,771.00**	
2.00	**PARTITIONS**					
2.01	**100mm thick NFR Gypsum partition** Supply and installation of 100mm thick non fire rated gypsum partition using 2 layer of 12.5mm thick gypsum board(knauf) on both side, with 50mm thick rokwool insulation, GI studs at 600mm c/c, GI tracks, joined, smoothened and taped, made ready to receive other finishes	75	sqm	167.00	12,525.00	
2.02	**100mm thick Gypsum partition/Baffle above glass partition** Supply and installation of 100mm thick non fire rated gypsum partition using 2 layer of 12.5mm thick normal gypsum board(knauf) on both side, with 50mm thick rokwool insulation, GI studs at 600mm c/c, GI tracks, joined, smoothened and taped, made ready to receive other finishes.	20	Lmt	188.00	3,760.00	
2.03	**100mm thick FR Gypsum partition** Supply and installation of 100mm thick fire rated gypsum partition using 2 layer of 12.5mm thick FR gypsum board(knauf) on both side, with 50mm thick rokwool insulation, GI studs at 600mm c/c, GI tracks, joined, smoothened and taped, made ready to receive other finishes.	15	sqm	194.00	2,910.00	

PROJECT : Amalgama MS 3604 JBC 4 DMCC – Design & Build RFP No. (AMALG-2024-RFP-01)						
ID WORKS						Date: 16/12/2024
2.04	**Wall Liner (NFR Gypsum)** Supply and installation of one layer of 12.5mm thick normal gypsum board with GI studs framing.	80	sqm	104.00	8,320.00	
2.05	**Wall Liner (FR Gypsum)** Supply and installation of one layer of 12.5mm thick FR gypsum board with GI studs framing.	12	sqm	111.00	1,332.00	
2.06	**Single glazed partition -** Supply and installation of single glazed partition using 13.52mm acoustic laminated glass, with 25x25mm QIC Internal glazing system (Powdercoated finish) and cleat slots for seamless joining. (Acoustic Rating-Rw-38dB).	32	sqm	729.00	23,328.00	
				SUB TOTAL PARTITIONS	**52,175.00**	
3.00	**FLOOR WORKS**					
3.01	**60X60 Raised floor -** Supply and installation of 60x60 bare finish cementatious raised floor with pedestal Location - Entire office area Make-Unitile	224	sqm	220.00	49,280.00	
3.02	**60X60 HPL Raised floor -** Supply and installation of 60x60 HPL anti static raised floor with pedestal Location - Server room Make-Unitile	6	sqm	625.00	3,750.00	
3.03	**CPT 01 Carpet Tile** - Supply and installation of 50x50cm carpet tile flooring as per approved design. Location - Conference room pc rate 160dhs/sqm considered Make-Modulyss	30	sqm	241.00	7,230.00	
3.04	**CPT 02 Carpet Tile** - Supply and installation of 50x50cm carpet tile flooring as per approved design. pc rate 100dhs/sqm considered Make-Modulyss Location - work station &closed rooms	130	sqm	153.00	19,890.00	
3.05	**LVT flooring** - Supply and installation of 2mm thick Vinyl tile flooring. Herringbone design Brand - Virgin Location- Corridor,reception&pantry	64	sqm	253.00	16,192.00	
3.06	Calcium silicate board backing for the above LVT flooring	64	sqm	111.00	7,104.00	
3.07	**Transition Strip -** Supply and installation of SS finish transition strip/aluminium profile between different floor finishes.	30	lm	104.00	3,120.00	
				SUB TOTAL FLOOR	**106,566.00**	
4.00	**CEILING WORKS**					
4.01	**Plain gypsum ceiling-** Supply and installation of 12.5mm thick normal gypsum ceiling; with necessary support works. Ready to receive paint finish **Location-Reception&closed rooms**	122	sqm	118.00	14,396.00	
4.02	**Plain gypsum ceiling-** Supply and installation of 12.5mm thick FR gypsum ceiling; with necessary support works. Ready to receive paint finish **Location-Server room**	6	sqm	132.00	792.00	

PROJECT : Amalgama MS 3604 JBC 4 DMCC – Design & Build RFP No. (AMALG-2024-RFP-01)						
ID WORKS						Date: 16/12/2024
4.03	**Acoustic Baffle ceiling** - Supply & installation of 200mm high acoustic baffle ceiling including necessary supports. Location-Pantry	10	sqm	980.00	9,800.00	
4.04	**Stretch ceiling** - Supply & installation of stretch ceiling with led lights including necessary wooden box supports. Location-Conference room make euroceil	6	sqm	1,367.00	8,202.00	
4.05	**Open ceiling paint** - Supply and apply fenomastic paint to the open ceiling including MEP services.	135	sqm	49.00	6,615.00	
4.06	**Paint** - Supply and apply 2coats fenomastic paint to the gypsum ceiling with primer&stucco base Make-Jotun	128	sqm	36.00	4,608.00	
4.07	**Gypsum bulkhead -** Supply and installation of gypsum bulkhead-**open ceiling area**	10	lm	126.00	1,260.00	
4.08	**Curtain Pelmet** - supply and installation of gypsum curtain pelmet with mdf backing	42	lm	161.00	6,762.00	
4.09	**Access Panel** - 600mmx600mm gypsum square shape access panel	6	Nos	389.00	2,334.00	
				SUB TOTAL CEILING	**54,769.00**	
5.00	**WALL FINISHES**					
5.01	**Wall paint** - Supply and apply of 2coats fenomastic emulsion wall paint with primer&stucco base Make - Jotun	100	sqm	36.00	3,600.00	
5.02	**Texture paint -** Supply and apply of texture wall paint. Make- Jotun Lady design	25	sqm	153.00	3,825.00	
5.03	**Wall paint** - Supply and apply of 2coats fenomastic grey wall paint above the false ceiling level @open ceiling area Make - Jotun	39	Lmt	36.00	1,404.00	
5.04	**Back Painted Glass -** Supply and installation of 6mm thick back painted glass cladding with proper MDf backing	27	sqm	813.00	21,951.00	
5.05	**Acoustic wallpaper -** Supply and installation of acoustic wallpaper with glue&wall preparation works Make-NGC Nafees	40	sqm	569.00	22,760.00	
5.06	**Graphics -** Supply and installation of graphics with glue&wall preparation works	10	sqm	168.00	1,680.00	
5.07	**MDF Skirting** - Supply and installation of 100mm high painted MDF skirting.	134	lm	50.00	6,700.00	
5.08	**Frosted Film** - Supply and installation of Frosted film on the glass partition and doors @ 1.2m height	21	sqm	138.00	2,898.00	
5.09	**Laminated panelling** - Supply and installation of laminated panelling on wall with proper back supports	62	sqm	584.00	36,208.00	
5.10	**Marble cladding** - Supply and installation of Travertino marble cladding on wall with proper MDF back supports	15	sqm	1,378.00	20,670.00	
				SUB TOTAL WALL FINISHES	**121,696.00**	
6.00	**DOOR WORKS**					

PROJECT : Amalgama MS 3604 JBC 4 DMCC – Design & Build RFP No. (AMALG-2024-RFP-01)						
ID WORKS						Date: 16/12/2024
6.01	Supply and installation of framed single leaf swing door using 13.52mm thick acoustic laminated glass with QIC Evolution outerframe (Size-44x68mm) and QAS Integra Shutter frame (56x30mm) ,fitted with GEZE Floor spring, Offset Straps, bottom lock and 1200mm long pull handle. (32mm dia, 1000mm C/C). All fittings are in powder coated finish. (Acoustic Rating-Rw 38dB) Size-900x2400mm	6	No	6,917.00	41,502.00	
6.02	Supply & install of fire rated wooden door made in wood frame & architraves. Shutter to have 54 mm thk flush door shutter in both side in laminatedfinish. Size: 1000 x 2200 mm @Server room	1	No.	4,046.00	4,046.00	Ironmongeries PC rate considered 400 AED/set.
6.03	Supply & install of NFR sliding wooden door made in wood frame & architrave . Shutter have 45 mm thk flush door shutter in both side laminate finish. Size: 1500 x 2200 mm	1	No.	6,750.00	6,750.00	
6.04	Refurbishment of existing wooden door matching to new finish by existing ironmongeries. Size: 1800mmL x 2200 mm Ht Location : Main entrance	1	Nos.	4,500.00	4,500.00	
6.05	Refurbishment of existing wooden door matching to new finish by existing ironmongeries. Size: 800mmL x 2200 mm Ht Location : Toilet	2	Nos.	2,250.00	4,500.00	
6.06	NEW FR DOOR Supply & install of fire rated wooden door made in wood frame & architraves. Shutter to have 54 mm thk flush door shutter in both side Laminated finish Size: 1900 x 2200 mm	1	Nos.	7,600.00	RATE ONLY	
				SUB TOTAL DOOR	**61,298.00**	
7.00	**JOINERY WORKS**					
	Custom made Joinery					
7.01	**Recepion table** O/a size: 1870mm (L)x900mm (W)x1000mm (ht) - The upper counter shall be in corian.The lower counter top, front fascia & sides shall be in travertine finish. The internal carcass shall be in melamine finish. Movable Lockable pedestal shall be in melamine finish.	1	No.	16,230.00	16,230.00	
7.02	**Meeting room TV wall unit.** Made of the MDF with oak veneer look laminate finish and necessary MDF frame work and metal support for TV. Size - 1760x200x2500mm ht.	2	No.	2,313.00	4,626.00	
7.03	MDF slatted cladding in lamiante finish. O/a size: 50x150mm with a spacing of 200mm	20	No.	338.00	6,760.00	

PROJECT : Amalgama MS 3604 JBC 4 DMCC – Design & Build RFP No. (AMALG-2024-RFP-01)

ID WORKS Date: 16/12/2024

7.04	Planter box O/a size: 1600mm (L)x400mm (D)x900mm (Ht) For Live plant. Including storage cabinet. The inside of storage cabinet shall be in melamine finish with adjustable shelfs. 1.2mm thick G.I tray considered for fixing live plants. Planter box O/a size: 1600mm (L)x400mm (D)x900mm (Ht) For Live plant. Including storage cabinet. The inside of storage cabinet shall be in melamine finish with adjustable shelfs. 1.2mm thick G.I tray considered for fixing live plants.	4	No.	3,185.00	12,740.00	
7.05	Full height storage unit in laminate finish O/a size: 4150mm (L)x600mm(W)x2400mm (Ht)	1	No.	12,580.00	12,580.00	
7.06	Pantry Cabinet Lower counter O/a size: 2250mm(L)x600mm(W)x 900mm(Ht) - item shall be manufactured in MDF laminated finish shutters, fixed shelfs & counter top & back splash shall be in corian counter top for the coffee machine area. Over head cabinet 2250mm(L)x450mm(W)x600mm(Ht) item shall be manufactured in MDF laminated finish shutters & fixed shelfs.	1	No.	12,989.00	12,989.00	
7.07	High Table O/a size: 2250mm(L)x600mm(W)x950mm (Ht) in MDF laminated finish with M.S 20x30mm R.H.S tube in black powder coated finish.	1	No.	5,063.00	5,063.00	
7.08	Printer area over head cabinet in MDF laminated finish for shutters and internal carcass of the unit. O/a size: 1500mm (L)x450mm(W)x900mm (Ht)	1	No.	2,350.00	2,350.00	
				SUB TOTAL JOINERY	**73,338.00**	
8.00	**LOGO**					
8.01	Supply and installation of logo	1	No.	2,778.00	2,778.00	
				SUB TOTAL LOGO WORKS	**2,778.00**	
9.00	**PLANTS**					
9.01	Plants with pot	9	No.	3,524.00	31,716.00	
9.02	Plants on planter box	4	set	3,623.00	14,492.00	
				SUB TOTAL PLANTS	**46,208.00**	
10.00	**WHITE GOODS**					
10.01	Water dispensor	1	No.	750.00	750.00	
10.02	Kettle Make Midea 1.7 ltr	1	No.	188.00	188.00	
10.03	Microwave oven make Midea 25 ltr	1	No.	438.00	438.00	
10.04	Built in fridge	1	No.	1,500.00	1,500.00	
10.05	Waste bin	1	No.	313.00	313.00	
				SUB TOTAL WHITE GOODS	**3,189.00**	

PROJECT : Amalgama MS 3604 JBC 4 DMCC – Design & Build RFP No. (AMALG-2024-RFP-01)						
ID WORKS					Date: 16/12/2024	
11.00	**BLINDS**					
11.01	Supply and fixing of sunscreen manual roller blinds Make-Global shades	115	sqm	95.00	10,925.00	
11.02	Supply and fixing of sunscreen motorized roller blinds 13sqm Motor 5nos Somfy Remote 1nos Location-Conference room	1	Item	8,264.00	Rate only	
				SUB TOTAL BLINDS	**10,925.00**	

PROJECT : Amalgama MS 3604 JBC 4 DMCC – Design & Build RFP No. (AMALG-2024-RFP-01)						
MEP&LIGHTING BOQ						16/12/2024
Sl NO.	**DESCRIPTION**	**QTY**	**UNIT**	**RATE**	**AMOUNT**	**COMMENTS**
1	**LIGHTING FIXTURES WORKS**					
1.1	***Supply of Light fittings / fixtures as per received proposed drawings / all in accordance with design visual : Non- dimmable.***					
1.101	**Recessed trimless spot light**	44	Nos	181.00	7,964.00	
1.102	**Decorative suspended light Dia - 450mm**	23	Nos	938.00	21,574.00	
1.103	**Suspended Linear lights Dim : 1500mm L**	7	Nos	563.00	3,941.00	
1.104	**Decorative Linear lights 1 Dim : 1500mm L**	3	Nos	1,750.00	5,250.00	
1.105	**Decorative Linear lights 2 Dim : 1500mm L**	1	Nos	2,750.00	2,750.00	
1.106	**Decorative Suspendedn lights 2 Dim : 800mm Dia**	1	Nos	3,000.00	3,000.00	
1.107	**Twin spot box light**	5	Nos	400.00	2,000.00	
1.108	**LED Strip lights**	35	m	81.00	2,835.00	
1.109	**Lights for existing toilets**					**Existing lights to be reused.**
				TOTAL FOR LIGHT FIXTURES		**49,314.00**
2	**ELECTRICAL WORK**					
2.1	***Power distribuition SMDB / DB works:***					

PROJECT : Amalgama MS 3604 JBC 4 DMCC – Design & Build RFP No. (AMALG-2024-RFP-01)						
MEP&LIGHTING BOQ						16/12/2024
Sl NO.	**DESCRIPTION**	**QTY**	**UNIT**	**RATE**	**AMOUNT**	**COMMENTS**
2.101	Modification, relocation of existing DB	1	Nos	6,250.00	6,250.00	
2.2	***Power cabling works :***					
2.201	Incoming cables for the DB				N/A	**Existing to be reused**
2.3	***Cable tray and trunking works for Power cables:***					
2.301	Supply and installation of cable trunking for **Power** distributions at **high level**.	1	Item	3,250.00	3,250.00	
2.302	Supply and installation of cable trunking for **Light** distributions at **high level.**	1	Item	3,250.00	3,250.00	
2.303	Supply and installation of cable trunking for **data cables** distributions at **high level.**	1	Item	2,500.00	2,500.00	
2.4	***Isolator as per the power requirements.***				***N/A***	
2.5	***Light Installation works***					
2.501	Supply and installation of **PVC** Conduit and wiring for the light fixtures	84	Nos	181.00	15,204.00	
2.502	Supply and installation of **PVC** Conduit and wiring for the Strip light	35	Mtr	63.00	2,205.00	
2.503	Installation of technical light fixtures	79	Nos	35.00	2,765.00	
2.504	Installation of LED strip lights	35	Mtr	35.00	1,225.00	
2.505	Installation of Decorative / Pendant lights	5	Nos	104.00	520.00	
2.6	***Switches Installation & Supply of lighting control system works:***					
2.601	Supply and installation of **1 Gang 1 Way** Switch *Brand : MK / SCHNEIDER* *Finishes: PVC WHITE FINISH*	5	Nos	194.00	970.00	
2.602	Supply and installation of **2 Gang 1 Way** Switch *Brand :* *Finishes:*	3	Nos	222.00	666.00	
2.603	Supply and installation of **3 Gang 1 Way** Switch *Brand :* *Finishes:*	2	Nos	264.00	528.00	
2.604	Supply and installation of **Light control system** - Dali type with Button Keypad				N/A	
2.605	Supply and installation of **Motion sensors / PIR Motion / Occupancy sensors.** *Brand : Schneider / equivalent* *Locations : Pantry, Entrance, Board room.*				N/A	
2.7	***Power Sockets Installation works***					

PROJECT : Amalgama MS 3604 JBC 4 DMCC – Design & Build RFP No. (AMALG-2024-RFP-01)						
MEP&LIGHTING BOQ						16/12/2024
Sl NO.	**DESCRIPTION**	**QTY**	**UNIT**	**RATE**	**AMOUNT**	**COMMENTS**
2.701	Supply & installation of **13A Single power** socket with necessary conduiting, wiring and accessories. *Brand : MK / Schneider / Legrand equivalent* *Finishes : PVC White*	5	Nos	361.00	1,805.00	
2.702	Supply & installation of **13A Double power** socket with necessary conduiting, wiring and accessories. *Brand : MK / Schneider / Legrand equivalent* *Finishes : PVC White*	10	Nos	403.00	4,030.00	
2.703	Modfication of existing water heater power	1	Nos	347.00	347.00	
2.704	Supply & installation of **FB1** Three Compartment Floor box, including wiring and PVC coated GI flexibles / PVC flexibles Config: 1 Nos. - 13A Twin Socket outlets, spaces for 2 nos. data outlets, spaces for 1 No of HDMI. *Brand: Davis / equivalent.*	14	Nos	903.00	12,642.00	
2.705	Supply and installation of **13A unswitched spur outlet** including containment and wiring for Motorized blinds.	1	Nos	417.00	RATE ONLY	
2.706	Supply and installation of **13A unswitched spur outlet** including containment and wiring for VAV	7	Nos	417.00	2,919.00	
2.706	Supply and installation of **13A switched fused spur outlet** including containment and wiring for FACP, 24/7 DCD panel, Emergency panel, MSFD	4	Nos	417.00	1,668.00	
2.707	Supply and installation of **16A/32A commando socket for IT racks** including necessary containment and wiring accessories for Dishwasher, Washing machine.	1	Nos	1,111.00	1,111.00	
2.708	Allow cost for power supply for **FCUs** - Type Chilled water indoor units	3	Nos	417.00	1,251.00	
2.8	***Containment works***					
2.801	Supply and installation of PVC Conduit for **IT Data** points	50	Nos	139.00	6,950.00	
2.802	Supply and installation of PVC / GI Conduit for **HDMI** points	2	Nos	208.00	416.00	
2.803	Supply and installation of PVC Conduit for **Access** points	1	Nos	208.00	208.00	
2.804	Supply and installation of PVC Conduit for **Wi-fi** points	4	Nos	139.00	556.00	
2.805	Supply and installation of PVC Conduit for **Camera**	4	Nos	139.00	556.00	
2.806	Supply and installation of GI Conduit for **AV** works like speakers, Projectors, Room booking system etc.	1	Item	2,083.00	2,083.00	
2.807	PVC Conduiting works involved in carrying **Fiber optic** cabling Works from building IT room to proposed premises.	1	Item	1,111.00	1,111.00	
2.9	***Sundries***					
2.901	Allow for **testing and commissioning** of electrical services (Any 3rd party testing and certifications excluded)	1	Item	694.00	694.00	
2.902	Allow for documents submissions like shop drawings, As-built **drawings,** operating instructions and maintenance manuals **(O&Ms**) as per built specifications.	1	Item	1,111.00	1,111.00	
2.903	**Civil works** related with MEP works such as chasing and chipping on wall and floor, Wall & ceiling cutting for services to install and making ready to receive final finishes, AC grill cutting and its related finishing civil works etc.	1	Item	1,111.00	1,111.00	

PROJECT : Amalgama MS 3604 JBC 4 DMCC – Design & Build RFP No. (AMALG-2024-RFP-01)						
MEP&LIGHTING BOQ						16/12/2024
Sl NO.	**DESCRIPTION**	**QTY**	**UNIT**	**RATE**	**AMOUNT**	**COMMENTS**
2.904	Allow for identification **labels** including plates, discs, labels, charts and color coding for electrical services.	1	Item	417.00	417.00	
				TOTAL FOR ELECTRICAL WORKS		**80,319.00**
3	**HVAC WORKS**					
3.1	***AC Works***					
3.001	Supply or Any relocation Chilled water FCU's supports & necessary accessories				Excluded	
3.002	Relocation of exsiting Thermostarts	3	Nos	556.00	1,668.00	
3.003	Supply and installation of VAV's with fittings supports & necessary accessories (Closed rooms)	7	Nos	3,333.00	23,331.00	**If in future any VAV's requires will be considered it as a variation.**
3.004	Supply and installation of Thermostarts VAV's	7	Nos	600.00	4,200.00	
3.005	Supply and installation of GI Ducting ,fittings supports & necessary accessories (SAD/RAD)	90	Sq mt	278.00	25,020.00	**Existing FCU's are reused and to be placed in same location as existing.**
3.006	Supply and installation of GI Ducting ,fittings supports & necessary accessories (FAD/EAD)	1	Item	4,861.00	4,861.00	
3.007	Supply and installation of Accostic lining with necessary accessories	45	Sq mt	90.00	4,050.00	
3.008	Supply and installation of CTA Closed offices	7	Nos	1,181.00	8,267.00	
3.009	Supply and installation of MSFD -Server room	1	Nos	3,472.00	3,472.00	
3.01	Supply linear slot diffuser	25	Mtrs	250.00	6,250.00	
3.011	Return linear slot diffuser	25	Mtrs	222.00	5,550.00	
3.012	Supply and installation of Square diffusers	16	Nos	208.00	3,328.00	
3.013	Plenum boxes for Supply of Air Outlets	1	Item	8,257.00	8,257.00	
3.014	Supply and installation of VCDs	1	Item	5,410.00	5,410.00	
3.015	Supply and installation of flexible,and other necessary fixtures	1	Item	3,701.00	3,701.00	
3.016	Chemical flushing (Water bird)	1	Nos	9,375.00	9,375.00	**To be include If Client requires.**
3.017	Air balancing & Testing & commissioning	1	Item	2,083.00	2,083.00	
3.018	Performance testing Existing FCU's	3	Nos	903.00	2,709.00	
3.019	Intergration of BMS works	1	Item	45,000.00	45,000.00	**Modification of existing BMS for new VAVs and to be connected with existing Building BMS.**
				TOTAL FOR HVAC WORKS		**166,532.00**
4	**CIVIL DEFENSE WORKS**					
4.1	**FIRE ALARM WORKS**					

PROJECT : Amalgama MS 3604 JBC 4 DMCC – Design & Build RFP No. (AMALG-2024-RFP-01)						
MEP&LIGHTING BOQ						16/12/2024
Sl NO.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT	COMMENTS
4.101	Supply and installation of Single loop Fire Addressable Alarm Control Panel **(FACP)**	1	Nos	16,667.00	16,667.00	
4.102	Supply and Installation of new addressable optical **smoke** detectors with built in isolator base.	9	Nos	1,040.00	9,360.00	
4.103	Relocation of existing Smoke detector , heat detector	5	Nos	533.00	2,665.00	
4.104	Supply & Installation of Addressable **break glass / Manual call point** with cover	1	Nos	1,200.00	1,200.00	
4.105	Supply & Installation of Addressable **sounder**	1	Nos	1,200.00	1,200.00	
4.106	Supply and Installation of **flasher**	1	Nos	1,200.00	1,200.00	
4.107	Supply and Installation of New IFU with Necessary Wiring and accessories for interfacing with DCD panel, EMP	2	Nos	1,467.00	2,934.00	
4.108	Supply and Installation of New IFU with Necessary Wiring and accessories for Building FACP	2	Nos	1,467.00	2,934.00	
4.109	Programming of new fire alarm panel to include existing and new smoke detector loops.	1	Item	11,333.00	11,333.00	
4.11	Connection to building Main FACP	1	Item	1,600.00	1,600.00	
				TOTAL FOR FIRE ALARM WORKS		**51,093.00**
4.2	**EMERGENCY AND EXIT LIGHT WORKS**					
4.201	Supply & Installation of Self Contained New Emergency with necessary wiring and accessories	7	Nos	767.00	5,369.00	
4.202	Supply & Installation of New Self-contained Exit Light with necessary wiring and accessories	1	Nos	800.00	800.00	
4.203	Supply & Installation of New Self-contained Directional Exit Light with necessary wiring and accessories	1	Nos	767.00	767.00	
4.204	Supply and installation of emergency monitoring panel **(EMP)**	1	Nos	8,667.00	8,667.00	
4.205	Programing, Testing and commissioning for the Emergency panel	1	item	667.00	667.00	
				TOTAL FOR EMERGENCY AND EXIT LIGHT WORKS		**16,270.00**
4.3	**FIRE FIGHTING WORKS**					
4.301	Relocation of Pendent sprinklers to Upright sprinklers	12	Nos	533.00	6,396.00	
4.302	Relocation of Pendent sprinklers	13	Nos	533.00	6,929.00	
4.303	Supply and installation of Additional New Pendent Sprinkler	5	Nos	733.00	3,665.00	
4.304	Fire extinguisher set	4	Nos	600.00	2,400.00	
4.305	Shop drawing prepration and cordination for DCD approval	1	LS	1,333.00	1,333.00	
4.306	Charges for Zone control valve closing and pressure test	1	Nos	4,667.00	4,667.00	

PROJECT : Amalgama MS 3604 JBC 4 DMCC – Design & Build RFP No. (AMALG-2024-RFP-01)						
MEP&LIGHTING BOQ						16/12/2024
Sl NO.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT	COMMENTS
			TOTAL FOR FIRE FIGHTING WORKS			25,390.00

PROJECT : Amalgama MS 3604 JBC 4 DMCC – Design & Build RFP No. (AMALG-2024-RFP-01)						
IT/AV WORKS						Date: 16/12/2024
Sl NO.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT	REFERENCE
1.00	IT WORK					
	STRUCTURED CABLING SYSTEM					
	Horizontal CAT6A Cabling - Brand : Corning					
1.01	Faceplate, 86x86, 1 Port, Arctic White	5	Nos	10.00	50.00	
1.02	Sloped Shuttered Adapter, 1 Port, Arctic White PK/10	48	Nos	10.00	480.00	
1.03	UTP RJ45 Cat 6A Keystone Punchdown Jack Module, AW for Patch panel	53	Nos	25.00	1,325.00	
1.04	UTP RJ45 Cat 6A Keystone Punchdown Jack Module, AW for Floor box / Wall socket	53	Nos	25.00	1,325.00	
1.05	Copper Cable, Cat 6A, 23 AWG, U/UTP, LSZH-1, 500m/roll	6	Nos	1,458.00	8,748.00	
1.06	Network rack Make-Avalon	1	Nos	3,889.00	3,889.00	
1.07	06WAY PDU UNIVERSAL SOCKET WITH SWITCH, 13AMP, 1.8MTR CABLE LENGTH, UK PLUG, 19" INSTALLATION	1	Nos	174.00	174.00	
1.08	Category 6A U/UTP Patch Cord E Series PVC 01 MTR	53	Nos	28.00	1,484.00	
1.09	Category 6A U/UTP Patch Cord E Series PVC 03 MTR	53	Nos	33.00	1,749.00	
1.10	Installation Testing and Commissioning (Including Calibrated Fluke Testing and documentation)	53	Nos	167.00	8,851.00	
1.11	Supply and installation of 8 core single mode cable from server room to floor telephone room to hire ISP services	1	LS	3,472.00	3,472.00	
1.12	Supply and installation of Ubiquiti Wi-fi Access points	4	Nos	1,042.00	4,168.00	
1.13	Supply and installation wifi- controller	1	Nos	1,736.00	1,736.00	
1.14	Testing and commisioning	1	Item	903.00	903.00	
	SUB TOTAL STRUCTURED CABLING				38,354.00	
2.00	AV WORKS					
2.01	Supply and installation of 65" Samsung TV including cabling and wall mounts for small meeting room	1	Nos	4,625.00	4,625.00	
2.02	Supply and installation of 85" Samsung TV including cabling and wall mounts for Conference room.	1	Nos	9,750.00	9,750.00	
2.03	Supply and installation Kramer Cable cubby with 2 data and 2 power and 1 HDMI	2	Nos	3,800.00	7,600.00	
2.04	Supply and installation of Logitech Rally plus (2 Mics, 2 Speakers, + Camera) device support BYOD	1	Nos	9,206.00	9,206.00	
2.05	Supply and installation of 65" Samsung TV including cabling and wall mounts for Manager	1	Nos	4,625.00	Rate only	
	SUB TOTAL AV				31,181.00	

QUOTATION

DATE: 13 December 2024
Quotation #: DC-131224-020-VS

PROJECT : Amalgama

SCOPE OF WORK : SUPPLY AND INSTALLATION OF FURNITURE

Sl NO.	DESCRIPTION	VISUAL PRESENTATION	QTY	UNIT	UNI RATE	TOTAL (AED)
Lounge / Waiting Area						
1	Task Chair - Seat: fabric upholstered (only 4 options available). - Back: mesh upholstered (only 4 options available). - Armrest: nylon. - Synchronized-tilting system with lock. - Nylon base. -Frame: grey. Dimension: W710 x D640 x H1040 - 1115 mm Origin: FarEast Delivery: 11-12 Weeks Warranty: 5 Years (Against Manufacturing Defects)		1	EA	730.00	730.00
2	Armchair - Fabric upholstered. - Powder coated steel leg. Dimension: W780 x D780 x H930 mm Origin: FarEast Delivery: 11-12 Weeks Warranty: 5 Years (Against Manufacturing Defects)		1	EA	2,464.00	2,464.00
3	Side Table - MDF painted top and base. Dimension: Dia 450; H500 mm Origin: FarEast Delivery: 11-12 Weeks Warranty: 5 Years (Against Manufacturing Defects)		1	EA	1,590.00	1,590.00
Conference Room - 12 Pax.						
4	Meeting Table - 36mm wood veneer tabletop with PU leather upholstered flip-up. - Stainless steel leg with veneer support box under. - Under channel included, wire from melamine box. - 3pcs of stainless steel legs included. **- PDU not included. Quoted seperately.** Dimension: W4000 x D1200 x H750 mm Origin: FarEast Delivery: 11-12 Weeks Warranty: 5 Years (Against Manufacturing Defects)		1	EA	13,210.00	13,210.00

5	PDU for Meeting Table - Motorized rotary. - Aluminum based plain surface when closed. - Frame / cover and side parts color: black. - Motorized frame opening - switch button. - Finish: black or silver. - 2 x UK power sockets. - 2 x data cat 6A RJ45 with 3 meter cable. - 1 x HDMI with cable. - 1 x twin USB power charger (Type A+C). - 1 x wireless charger. - 3 meter power cable with UK plug. Origin: DI-UAE Delivery: 4-6 Weeks Warranty: 5 Years (Against Manufacturing Defects)		2	EA	1,472.00	2,944.00
6	Meeting Chair - High quality PU leather back and seat. - Aluminium armrest with soft PU pad. - Synchronized-tilting system with lock. - Aluminium leg. Dimension: W670 x D660 x H840 - 900 mm Origin: FarEast Delivery: 11-12 Weeks Warranty: 5 Years (Against Manufacturing Defects)		12	EA	1,464.00	17,568.00
Meeting Room - 4 Pax.						
7	Meeting Table - Table top material: thickness: 25mm. - Core material: E1 particle board from FSC certified factory. - Decor paper: schattdecor from Germany - PVC edge, knife edge. - Leg: steel - Snake pipe is included. **- PDU not included. Quoted seperately.** Dimension: Dia 1100; H750 mm Origin: FarEast Delivery: 11-12 Weeks Warranty: 5 Years (Against Manufacturing Defects)		1	EA	1,995.00	1,995.00
8	PDU for Meeting Table - Flexpoint 80UK/R22 (white) power grommet. - 1 x universal power sockets. - 1 x HDMI coupler. - 1 x USB Type A power charger. - 2 x USB Type C power charger. - 3 meter power cable with UK plug. - Color: White. Cut Out Dimension: Dia 800 mm Origin: DI-UAE Delivery: 4-6 Weeks Warranty: 5 Years (Against Manufacturing Defects)		1	EA	493.00	493.00

9	Meeting Chair - High quality PU leather back and seat. - Fixed aluminium armrest. - Tilting system with lock. - Aluminium leg. - Height adjustable. Dimension: W580 x D620 x H840-940 mm Origin: FarEast Delivery: 11-12 Weeks Warranty: 5 Years (Against Manufacturing Defects)		4	EA	1,254.00	5,016.00
Cabin 01						
10	Executive Desk - (L Shaped) - Table top material: thickness: 25mm. - Core material: E1 particle board from FSC certified factory. - Decor paper: schattdecor from Germany. - PVC edge. - Steel leg. - Sideboard with open shelf in front+open shelf at side + swing door + 3 drawers. (1600mm side cabinet is with 1 swing door) - Flip aluminium cover and steel wire box under for wiring is included. - Melamine privacy panel and snake pipe is included. **- PDU not included. Quoted seperately.** Overall Dimension: W2200 x D2000 x H750 mm Desk Dimension: W2200 x D800 x H750 mm Side Return Dimension: W2000 x D500 x H625 mm Origin: FarEast Delivery: 11-12 Weeks Warranty: 5 Years (Against Manufacturing Defects)		1	EA	4,422.00	4,422.00
OPT - 2	Height Adjustable Executive Desk - (L Shaped) - **(OPT - 2)** - Table top material: thickness: 18mm. - Core material: E1 particle board from FSC certified factory. - Decor paper: schattdecor from Germany. - PVC edge. - Electrical height adjustable frame. - Timotion Dual motor. - Weight capacity: 120 kg. - Electrical control. - 2 tubes height range 710-1170 mm. - Flip-up and cable tray is included. - Side cabinet with 2 drawers + 2 swing doors + open + 1 swing door. - Modesty panel and snake spine is included. **- PDU not included. Quoted seperately.** Overall Dimension: W2200 x D2000 x H750 mm Desk Dimension: W2200 x D800 x H750 mm Side Return Dimension: W2000 x D450 x H550 mm Origin: FarEast Delivery: 11-12 Weeks Warranty: 5 Years (Against Manufacturing Defects)		1	EA	5,414.00	**RATE ONLY**

11	PDU for Executive Desk - Full black finish. - Push to open mechanism. - 3 x Universal power sockets, 230v. - 1 x data cat 6A RJ 45 with 3 meter data cable. - 1 x twin USB (Type A+C) fast charging - 5V (30W). - 3 meter power cable with UK plug. Origin: DI-UAE Delivery: 4-6 Weeks Warranty: 5 Years (Against Manufacturing Defects)		1	EA	1,043.00	1,043.00
12	Executive Chair - High quality PU leather back& seat. - Fixed aluminium armrest with soft PU pad. - Imported Donati mechanism from Italy. - Lockable at 5 different positions. - Aluminium leg. Dimension: W680 x D660 x H1130 - 1190 mm Origin: FarEast Delivery: 11-12 Weeks Warranty: 5 Years (Against Manufacturing Defects)		1	EA	1,639.00	1,639.00
13	Visitor Chair - High quality PU leather back and seat. - Fixed aluminium armrest. - Tilting system with lock. - Aluminium leg. - Height adjustable. Dimension: W580 x D620 x H840 - 940 mm Origin: FarEast Delivery: 11-12 Weeks Warranty: 5 Years (Against Manufacturing Defects)		2	EA	1,254.00	2,508.00
14	Cabinet - Melamine board cabinet. - With open shelf. - DSwing doors. - With lock. - Movable shelf inside Dimension: W2200 x 450 x H880 mm Origin: FarEast Delivery: 11-12 Weeks Warranty: 5 Years (Against Manufacturing Defects)		1	EA	3,548.00	3,548.00
Cabin 02						

15	Executive Desk - (L Shaped) - Table top material: thickness: 25mm. - Core material: E1 particle board from FSC certified factory. - Decor paper: schattdecor from Germany. - PVC edge. - Steel leg. - Sideboard with open shelf in front+open shelf at side + swing door + 3 drawers. (1600mm side cabinet is with 1 swing door) - Flip aluminium cover and steel wire box under for wiring is included. - Melamine privacy panel and snake pipe is included. **- PDU not included. Quoted seperately.** Overall Dimension: W2200 x D2000 x H750 mm Desk Dimension: W2200 x D800 x H750 mm Side Return Dimension: W2000 x D500 x H625 mm Origin: FarEast Delivery: 11-12 Weeks Warranty: 5 Years (Against Manufacturing Defects)		1	EA	4,422.00	4,422.00
OPT - 2	Height Adjustable Executive Desk - (L Shaped) - **(OPT - 2)** - Table top material: thickness: 18mm. - Core material: E1 particle board from FSC certified factory. - Decor paper: schattdecor from Germany. - PVC edge. - Electrical height adjustable frame. - Timotion Dual motor. - Weight capacity: 120 kg. - Electrical control. - 2 tubes height range 710-1170 mm. - Flip-up and cable tray is included. - Side cabinet with 2 drawers + 2 swing doors + open + 1 swing door. - Modesty panel and snake spine is included. **- PDU not included. Quoted seperately.** Overall Dimension: W2200 x D2000 x H750 mm Desk Dimension: W2200 x D800 x H750 mm Side Return Dimension: W2000 x D450 x H550 mm Origin: FarEast Delivery: 11-12 Weeks Warranty: 5 Years (Against Manufacturing Defects)		1	EA	5,414.00	**RATE ONLY**
16	PDU for Executive Desk - Full black finish. - Push to open mechanism. - 3 x Universal power sockets, 230v. - 1 x data cat 6A RJ 45 with 3 meter data cable. - 1 x twin USB (Type A+C) fast charging - 5V (30W). - 3 meter power cable with UK plug. Origin: DI-UAE Delivery: 4-6 Weeks Warranty: 5 Years (Against Manufacturing Defects)		1	EA	1,043.00	1,043.00

17	Executive Chair - High quality PU leather back& seat. - Fixed aluminium armrest with soft PU pad. - Imported Donati mechanism from Italy. - Lockable at 5 different positions. - Aluminium leg. Dimension: W680 x D660 x H1130 - 1190 mm Origin: FarEast Delivery: 11-12 Weeks Warranty: 5 Years (Against Manufacturing Defects)		1	EA	1,639.00	1,639.00
18	Visitor Chair - High quality PU leather back and seat. - Fixed aluminium armrest. - Tilting system with lock. - Aluminium leg. - Height adjustable. Dimension: W580 x D620 x H840 - 940 mm Origin: FarEast Delivery: 11-12 Weeks Warranty: 5 Years (Against Manufacturing Defects)		2	EA	1,254.00	2,508.00
19	Cabinet - Melamine board cabinet. - With open shelf. - DSwing doors. - With lock. - Movable shelf inside Dimension: W2200 x 450 x H880 mm Origin: FarEast Delivery: 11-12 Weeks Warranty: 5 Years (Against Manufacturing Defects)		1	EA	3,548.00	3,548.00
MD Cabin						
20	Executive Desk - (L Shaped) - Table top material: thickness: 25mm. - Core material: E1 particle board from FSC certified factory. - Decor paper: schattdecor from Germany. - PVC edge. - Steel leg. - Sideboard with open shelf in front+open shelf at side + swing door + 3 drawers. (1600mm side cabinet is with 1 swing door) - Flip aluminium cover and steel wire box under for wiring is included. - Melamine privacy panel and snake pipe is included. **- PDU not included. Quoted seperately.** Overall Dimension: W2200 x D2000 x H750 mm Desk Dimension: W2200 x D800 x H750 mm Side Return Dimension: W2000 x D500 x H625 mm Origin: FarEast Delivery: 11-12 Weeks Warranty: 5 Years (Against Manufacturing Defects)		1	EA	4,422.00	4,422.00

OPT - 2	Height Adjustable Executive Desk - (L Shaped) - **(OPT - 2)** - Table top material: thickness: 18mm. - Core material: E1 particle board from FSC certified factory. - Decor paper: schattdecor from Germany. - PVC edge. - Electrical height adjustable frame. - Timotion Dual motor. - Weight capacity: 120 kg. - Electrical control. - 2 tubes height range 710-1170 mm. - Flip-up and cable tray is included. - Side cabinet with 2 drawers + 2 swing doors + open + 1 swing door. - Modesty panel and snake spine is included. **- PDU not included. Quoted seperately.** Overall Dimension: W2200 x D2000 x H750 mm Desk Dimension: W2200 x D800 x H750 mm Side Return Dimension: W2000 x D450 x H550 mm Origin: FarEast Delivery: 11-12 Weeks Warranty: 5 Years (Against Manufacturing Defects)		1	EA	5,414.00	**RATE ONLY**
21	PDU for Executive Desk - Full black finish. - Push to open mechanism. - 3 x Universal power sockets, 230v. - 1 x data cat 6A RJ 45 with 3 meter data cable. - 1 x twin USB (Type A+C) fast charging - 5V (30W). - 3 meter power cable with UK plug. Origin: DI-UAE Delivery: 4-6 Weeks Warranty: 5 Years (Against Manufacturing Defects)		1	EA	1,043.00	1,043.00
22	Executive Chair - High quality PU leather back& seat. - Fixed aluminium armrest with soft PU pad. - Imported Donati mechanism from Italy. - Lockable at 5 different positions. - Aluminium leg. Dimension: W680 x D660 x H1130 - 1190 mm Origin: FarEast Delivery: 11-12 Weeks Warranty: 5 Years (Against Manufacturing Defects)		1	EA	1,639.00	1,639.00
23	Visitor Chair - High quality PU leather back and seat. - Fixed aluminium armrest. - Tilting system with lock. - Aluminium leg. - Height adjustable. Dimension: W580 x D620 x H840 - 940 mm Origin: FarEast Delivery: 11-12 Weeks Warranty: 5 Years (Against Manufacturing Defects)		2	EA	1,254.00	2,508.00

24	Cabinet - Melamine board cabinet. - With open shelf. - DSwing doors. - With lock. - Movable shelf inside Dimension: W2200 x 450 x H880 mm Origin: FarEast Delivery: 11-12 Weeks Warranty: 5 Years (Against Manufacturing Defects)		1	EA	3,548.00	3,548.00
25	Single Seater Sofa - Fabric upholstered. - Stainless steel leg in electroplated gold finish. - Including 1pc of cushion. Dimension: W1063 x D885 x H735 mm Origin: FarEast Delivery: 11-12 Weeks Warranty: 5 Years (Against Manufacturing Defects)		1	EA	2,848.00	2,848.00
26	2 - Seater Sofa - Fabric upholstered. - Stainless steel leg in electroplated gold finish. - Including 2 pcs of cushion. Dimension: W2300 x D890 x H735 mm Origin: FarEast Delivery: 11-12 Weeks Warranty: 5 Years (Against Manufacturing Defects)		1	EA	4,645.00	4,645.00
27	Side Table - Marble top. - Stainless steel leg in electroplated gold finish. Dimension: Dia 500; H540 mm Origin: FarEast Delivery: 11-12 Weeks Warranty: 5 Years (Against Manufacturing Defects)		2	EA	1,688.00	3,376.00
Open Workstations - 15 Pax.						
28	Workstation (Face To Face) - 4 Pax. - Table top material: thickness: 25 mm. - Core material: E1 particle board from FSC certified factory. - Decor paper: schattdecor from Germany. - PVC edge. - Leg: steel leg. - Flip aluminium cover and steel wire box under for wiring is included. - Fabric screen panel (middle panel) and snake pipe is included. **- Mobile pedestal not included. Quoted seperately.** **- PDU not included. Quoted seperately.** Overall Dimension: W2800 x D1400 x H750 mm Desk Dimension: W1400 x D700 x H750 mm Screen Dimension: W1200 x D300 x H20 mm Origin: FarEast Delivery: 11-12 Weeks Warranty: 5 Years (Against Manufacturing Defects)		3	EA	4,249.00	12,747.00

OPT - 2	Height Adjustable Workstation (Face To Face) - 4 Pax. - **(OPT - 2)** - Table top material: thickness: 25 mm. - Core material: E1 particle board from FSC certified factory. - Decor paper: schattdecor from Germany. - PVC edge. - Electrical height adjustable frame. - Timotion dual motor. - Weight capacity: 120 kg. - Electrical control. - 2 tubes height range 710-1170 mm. - Flip-up and cable tray is included. - Fabric screen and snake pipe is included. - Screen (2 pcs) height is 680 mm,length is same as desk. **- Mobile pedestal not included. Quoted seperately.** **- PDU not included. Quoted seperately.** Overall Dimension: W2800 x D1400 x H750 mm Desk Dimension: W1400 x D700 x H750 mm Screen Dimension: W1200 x D680 x H20 mm Origin: FarEast Delivery: 11-12 Weeks Warranty: 5 Years (Against Manufacturing Defects)		3	EA	10,828.00	**RATE ONLY**
29	Workstation (Face To Face) - 2 Pax. - Table top material: thickness: 25 mm. - Core material: E1 particle board from FSC certified factory. - Decor paper: schattdecor from Germany. - PVC edge. - Leg: steel leg. - Flip aluminium cover and steel wire box under for wiring is included. - Fabric screen panel (middle panel) and snake pipe is included. **- Mobile pedestal not included. Quoted seperately.** **- PDU not included. Quoted seperately.** Overall Dimension: W1400 x D1400 x H750 mm Desk Dimension: W1400 x D700 x H750 mm Screen Dimension: W1200 x D300 x H20 mm Origin: FarEast Delivery: 11-12 Weeks Warranty: 5 Years (Against Manufacturing Defects)		1	EA	2,247.00	2,247.00

OPT - 2	Height Adjustable Workstation (Face To Face) - 2 Pax. - **(OPT - 2)** - Table top material: thickness: 25 mm. - Core material: E1 particle board from FSC certified factory. - Decor paper: schattdecor from Germany. - PVC edge. - Electrical height adjustable frame. - Timotion dual motor. - Weight capacity: 120 kg. - Electrical control. - 2 tubes height range 710-1170 mm. - Flip-up and cable tray is included. - Fabric screen and snake pipe is included. - Screen (1 pc) height is 680 mm,length is same as desk. **- Mobile pedestal not included. Quoted seperately.** **- PDU not included. Quoted seperately.** Overall Dimension: W1400 x D1400 x H750 mm Desk Dimension: W1400 x D700 x H750 mm Screen Dimension: W1400 x D680 x H20 mm Origin: FarEast Delivery: 11-12 Weeks Warranty: 5 Years (Against Manufacturing Defects)		1	EA	5,414.00	**RATE ONLY**
30	PDU for Workstation - Silver aluminum profile 1.5U with holding angles. - 2 x UK power sockets - 3 pin BS, 230V. - 2 x data cat 6A RJ 45 with 3 meter data cable On/Off power switch. - 1 x twin USB (Type A+C) fast charging (30W). - On/Off Power Switch - 1 x 3 meter starter lead, female GST18i to UK Plug BS1363, 13A fused. (Wieland type connector). Origin: DI-UAE Delivery: 4-6 Weeks Warranty: 5 Years (Against Manufacturing Defects)		14	EA	429.00	6,006.00
31	Mobile Pedestal - Super fine cold rolled steel plate. - 0.8 mm thickness. - 10 times anti-rust treatment. - Automatic powder coating. - Three full-extension drawers. - With lock. - With top cushion. Dimension: W393 x D500 x H600 mm Origin: FarEast Delivery: 11-12 Weeks Warranty: 5 Years (Against Manufacturing Defects)		14	EA	575.00	8,050.00