REFURBISHMENT WORKS AT

ROVE HOTEL, DUBAI HEALTH CARE CITY

PUBLIC AREA - FIT OUT & MEP WORKS PACKAGE

ROVE

HOTELS

BILL OF QUANTITIES - REV 0

اتش تي سي للتصميم الداخلي ش.ذ.م.م
P.O Box 124791
DUBAI U.A.E
HTS INTERIOR DESIGN L.L.C.

REFURBISHMENT WORK AT ROVE DHCC

PUBLIC AREA

BILL OF QUANTITIES - R0

GRAND SUMMARY

SL NO.	LOCATION	AMOUNT (AED)
1	RECEPTION	803,146.00
2	LOBBY LOUNGE	743,715.00
3	F&B	1,131,937.00
4	LOCKER ROOM	52,700.00
5	PRE FUNCTION	534,772.00
6	MULTI FUNCTION	221,100.00
7	LAUNDRY	7,650.00
8	POOL DECK	39,100.00
	GRAND TOTAL AMOUNT AED:	3,534,120.00

P.O Box 124791
DUBAI U.A.E
HTS INTERIOR DESIGN L.L.C.

REFURBISHMENT WORK AT ROVE DHCC

PUBLIC AREA

BILL OF QUANTITIES - R0

SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)	HTS REMARKSDATED 22.05.25
	BILL NO 1- RECEPTION					
1.00	**PRELIMINARIES**					
1.01	General- Contractor's preliminaries for mobilization, site preparation, Provision for all temporary barricades	1	Item	17,000.00	**17,000.00**	
1.02	Charges for setting out transportations to/from site, material deliveries, small tools and equipment's, protection of finished products in on-going site, site attendance and call out attendance.	1	Item	-	**Included**	
1.03	Charges for Preparation of Technical drawings (Architectural & MEP)and submission to Relevant authorities.	1	Item	25,500.00	**25,500.00**	
1.04	Charges for Preparation of As built drawings (Architectural & MEP)	1	Item	25,500.00	**25,500.00**	
1.05	Charges for Project management, site supervision & coordination and security.	1	Item	170,000.00	**170,000.00**	
1.06	Health, Safety and Environmental Procedures.	1	Item	-	**Included**	
1.07	Allow for coordination with government/authorities along with submission of proposed designs and obtaining completion certificate.	1	Item	34,000.00	**34,000.00**	
1.08	Allow provisional Sum for Insurance for the entire fit-out period. Such as the following; - Contractors all Risk Insurance. - Third Party Liability Insurance. ~~- Motor Vehicle Insurance.~~	1	Item	-	**-**	**Motor Vehicle Insurance is excluded**
1.09	Allow for providing scaffolding for the builder's works.	1	Item	110,500.00	**110,500.00**	
1.10	Allow for providing hoarding up to 4 Mtr Height.	1	Item	51,000.00	**51,000.00**	**Moveable Temp Hoarding to be used**
1.11	Contractors facilities shall include: offices, toilets, stores, mess rooms.	1	Item		**Provided by Client**	
1.12	Employers facilities shall include: offices, Temporary telephones, electronic mail and facsimile.	1	Item		**Provided by Client**	
1.13	Control of noise and pollution.	1	Item		**Noted**	
1.14	Allow for Coordination for works done by others.	1	Item	17,000.00	**17,000.00**	
1.15	Allow for water for the works	1	Item	2,550.00	**2,550.00**	
1.16	Allow for Electricity for the works	1	Item	3,400.00	**3,400.00**	
1.17	Allow for establishing temporary storage facilities at the location provided by the Employer.	1	Item	-	**Provided by Client**	
1.18	Contractors facilities shall include: offices, toilets, stores, mess rooms	1	Item	-	**Provided by Client**	
1.19	Employers facilities shall include: offices, Temporary telephones, electronic mail and facsimile	1	Item	-	**Provided by Client**	
1.20	Access for and Possession or use of the Site	1	Item	-	**Noted**	
1.21	The Maintenance of existing services on, under or over the Site	1	Item	-	**Excluded**	
1.22	Protection of existing finishes at site.	1	Item	34,000.00	**34,000.00**	
1.23	The Execution of the Works in the required specific order, sections or phases	1	Item	-	**-**	
1.24	Regular cleaning of site during construction period and after completion professional deep cleaning and made ready to occupy. Including carting away the debris to Municipal dumping area.	1	Item	39,100.00	**39,100.00**	
1.25	Advance and performance bond charges	1	Item	-	**TBC**	

اتش تي سي للتصميم الداخلي ش.ذ.م.م
P.O Box 124791
DUBAI U.A.E
HTS INTERIOR DESIGN L.L.C.

REFURBISHMENT WORK AT ROVE DHCC

PUBLIC AREA

BILL OF QUANTITIES - R0

SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)	HTS REMARKSDATED 22.05.25
	BILL NO 1- RECEPTION					
2.00	**DEMOLITION & ALTERATION WORKS**					
	Demolition of the following items as necessary for the proposed design including disposal to approved locations, cleaning, making good affected and all ancillary works as necessary.					
2.01	Removal of existing Table	1	Item			
2.02	Removal of existing carpet.	1	Item	22,100.00	22,100.00	
2.03	Removal of existing light fixtures.	1	Item			
2.04	Removal of exiting loose furniture.	1	Item			
2.05	Alteration works to the existing art works	1	Item	-	By Artwork specialist	
	Note: Existing floor and ceiling is to be retained					
3.00	**WALL FINISH**					
	Paint Finish					
3.01	**PNT- 01 ;** Supply and apply fenomastic My home Rich Smooth paint; Satin RAL 9010	245	Sqm	85.00	20,825.00	
3.02	**PNT- 02 ;** Supply and apply catalyzed paint on MDF in terracotta finish; NCS S 3560-Y70R	30	Sqm	255.00	7,650.00	
3.03	**PNT- 40 ;** Supply and apply special paint concrete effect Matt NCS S 1502-Y50R	90	Sqm	340.00	30,600.00	
3.04	**PNT- 41 ;** Supply and apply custom embossed plaster with paint, matt finish	10	Sqm	850.00	8,500.00	
4.00	**CEILING FINISH**					
	Paint Finish					
4.01	Supply and fix new MDF portal ceiling as per the drawing; ZBR-00-DRG-ID-01000-050	16	Sqm	85.00	1,360.00	
4.02	**PNT- 02 ;** Supply and apply catalyzed paint on MDF in terracotta finish; NCS S 3560-Y70R	16	Sqm	85.00	1,360.00	

اتش تي اس للتصميم الداخلي ش.ذ.م.م
P.O Box 124791
DUBAI U.A.E
HTS INTERIOR DESIGN L.L.C.

REFURBISHMENT WORK AT ROVE DHCC

PUBLIC AREA

BILL OF QUANTITIES - R0

SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)	HTS REMARKSDATED 22.05.25
	BILL NO 1- RECEPTION					
5.00	**DOORS**					
5.01	Allow for repainting the existing frameless door; D1 with paint PNT 01	2	Nos	2,550.00	5,100.00	
5.02	**D2,** Supply & install of NFR single leaf wooden door made in solid beech/Marenti solid wood frame & architrave. Shutter to have 45 mm thk door shutter in both side PU paint in lacquer finish. Size: 970mmL x 2100 mm Ht Location : GF RECEPTION	2	Nos	5,440.00	10,880.00	
6.00	**JOINERY WORKS**					
6.01	**JN-01A, RECEPTION DESK**, refurbishment of existing reception desk to be cladded with tiles (TL 07) and metal trim (MT-01) around digital screen logo and skirting+ bottom panel; as per drawing ZBR-DT-GRG-1D-05000-001 and specifications. Dimension - 2600x600x750/1100 mm ht.	2	No.	18,685.00	37,370.00	
6.02	**JN02.A, COMMUNAL TABLE,** made of MDF framed table top finished with Poblenou Silestone - Loft (ST-06) and the base in metal (MT-02) finish. Dimension -82351+1733x1040x1000/800mm ht. Both side planter box in MR MDF backing with ready to receive decorative tile finish ; as per drawing ZBR-DT-GRG-1D-05000-002 and specifications. Dimension -1040x300x800 + 1040x720x1000 mm HT	1	No.	53,550.00	53,550.00	
7.00	**LOOSE FURNITURE & ACCESSORIES**					
	Supply and installation of the following**;**					
7.01	ACC 01A; Wall mounted shelves	1	No	5,950.00	5,950.00	
7.02	ACC 01B; Wall mounted shelves	1	No	5,950.00	5,950.00	
7.03	ACC 01C; Wall mounted shelves	1	No	5,950.00	5,950.00	
7.04	ACC 01D; Wall mounted shelves	1	No	5,950.00	5,950.00	
7.05	ACC 23; Planter	2	Nos	-	Existing at site	
7.06	ACC 24A; Planter	2	Nos	-	Existing at site	
7.07	ACC 24B; Planter	2	Nos	-	Existing at site	

اتش تي سي للتصميم الداخلي ش.ذ.م.م
P.O Box 124791
DUBAI U.A.E
HTS INTERIOR DESIGN L.L.C.

REFURBISHMENT WORK AT ROVE DHCC

PUBLIC AREA

BILL OF QUANTITIES - R0

SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)	HTS REMARKSDATED 22.05.25
	BILL NO 1- RECEPTION					
8.00	**ELECTRICAL ENGINEERING INSTALLATIONS**					
	Supply and installation of Lights					
8.01	LI-29- Decorative pendant light - Set of 3	2	Nos	14,565.00	29,130.00	
8.02	LI-31- Table light	1	Nos	12,043.00	12,043.00	
8.03	Light points wiring and containment works	3	Nos	281.00	843.00	
	Lighting Control Installations					
8.04	Allowance for interface the new lights with existing lighting control system	1	Item	7,650.00	7,650.00	
	Supply and installation of Power sockets					
8.05	Twin socket	1	Nos	111.00	111.00	
8.06	Small power points	1	Nos	94.00	94.00	
8.07	Small power points wiring and containment works	2	Nos	315.00	630.00	
	TOTAL SUMMARY FOR BILL NO.1				**803,146.00**	

اتش تي سي للتصميم الداخلي ش.ذ.م.م
P.O Box 124791
DUBAI U.A.E
HTS INTERIOR DESIGN L.L.C.

REFURBISHMENT WORK AT ROVE DHCC
PUBLIC AREA
BILL OF QUANTITIES - R0

SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)
	BILL NO 2- LOBBY LOUNGE				
1.00	**DEMOLITION & ALTERATION WORKS**				
	Demolition of the following items as necessary for the proposed design including disposal to approved locations, cleaning, making good affected and all ancillary works as necessary.				
1.01	Removal of existing slated ceiling.	1	item	10,200.00	10,200.00
1.02	Removal of existing bench.	1	item		
1.03	Removal of existing light fixtures.	1	item		
1.04	Removal of existing loose furniture.	1	item		
2.00	**WALL FINISH**				
	Paint Finish				
2.01	**PNT- 01 ;** Supply and apply fenomastic My home Rich Smooth paint; Satin RAL 9010	285	Sqm	85.00	24,225.00
2.02	**PNT- 03 ;** Supply and apply fenomastic My home Rich Smooth paint; Satin in Terracotta NCS 3560-Y70R	26	Sqm	255.00	6,630.00
2.03	**PNT- 42 ;** Supply and apply metal paint to Match PNT 01	10	Sqm	85.00	850.00
2.04	**SP- 15 ;** Supply and install corrugated acrylic panel framed.	57	Sqm	1,700.00	96,900.00
3.00	**CEILING FINISH**				
	Paint Finish				
3.01	Allowance for repainting exposed slab (PNT 04); Fenomastic My Home Rich Matt, Dark grey RAL 7021	226	Sqm	85.00	19,210.00
4.00	**DOORS**				
4.01	**D3,** Rework on existing double door SP-05 vinyl wraping. Size: 2000 x 2100 mm Location : LIFT LOBBY	2	Nos	2,550.00	5,100.00
4.02	**D4,** Supply & install of Non FR single wooden door made in solid beech/Marenti solid wood frame & architrave. Shutter have 45 mm thk solid core door shutter in both side PU paint in lacquer finish with metal kick plate Size: 1050 x 2120 mm Location : GF Lobby lounge Area	1	No.	5,440.00	5,440.00

P.O Box 124791
DUBAI U.A.E
HTS INTERIOR DESIGN L.L.C.

REFURBISHMENT WORK AT ROVE DHCC					
PUBLIC AREA BILL OF QUANTITIES - R0					
SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)

REFURBISHMENT WORK AT ROVE DHCC
PUBLIC AREA
BILL OF QUANTITIES - R0

SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)
	BILL NO 2- LOBBY LOUNGE				
5.00	**JOINERY WORKS**				
5.01	**JN-05.A, METAL SHELVES** made of MDF PU paint finish bottom unit with top metal frame and open ledges in MDF PU Paint finish. Dimension -1600x600x3050 mm ht.	3	Nos	10,200.00	30,600.00
5.02	**JN-06.B,CONSOLE TABLE** made of 50mm thk veneer MDF framed table top finished with ST-06 engineered stone and bottom supported by 303 dia solid wooden legs finished in PNT-05. Dimension - 3971x1075x780 mm ht.	1	No	27,200.00	27,200.00
5.03	**JN-06.C, CONSOLE TABLE** Made of MDF veneer framed carcass ,shutter finished with MDF PU painted backing and fascia in ratan finish, counter top in engineered stone (St-06) and bottom supported ny metal legs. Dimension -1600x600x680 mm ht.	2	Nos	16,150.00	32,300.00
5.04	**JN-18.A, BANQUETTE SEATING** Made of plywood backing with metal (MT-19)finish bottom and FB-32 leather upholstered seating ,back rest made in plywood backing with FB33 leather upholstery including lather strap metal button design,including metal(MT-19) finish side tables 3 nos. Dimension - 8270x520x446/628 mm ht.	1	No	86,777.00	86,777.00
5.05	**JN-52,LINEAR METAL SHELVING,** Made of MDF Veneer(WD-01,A) and rattan (Sp-17) combination bottom unit and top existing shelf as it is. Dimension - 6220x350x4600 mm ht.	1	No	113,312.00	113,312.00
6.00	**LOOSE FURNITURE & ACCESSORIES**				
	Supply and installation of the following;				
6.01	ACC 24A; Planter	4	Nos	-	Existing at site
6.02	ACC 26A; Cushions	6	Nos	595.00	3,570.00
6.03	ACC 26B; Cushions	3	Nos	595.00	1,785.00

انتس تي سي للتصميم الداخلي ش.ذ.م.م
P.O Box 124791
DUBAI U.A.E
HTS INTERIOR DESIGN L.L.C.

REFURBISHMENT WORK AT ROVE DHCC					
PUBLIC AREA BILL OF QUANTITIES - R0					
SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)

REFURBISHMENT WORK AT ROVE DHCC
PUBLIC AREA
BILL OF QUANTITIES - R0

SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)
	BILL NO 2- LOBBY LOUNGE				
7.00	**ELECTRICAL ENGINEERING INSTALLATIONS**				
	Supply and installation of Lights				
7.01	LI-32- Decorative pendant light	20	Nos	5,571.00	111,420.00
7.02	LI-33- Decorative pendant light	2	Nos	12,850.00	25,700.00
7.03	LI-34- Decorative pendant light	1	Nos	10,600.00	10,600.00
7.04	LI-35- Decorative pendant light	3	Nos	10,600.00	31,800.00
7.05	LI-36- Table light	1	Nos	5,330.00	5,330.00
7.06	LI-37- Table light	4	Nos	5,330.00	21,320.00
7.07	LED strip lights	7	m	326.00	2,282.00
7.08	Light points wiring and containment works	21	Nos	281.00	5,901.00
7.09	Light points wiring and containment works for LED strip lights	7	Nos	281.00	1,967.00
	Lighting Control Installations				
7.10	Allowance for interface the new lights with existing lighting control system	1	Item	16,150.00	16,150.00
	Supply and installation of Power sockets				
7.11	Twin Universal socket	7	Nos	162.00	1,134.00
7.12	Single Universal socket	4	Nos	128.00	512.00
7.13	Floor box	1	Nos	468.00	468.00
7.14	6x New Universal socket for Table	1	Nos	94.00	94.00
7.15	Power provision through Joinery	1	Nos	94.00	94.00
7.16	Power provision for Framery Pods	2	Nos	94.00	188.00
7.17	New Power socket for TV	3	Nos	111.00	333.00
7.18	Relocation of existing FB	3	Nos	111.00	333.00
7.19	Small power points wiring and containment works	22	Nos	315.00	6,930.00

P.O Box 124791
DUBAI U.A.E
HTS INTERIOR DESIGN L.L.C.

REFURBISHMENT WORK AT ROVE DHCC					
PUBLIC AREA					
BILL OF QUANTITIES - R0					
SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)
	TOTAL SUMMARY FOR BILL NO.2				706,655.00

REFURBISHMENT WORK AT ROVE DHCC

PUBLIC AREA

BILL OF QUANTITIES - R0

SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)	HTS REMARK 22.05.25
	BILL NO 3 - F&B					
1.00	**WALL FINISH**					
	Paint Finish					
1.01	**PNT- 01 ;** Supply and apply fenomastic My home Rich Smooth paint; Satin RAL 9010	250	Sqm	85.00	21,250.00	
1.02	**PNT- 03 ;** Supply and apply fenomastic My home Rich Smooth paint; Satin in Terracotta NCS 3560-Y70R	18	Sqm	255.00	4,590.00	
1.03	**PNT- 06 ;** Supply and apply fenomastic My home Rich Smooth paint; Satin in sage green NCS S 3010-G20Y	48	Sqm	85.00	4,080.00	
1.04	**PNT- 42 ;** Supply and apply metal paint to Match PNT 01	3	Sqm	85.00	255.00	
1.05	**SP- 15 ;** Supply and install corrugated acrylic panel framed.	18	Sqm	1,700.00	30,600.00	
1.06	**TL- 05 ;** Supply and install 6x24mm wall tile, Lume - Off white.	42	Sqm	595.00	24,990.00	
1.07	**TL- 09 ;** Supply and install glazed porcelain tile**.**	5	Sqm	680.00	3,400.00	
1.08	**Green wall**	12	Sqm	4,250.00	51,000.00	
2.00	**CEILING FINISH**					
	Paint Finish					
2.01	Allowance for repainting exposed slab ; Fenomastic My Home Rich Matt, Black, RAL:TBC	268	Sqm	170.00	45,560.00	
2.02	Supply and installation of suspended ceiling panel (WD-01.A) - Type 1	20	Sqm	2,125.00	42,500.00	
2.03	Supply and installation of suspended ceiling panel (WD-01.A) - Type 2	17	Sqm	2,125.00	36,125.00	
2.04	Allowance for repainting the existing beam to match MT 02.	10	lm	170.00	1,700.00	
2.05	Foam spary acoustic ceiling	1	Item		Excluded	Excluded existing MEP & slab to remain
3.00	**DOORS**					
3.01	**D5,** Supply & install of Non FR single wooden door made in solid beech/Marenti solid wood frame & architrave. Shutter have 45 mm thk solid core door shutter in both side PU paint in lacquer finish with metal kick plate and vision panel Size: 1050 x 2120 mm Location : GF Lobby lounge Area	2	No.	7,650.00	15,300.00	
3.02	**D6**, Supply & install of Non FR single wooden door made in solid beech/Marenti solid wood frame & architrave. Shutter have 45 mm thk solid core door shutter in both side PU paint in lacquer finish with metal kick plate and vision panel Size: 1050 x 2120 mm Location : GF F&B Area	1.00	No.	7,650.00	7,650.00	
						-

P.O Box 124791 DUBAI U.A.E
HTS INTERIOR DESIGN L.L.C.

REFURBISHMENT WORK AT ROVE DHCC

PUBLIC AREA

BILL OF QUANTITIES - R0

SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)	HTS REMARK 22.05.25
	BILL NO 3 - F&B					
4.00	**JOINERY WORKS**					
4.01	**JN-49, BANQUETTE SEATING** Made of plywood backing to receive tile(TL-08) bottom with metal (MT-19)finish skirting, and FB-47 leather upholstered seating ,back rest made in plywood backing with FB33 leather upholstery including lather strap metal button design,including metal(MT-34) finish side tables 3 nos. Dimension - 3294+2303+1557x520x412/488 mm ht. DWG Reff. ZBR-DT-DRG-ID 05000-008	1.00	No.	66,341.00	66,341.00	
4.02	**JN-50,BAR COUNTER** Made of MDF Veneer(WD-01A) /Rattan (SP-07)finish barcounter front facia with counter top in ST-07 engineered stone. Back Unit in bottom MDF Venner finish and top unit in combination of MDF PU paint and veneer/metal open shelves Dimension - 5650+3000x600x800/1100 mm ht. Back unit - 3200x450x2800 mm Ht DWG Reff. ZBR-DT-DRG-ID 05000-010	1.00	No.	90,440.00	90,440.00	
4.03	**JN-51,HIGH COUNTER** Made of U shaped table top in (ST-07) engineered stone finish eith necessary wooden support and base in painted(PNT-02) solid wood , including bottom tables made of MDF laminated finish and outer facia (TL-10)finish. Dimenison - 3012+1799+3012x790/213x900 mm ht. DWG Reff. ZBR-DT-DRG-ID 05000-011	1.00	No.	63,410.00	63,410.00	
4.04	**JN-53, LONG BANQUETTE SEATING,** Made bottom in combination of Wood veneer and tile and the seating in (FB-47) leather and (MT-34) metal frame. Dimension - 4425+1888+1092x650x1100 mm ht. DWG Reff. ZBR-DT-DRG-ID 05000-014	1.00	No.	70,125.00	70,125.00	
4.05	**JN-54, HIGH TABLE WITH PLANTER,** Made of table top in (WD-01,B)solid wood with (MT-32)metal foot rail, including planter box made of MDF PU paint(PNT-02) finish flutted design with metal GI tray inside. Dimension - 3590x900x930mm Ht + 800 Dia x 1100 mm ht. DWG Reff. ZBR-DT-DRG-ID 05000-015	1.00	No.	25,500.00	25,500.00	
4.06	**JN-55, BUILD IN CURVED SEATING,** Made of MDF veneer (WD_01,A) framed metal planter box with seating in suspended metal with ((FB-55) fabric seating and back rest in (FB-57) fabric finish. Dimension - 6200x500x1000 mm ht. Planter - 1450x800x1000 mm Ht DWG Reff. ZBR-DT-DRG-ID 05000-016	1.00	No.	83,470.00	83,470.00	
4.07	**JN-56, RECTANGULAR HIGH TABLE,** Made of Soild wooden(WD-01,B) table top supported by solid wood painted/wooden finish leg.including metal frame support wooden shelf finished in MDF veneer and Rattan finish. Dimension - 3676x518x 1020/3061mm ht. DWG Reff. ZBR-DT-DRG-ID 05000-017	1.00	No.	30,600.00	30,600.00	
4.08	**JN-57.A ,WAITER STATION,** Made combination of MDF veneer/PU paint finish unit with side pocket shelf, ST-07 engineered stone counter top Size- 900x600x1000 mm ht. DWG Reff. ZBR-DT-DRG-ID 05000-018	1.00	No.	11,900.00	11,900.00	
4.09	**JN-57.B ,WAITER STATION,** Made combination of MDF veneer/PU paint finish unit with ST-07 engineered stone counter top Size- 900x600x1000 mm ht. DWG Reff. ZBR-DT-DRG-ID 05000-019	1.00	No.	11,900.00	11,900.00	

اتش تي سي للتصميم الداخلي ش.ذ.م.م
P.O Box 124791
DUBAI U.A.E
HTS INTERIOR DESIGN L.L.C.

REFURBISHMENT WORK AT ROVE DHCC

PUBLIC AREA

BILL OF QUANTITIES - R0

SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)	HTS REMARK 22.05.25
	BILL NO 3 - F&B					
5.00	**LOOSE FURNITURE & ACCESSORIES**					
	Supply and installation of the following; as per specification & drawing ref: ZBR-00-DRG-ID-01300-010 REV 1					
5.01	ACC 24A; Planter	3.00	Nos	-	Existing at site	
5.02	Metal Drapery	1.00	Item	-	Excluded	Data is not available
6.00	**ELECTRICAL ENGINEERING INSTALLATIONS**					
	Supply and installation of Lights					
6.01	LI-06- Wall Lamp	1	Nos	5,293.00	5,293.00	
6.02	LI-08- New Chandelier light	2	Nos	26,327.00	52,654.00	
6.03	LI-09- Pendant light	1	Nos	12,060.00	12,060.00	HTS will provide sample for client approval. Brand: Local UAE
6.04	LI-10- New Chandelier light	1	Nos	22,577.00	22,577.00	
6.05	LI-12- Suspended Downlight	12	Nos	643.00	7,716.00	
6.06	LI-40- Pendant light	4	Nos	20,760.00	83,040.00	
6.07	LI-41- Suspended Light	4	Nos	10,754.00	43,016.00	
6.08	LI-42- New Chandelier light	2	Nos	26,327.00	52,654.00	
6.09	LI-43- Wall light	15	Nos	1,705.00	25,575.00	
6.10	LI-44- New Chandelier light	2	Nos	5,357.00	10,714.00	
6.11	Wall light	3	Nos	7,543.00	22,629.00	
6.12	LED strip lights	7	m	326.00	2,282.00	
6.13	Light points wiring and containment works	47	Nos	281.00	13,207.00	
6.14	Light points wiring and containment works for LED strip lights	7	Nos	281.00	1,967.00	
	Lighting Control Installations					
6.15	Allowance for interface the new lights with existing lighting control system	1	Item	16,150.00	16,150.00	
	Supply and installation of Power sockets					
6.16	Twin Universal socket	9	Nos	162.00	1,458.00	
6.17	Single Universal socket	3	Nos	128.00	384.00	
6.18	Floor box	5	Nos	468.00	2,340.00	
6.19	Power provision for wall Lamp	20	Nos	94.00	1,880.00	
6.20	Small power points	37	Nos	315.00	11,655.00	
	TOTAL SUMMARY FOR BILL NO.3				**1,131,937.00**	

P.O Box 124791 DUBAI U.A.E HTS INTERIOR DESIGN L.L.C.

REFURBISHMENT WORK AT ROVE DHCC

PUBLIC AREA

BILL OF QUANTITIES - R0

SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)
	BILL NO 4 - LOCKER ROOM				
1.00	**WALL FINISH**				
1.01	**MT-02;** New architrave opening	1	Item	30,600.00	30,600.00
2.00	**JOINERY WORKS**				
2.01	**LOCKER ROOM1,** Repaint on existing locker Size - 3240+4915+2160x600x2400 mm HT	1	No.	22,100.00	22,100.00
2.02	**LOCKER ROOM 2,** Repaint on existing locker Size - 2700+3780x600x2400 mm HT	1	No.		
	TOTAL SUMMARY FOR BILL NO.4				**52,700.00**

اتش تي سي للتصميم الداخلي ش.ذ.م.م
P.O Box 124791
DUBAI U.A.E
HTS INTERIOR DESIGN L.L.C.

REFURBISHMENT WORK AT ROVE DHCC

PUBLIC AREA

BILL OF QUANTITIES - R0

SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)
	BILL NO 5 - PRE FUNCTION				
1.00	**DEMOLITION & ALTERATION WORKS**				
	Demolition of the following items as necessary for the proposed design including disposal to approved locations, cleaning, making good affected and all ancillary works as necessary.				
1.01	Removal of existing carpet.	1	item	4,250.00	4,250.00
1.02	Removal of existing joinery works next to column including wall.	3	Nos	850.00	2,550.00
2.00	**WALL FINISH**				
	Paint Finish				
2.01	**PNT- 01 ;** Supply and apply fenomastic My home Rich Smooth paint; Satin RAL 9010	245	Sqm	85.00	20,825.00
2.02	**PNT- 03 ;** Supply and apply fenomastic My home Rich Smooth paint; Satin in Terracotta NCS 3560-Y70R	68	Sqm	85.00	5,780.00
3.00	**CEILING FINISH**				
	Ceiling Rectification works				
3.01	Allow necessary rectification works on existing ceiling if required.	1	Item	8,500.00	8,500.00
	Paint Finish				
3.02	Paint finish to ceiling (PNT 07); Apply White Paint finish.	20	Sqm	60.00	1,200.00
3.03	Allowance for repainting exposed slab (PNT 08); Fenomastic My Home Rich Matt, Terracotta NCS S 3560 Y70R	57	Sqm	255.00	14,535.00
3.04	Allowance for repainting exposed slab; Fenomastic My Home Rich Matt, Black Paint	105	Sqm	60.00	6,300.00
4.00	**DOORS**				
4.01	**D3,** Rework on existing double door SP-05 vinyl wraping. Size: 2000 x 2100 mm Location : LIFT LOBBY	2	Nos	2,550.00	5,100.00
4.02	**D7,** Existing frameless door to be repainted (PNT-03). Size: 1050 x 2120 mm Location : FF Pre function	1	No.	1,700.00	1,700.00
4.03	**D8,** Existing door and fixed paneling to be repainted (PNT 02). Size: as per site condition Location : FF Pre function	1	No.	3,400.00	3,400.00
4.04	**D9**, Existing door and fixed paneling to be repainted (PNT 02). Size: as per site condition Location : FF Pre function	2	No.	3,400.00	6,800.00
4.05	**D10**, Existing door to be repainted (PNT 02). Size: as per site condition Location : FF Pre function	1	No.	3,400.00	3,400.00
4.06	**D11,** Existing door to be repainted (PNT 02). Size: as per site condition Location : FF Pre function	1	No.	3,400.00	3,400.00

P.O Box 124791
DUBAI U.A.E
HTS INTERIOR DESIGN L.L.C.

REFURBISHMENT WORK AT ROVE DHCC					
PUBLIC AREA					
BILL OF QUANTITIES - R0					
SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)

اتش تي اس للتصميم الداخلي ش.ذ.م.م
P.O Box 124791
DUBAI U.A.E
H T S INTERIOR DESIGN L.L.C.

REFURBISHMENT WORK AT ROVE DHCC

PUBLIC AREA

BILL OF QUANTITIES - R0

SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)
	BILL NO 5 - PRE FUNCTION				
5.00	**JOINERY WORKS**				
5.01	**JN-11 ,SUSPENDED METAL SCREEN,** Made of MT-02 metal profile with MT-31 perforated metal mesh screen DWG Reff. ZBR-DT-DRG-ID 05000-020	1	No.	18,636.00	18,636.00
5.02	**JN-12 ,SEATING/PHONE/BOOTH /SHELF,** Made of MDF veneer finish backing with metal frame and pouf seating in selected fabric. Dimension - 5200x2010 mm Ht. DWG Reff. ZBR-DT-DRG-ID 05000-021	1	No.	42,500.00	42,500.00
5.03	**JN-13 ,HIGH TABLE UNIT,** Made of MDF Veneer cladded on existing column @1100 mm ht, and table top in ST-07 engineered stone finish. Dimension - 1764+1090+1764x430x900/1100 mm Ht DWG Reff. ZBR-DT-DRG-ID 05000-022	2	Nos	39,780.00	79,560.00
5.04	**JN-58 ,HIGH TABLE WITH PLANTER,** Made of table top in (WD-01,B)solid wood with (MT-32)metal foot rail, including planter box made of MDF PU paint(PNT-02) finish flutted design with metal GI tray inside. Dimension - 3425x600x880mm Ht + 600 Dia x 1100 mm ht. DWG Reff. ZBR-DT-DRG-ID 05000-023	1	No.	31,025.00	31,025.00
5.05	**JN-59 ,RECTANGULAR HIGH TABLE,** Made of Soild wooden(WD-01,B) table top supported by solid wood painted/wooden finish leg.including metal frame support wooden shelf finished in MDF veneer and Rattan finish. Dimension - 2496x518x 1020/3061mm ht. DWG Reff. ZBR-DT-DRG-ID 05000-024	1	No.	20,825.00	20,825.00
6.00	**LOOSE FURNITURE & ACCESSORIES**				
	Supply and installation of the following;				
6.01	ACC-02; Pingpong Table	1	No	5,950.00	5,950.00

اتش تي سي للتصميم الداخلي ش.ذ.م.م.
P.O Box 124791
DUBAI U.A.E
HTS INTERIOR DESIGN L.L.C.

REFURBISHMENT WORK AT ROVE DHCC					
PUBLIC AREA					
BILL OF QUANTITIES - R0					
SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)
	`				

REFURBISHMENT WORK AT ROVE DHCC

PUBLIC AREA

BILL OF QUANTITIES - R0

SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)
	BILL NO 5 - PRE FUNCTION				
7.00	**ELECTRICAL ENGINEERING INSTALLATIONS**				
	Supply and installation of Lights				
7.01	LI-46.A- Decorative pendant light	3	Nos	9,060.00	27,180.00
7.02	LI-46.B- Decorative pendant light	8	Nos	9,060.00	72,480.00
7.03	LI-47- Decorative pendant light	5	Nos	12,060.00	60,300.00
7.04	LI-48- Track lights including tracks	4	Nos	6,810.00	27,240.00
7.05	Floor Lamp	4	Nos	7,594.00	30,376.00
7.06	LED strip lights			-	-
7.07	Light points wiring and containment works	35	Nos	281.00	9,835.00
7.08	Light points wiring and containment works for LED strip lights	1	Nos	281.00	281.00
	Lighting Control Installations				
7.09	Allowance for interface the new lights with existing lighting control system	1	Item	11,475.00	11,475.00
	Supply and installation of Power sockets				
7.10	Twin Universal socket	9	Nos	162.00	1,458.00
7.11	Single Universal socket	7	Nos	128.00	896.00
7.12	Floor box	2	Nos	468.00	936.00
7.13	4x New Universal socket for Table	1	Nos	94.00	94.00
7.14	Power provision For Kitchen				Existing to be retained.
7.15	Small power points wiring and containment works	19	Nos	315.00	5,985.00

P.O Box 124791
DUBAI U.A.E
H T S INTERIOR DESIGN L.L.C.

REFURBISHMENT WORK AT ROVE DHCC					
PUBLIC AREA					
BILL OF QUANTITIES - R0					
SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)
	TOTAL SUMMARY FOR BILL NO.5				534,772.00

REFURBISHMENT WORK AT ROVE DHCC

PUBLIC AREA

BILL OF QUANTITIES - R0

SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)
	BILL NO 6 - MULTI FUNCTION AREA				
1.00	**DEMOLITION & ALTERATION WORKS**				
	Demolition of the following items as necessary for the proposed design including disposal to approved locations, cleaning, making good affected and all ancillary works as necessary.				
1.01	Removal of existing cabinets.	1	Item	8,500.00	8,500.00
1.02	Removal of existing ceiling to receive new.	1	Item		
2.00	**WALL FINISH**				
	Wall Rectification works				
	Paint Finish				
2.01	**PNT- 01 ;** Supply and apply fenomastic My home Rich Smooth paint; Satin RAL 9010	60	Sqm	85.00	5,100.00
2.02	**PNT- 40 ;** Supply and apply special paint; Concrete Effect Matt NCS S 1502-Y50R	35	Sqm	255.00	8,925.00
3.00	**CEILING FINISH**				
	Paint Finish				
3.01	Supply and installation of new suspended gypsum ceiling; including paint finish PNT-01	22	Sqm	60.00	1,320.00
3.02	Supply and installation of powder coated metal ceiling; Sage Green NCS S 3010-G20Y (MT 32)	24	Sqm	1,190.00	28,560.00
4.00	**DOORS**				
4.01	**D12** - Supply and installation of new glass door shutter in GL 01 as per door schedule ZBR-DT-DRG-ID-06000-011.	1	No	13,600.00	13,600.00

P.O Box 124791
DUBAI U.A.E
HTS INTERIOR DESIGN L.L.C.

REFURBISHMENT WORK AT ROVE DHCC

PUBLIC AREA

BILL OF QUANTITIES - R0

SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)

اتش تي سي للتصميم الداخلي ش.ذ.م.م.
P.O Box 124791
DUBAI U.A.E
HTS INTERIOR DESIGN L.L.C.

REFURBISHMENT WORK AT ROVE DHCC

PUBLIC AREA

BILL OF QUANTITIES - R0

SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)
	BILL NO 6 - MULTI FUNCTION AREA				
5.00	**JOINERY WORKS**				
5.01	**JN-60, CABINET DETAIL** made of MDF veneer finish bottom unit with ST-07 engineered stone counter top an dtop unit in Pu Paint finish back panel with MDF Veneer finish open shelves,including Side unit with metal frame support. Dimension - 2870+1482x787/350x3000 mm ht. DWG Reff. ZBR-DT-DRG-ID 05000-026	1	No.	56,100.00	56,100.00
5.02	**JN-61, TV UNIT** made of MDF veneer wall panel painted MDF center TV backing + white board separated by 5mmgrove Dimension - 1910x150x3000 mm ht. DWG Reff. ZBR-DT-DRG-ID 05000-027	1	Nos	15,300.00	15,300.00
5.03	**JN-62, SHELVING DETAIL** made of MDF veneer wall hanging ledges with necessary metal support. Dimension - 1565+1561x150x150 + 1500x150x150- 3 nos DWG Reff. ZBR-DT-DRG-ID 05000-028	1	No.	10,472.00	10,472.00
5.04	**JN-63, COMMUNAL TABLE** made of MDF veneer WD-01A) table top with bottom(WD-01,B) solid wood asper the design given Dimension - 5098x1400x980 mm Ht DWG Reff. ZBR-DT-DRG-ID 05000-029	1	No.	30,600.00	30,600.00
6.00	**ELECTRICAL ENGINEERING INSTALLATIONS**				
	Supply and installation of Lights				
6.01	LI-52- Decorative pendant light	1	Nos	4,327.00	4,327.00
6.03	LED strip lights				N/A
6.04	Light points wiring and containment works	8	Nos	281.00	2,248.00
6.05	Light points wiring and containment works for LED strip lights				N/A
	Lighting Control Installations				
6.06	Allowance for interface the new lights with existing lighting control sys	1	Item	3,825.00	3,825.00
	Supply and installation of Power sockets				
6.07	Twin Universal socket	4	Nos	162.00	648.00
6.08	Floor box for Table Integrated sockets	1	Nos	468.00	468.00
6.09	Power provision For TV, Wall Lamp	3	Nos	94.00	282.00
6.10	Small power points wiring and containment works	8	Nos	315.00	2,520.00
7.00	**MECHANICAL ENGINEERING INSTALLATIONS**				
7.01	Works related with HVAC modifications Note: Contractor to check @ site for the modification works	1	Item	11,560.00	11,560.00
8.00	**FIRE SAFETY ENGINEERING INSTALLATIONS**				
8.01	Works related with FA, FF, Emergency and Exit light modifications Note: Contractor to check @ site for the modification works	1	Item	16,745.00	16,745.00

P.O Box 124791
DUBAI U.A.E
HTS INTERIOR DESIGN L.L.C.

REFURBISHMENT WORK AT ROVE DHCC

PUBLIC AREA

BILL OF QUANTITIES - R0

SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)
	TOTAL SUMMARY FOR BILL NO.6				221,100.00

REFURBISHMENT WORK AT ROVE DHCC

PUBLIC AREA

BILL OF QUANTITIES - R0

SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)
	BILL NO 7 - LAUNDRY				
1.00	**WALL FINISH**				
1.01	New cladding at the laundry area; as per specifications and drawings ref: ZBR-00-DRG-ID-02400-010			-	n/a
2.00	**JOINERY WORKS**				
2.01	Allowance for new bench at Laundry area; as per specifications and drawings ref: ZBR-00-DRG-ID-02400-010	1	No	7,650.00	7,650.00
	TOTAL SUMMARY FOR BILL NO.7				**7,650.00**

P.O Box 124791
DUBAI U.A.E
HTS INTERIOR DESIGN L.L.C.

REFURBISHMENT WORK AT ROVE DHCC

PUBLIC AREA

BILL OF QUANTITIES - R0

SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)
	BILL NO 8 - POOL DECK				
1.00	**DEMOLITION WORKS**				
	Demolition of the following items as necessary for the proposed design including disposal to approved locations, cleaning, making good affected and all ancillary works as necessary.				
1.01	Removal of existing floor finish.	1	Item	5,950.00	5,950.00
1.02	Removal of existing cabinets.	1	Item		
2.00	**FLOOR FINISH**				
2.01	Supply and installation of Teak timber floor decking at shower column; as per specification and drawing ref: ZBR-00-DRG-ID-02500-010.	1	Item	14,450.00	14,450.00
2.02	Allowance for new cone shaped tile podium; as per specification and drawing ref: ZBR-00-DRG-ID-02500-010.	5	Nos	2,550.00	12,750.00
	Additional waterproofing @ Shower area only	1	Item	5,950.00	5,950.00
3.00	**WALL FINISH**				
3.01	Allowance for monochrome mural on the wall				**By Art work specialist**
	TOTAL SUMMARY FOR BILL NO.8				**39,100.00**

P.O Box 124791
DUBAI U.A.E
HTS INTERIOR DESIGN L.L.C.