CREATIVE LAB
YOUR CREATIVE FITOUT PARTNER

04/08/2025
Ref: CL_333_ELELX_04082025_R0

To,
ELECTROLUX
UNIT NO: 2904,2905,2906 - 29th Floor
Fortune Tower, JLT, Dubai, UAE.

Sub: BUDGETARY PROPOSAL FOR ELECTROLUX

SL.NO.	DESCRIPTION	QTY	UNIT	RATE	TOTAL
A	**GENERAL REQUIREMENTS & PRELIMINARIES**				
1	Charges towards preparation of approval set of drawings for approval from building management, Concordia for proposed layout and closure of file with issuance of completion certificate . (All kind of fees & security deposits to be paid by client as per actuals)	1	LS	AED18,000	AED18,000
2	Charges towards CAR policy insurance towards protection of new leased premises as well as existing build. (up to 3 Million DHS)	1	LS	AED3,000	AED3,000
3	Charges towards mobilization & Demobilization, tools, Equipment's, scaffolding works and protection of the site during the entire period of work.	1	LS	AED4,500	AED4,500
4	Charges towards Site protection	1	LS	AED4,500	AED4,500
	All approval fees/ deposits to be paid by client as per actuals				
				TOTAL FOR PRELIMINARIES	**AED30,000**
B	**DEMOLITION WORKS**				
	Charges towards demolition and carting away of the debris to the designated municipality yard.				
1	Charges towards Sanitary fitting and kitchen cabinets removal carting away of the debris to the designated municipality yard.	1	LS	AED1,500	AED1,500
2	Existing block wall - partition wall between unit	120	Sqm	AED100	AED12,000
3	Existing gypsum wall	50	sqm	AED75	AED3,750
4	Existing wall cladding in toilet area	70	Sqm	AED45	AED3,150
5	Charges towards demolition of exiting flooring	430	Sqm	AED45	AED19,350
6	Charges towards demolition of exiting ceiling	430	Sqm	AED65	AED27,950
				TOTAL FOR DEMOLITION WORKS	**AED67,700**
C	**FIT OUT WORKS**				
	PARTITION WORKS - ASSUMED FLOOR HEIGHT 3.3 M				
1	Supply and installation of 75mm thick drywall **single layer wall cladding 12.5mm gypsum board** @ 600mm C/C with rock wool insulation with density 50kg/m^3 inside up to the **Height 2.4m** all in accordance with the drawings and specifications. **Location : On column of TV unit**	13	Sqm	AED120	AED1,560
2	Supply and installation of 75mm thick drywall **single layer wall cladding 12.5mm gypsum board** @ 600mm C/C with rock wool insulation with density 50kg/m^3 inside up to the **Height 2.4m** all in accordance with the drawings and specifications. **Location :Existing Block wall**	180	Sqm	AED120	Optional

Tel: + 971 4 346 0061 Email : info@creativelabs.ae Web: www.creativelabs.ae
Warehouse No. 3 Mostafawi Compound , Al Quoz 3 , P.O. Box 122718, Dubai – United Arab Emirates

CREATIVE LAB
YOUR CREATIVE FITOUT PARTNER

SL.NO.	DESCRIPTION	QTY	UNIT	RATE	TOTAL
3	Supply and installation of 100mm thick **drywall partition** made up of single layer **12.5mm gypsum board** on both sides of 70mm metal c studs @ 600mm C/C with rock wool insulation with density 50kg/m^3 inside up to the **Height 3.3 m** all in accordance with the drawings and specifications. **Location :** meeting room 5 Pax, phone booth , workstation, Gm office, meeting room, waiting lounge	140	Sqm	AED160	AED22,400
4	Supply and installation of 100mm thick **drywall partition** made up of single layer **12.5mm Fire rated gypsum board** on both sides of 70mm metal c studs @ 600mm C/C with rock wool insulation with density 50kg/m^3 inside up to the **Height 3.3 m** all in accordance with the drawings and specifications. **Location : server room**	35	Sqm	AED210	AED7,350
5	Supply and installation of 75mm thick drywall **single layer wall cladding** made up of single layer **12.5mm Fire rated gypsum board** on one sides of 70mm metal c studs @ 600mm C/C with rock wool insulation with density 50kg/m^3 inside up to the **Height 2.4m** all in accordance with the drawings and specifications. **Location : server room**	14	Sqm	AED180	AED2,520
6	Supply and installation of 100mm thick drywall partition made up of **single layer 12.5mm Cement board** on both sides of 70mm metal c studs @ 600mm C/C with rock wool insulation with density 50kg/m3 inside up to the Height 3.3 m all in accordance with the drawings and specifications. Location : Toiler area	65	Sqm	AED210	AED13,650
7	Supply and installation of **100mm thick gypsum baffles**	12	Rm	AED180	AED2,160
8	Supply and installation of **12mm thick clear tempered** single glazed partition with aluminum profiles with from finished floor to false ceiling heigh	35	Sqm	AED550	AED19,250
9	Supply and installation of **HPL partition - Including door**	5	Sets	AED6,000	AED30,000
10	Supply and installation of **wooden reinforcement** for TV unit	6	Rm	AED650	AED3,900
11	Supply and installation of MDF **skirting**	230	Rm	AED75	AED17,250
12	Supply and installation of **curtain - blinds**	160	Sqm	AED180	AED28,800
13	Charges towards modification of bay window seating by cladding mdf with laminate finish	1	Rm	AED75,000	AED75,000
	DOOR WORKS				
14	Supply & Installation of **MR MDF door in Veneer finish** including all the accessories and handles. Size : 900mm X 3000mm. Location: Toilet area	2	Nos	AED3,400	AED6,800
15	Supply & Installation of hidden door **MDF door in Veneer finish** including all the accessories and handles. Size : 900mm X 3000mm. Location : Meeting area	1	Nos	AED4,200	AED4,200
16	Supply and installation of **glass entrance door**	1	Nos	AED4,600	AED4,600
17	Note : Existing emergency exit double swing door remain to be same				
18	Supply and installation of **Ms Steel above door** Length: 3450mm	1	LS	AED9,000	AED9,000

Tel: + 971 4 346 0061 Email : info@creativelabs.ae Web: www.creativelabs.ae
Warehouse No. 3 Mostafawi Compound , Al Quoz 3 , P.O. Box 122718, Dubai – United Arab Emirates

SL.NO.	DESCRIPTION	QTY	UNIT	RATE	TOTAL
19	Supply and installation of **bi holding door** HUFCOR OPERABLE PARTITION SERIES 632 (MANUALLY OPERATED) Paired panels Acoustic Rating of 51-STC (Lab tested) Panel Finishes: Unfinished ready to accept finishes by others Panel Frames: Lamb's Wool / Gray / Brown (TBC) Track Finish: Clear Anodized Aluminum Track Type – 40 Opening : 3450mm (W) x 2900mm (H)	1	Nos	AED48,000	AED48,000
20	Supply and installation of frosting on the glass partition up to 1.0m height.	16	Sqm	AED150	AED2,400
	FLOORING WORKS				
21	Supply & apply of **self leveling** Location : Full Floor	475	Sqm	AED60	AED28,500
22	Supply and application of **cementitious waterproofing** system to wet areas Location : Toilet area, pantry area(wall)	50	Sqm	AED180	AED9,000
23	Supply and installation of **HPL finish,** corner lock raised access floor system include all necessary fitting accessories; all in accordance Location : server room	11	Sqm	AED450	AED4,950
24	Supply and installation of **LVT Flooring** Location : Reception area, path way, pantry	146	Sqm	AED210	AED30,660
25	Supply and installation of **50 x 50 nylon carpet tiles** with necessary materials for fixing. Location : workstation, meeting room, phonebooth	250	Sqm	AED180	AED45,000
26	Supply and installation of **roller carpet** with necessary materials for fixing. Location : 12 pax meeting room, Gm room	58	Sqm	AED320	AED18,560
27	Supply & Installation of **60X60cm Floor tile** Location: Toilet area	30	Sqm	AED180	AED5,400
28	Supply & Installation of **transition strip**	51	Rm	AED150	AED7,650
	CEILING WORKS				
29	Supply and installation of **Plain Gypsum ceiling** including all necessary suspension and support framing, fittings and fixing accessories, all in accordance with the drawings and specification. Location : all room	440	Sqm	AED150	AED66,000
30	Supply and installation of **60 x60 gypsum ceiling** Location : Server room, toilet area	36	sqm	AED120	AED4,320
31	Supply and installation of **Curtain pelmet**	70	Rm	AED120	AED8,400
32	Supply and installation of **access panel** in the ceiling	6	Nos	AED450	AED2,700
33	Supply & Installation of **bulkhead for Cove light** Location : Reception area, Gm room , meeting room 12 pax	60	Rm	AED150	AED9,000
	FINISHES WORKS				
34	Supply and installation of wall paper on collum	18	sqm	AED120	AED2,160
35	Supply & applying of two coats paint with putty, primer, sanding works including materials, labor and required accessories with Jotun Fenomastic paint : Internal Walls. Height -2.4m **Make: Jotun**	395	M2	AED35	AED13,825
35	Supply & applying of two coats paint with putty, primer , sanding works including materials, labor and required accessories with Jotun Fenomastic paint : Gypsum ceiling **Make: Jotun**	440	M2	AED35	AED15,400

Tel: + 971 4 346 0061 Email : info@creativelabs.ae Web: www.creativelabs.ae
Warehouse No. 3 Mostafawi Compound , Al Quoz 3 , P.O. Box 122718, Dubai – United Arab Emirates

CREATIVE LAB
YOUR CREATIVE FITOUT PARTNER

SL.NO.	DESCRIPTION	QTY	UNIT	RATE	TOTAL
				TOTAL FOR FIT OUT WORKS	AED570,365
D	**JOINERY WORKS -** ***Design to be confirmed - Provisional Sum***				
	RECEPTION AREA				
1	Supply and installation reception table made up of MDF with PU paint finish+ MDF with veneer finish + Corian counter top Size:2000mmX800mmx10000mm	1	Nos	AED12,000	AED12,000
2	Supply and installation of wall paper	21	Sqm	AED120	AED2,520
3	Supply and installation of wall cladded with MDF with veneer finish + wallpaper + LED Strip light Length : 8820mm X 2400mm	1	Nos	AED21,000	AED21,000
4	Supply and installation of LOGO - Provisional sum	1	Nos	AED15,000	AED15,000
	PASSAGE AREA				
5	Supply and installation of display unit made up of MDF with PU paint finish Size: 3840mm X 2400mm	1	Nos	AED19,700	AED19,700
6	Supply and installation of storage unit made up of MDF with laminate finish Size: 7000mm X 2400mm	1	Nos	AED34,000	AED34,000
7	Supply and installation of step seater made up of MDF with laminate finish + planter box(1200mm x1000mm x 1000mm) Size: 1000mm (H)X 4900mm(L)	1	Nos	AED39,000	AED39,000
8	Supply and installation of wall paper Size: 1200mm (H)X 4900mm(L)	1	Ls	AED1,800	AED1,800
	PANTRY UNIT				
9	Supply and installation of base cabinet made up of MDF with laminate finish Size: (4400mm+2400mm) x 2400mm	1	Nos	AED40,000	AED40,000
10	Supply and installation of High Table made upon mdf with laminate finish Size: 3820 x1000mm	1	Nos	AED8,100	AED8,100
	WORKSTATION AREA 17 NOS				
11	Supply and installation of planter box made with of mdf with laminate finish Size: 2400 x1000mm	1	Nos	AED6,000	AED6,000
12	Supply and installation of High Table made up of mdf with PU paint finish + Seater Size: (3300+1800)x1000mm	1	Nos	AED12,000	AED12,000
	MEETING ROOM 12 PAX				
13	Supply and installation of wall paper Size: 6900mm X 2400mm	1	Nos	AED4,000	AED4,000
14	Supply and installation of writable glass Size: 1200mm X 1200mm	1	Nos	AED1,500	AED1,500
15	Supply and installation of Tv wall finished with wall paper Size: 3800mm X 2400mm	1	Nos	AED7,500	AED7,500
	GM OFFICE				
16	Supply and installation cabinet made up of Mdf with PU paint finish + Texture paint + veneer cabinet + Led strip light Size: 5200mm X 2400mm	1	Nos	AED28,000	AED28,000
17	Supply and apply of textured paint finish + TV wall unit made of mdf with veneer finish + LED strip light Size: 2800mm X 2400mm	1	Nos	AED5,000	AED5,000
	PHONE BOOTH				

Tel: + 971 4 346 0061 Email : info@creativelabs.ae Web: www.creativelabs.ae
Warehouse No. 3 Mostafawi Compound , Al Quoz 3 , P.O. Box 122718, Dubai – United Arab Emirates

CREATIVE LAB
YOUR CREATIVE FITOUT PARTNER

SL.NO.	DESCRIPTION	QTY	UNIT	RATE	TOTAL
18	Supply and installation of phone booth ledge made up of MDF with PU paint finish Size : 2900MM length	1	Nos	AED3,500	AED3,500
19	Supply and installation of acoustic wall cladding	27	Sqm	AED600	AED16,200
	WORKSTATION AREA 34 NOS				
20	Supply and installation of printer bay cabinet made up of Mdf with PU paint finish Size: 1990mm X 2400mm	1	Nos	AED10,000	AED10,000
21	Supply and installation of planter box made with of mdf with laminate finish Size: 1240 x1000mm	5	Nos	AED3,000	AED15,000
22	Supply and installation of planter box made with of mdf with laminate finish Size: 640 x1000mm	1	Nos	AED2,000	AED2,000
	MEETING ROOM 6 AND 5				
23	Supply and installation of cabinet made up of Mdf with PU paint finish				
24	Size: 3400MM x 2400mm	1	Nos	AED18,000	AED18,000
25	Size: 2500mm X 2400mm	1	Nos	AED13,000	AED13,000
26	Supply and installation of base TV cabinet made up of Mdf with PU paint finish Size: 3400MM Length	1	Nos	AED3,500	AED3,500
				TOTAL FOR JOINERY WORKS	**AED338,320**
E	**TOILET WORK**				
1	Supply & Installation of **60X60cm Floor tile** Location: Toilet area			Mentioned above	
2	Supply & Installation of **Waterproofing** Location: Toilet area			Mentioned above	
3	Supply & Installation of **Marble threshold**	2	Rm	AED750	AED1,500
4	Supply and installation of **wall Tile 60x60cm** as per the drawing and specification. Height - 2.4 m Make: RAK Ceramics Location : Toilet	78	Sqm	AED180	AED14,040
5	Supply & Installation of **vanity counter** in Corian top. Location: toilet Size:2400mm	1	Nos	AED9,000	AED9,000
6	Supply & Installation of **vanity counter** in Corian top. Location: toilet Size:1700mm	1	Nos	AED6,500	AED6,500
7	Supply and installation of Bench made up of MDF with PU paint finish	1	Nos	AED3,500	AED3,500
8	Supply & Installation of mirror in toilet				
	Size: 1700mm X 1200mm	1	Nos	AED1,000	AED1,000
	Size: 2400mm X 1200mm	1	Nos	AED1,400	AED1,400
				TOTAL FOR TOILET WORK	**AED36,940**
F	**ELECTRICAL AND LIGHTING WORKS**				
1	Preparation of complete electrical drawings, Preparing load schedules , tracing of each circuits and preparing necessary documents as per DEWA standards and getting approval for the same.	1	LS	AED10,000	AED10,000
2	Charges towards modification of existing DB	3	No	AED6,500	AED19,500
3	Supply & Installation of new DB	1	No	AED8,000	AED8,000

Tel: + 971 4 346 0061 Email : info@creativelabs.ae Web: www.creativelabs.ae
Warehouse No. 3 Mostafawi Compound , Al Quoz 3 , P.O. Box 122718, Dubai – United Arab Emirates

SL.NO.	DESCRIPTION	QTY	UNIT	RATE	TOTAL
4	Modification of SMDB if required	1	No	AED18,000	Rate only
5	Supply & installation of 13 Amp double power socket. Make : Legrand (Conduiting and cabling included)	15	Nos	AED450	AED6,750
6	Supply & installation of 13 Amp single power socket. Make: Legrand (Conduiting and cabling included)	5	Nos	AED420	AED2,100
7	Supply and installation of Floor Box with 2 twin power socket and provision for 2 data. Make : MK- Reception and meeting area	33	Nos	AED1,100	AED36,300
8	Charges towards power point for FCU and LOGO	1	Nos	AED1,200	AED1,200
9	Supply & Installation Of 1 Gang Switch With Wiring - Make: Legrand	25	Nos	AED360	AED9,000
10	Charges towards Cable Tray/Trunking,Cable Pulling, Glanding & Termination	1	LS	AED8,300	AED8,300
11	Charges towards conduiting for HDMI	1	LS	AED8,500	AED8,500
12	Charges towards conduiting for Wi-Fi, cctv and for IT works	1	LS	AED7,500	AED7,500
13	Testing & commissioning of electrical System	1	LS	AED6,500	AED6,500
14	Charges towards modification of FM 200	1	LS	AED24,000	AED24,000
	LIGHTING - *Provisional Sum*				
15	GIOMILANO HABOR 32W 4000K LED DECORATIVE LINEAR LIGHT WITH LED DRIVER- IP20 MATERIAL: WOOD LAMP BODY+ACRYLIC LAMP SHADE SIZE: L1200MM	30	Nos	AED2,100	AED63,000
16	TECNOLIGHT LINEA60 26W/MTR 4000K LED RECESSED LINEAR LIGHT WHITE FINISH POWERED BY SAMSUNG LLE WITH LED DRIVER SIZE: W60XH70 mm	50	RM	AED360	AED18,000
17	GIOMILANO ASTHER LED DECORATIVE PENDANT LIGHT- IP20 MATERIAL: FABRIC SIZE: D400mm	3	Nos	AED1,500	AED4,500
18	TECNOLIGHT NIKKO 20W 4000K RECESSED LED DOWNLIGHT WHITE FINISH POWERED BY SAMSUNG WITH LED DRIVER - IP40 SIZE: D190XH45 MM	6	Nos	AED150	AED900
19	TECNOLIGHT BRAVA 40W 4000K HANGING LED RING LIGHT BLACK FINISH POWERED BY SAMSUNG WITH LED DRIVER - IP40 Dia: 600MM	1	Nos	AED720	AED720
20	TECNOLIGHT LINEA60 4000K LED HANGING LINEAR LIGHT BLACK FINISH POWERED BY SAMSUNG LLE WITH DALI DIMMABLE LED DRIVER - IP20 SIZE: L2400XW60XH70 mm	2	Nos	AED840	AED1,680

Tel: + 971 4 346 0061 Email : info@creativelabs.ae Web: www.creativelabs.ae
Warehouse No. 3 Mostafawi Compound , Al Quoz 3 , P.O. Box 122718, Dubai – United Arab Emirates

SL.NO.	DESCRIPTION	QTY	UNIT	RATE	TOTAL
21	TECNOLIGHT MYSTRO 20W 4000K RECESSED LED DOWNLIGHT WHITE FINISH POWERED BY CREE WITH ON/OFF LED DRIVER - IP44 SIZE: D115x76 mm	50	Nos	AED180	AED9,000
22	TECNOLIGHT MYSTRO 12W 4000K RECESSED LED SPOTLIGHT WHITE FINISH POWERED BY CREE WITH LED DRIVER - IP44 SIZE: D85X65 mm	110	Nos	AED130	AED14,300
23	TECNOLIGHT FLEX 2835 14.4W/MTR 24V 4000K LED STRIPLIGHT 120LED/MTR POWERED BY BRIDGELUX - IP33	120	RM	AED180	AED21,600
24	GIOMILANO GO-120331024 4000K LED DECORATIVE LINEAR LIGHT BRASS FINISH WITH LED DRIVER- IP20 SIZE: L1500MM	2	Nos	AED1,880	AED3,760
25	GIOMILANO GO-410325 4000K LED DECORATIVE LINEAR LIGHT GOLD FINISH WITH LED DRIVER- IP20 SIZE: L900MM	1	Nos	AED2,700	AED2,700
26	GIOMILANO GO-100413 4000K LED DECORATIVE PENDANT LIGHT GOLD FINISH WITH LED DRIVER- IP20 SIZE: L900MM	1	Nos	AED1,450	AED1,450
27	GIOMILANO GO-100413 4000K LED DECORATIVE PENDANT LIGHT GOLD FINISH WITH LED DRIVER- IP20 SIZE: L900MM	1	Nos	AED1,450	AED1,450
28	Charges towards minor modification in existing power points	30	Nos	AED150	AED4,500
29	Charges towards power point	199	Nos	AED250	AED49,750
				TOTAL FOR ELECTRICAL WORKS	**AED344,960**
G	**FIRE FIGHTING/FIRE ALARM/ EMERGENCY WORKS**				
	FIRE FIGHTING SYSTEM				
1	Drainage and recharging of sprinkler: Drainage of existing sprinkler pipe in order to carry out changes and recharging of sprinkler after modification work.	1	Job	AED7,000	AED7,000
2	Supply and Installation of new pendant sprinkler points.	55	NO.	AED1,100	AED60,500
3	Supply and installation of Fire Extinguisher set as required by DCD. (CO2 and DCP).	2	NO.	AED750	AED1,500
4	charges toward shutdown	1	NO.	AED3,500	AED3,500
5	Pressure testing of sprinkler system.	1	Job	AED6,000	AED6,000
	FIRE ALARM SYSTEM				

Tel: + 971 4 346 0061 Email : info@creativelabs.ae Web: www.creativelabs.ae
Warehouse No. 3 Mostafawi Compound , Al Quoz 3 , P.O. Box 122718, Dubai – United Arab Emirates

CREATIVE LAB
YOUR CREATIVE FITOUT PARTNER

SL.NO.	DESCRIPTION	QTY	UNIT	RATE	TOTAL
6	Supply and installation of smoke detectors with cabling as per the proposed Plan layout.	25	NO.	AED1,400	AED35,000
7	Supply and installation of Fire Alarm Sounder as per proposed plan layout.	4	NO.	AED1,300	AED5,200
8	Supply and installation of manual break glass	2	NO.	AED1,200	AED2,400
9	Interfacing of existing unit with new devices.	3	NO.	AED4,000	AED12,000
10	supply& installation of new fire panel and interfacing with the building fire panel system.	1	Job	AED18,000	AED18,000
11	Programming of Fire Alarm System for additional items installed like a Smoke detector, Emergency light, break glass and wall mounted sounder etc.	1	Job	AED8,000	AED8,000
12	Supply and installation of Emergency light either self-contained or normal wiring light.	16	NO.	AED950	AED15,200
13	Supply and installation of directional exit sign with arrows in the corridor and common areas either self-contained or normal wiring light.	6	No.	AED950	AED5,700
14	Supply and installation of Exit light either self-contained or normal wiring light.	3	NO.	AED900	AED2,700
15	Inspection and Certification: Testing, commissioning, certification of material used, and attending of DCD final inspection.	1	Job	AED8,000	AED8,000
	TOTAL FOR FIRE FIGHTING/FIRE ALARM/ EMERGENCY WORKS				**AED190,700**
H	**PLUMBING & DRAINAGE WORKS**				
1	Charges towards PPR & HDPE pipe for plumbing & drainage works	1	LS	AED4,900	AED4,900
2	Supply & Installation of concealed cistern type floor standing WC with all accessories **Make: RAK Ceramics**	5	Nos	AED3,400	AED17,000
3	Supply & Installation of **floor trap**	8	Nos	AED450	AED3,600
4	Supply and installation of **Floor Clean outlet**	4	Nos	AED500	AED2,000
5	Supply and installation of **Gate Valves**	4	Nos	AED500	AED2,000
6	Supply & Installation of **counter top washbasin + mixer** **Make: RAK Ceramics**	5	Nos	AED3,800	AED19,000
7	Supply & Installation of new **kitchen sink single bowl along with mixer i**n pantry area Make: Bagno Desing / Clayton	1	Nos	AED3,500	AED3,500
8	Supply & Installation of urinal	2	Nos	AED2,900	AED5,800
9	Supply & Installation of urinal Partition in HPL	1	Nos	AED1,500	AED1,500
10	supply and installation of Water Heater	2	Nos	AED2,100	AED4,200
11	Supply and installation of Water Hammer Arrestor	5	Nos	AED1,000	AED5,000
12	Allow Sum for connecting to the existing System	1	LS	AED2,500	AED2,500
13	Testing and Commissioning	1	Nos	AED6,000	AED6,000
	TOTAL FOR PLUMBING & DRAINAGE WORKS				**AED77,000**
I	**HVAC WORKS**				
	Air Conditioning Works for server room				
1	Supply of 3.5 TR FCU Make: Mekar,Model: 097MKHS924HD	1	Nos		
2	Installation of new FCU with necessary support, vibration isolators.	1	Nos		

Tel: + 971 4 346 0061 Email : info@creativelabs.ae Web: www.creativelabs.ae
Warehouse No. 3 Mostafawi Compound , Al Quoz 3 , P.O. Box 122718, Dubai – United Arab Emirates

SL.NO.	DESCRIPTION	QTY	UNIT	RATE	TOTAL
3	Supply installation of the new chilled water supply and return pipeline with necessary support and fittings. Note: We have considered tapping into the chilled water stubout inside the office; if building management requests a connection to the main stubout, this will be regarded as a variation	1	Item	AED22,000	AED22,000
4	Supply installation of ready made valve packages for new FCU with all necessary fittings. Note: Hertz PICV Actuator valve,ready made valve package.	1	Nos		
5	Supply installation of the new condensated drain pipes with insulation with fittings. Note: We presume that the new false ceiling level is enough for the proposed condensate drainage line, if any CDP pump requirement will be consider as a variation.	1	Nos		
6	Pressure testing & chemical flushing for CHW pipes	1	Stubout		
7	Supply and installation new thermostat with necessary wiring and termination for FCU Make:Honeywell 24V modulating thermostat. Note:BMS interfaceing and cabling works are excluded from our offer	1	Nos		
8	Supply & installation of rectangular pre insulated ductwork for new FCU units including necessary, flexible duct, duct connectors, acoustic lining and insulation etc. Make:Pearl,Non Fire Rated type PI sheet.	1	Item		
9	Supply & installation of MSFD. Make:Airmaster (UAE)	2	Nos		
	Air Conditioning Works for Office Area				
10	Supply & installation of rectangular pre insulated ductwork for existing FCU's including necessary, flexible duct, duct connectors, acoustic lining and insulation etc. Make: Pearl,Non-Fire Rated type PI sheet.	6	Item	AED80,500	AED80,500
11	Relocation of existing FCU unit thermostat with necessary wiring. Note: BMS Integration and related workers are excluded from our offer.	6	Nos		
12	Supply and Installation of Square VCD with all support and fittings	12	Nos		
13	Supply and installation of 8' round VCD with necessary supports and fittings.	56	Nos		
14	Supply and Installation of linear Plenum box with all Flexible Ducts and fittings.	68	Rm		
15	Supply and Installation of linear Plenum box with all Flexible Ducts and fittings.	4	Rm		
16	Supply and Installation of 2-slot linear AC diffuser with all Flexible Ducts and fittings.	136	Rm		
17	Supply and installation of 450x450 square diffuser with necessary supports and fittings.	6	Nos		
18	Supply and installation of 200 dia exhaust diffuser at pantry and toilet with necessary supports and fittings.	8	Nos		
19	Supply & installation of rectangular pre insulated ductwork for pantry and toilet exhaust works including necessary duct connectors and insulation etc.	1	Nos		

Tel: + 971 4 346 0061 Email : info@creativelabs.ae Web: www.creativelabs.ae
Warehouse No. 3 Mostafawi Compound , Al Quoz 3 , P.O. Box 122718, Dubai – United Arab Emirates

SL.NO.	DESCRIPTION	QTY	UNIT	RATE	TOTAL
20	Supply and Installation of 450 cfm ducted inline exhaust fan for Pantry Make:KJ Fans,Korea	1	Nos		
21	Charges for FCU cooling coil external chemical cleaning,chilled water strainer and return filter clening	6	Item		
22	Supply and installation of CTA with necessary supports and fittings.	4	Nos		
23	Supply and installation of bypass type VAV with necessary supports and fittings.	1	Nos	AED2,100	Rate only
24	Supply and installation of VAV thermostat with necessary wiring.	1	Nos	AED500	Rate only
25	Supply and installation of VAV thermostat with necessary wiring.	1	Item	AED5,000	Excluded
	TOTAL FOR HVAC WORKS				**AED102,500**
	SUMMARY OF WORKS				
A	TOTAL FOR PRELIMINARIES				**AED30,000**
B	TOTAL FOR DEMOLITION WORKS				**AED67,700**
C	TOTAL FOR FIT OUT WORKS				**AED570,365**
D	TOTAL FOR JOINERY WORKS				**AED338,320**
E	TOTAL FOR TOILET WORK				**AED36,940**
F	TOTAL FOR ELECTRICAL WORKS				**AED344,960**
G	TOTAL FOR FIRE FIGHTING/FIRE ALARM/ EMERGENCY WORKS				**AED190,700**
H	TOTAL FOR PLUMBING & DRAINAGE WORKS				**AED77,000**
I	TOTAL FOR HVAC WORKS				**AED102,500**
J	TOTAL FOR LOOSE FURNITURE				**AED136,945**
	Total Project Value - Excluding VAT				**AED1,895,430**
5% VAT applicable of the above total					

Exclusions & Clarifications

1 Plants excluded

2 All white goods excluded

3 Final fixtures for IT work excluded

4 Any works related to the passage or corridor areas are excluded from the submitted proposal.

Terms & Conditions :

1 Any additional works other than mentioned in the BOQ will be quoted separately & will be treated as a variation to the contract.

2 All our contracts are re measurable (unless if agreed as lump sum contract) & invoicing will be based on final re measured quantities quoted.

3 The prices quoted are valid for 30 days only.

4 Upon confirmation of the contract a Local Purchase order of the total contract value should be raised in our name, M/s Creative Lab Interiors and contracting LLC & Advance payment Cheque of the total contract value to be enclosed with the same.

5 Commencement of the contract will be considered only after receipt of the LPO & Advance Payment Cheque.

6 Upon confirmation of the contract client will have to strictly comply with the agreed payment terms. In the absence of timely payment, the client will be declared in default immediately without requirement of any further notice from Creative Lab.

Tel: + 971 4 346 0061 Email : info@creativelabs.ae Web: www.creativelabs.ae
Warehouse No. 3 Mostafawi Compound , Al Quoz 3 , P.O. Box 122718, Dubai – United Arab Emirates

SL.NO.	DESCRIPTION	QTY	UNIT	RATE	TOTAL
7	Creative Lab Reserves complete right to stop the works if the above payment terms are defaulted. Commencement of works will only start once the agreed payment has been credited to the account of Creative Lab. Client agrees and accepts that, they do not have any right to take any legal action/penalty against Creative Lab if the assignment is put on hold due to nonpayment of the invoice as per agreed payment terms. Creative Lab will not be responsible for any loss that the client may suffer/incur due to delay in completion of the assignment in case of default in the payment terms mentioned above. Creative Lab reserves complete right to remove the installed material from site in case of nonpayment.				
8	**VARIATIONS:**				
a.	For all Variations to the contract, they must be supported with a written confirmation on the prices & scope of works. No verbal instructions from client will be accepted or considered .and no further action will be taken on the assignment				
b.	Once the instructions are received in writing along with Local Purchase Order and 100% advance payment for the same, only then Creative Lab will proceed with the Scope of Works.				
c.	Extra time required to complete the variation also has to be confirmed and agreed in writing by the client for Creative Lab to proceed with the variation scope.				

Note: All the above conditions have to be strictly met for Creative Lab to proceed with execution variation works.

9 **DELIVERY:**

a. Delivery dates have to be mutually agreed and confirmed in writing once the contract is finalized

b. All delivery dates are based on actual working days. (Sunday & Holidays Excluded)

Note: No refunds / cancellations will be accepted under any circumstances for the above 'Customized' items.

10 All Payments for Approval fees, security deposits etc. to be paid by clients directly to the Concerned Department /Authorities, any delays in doing so will delay the commencement date of works.

11 All our Terms & Conditions are an integral part of our quotation and shall be an integral part of the contract.

12 For any reasons if the client cancels the contract or a part of it, no refunds will be made by Creative Lab

13 Unless full & final payment of the total contract value & variations (if any) is not received, Completion certificate will not be handed

Delivery -TBD

Payment terms: TBD

Should you have any queries regarding the above quotation, feel free to contact the undersigned.

Assuring you the best of our services and cooperation at all times.

Thanking you.

Yours faithfully,

For Creative Lab

P.O.Box: 122718
DUBAI - U.A.E.
CREATIVE LAB INTERIORS AND CONTRACTING LLC

Nirav Shah

050 9110309

Tel: + 971 4 346 0061 Email : info@creativelabs.ae Web: www.creativelabs.ae
Warehouse No. 3 Mostafawi Compound , Al Quoz 3 , P.O. Box 122718, Dubai – United Arab Emirates