Design Infinity

WWW.DESIGN-INFINITY.COM

COMMERCIAL PROPOSAL

HUSPY- 28th Floor Omega Tower

LOCATION:ABU DHABI

Design Infinity

Table of CONTENTS

1. Cover Letter with Notes & Exclusions
2. Bill of Quantities
4. Contact Person

Design Infinity

COVER LETTER

Design Infinity *Beyond Imagination ...*

Date: 27/01/2026

REF: DI/AK//2025/R2

Dear Sir

SUB : INTERIOR FITOUT WORKS Huspy, 28th Floor Omega Tower Abu Dhabi ,

We thank you for allowing us to offer our offer for INTERIOR FITOUT WORKS FOR HUSPY 28th Floor Omega Tower Abu Dhabi.
Please find herewith our offer as per the attached amounting as below.

VALUE ENGINEERING OPTION

TOTAL FOR FIT OUT	**3,121,372.00**
Discount	**61,372.00**
GRAND TOTAL	**3,060,000.00**

VAT 5% AED : 153,000.00

Completion: As per shedule

Validity: 30 days from the above date.

Payment Terms: 25% advance against confirmation,65% interim payment upon site progress,5% on completion &5% retention against bank guarantee cheque

We look forward to establishing a constructive dialogue with you at all stages of your evaluation process. Assuring you of our best services at all times.

We hope our offer is in line with your requirement and look forward to working with you.

Thank you and best regards,

ANJANA KAMATH
Associate Director – Sales

P.O. Box. 62522 | Dubai | UAE
Tel: +971 4 3795902
Fax: +971 4 3795903
Email: info@design-infinity.com

P. O. Box. 62560 | Abu Dhabi | UAE
Tel: +971 2 4482286
Fax: +971 2 4482287
Email: info@design-infinity.com

www.design-infinity.com

SUB : INTERIOR FITOUT WORKS Huspy, 28th Floor Omega Tower Abu Dhabi ,

NOTES AND EXCLUSION

1 All Government/ Municipal/Civil defence fees, deposits, building deposits are to be paid by the Client on actuals.

2 Any changes to the work, on the instructions from building management/authorities/employer, will have an additional cost implication and to be agreed upon finalizing of details.

3 MEP is predesigned by considering to reuse all existing FCUs, Smoke, sprinklers, speakers.

4 Any Upgradation on existing MEP services are not considered such as Power upgradation, Firefighting main line upgradations etc.

5 All FCUs existing is considered to be reused without any relocations and in good working condition.

6 Incoming power cable to existing SMDB- Existing to be reused.

7 Considered that existing SMDB for the floor in electrical room to be reused for the proposed space.

8 Emergency light is proposed with self contained monitoring type.

9 Modification of Sprinkler main line is not included in our scope if required will be quoted separately

10 We have considered relocation of sprinklers only in the new partition areas. If sprinklers in other areas are not operational, it will be quoted

11 We have considered that the existing devices are in healthy condition.

12 VE Items

Carpet-Armstrong make

Glass partition &doors -Non acoustic Frameless glass partition considered

Textured paint changed to Fenomastic paint from jotun

Veneer changed to veneer look laminate finish on all joinery items

Smart film changed to normal frosted film

EXCLUSIONS

1 Loose Furniture &Plants
2 New FCUs / BTU meter/Water meter works
3 Individual control for closed rooms
4 IT AV All ELV works
5 Aluminium cladding for chilled water and ducts
6 Art work / artifacts / graphics
7 White goods / kitchen equipment's
8 Any item not mentioned in the BOQ
9 VAT

P.O. Box. 62522 | Dubai | UAE
Tel: +971 4 3795902
Fax: +971 4 3795903
Email: info@design-infinity.com

P. O. Box. 62560 | Abu Dhabi | UAE
Tel: +971 2 4482286
Fax: +971 2 4482287
Email: info@design-infinity.com

www.design-infinity.com

Design Infinity

BILL OF QUANTITIES

Design Infinity *Beyond Imagination ...*

Huspy, 28th Floor Omega Tower Abu Dhabi, United Arab Emirates

DI/AK /25/R1 **Date 27/01/2026**

Item	DESCRIPTION	Qty	Unit	Amount (Dhs.)	TOTAL (Dhs.)
1	**GENERAL REQUIREMENTS/PRELIMINARIES**				
1.01	Mobilization & demobilization of the material to site	1	Job	35,000.00	35,000.00
1.02	Preparation of drawings	1	Job	20,000.00	20,000.00
1.03	Allow for necessary scaffolding / hoarding	1	Job	9,500.00	9,500.00
1.04	Provision, site supervision including project manager, site supervisor and site personnel's.	1	Job	40,000.00	40,000.00
1.05	Provide Cleaning of site on regular basis.	1	Job	9,500.00	9,500.00
1.06	Insurance for office interior work (CAR) Coverage asper the DI standards	1	Job	4,500.00	4,500.00
1.07	PI Insurance for office interior work	1	Job	10,500.00	10,500.00
1.08	Performance and advance guarantee charges	1	Job	25,000.00	25,000.00
1.09	Liaison charges for authority approval	1	Job	25,000.00	25,000.00
1.1	Fitout to cordination fees to Asteco	1	item	19,425.00	19,425.00
	Note : Authority Approval Fees shall be paid by client on actuals				
	SUB TOTAL-GENERAL REQUIREMENTS/PRELIMINARIES				**198,425.00**
2	**DEMOLITION/ CIVIL WORKS**				
2.01	Demolition of existing block wall for the new opening .	1	item	9,500.00	9,500.00
	SUB TOTAL DEMOLITION / CIVIL WORKS				**9,500.00**
3	**FLOORING WORKS**				
3.01	Supply and installation of raised floor Make :UNITILE UNIFOLD 1650 BARE, CORNER LOCK SYSTEM	1050	sqm	213.00	223,650.00
3.02	Supply and installation of antistatic raised floor Make : UNITILE USF 800 EB EDGE SUPPORT RIGID GRID (ESRG) SYSTEM	5	sqm	LS	3,750.00

Design Infinity *Beyond Imagination ...*

Huspy, 28th Floor Omega Tower Abu Dhabi, United Arab Emirates					
DI/AK /25/R1					Date 27/01/2026
Item	DESCRIPTION	Qty	Unit	Amount (Dhs.)	TOTAL (Dhs.)
3.03	Supply and installation of 5mm LVT Concrete texture flooring . Make :Amtico Access	425	sqm	184.00	78,200.00
3.04	Supply and installation of calcium silicate backing for the installation of LVT	425	sqm	120.00	RATE ONLY
3.04a	Supply and installation of Fiberbond self levelling for installation of LVT Flooring	425	sqm	87.00	36,975.00
3.05	Supply and installation of 500 x500 mm carpet tile flooring Make : First Define	570	sqm	162.00	RATE ONLY
3.05a	Supply and installation of 500 x500 mm carpet tile flooring Make : AMSTRONG	570	sqm	125.00	71,250.00
3.06	Supply and installation of carpet rug	9	sqm	934.00	8,406.00
3.07	Supply and installation of threshold	2	Nos	LS	2,500.00
3.08	Supply and installation of SS metal strip insert	200	Rm	114.00	22,800.00
	SUB TOTAL-FLOORING WORKS				
					447,531.00
4	**CEILING WORKS**				
4.01	Supply and installation of 12.5mm thick FR gypsum board ceiling with necessary fittings Make : Knauf / Equivalent	483	m2	134.00	64,722.00
4.02	Supply and apply of white Fenomastic paint for the proposed gypsum ceiling	483	m2	34.00	16,422.00
4.03	Supply and installation of gypsum bulkhead with Fenomastic paint	312	Rm	140.00	43,680.00
4.04	Supply and installation of 60 x60 Metal ceiling Tile Location : Server room	5	sqm	200.00	1,000.00
4.05	Supply and installation of Fenomastic paint on open ceiling .	790	sqm	54.00	42,660.00

Design Infinity *Beyond Imagination ...*

Huspy, 28th Floor Omega Tower Abu Dhabi, United Arab Emirates					
DI/AK /25/R1					Date 27/01/2026
Item	DESCRIPTION	Qty	Unit	Amount (Dhs.)	TOTAL (Dhs.)
4.06	Supply and installation of acoustic PETFelt ceiling linear baffles. Spacing : 50mm Size : 150 (H) x 24 (12+12) (T)mm Brand : acoustic.ae Material specification : PET Material : 100% Polyester fiber including 60% regenerated fibers made of post-consumer discarded PET drinking bottles. Core: BS EN 717-1 EO Class	200	sqm	394.00	78,800.00
4.07	Supply and installation of acoustic PETFelt ceiling cloud with 50mm border thickness. Brand : acoustic.ae Material specification : PET Material : 100% Polyester fiber including 60% regenerated fibers made of post-consumer discarded PET drinking bottles. Core: BS EN 717-1 EO Class Density : 200 kg/cubic.m				
	Diameter 1.8m	3	Nos	2,580.00	7,740.00
	Diameter 1.2m	12	Nos	2,007.00	24,084.00
4.08	Supply and installation of access panel	1	Item	4,667.00	4,667.00
4.09	Supply and installation of curtain pelmet	155	sqm	154.00	23,870.00
	SUB TOTAL-CEILING WORKS				**307,645.00**
5	**WALLS AND WALL FINISHES WORKS**				
5.01	Supply and installation of 122 mm thick wall partition comprising of 70mm steel studs and 72mm track, 50Kg/m3 density of Rockwool insulation covered by 12.5mm regular gypsum board on both sides	245	m2	194.00	47,530.00

Design Infinity *Beyond Imagination ...*

Huspy, 28th Floor Omega Tower Abu Dhabi, United Arab Emirates					
DI/AK /25/R1					Date 27/01/2026
Item	DESCRIPTION	Qty	Unit	Amount (Dhs.)	TOTAL (Dhs.)
5.02	Supply and Installation of Apton Acoustic Relocatable Modular Single glazed partition system of Quartz series, using 27X27mm profiles for verticals and horizontal top and bottom in RAL 9005 Black Powder coated finish, using 13.52 mm thick acoustic laminated low Iron tempered glasses , glass to glass joints to be bonded with clear Apton straight PETG Strips for "butt" / "L" /90° corner joints from FFL to 2400mm. 38dB Acoustic rating. **Make : Apton**	60	m2	894.00	Rate only
5.02a	Supply and installation of 12mm thick frameless tempered glass partition using black powder coated U channel Height 2700mm	60	m2	374.00	22,440.00
5.03	Supply and installation of 122 mm thick wall baffle comprising of 70mm steel studs and 72mm track, 50Kg/m3 density of Rockwool insulation covered by 12.5mm regular gypsum board on both sides.	30	RM	194.00	5,820.00
5.04	Supply and installation of 50 mm thick wall cladding comprising of 70mm steel studs and 72mm track, 50Kg/m3 density of Rockwool insulation covered by 12.5mm regular gypsum board .	779	sqm	134.00	104,386.00
5.05	Supply and installation white Fenomastic paint	475	sqm	34.00	16,150.00
5.06	Supply and installation of texture paint	375	sqm	160.00	Rate only
5.06a	Supply and installation of fenomastic paint Make Jotun	375	sqm	34.00	12,750.00
5.07	Supply and installation of wall paper Make : Black edition Ngc Nafees	195	m2	96.00	18,720.00
5.08	Supply and installation of smart film for acoustic glass partition and door	80	m2	1,080.00	Rate only
5.08a	Supply and fixing Frosted film on glass Height 1200mm	80	m2	120.00	9,600.00
5.09	Supply and installation 50mm high mdf skirting	440	Rm	47.00	20,680.00

Design Infinity *Beyond Imagination ...*

Huspy, 28th Floor Omega Tower Abu Dhabi, United Arab Emirates					
DI/AK /25/R1					Date 27/01/2026
Item	DESCRIPTION	Qty	Unit	Amount (Dhs.)	TOTAL (Dhs.)
5.1	Supply and installation 100mm high curved mdf skirting	70	sqm	67.00	4,690.00
	SUB TOTAL-PARTITION WORKS				**262,766.00**
6	**DOORS**				
6.01	Supply & Installation of Apton Glide 2-S Single Glazed single leaf sliding door with Sliding door systems in RAL 9005 Black Powder coated as per Apton standards, Sliding Track using over head Sliding track, Closing Channel & Single leaf glazed shutter of 13.52 mm acoustic laminated Low Iron Tempered acoustic laminated glass to achieve 37dB Acoustical Performance. Door Size : 1000mm x 2800mm	6	No's	8,200.00	Rate only
6.01a	Supply and installation of frameless single leaf glass door using floor spring and H type handle Size 1000x2700mm	6	No's	2,934.00	17,604.00
6.02	Supply and installation of automatic glass sliding door	2	No's	29,667.00	59,334.00
6.03	Supply & install of 60 minutes FR single leaf wooden door made in solid beech/Marenti solid wood frame & architrave. Shutter to have 54 mm thk FR core door shutter in both side oak veneer in lacquer finish. Size: 1000mmL x 2400 mm Ht Location : Server room.	1	No's	4,440.00	4,440.00
6.04	Refurbishment, reveneering and refixing of Double leaf existing wooden door with new veneer finish and by reusing of existing ironmongeries. Location : @ corridor	2	No's	4,500.00	Rate only
	SUB TOTAL- DOORS				**81,378.00**

Design Infinity *Beyond Imagination ...*

Huspy, 28th Floor Omega Tower Abu Dhabi, United Arab Emirates					
DI/AK /25/R1					Date 27/01/2026
Item	DESCRIPTION	Qty	Unit	Amount (Dhs.)	TOTAL (Dhs.)
7	JOINERY WORKS / COSTUM MADE				
7.01	Reception counter (JY-01), made of MDF with oak veneer look laminate finish + PU paint ribbed finish skirting. Included 30mm thk black PU paint finish table top and mobile pedestal unit. Size- 3000x600x750mm ht. Location: @ Reception Area.	1	No.	12,036.00	12,036.00
7.02	Reception side wall (JY-02), made of MDF with Veneer look laminate + mdf in textured paint finish Size- 7000x300x3750mm ht. Location: @ Reception Area.	1	No.	21,868.00	21,868.00
7.03	Reception side wall (JY-02a), made of MDF with textured paint finish . Size- 6400x300x3750mm ht. Location: @ Reception Area.	1	No.	16,576.00	16,576.00
7.04	Open Shelving (JY-03), made of mdf with oak veneer look laminate finish and necessary support. Size- 1510x710x3750mm ht.	1	No.	9,006.00	9,006.00
7.05	Storage Unit (JY-04), made of mdf with oak veneer look laminate finish and shutter shall be swing type. Size- 5490x400x3750mm ht.	1	No.	30,150.00	30,150.00
7.06	Meetingroom TV Wall (JY-05), made of mdf with oak veneer look laminate finish and necessary frame work. Size- 2400x200x2900mm ht.	1	No.	8,371.00	8,371.00
7.07	Planter unit with Cabinet (JY-06), made of mdf with oak veneer look laminate finish and shutter shall be swing type. Include provision for plants. Size- 1400x400x1050mm ht.	6	Nos.	3,431.00	20,586.00
7.08	Wooden Slats (JY-07), made of mdf with oak veneer look laminate finish and necessary support. Size- 100x50x2900mm ht.	33	Nos.	816.00	26,928.00
7.09	Booth Seating (JY-08), made of mdf with oak veneer finish look laminate finish base, seat and backrest in fabric/PU leather finish. Size- 3200x600x2900mm ht.	2	Nos.	11,398.00	22,796.00

Design Infinity *Beyond Imagination ...*

Huspy, 28th Floor Omega Tower Abu Dhabi, United Arab Emirates					
DI/AK /25/R1					Date 27/01/2026
Item	**DESCRIPTION**	**Qty**	**Unit**	**Amount (Dhs.)**	**TOTAL (Dhs.)**
7.1	Pantry Back wall unit (JY-09), made of mdf with oak veneer look laminate finish included open shelf and 12mm thk solid surface top for bottom storage unit. Shutter shall be swing type. Size- 5800x600x2900mm ht.	1	No.	32,667.00	32,667.00
7.11	Front bar Counter (JY-10), made of mdf with grey marble top with PU painted finish ribbed pattern facia and side leg. Size- 3885x600x900mm ht.	1	No.	21,638.00	21,638.00
7.12	Collab Table (JY-11), made of mdf with oak veneer look laminate finish. Size- 4200x1000x900mm ht.	2	Nos.	8,624.00	17,248.00
7.13	Raised Platform (JY-12), made of mdf with oak veneer look laminate finish facia and ready to receive the carpet. (Carpet supply & install by DI) Size- 3115x2400x150mm ht.	1	No.	7,644.00	7,644.00
	SUB TOTAL JOINERY WORKS / COSTUM MADE				**247,514.00**
8	**LIGHT FIXTURES**				
	Supply of Light fittings / fixtures as per received proposed drawings / all in accordance with design visual :				
	Note: **Brand : Creta / Equivalent.** **Non-Dimmable**				
8.01	LT-01 - SUSPENDED LINEAR Location: WORK STATION bar counter	90	MTRS	307.00	27,630.00
8.02	LT-02 - MAGNETIC TRACK-Normal Location: COORIDOR	10	MTRS	160.00	1,600.00
8.03	LT-02-A - MAGNETIC TRACK Location: COORIDOR	160	MTRS	264.00	42,240.00
8.04	LT-02-B - TRACK LIGHT LED SPOT-5 x LED's Location: COORIDOR	104	NOS	334.00	34,736.00
8.05	LT-03 - RECESSED DOWNLIGHT Location: MEETING ROOM	65	NOS	160.00	10,400.00

Huspy, 28th Floor Omega Tower Abu Dhabi, United Arab Emirates

DI/AK /25/R1 **Date 27/01/2026**

Item	DESCRIPTION	Qty	Unit	Amount (Dhs.)	TOTAL (Dhs.)
8.06	LT-04 - SUSPENDED CYLINDERICAL PENDANT Location: WORK STATION	156	NOS	240.00	37,440.00
8.07	LT-05 - RECESSED TWIN SPOT Location: BOOTH SEATING RECEPTION SEATING	14	NOS	307.00	4,298.00
8.08	LT-06 - LED STRIP LIGHT Location: COVE AREA	150	MTRS	87.00	13,050.00
8.09	LT-07 - SUSPENDED RING PENDANT-Dia 1200mm Location: HOT DESK TOWNHALL	10	NOS	2,134.00	21,340.00
8.1	LT-07-a - SUSPENDED RING PENDANT-Dia 900mm Location: meeting room 4 pax	1	NOS	1,600.00	1,600.00
8.11	LT-08 - SUSPENDED LINEAR-OVAL Location: MEETING ROOM 6 AND 8 PAX	25	MTRS	734.00	18,350.00
8.12	LT-09 - 60X60 PANEL LIGHT Location: SERVER ROOM	1	NOS	114.00	114.00
8.13	LT-10 - DECORATIVE PENDANT-L1500mm Location: RECEPTION	1	NOS	2,600.00	2,600.00
8.14	LT-11 - DECORATIVE WALL LIGHT Location: RECEPTION	2	NOS	1,267.00	2,534.00
					217,932.00
9	**ELECTRICAL POWER WORKS.**				
	Power distribution SMDB / DB works:				
9.01	Modification of existing SMDBs	1	Item	8,667.00	8,667.00
9.02	Supply and installation of new DBs	6	Nos	5,600.00	33,600.00
	Power cabling works :				
9.03	Incoming power cable to New DBs	1	Item	41,334.00	41,334.00
	Cable tray and trunking works for Power cables:				
9.04	Supply and installation of new cable tray to meter cabinet	1	Item	3,934.00	3,934.00
9.05	Supply and installation of new cable tray for the incoming power cables to New DBs	1	Item	16,667.00	16,667.00

Huspy, 28th Floor Omega Tower Abu Dhabi, United Arab Emirates					
DI/AK /25/R1					Date 27/01/2026
Item	DESCRIPTION	Qty	Unit	Amount (Dhs.)	TOTAL (Dhs.)
9.06	Modification of existing cable trunking for **Power** distributions at **high level**.	1	Item	21,547.00	21,547.00
9.07	Modification of existing cable trunking for **Light** distributions at **high level**.	1	Item	16,667.00	16,667.00
9.08	Modification of existing cable tray for the **Data cables** from IT cabinet at High level.	1	Item	22,400.00	22,400.00
	Light Installation works				
9.08	Supply and installation of conduit and wiring for the light fixtures	354	Nos	214.00	75,756.00
9.09	Supply and installation of conduit and wiring for the Linear LED light fixtures	435	m	87.00	37,845.00
9.1	Supply and installation of ceiling fittings for the light fixtures	441	Nos	27.00	11,907.00
9.11	Installation of technical light fixtures	342	Nos	40.00	13,680.00
9.12	Installation of Linear light fixtures	435	m	34.00	14,790.00
9.13	Installation of Decorative lights	12	Nos	200.00	2,400.00
	Switches Installation & Supply of lighting control system works:				
9.14	Supply and installation of **Multi Gang 1 Way** Switch Brand : Schneider / BG / equivalent. Finishes: PVC white.	4	Nos	867.00	3,468.00
9.15	Supply and installation of **2g/1g Gang 1 Way** Switch Brand : Schneider / BG / equivalent. Finishes: PVC white.	12	Nos	194.00	2,328.00
	Power Sockets Installation works				
9.16	Supply & installation of **13A Single power** socket with necessary conduiting, wiring and accessories for general purposes Brand : Schneider / BG / equivalent. Finishes: PVC white / Black	10	Nos	347.00	3,470.00

Design Infinity *Beyond Imagination ...*

Huspy, 28th Floor Omega Tower Abu Dhabi, United Arab Emirates					
DI/AK /25/R1					Date 27/01/2026
Item	**DESCRIPTION**	**Qty**	**Unit**	**Amount**	**TOTAL**
				(Dhs.)	**(Dhs.)**
9.17	Supply & installation of **13A Double power** socket with necessary conduiting, wiring and accessories. Brand : Schneider / BG / equivalent. Finishes: PVC white / Black	35	Nos	360.00	12,600.00
9.18	Supply & installation of Floor box FB2 socket with necessary conduiting, wiring and accessories. Considered 1 single socket for each user. Brand : MK/Davis/ equivalent. Finishes: PVC white.	73	Nos	907.00	66,211.00
9.19	Supply & installation of 13A Double power socket - Weather proof	4	Nos	520.00	2,080.00
9.2	Allow cost for power supply for new FCUs, VAVs	18	Nos	467.00	8,406.00
9.21	Allow cost for power supply for IT racks	2	Nos	867.00	1,734.00
9.22	Allow cost for power supply for Wifi, CCTV, FACP, 24x7, Hand dryer(2), Access doors(2)	10	Nos	400.00	4,000.00
9.23	Allow cost for power supply for Signages(3), Sliding doors(2)	6	Nos	867.00	5,202.00
9.24	Allow cost for power supply for smart glass	6	Nos	734.00	4,404.00
9.25	Supply and installation of Isolator power provision for Video wall	1	Nos	1,667.00	1,667.00
9.26	Supply and installation of Isolator power provision for coffee machine	1	Nos	600.00	600.00
9.27	Cables charges for coffee machines	1	Nos	1,800.00	1,800.00
9.28	Existing Electrical meter works rearrangement works @ electrical room	1	Item	11,334.00	11,334.00
	Containment works				
9.29	Supply and installation of Conduit for **IT Data** points	150	Nos	134.00	20,100.00
9.30	Supply and installation of Conduit for **HDMI** points	7	Nos	200.00	1,400.00
9.31	Supply and installation of Conduit for **Wi-fi** points	12	Nos	134.00	1,608.00
9.32	Supply and installation of Conduit for **Camera**	18	Nos	134.00	2,412.00
9.33	Supply and installation of Conduit for **Access control**	3	Nos	200.00	600.00
9.34	Supply and installation of Conduit for **AV** works like speakers etc.	15	Nos	134.00	2,010.00

Design Infinity *Beyond Imagination ...*

Huspy, 28th Floor Omega Tower Abu Dhabi, United Arab Emirates					
DI/AK /25/R1					Date 27/01/2026
Item	DESCRIPTION	Qty	Unit	Amount (Dhs.)	TOTAL (Dhs.)
9.35	Supply and installation of cable trays for ELV system	1	Item	12,000.00	12,000.00
	Sundries				
9.36	Allow for **testing and commissioning** of electrical services (Any 3rd party testing and certifications excluded)	1	Item	1,667.00	1,667.00
9.37	Co-ordination of ADCD approvals	1	Item	6,000.00	6,000.00
9.38	Electrical metering works	1	Nos	6,000.00	6,000.00
9.4	Allow for identification **labels** including plates, discs, labels, charts and colour coding for electrical services.	1	Item	667.00	667.00
					504,962.00
10	**HVAC WORKS**				
	AC WORKS				
10.01	Supply and installation of New additional Chilled water FCU along with the copper piping fittings supports and necessary accessories				Existing to be reused.
10.02	Supply and installation of PI Ducting ,fittings supports & necessary accessories (SAD/RAD)	1	Item	172,079.00	172,079.00
10.03	Supply and installation of Thermostat	12	Nos	1,099.00	13,188.00
10.04	Supply linear slot diffuser	1	Item	21,974.00	21,974.00
	Return linear slot diffuser	1	Item	8,584.00	8,584.00
10.05	Supply and installation of Square diffusers	1	Item	19,502.00	19,502.00
10.06	Plenum boxes for Supply of Air Outlets	1	Item	17,854.00	17,854.00
10.07	Supply and installation of VCDs	1	Item	21,424.00	21,424.00
10.08	Supply and installation of MSFD	2	Nos	2,541.00	5,082.00
10.09	Supply and installation of flexible, and other necessary fixtures	1	Item	7,691.00	7,691.00
10.1	Modification of existing FA and extract air ducts for the proposed space and Pantry	1	Item	30,214.00	30,214.00
10.11	Air balancing & Testing & commissioning	1	Item	17,579.00	17,579.00
10.12	Performance testing for Existing FCU's	12	Nos	687.00	8,244.00

Design Infinity *Beyond Imagination ...*

Huspy, 28th Floor Omega Tower Abu Dhabi, United Arab Emirates					
DI/AK /25/R1					Date 27/01/2026
Item	DESCRIPTION	Qty	Unit	Amount (Dhs.)	TOTAL (Dhs.)
10.13	Integration of BMS works Reprogramming of Existing Thermostats FCU	1	P.S	109,867.00	109,867.00
10.14	Supply and installation of CTA for closed rooms	6	nos	867.00	5,202.00
10.15	Chemical flushing	1	Item	11,674.00	11,674.00
10.16	Relocation of existing Chilled water FCU's including modification of chilled water pipes and relocation of existing Valve packages	1	Item	76,907.00	RATE ONLY
10.17	Supply and installation of new VAV, controllers and including BMS integration works	1	Item	43,947.00	43,947.00
	SUB TOTAL-HVAC WORKS				**514,105.00**
11	**CIVIL DEFENCE WORKS**				
	FIRE FIGHTING WORKS				
11.01	Supply and Installation of pendant sprinkler with pipe and accessories	23	Nos	790.00	18,170.00
11.02	Supply and Installation of upright sprinkler with pipe and accessories	23	Nos	756.00	17,388.00
11.03	Relocation of existing Upright sprinkler with accessories	57	Nos	550.00	31,350.00
11.04	Supply and Installation of 5 kg CO2 fire extinguisher	7	Nos	255.00	1,785.00
11.05	Supply and Installation of 6 kg DCP fire extinguisher	7	Nos	303.00	2,121.00
11.06	Draining and Recharging with Pressure Testing Charges	1	Item	6,180.00	6,180.00
11.07	Supply & Installation of Pipes & Fittings	1	Item	3,434.00	3,434.00
11.08	Fire Suppression system (FM 200)	1	Item	48,000.00	RATE ONLY
11.09	DCD Charges	1	Item	687.00	687.00
	FIRE ALARM WORKS				
11.1	Supply and installation of Single loop Fire Addressable Alarm Control Panel **(FACP)**	1	Nos	18,540.00	18,540.00

Design Infinity *Beyond Imagination ...*

Huspy, 28th Floor Omega Tower Abu Dhabi, United Arab Emirates					
DI/AK /25/R1					Date 27/01/2026
Item	DESCRIPTION	Qty	Unit	Amount (Dhs.)	TOTAL (Dhs.)
11.11	Supply and Installation of new addressable optical **smoke** detectors with built in isolator base.	35	Nos	1,168.00	40,880.00
11.12	Supply and Installation of new addressable optical **Void smoke** detectors with built in isolator base.	9	Nos	1,511.00	13,599.00
11.13	Supply and Installation of new addressable Heat detectors with built in isolator base.	1	Nos	1,305.00	1,305.00
11.14	Relocation of existing Smoke detectors	7	Nos	618.00	4,326.00
11.15	Relocation of existing FA devices, MCP, Sounders	7	Nos	618.00	4,326.00
11.16	Supply & Installation of Addressable **break glass / Manual call point**	4	Nos	1,305.00	5,220.00
11.17	Supply & Installation of Addressable Sounder and flasher	4	Nos	1,305.00	5,220.00
11.18	Supply & Installation of IFUs -Building FACP(2), EMP, Music system, Sliding/Access doors(2), 24 x 7	8	Nos	1,580.00	12,640.00
11.19	Supply of Fire Resistance Cables and PVC Conduits	1	Ls	3,434.00	3,434.00
11.2	Isolation charges for Building FACP and Speaker system	1	Item	4,807.00	4,807.00
11.21	Testing, Programming and Installation of Building FACP	1	Item	6,180.00	6,180.00
	EMERGENCY AND EXIT LIGHT WORKS				
11.23	Supply & Installation of Emergency Lights	25	Nos.	756.00	18,900.00
11.24	Supply & Installation of Exit Lights	4	Nos.	756.00	3,024.00
11.25	Supply & Installation of Exit Lights - Directional	6	Nos.	790.00	4,740.00
11.26	Supply of Fire Resistance Cables and PVC Conduits	1	Ls	2,747.00	2,747.00
11.27	Isolation, Deletion & Reprogramming of Existing CBS Emergency System	1	Item	4,120.00	4,120.00
11.28	Supply and installation of Emergency monitoring panel	1	Nos.	8,927.00	8,927.00
11.29	Programming Testing & Commissioning of Monitoring Panel	1	Item	1,374.00	1,374.00
	SUB TOTAL FOR CIVIL DEFENCE WORKS				**245,424.00**
12	**MISCELLENEOUS WORKS**				

Design Infinity *Beyond Imagination ...*

Huspy, 28th Floor Omega Tower Abu Dhabi, United Arab Emirates

DI/AK /25/R1 **Date 27/01/2026**

Item	DESCRIPTION	Qty	Unit	Amount (Dhs.)	TOTAL (Dhs.)
12.01	Supply an installation of manually operated sunscreen roller blinds	490	sqm	131.00	64,190.00
12.01	Supply and installation of signage	1	item	20,000.00	20,000.00
12.01	Supply and installation of natural plants LIVE FICUS LYRATA- , LIVE PACHIRA-	22	Nos	1,648.00	RATE ONLY
	SUB TOTAL FOR MISELLENEOUS WORKS				**84,190.00**
13	**PLUMBING WORKS**				
13.01	Supplyand installation of Kitchen sink and sink mixer	1	Nos	5,494.00	5,494.00
13.02	Supply and installation of the Waste pipe works with necessary fittings and accessories	1	Item	1,374.00	1,374.00
13.03	Supply and installation of floor trap	1	Nos	618.00	618.00
13.04	Supply and installation of Floor cleanout	1	Nos	344.00	344.00
13.05	Sani pump	1	Nos	6,180.00	6,180.00
13.06	Supply and install of Cold Water Supply Pipes & Fittings with necessary accessories	1	Item	756.00	756.00
13.07	Supply and install of Hot Water Supply Pipes & Fittings with necessary accessories	1	Item	893.00	893.00
13.08	Supply and installation of Water Heater (Ariston-80L)	1	Nos	1,305.00	1,305.00
13.09	Supply and install of Pex Pipes For Water Supply	1	Item	412.00	412.00
13.1	Supply and installation of Water hammer arrester	1	Nos	344.00	344.00
13.11	Supply and installation of Isolation Valves	1	item	687.00	687.00
13.12	Connecting with the existing lines	1	item	2,060.00	2,060.00
13.13	Pressure testing for water supply line	1	Item	2,747.00	2,747.00
13.14	Gravity test for drain lines & Commissioning	1	Item	2,060.00	2,060.00
13.15	Water Meter	1	Nos	2,747.00	2,747.00
	Necessary wall coring and related works	1	item	5,000.00	5,000.00

Design Infinity *Beyond Imagination ...*

Huspy, 28th Floor Omega Tower Abu Dhabi, United Arab Emirates					
DI/AK /25/R1					Date 27/01/2026
Item	DESCRIPTION	Qty	Unit	Amount (Dhs.)	TOTAL (Dhs.)
	1. We assumed all the Plumbing and Drainage provisions area availble at site . 3. Any Upgradation of plumbing works will be not part of our scope				
	SUB TOTAL FOR PLUMBING WORKS				**33,021.00**

Design Infinity *Beyond Imagination ...*

Huspy, 28th Floor Omega Tower Abu Dhabi, United Arab Emirates					
DI/AK /25/R1					Date 27/01/2026
Item	DESCRIPTION	Qty	Unit	Amount (Dhs.)	TOTAL (Dhs.)
	SUMMARY				
1	GENERAL REQUIREMENTS/PRELIMINARIES				198,425.00
2	DEMOLITION/ CIVIL WORKS				9,500.00
3	FLOORING WORKS				447,531.00
4	CEILING WORKS				307,645.00
5	WALLS AND WALL FINISHES WORKS				262,766.00
6	DOORS				81,378.00
7	JOINERY WORKS / COSTUM MADE				247,514.00
8	LIGHT FIXTURES				217,932.00
9	ELECTRICAL POWER WORKS.				504,962.00
10	HVAC WORKS				514,105.00
11	CIVIL DEFENCE WORKS				245,424.00
12	MISCELLENEOUS				84,190.00
13	PLUMBING WORKS			33,021.00	RATE ONLY
	SUB TOTAL				**3,121,372.00**

CONTACT PERSON

ANJANA KAMATH
Associate Director Sales

CONTACT DETAILS:

T: 04 379 5902

M: 050 745 5442

E: anjana@design-infinity.com

DUBAI (HEAD OFFICE) ADDRESS:
UNIT 201-203, 212-213 & 301-303
HAMSAH BUILDING, O-BLOCK
PO BOX 62522, AL KARAMA
DUBAI, UNITED ARAB EMIRATES
T: 04 379 5902

DUBAI BRANCH – OFFICE & WAREHOUSE
JOINERY, GLASS & METAL DIVISION
DUBAI INVESTMENT PARK 2
PLOT NUMBER: 597-813
TEL: 971 4 321 6946

ABU DHABI OFFICE
OFFICE NO. M1, P/181 BUILDING
PO BOX 62560, AL MUROOR
ABU DHABI, UNITED ARAB EMIRATES
T: 02 448 2286

WWW.DESIGN-INFINITY.COM