HTI CONTRACTING LLC
PO Box :390737
506 - Binary Tower , Business bay
Dubai , United Arab Emirates
www.hashtaginteriors.com

COMMERCIAL PROPOSAL
FOR
(ARCHITECTURAL WORKS)

LEANTECH SYSTEMS INFORMATION TECHNOLOGY LLC

1ST FLOOR, NASEEMA TOWER
SHEIKH ZAYED ROAD, DUBAI - UAE

To:
Ms. Ivana Popadic
Level 2, GV 8
Dubai fianacial Centre
Dubai -United Arab Emirates

Date:
May 3, 2025
Reference No.:
QTN-031/SR-136R1

HTI CONTRACTING LLC
PO Box :390737
506 - Binary Tower , Business bay
Dubai , United Arab Emirates
www.hashtaginteriors.com

General Terms & Conditions

Payment Terms: 50 % Advance Payment against order confirmation and release of purchase order.
25% 1st progressive payment upon completion of 40% of works.
20% 2nd progressive payment upon completion of 70% of works.
5% upon handover to the client.
Note: Performa invoice to be released within 7 days of issue to the client.

Project Timeline: Documents and Drawings Preparation: 7 Days from the date of order confirmation.
Approval: 2-3 weeks from the receipt of landlord NOC.
Site Works: 7-8 Weeks from the date of receipt of fit-out permit.
Total : 12-13 Weeks from the date of receipt of order confirmation.

Validity: Our quote is valid for a period of 30 days from hereof.

Warranty: As per manufacturer and 365 days DLP from the date of occupancy handing over of the phases.
Note: Damages due to Natural calamities/War etc. are excluded.

Insurance: Project insurance to be obtain as per company policy if required by any party.

We trust that you will find the attached quotation in line with your requirements, and shall look forward to your earliest response.

Yours faithfully
For HTI Contracting LLC

Suraj M Roy
roy@hashtaginteriors.com
054 585 0779

Special Note and Exclusion:

- ***a.*** *Scope is limited to BOQ*
- ***b.*** *Any additional works will be charged as variation.*
- ***c.*** *Feel/Charges to landlod, approval authorities are provisional sum.*
- ***d.*** *Server, IT equipments, PABX, active components, laptop, PC, white goods etc. are excluded.*
- ***e.*** *HVAC, Fire fighting, Fire Alarm works are as per building approved contractor.*
- ***f.*** *BTU meter, BMS, new thermostats etc. are excluded.*
- ***g.*** *Upright sprinklers, void smoke detector, fire pump etc. are excluded.*
- ***h.*** *Any specific requirements arise after project award by any statutory authority/client will be charged as variation.*
- ***i.*** *Variation to be approved prior to start of works and 100% payment to be cleared by the client upon confirmation.*
- ***j.*** *Incase of cancellation of project the client will be charged a fee of 25% of the project value.*
- ***k.*** *Delay in work by any 3rd party appointed by consultant/building management/client. HTI will not be held responsible.*
- ***l.*** *Any delay in payment, finishes approval, from approval authority or due to natural calamities HTI will not be held responsible.*
- ***m.*** *Any white goods, printer, coffee machine etc. are excluded.*
- ***n.*** *All materials & installations should be of approved types in compliance with the government a uthority and Civil Defense , health & safety, mechanical, electrical and ergonomic standards.*
- ***o.*** *24x7 by client*

HASHTAG
INTERIORS & CONTRACTING

HTI CONTRACTING LLC
PO Box :390737
506 - Binary Tower , Business bay
Dubai , United Arab Emirates
www.hashtaginteriors.com

SL NO.	MAIN SUMMARY DESCRIPTION OF WORKS		AMOUNT AED
A.	ARCHITECTURAL WORKS:		
1	PREAMBLE/GENERAL WORKS:	AED	66,250.00
2	DEMOLITION WORKS:	AED	35,500.00
3	GLAZING WORKS:	AED	74,375.00
4	PARTITION WORKS:	AED	42,080.00
5	FINISHING WORKS:	AED	143,980.00
6	FLOORING WORKS:	AED	131,770.00
7	CEILING WORKS:	AED	167,850.00
8	INTERNAL SIGNAGE/BRANDING WORKS:	AED	10,200.00
9	JOINERY / WOOD WORKS:	AED	301,600.00
10	ELECTRICAL AND LIGHTING WORKS:	AED	319,490.00
11	HVAC WORKS:	AED	112,595.00
12	FIRE FIGHTING AND FIRE ALARM WORKS:	AED	154,475.00
13	PLUMBING & SANITARY WORKS:	AED	45,085.00
14	MISCELLANEOUS WORKS:	AED	35,000.00
15	CLOSE-OUT FORMALITIES:	AED	10,000.00
16	LIFT LOBBY WORKS:		RATE ONLY
1	FURNITURE: FURNITURE WORKS:	AED	350,830.00
	TOTAL AMOUNT FOR ARCHITECTURAL WORKS	AED	2,001,080.00
	LESS: DISCOUNT	AED	81,080.00
	NET PROJECT VALUE AFTER DISCOUNT	AED	1,920,000.00
	5% VALUE ADDED TAX	AED	96,000.00

التش تي اي للمقاولات ش.ذ.م.م
DUBAI - U.A.E.
HTI CONTRACTING L.L.C

HASHTAG
INTERIORS & CONTRACTING

HTI CONTRACTING LLC
PO Box :390737
506 - Binary Tower , Business bay
Dubai , United Arab Emirates
www.hashtaginteriors.com

ARCHITECTURAL WORKS:			QTY	UNIT	RATE	AMOUNT
ITEM	DESCRIPTION OF WORKS				AED	AED
1.00	**PREAMBLE/GENERAL WORKS:**					
1.01	Mobilization and site setup- allow sum for contractor's site mobilization		1	Job	5,500.00	5,500.00
1.02	Allow for task lighting which are required during the construction		1	Job	1,000.00	1,000.00
	Note: Electricity connection will be taken from the existing DB at site. we have not considered temporary generator to supply the electricity.					
1.03	Allow sum for covering and protection of entrance area, lobby, corridor, service lifts and finished products to prevent any damages due to the on-going fit-out works as per the building management.		1	Job	4,500.00	4,500.00
1.04	Provision for implementing and providing adequate health and safety measures on site		1	Job	1,750.00	1,750.00
A.	**DOCUMENTS**					
1.05	Preparation of construction/workshop drawings for approval of local authorities (Dubai Municipality, Civil defense department and DEWA) and joinery workshop drawings and as-build drawings.		1	Job	15,000.00	15,000.00
B.	**PROJECT INSURANCES**					
1.06	Insurance policies for the project as per HASHTAG standard. Contractor/ Erection All Risks (CAR) and Third-Party Liability Insurance Cover (TPL) for AED 1,000,000		1	Job	8,000.00	8,000.00
C.	**CLEANING**					
1.07	Allow sum for removal of debris and daily general site cleaning for the entire project duration.		1	Job	7,500.00	7,500.00
D.	**SERVICES**					
1.08	Allow consumption charges for electricity, water, existing washroom facilities and additional connection charges to be paid to DEWA.		1	Job		BY CLIENT
E.	**APPROVAL PROCESS (AUTHORITIES AND BUILDING MANAGEMENT)**					
	AUTHORITY APPROVAL (FOR 1 LEASE)					
1.09	Contractors coordination charges to liaise with local authorities such as Dubai Munciplaity, Civil defense and DEWA to obtain complete approval.		1	Job	8,000.00	8,000.00
1.10	Deposits and fees for local authority approvals to complete the approval process from (Dubai Municipality, Civil defense and DEWA.		1	Provisional Sum	15,000.00	15,000.00
1.11	Allow sum for building management approval - fees for drawing approvals.		1	Job		BY CLIENT
		TOTAL AMOUNT FOR PREAMBLE/GENERAL WORKS				**AED 66,250.00**
2.00	**DEMOLITION WORKS:**					
2.01	As per the site condition to suit provision of the new approved layout. Carting Away debris to the approved municipal dumpsite.		1	Ls	35,500.00	AED 35,500.00
a.	Removal of ceiling.					
b.	Removal of gypsum partitions and GI stud etc.					
c.	Removal of lighting, AC ducting and grills etc					
e.	Removal of Joinery item and existing furniture.					
f.	Removal of glass partition, doors etc					
g.	Removal of existing flooring.					
h.	Transport charges, DM fees etc.					
		TOTAL AMOUNT FOR FINISHING WORKS				**AED 35,500.00**

HTI CONTRACTING LLC
PO Box :390737
506 - Binary Tower , Business bay
Dubai , United Arab Emirates
www.hashtaginteriors.com

ARCHITECTURAL WORKS:			QTY	UNIT	RATE	AMOUNT	
ITEM	DESCRIPTION OF WORKS				AED	AED	
3.00	**GLAZING WORKS:**						
3.01	Supply and installation of **12 mm thick** clear tempered glass partitions from floor to 2900 mm height. Glass partitions to be fixed on to 3cm BLACK aluminium channels at the top and bottom and glass to glass joint with clear silicon. **Glass Partition Height : 2900** **Location : As per design.**		65	Sqm	355.00	AED	23,075.00
3.02	**Swing Glass Door** Supply and installation of **12 mm thick** non fire rated single tempered clear swing glass framed door, size 900 x 2900 mm with black powder coated frame all around., complete with handle and lockset in SS finish accessories. Type: Single Leaf **Location :** Closed Cabins		8	Nos.	3,450.00	AED	27,600.00
3.03	**Framed Glass Door - D2** Supply and installation of **12 mm thick** non fire rated framed double leaf tempered clear glass AUTOMATIC GLASS SLIDING door with GEZE mechanism, size 1600 x 2100 mm, complete with handle and lockset in black powder coated finish accessories. Type: Double Leaf **Location : Main Entrance**		1	Nos.	23,700.00	AED	23,700.00
					TOTAL AMOUNT FOR GLAZING WORKS	**AED**	**74,375.00**
4.00	**PARTITION WORKS:**						
4.01	**Gypsum Partitions.** Supply and installation of drywall partitions 100mm thick on comprising of 70 mm steel studs and 72mm track, 30Kg/m3 density of rockwool insulation covered by 12.5mm regular gypsum board on both sides with frame works of standard sections at a distance of 600mm c/c maximum and with necessary horizontal members at the required heights up to slab sofit height with Jointing, taping and sanding. **Make : Gypsum Boards / Joint Compound / Corner Tape / Fiber Tape : USG or equivalent**	 	229	Sqm	110.00	AED	25,190.00
4.02	**Baffle Wall Partitions:.** Supply and installation of baffle drywall partitions 100mm thick on comprising of 70 mm steel studs and 72mm track, 30Kg/m3 density of rockwool insulation covered by 12.5mm regular gypsum board on both sides with frame works of standard sections at a distance of 600mm c/c maximum and with necessary horizontal members at the required heights up to slab height with Jointing, taping and sanding to receive the final finishes. **Make : Gypsum Boards / Joint Compound / Corner Tape / Fiber Tape : Boral or equivalent**	 	27	LM	110.00	AED	2,970.00
4.03	Supply and installation of 50 mm thick wall cladding regular gypsum board cladding on blockwall for smooth finish. **Location: Columns** **Make : Knauf**		174	Sqm	80.00	AED	13,920.00
					TOTAL AMOUNT FOR PARTITION WORKS	**AED**	**42,080.00**

ARCHITECTURAL WORKS:			QTY	UNIT	RATE	AMOUNT	
ITEM	DESCRIPTION OF WORKS				AED	AED	
5.00	**FINISHING WORKS:**						
5.01	Supply and Application of Paint on Partitions etc. as per site requirements. The rate shall be inclusive of Preparing the surface to receive the paint + stucco + 2 Coats of primer + 2 Coats of Painting. **Brand : Jotun or Berger**		694	Sqm	30.00	AED	20,820.00
5.02	Supply and Application of Texture Paint on walls as per site requirements. **Brand : Jotun or Berger**		155	Sqm	120.00	AED	18,600.00
5.03	**Wooden Wall Cladding:** Supply and installation of plain wooden cladding in Pu paint finish as per proposed design scheme. **Location: Reception** **Manufacture : Joinery Item**		12	Sqm	750.00	AED	9,000.00
5.04	Supply and installation of decorative Bevelled Subway Tile, 10x20 cm wall tile cladding with necessary glue and grout. **Location: Pantry**		4	Sqm	280.00	AED	1,120.00
5.05	Supply and installation of roller blinds from the external window per proposed design scheme.		324	Sqm	105.00	AED	34,020.00
5.06	Supply and installation of graphics as per proposed design scheme. **Location: Conference Room**		11	Sqm	145.00	AED	1,595.00
5.07	**Acoustic Panel Cladding:** Supply and installation of acoustic fabric panel with grooves cladding on the wall as per the proposed design. **Location: Conference Room 12 Pax, Meeting Room 6 & 8 pax.** Manufacture : Joinery Item		35	Sqm	710.00	AED	24,850.00
5.08	**Backpainted Glass Cladding:** Supply and installation of back-painted glass cladding upto 1600 mm high as per proposed design scheme. **Location: Reception, Meeting rooms, Conference room & Open workstation** **Manufacture : Joinery Item**		45	Sqm	755.00	AED	33,975.00
					TOTAL AMOUNT FOR FINISHING WORKS	**AED**	**143,980.00**
6.00	**FLOORING WORKS:**						
6.01	Allow for opening and closing for existing raised floor to facilitate the installation of MEP servicies and cabling works.		1	Ls	20,000.00	AED	20,000.00
6.02	Supply and application of 2 to 3mm thick waterproofing on the floor and walls upto 1 meter height. **Location: Pantry & Toilets**		1	Ls	3,000.00	AED	3,000.00
6.03	Supply and installation of 600x600 mm Porcelain tile flooring with cement board backing, necessary glue and grout. **Location: Toilets**		53	Sqm	180.00	AED	9,540.00

HTI CONTRACTING LLC
PO Box :390737
506 - Binary Tower , Business bay
Dubai , United Arab Emirates
www.hashtaginteriors.com

ARCHITECTURAL WORKS:			QTY	UNIT	RATE	AMOUNT	
ITEM	DESCRIPTION OF WORKS				AED	AED	
6.04	Supply and installation of 1200x600 mm Porcelain tile flooring with cement board backing, necessary glue and grout. **Location: Wet Pantry & Dining Area**		56	Sqm	190.00	AED	10,640.00
6.05	Supply and installation of carpet tile flooring as per proposed design scheme with 5 years commercial warranty. **Location : All Office** Sample and Specification Sheet to be Submitted for approvals.		514	Sqm	135.00	AED	69,390.00
6.06	**SPC Flooring -** Supply and installation of high grade 118x22 size premium quality wooden texture design SPC plank flooring with underlay as per proposed design scheme. **Location: Reception & Auditorium Area** Sample and Specification Sheet to be Submitted for approvals.		99	Sqm	140.00	AED	13,860.00
6.07	Supply and installation of metal termination strip between the different flooring.		28	Lm	110.00	AED	3,080.00
6.08	Supply and installation of marble threshold. Size: 1600L mm Location: Main entrance		1	No	550.00	AED	550.00
6.09	Supply and installation of marble threshold. Size: 900L mm Location: Toilets		6	No.s	285.00	AED	1,710.00
					TOTAL AMOUNT FOR FLOORING WORKS	**AED**	**131,770.00**
7.00	**CEILING WORKS:**						
7.01	Supply and installation of plain gypsum board ceiling with necessary support and GI channel as per the design ready to receive finish. **Location : As Per Proposed Design.** Make : Gypsum Boards Boral or equivalent		489	Sqm	105.00	AED	51,345.00
7.02	**Ceiling Painting.** Supply and Application of Paint : RAL : 9010, on Ceiling. **Brand : Jotun or Berger**		489	Sqm	30.00	AED	14,670.00
7.03	Supply and installation of upto 150 mm wide gypsum perimeter bulkhead around the external window for the provision of blinds.		116	Lm	80.00	AED	9,280.00
7.04	**Ceiling Painting.** Supply and Application of Paint : RAL : 9010, on Bulkheads. **Brand : Jotun or Berger**		116	Lm	20.00	AED	2,320.00
7.05	Supply and installation of upto 100 mm high cove bulkhead.		158	Lm	80.00	AED	12,640.00
7.06	**Ceiling Painting.** Supply and Application of Paint : RAL : 9010, on cove. **Brand : Jotun or Berger**		158	Lm	20.00	AED	3,160.00
7.07	**Open Ceiling Painting.** Supply and Application of Paint on open ceiling Ceilings including all MEP services. **Location : Open Staff / Pantry Area** **Brand : Jotun or Berger**		175	Sqm	45.00	AED	7,875.00

ARCHITECTURAL WORKS:			QTY	UNIT	RATE	AMOUNT	
ITEM	DESCRIPTION OF WORKS				AED	AED	
7.08	Supply and installation of 60x60 square ceiling tiles with 25 mm suspension metal suspension/grid fixed with hangers. **Location: Toilets, Store Room 1 & 2**		75	Sqm	85.00	AED	6,375.00
7.09	Supply and installation of 600x600 ceiling access panel.		31	Nos.	210.00	AED	6,510.00
7.10	**Acoustic Fabric Ceiling:** Supply and installation of acoustic fabric panel ceiling as per the proposed design. **Location : Open Workstation** **Manufacture : Joinery Item**		113	Sqm	475.00	AED	53,675.00
					TOTAL AMOUNT FOR CEILING WORKS	**AED**	**167,850.00**
8.00	**INTERNAL SIGNAGE/BRANDING WORKS:**						
8.01	Supply and installation of **COMPANY LOGO** in acrylic/MDF finish without backlit. Size: 1200L x 600H mm **Location : Reception** **Brands : Customized Locally** EPS file to be provided by client.		1	Nos.	6,200.00	AED	6,200.00
8.02	Supply and installation of only grey color frosting as per client's guidelines upto 1500 mm coverage. **Location : Glass partitions** **Brands : Customized Locally** EPS file to be provided by client.		40	Sqm	100.00	AED	4,000.00
					TOTAL AMOUNT FOR SIGANGE/BRANDING WORKS	**AED**	**10,200.00**
9.00	**JOINERY / WOOD WORKS:**						
9.01	**Skirting:** Supply and installation 50 mm high PU painted MDF skirting around the wall as per design.		421	LM	45.00	AED	18,945.00
9.02	**Reception Counter:** Supply and installation of locally customized reception counter made with MDF in Pu painted finish as per proposed design theme. Size: 2100 x 800 x 1100 mm **Location: Reception Counter** **Manufacture : Joinery Item**		1	Item	23,800.00	AED	23,800.00
9.03	**Pantry Unit:** **Low height unit:** Supply and installation of locally customized pantry counter fabricated with MR mdf inside laminate outside Pu paint finish underneath storage with shutter, shelves & quartz top. **Overhead unit:** Supply and installation of overhead cabinet made with MR mdf inside laminated outside Pu paint finish doors with shutters & shelves. Low height unit Size: 3500L x 600D x 900H mm Overhead unit Size: 3500L x 400D x 1200H mm **Location: Pantry** **Manufacture : Joinery Item**		1	Item	22,440.00	AED	22,440.00
9.04	**High Table:** Supply and installation of high table made with mdf in veneer finish with powdercoated metal legs as per the proposed design. Size: 3100L x 500D x 1100H mm Manufacture : Joinery Item **Location : Pantry** **Manufacture : Joinery Item**		1	Item	9,555.00	AED	9,555.00

HTI CONTRACTING LLC
PO Box :390737
506 - Binary Tower , Business bay
Dubai , United Arab Emirates
www.hashtaginteriors.com

ARCHITECTURAL WORKS:			QTY	UNIT	RATE	AMOUNT	
ITEM	DESCRIPTION OF WORKS				AED	AED	
9.05	**Wooden Upstand:** Supply and installation of plain wooden 2- level upstand in veneer finish per the proposed design. Size: 3200L x 900D x 300H mm **Location : Pantry/Terrace Entrance** **Manufacture : Joinery Item**		1	Item	11,430.00	AED	11,430.00
9.06	**High Table + Ledge:** Supply and installation of Ledge seating with fabric cushion seating & high table in veneer finish with wooden legs as per the proposed design. High Table Size: 3000L x 500D x 1100H mm Ledge Seating Size: 2000Lx 500D x 450 H mm Location: Pantry Manufacture : Joinery Item **Location : Pantry** **Manufacture : Joinery Item**		1	Item	13,420.00	AED	13,420.00
9.07	Supply and installation of locally customized full height Tv cabinet fabricated in mdf pu paint finish with open shelves as per proposed design theme. Size: 2500L x 400D x 2900H mm **Location: Pantry** **Manufacture : Joinery Item**		1	Item	16,315.00	AED	16,315.00
9.08	**Hot Desk:** Supply and installation of locally customized high table top made with MDF in veneer finish & wooden legs in paint finish with above planter box as per the design. Size: 2200L x 1200D x (1100+150)H mm **Location: Pantry** **Manufacture : Joinery Item**		1	Set	14,100.00	AED	14,100.00
9.09	Supply and installation of locally customized full height storage cabinet fabricated in mdf pu paint/veneer finish with open shelves as per proposed design theme. Size: 4900L x 400D x 2900H mm **Location: Auditorium Area** **Manufacture : Joinery Item**		1	Item	28,100.00	AED	28,100.00
9.10	Supply and installation of stepped seating made of mdf melamine in veneer finish, seating with upholsteries cushion seats as per the proposed design. Size: 10100L x 1200D x 850H mm **Location: Auditorium Area** **Manufacture : Joinery Item**		1	Item	53,865.00	AED	53,865.00
9.11	**High Table:** Supply and installation of high table made with mdf in veneer finish withpowdercoated metal legs as per the proposed design. Size: 3000L x 500D x 1100H mm Manufacture : Joinery Item **Location : Auditorium Area** **Manufacture : Joinery Item**		1	Item	9,555.00	AED	9,555.00

HTI CONTRACTING LLC
PO Box :390737
506 - Binary Tower , Business bay
Dubai , United Arab Emirates
www.hashtaginteriors.com

ARCHITECTURAL WORKS:			QTY	UNIT	RATE	AMOUNT	
ITEM	DESCRIPTION OF WORKS				AED	AED	
9.12	Supply and installation of locally customized full height storage cabinet fabricated in mdf veneer finish with open shelves as per proposed design theme. Size: 2500L x 300D x 2900H mm **Location: Hot Desk Cabin** **Manufacture : Joinery Item**		1	Item	14,500.00	AED	14,500.00
9.13	Supply and installation of locally customized full height storage cabinet fabricated in mdf Pu paint finish with open shelves & shutter as per proposed design theme. Size: 1800L x 500D x 2900H mm **Location: Conference Room** **Manufacture : Joinery Item**		1	Item	12,615.00	AED	12,615.00
9.14	Supply and installation of locally customized planter box fabricated in CEMENT BOARD finish as per proposed design theme. size 500L x 600D x 900H mm **Location: Meeting Room (4 Pax)** **Manufacture : Joinery Item**		2	Nos.	1,225.00	AED	2,450.00
9.15	Supply and installation of locally customized planter box fabricated in CEMENT BOARD finish as per proposed design theme. size 730L x 400D x 900H mm **Location: Workstation Area columns** **Manufacture : Joinery Item**		5	Nos.	1,225.00	AED	6,125.00
9.16	**Printer Overhead Cabinet:** Supply and installation of overhead cabinet fabricated in mdf inside laminate & outside veneer finish with shelves & shutters as per the proposed design. Size: 2400L x 600D x 900H mm **Location: Open Workstation** **Manufacture : Joinery Item**		1	Nos.	5,800.00	AED	5,800.00
9.17	**Ledge Seating:** Supply & installation of ledge seating made with cushion backing in fabric finish with backrest as per the design. Size: 3400L x 500D x 850 H mm **Location: Column Collaboration Area** **Manufacture : Joinery Item**		1	Item	16,070.00	AED	16,070.00
9.18	**Wall Mounted Shelves:** Supply and installation of wall mounted wooden shelves made in veneer finish as per proposed design scheme. Size: 4600L x 400D x 50H mm **Location: Engineer's Area Workstation** **Manufacture : Joinery Item**		3	No.s	2,685.00	AED	8,055.00
9.19	**Decorative Unit:** Supply and installation of full height cabinet made with mdf in pu paint finish with metal frame as per the proposed design. Size: 1600L x 200D x 2900H mm **Location: Open Workstation @ Male Toilets** Manufacture : Joinery Item		1	Nos.	14,460.00	AED	14,460.00
					TOTAL AMOUNT FOR JOINERY WORKS	**AED**	**301,600.00**

HTI CONTRACTING LLC
PO Box :390737
506 - Binary Tower , Business bay
Dubai , United Arab Emirates
www.hashtaginteriors.com

ARCHITECTURAL WORKS:			QTY	UNIT	RATE	AMOUNT	
ITEM	DESCRIPTION OF WORKS				AED	AED	
10.00	**ELECTRICAL AND LIGHTING WORKS:**						
10.01	Modification of the existing electrical supply with new MCCB and circuit brakers in DBs to suit the ratings and new load schedule.		3	No	3,500.00	AED	10,500.00
10.02	Modification of the existing SMDBs to suit the ratings and new load schedule.		1	No	5,500.00	AED	5,500.00
10.03	Supply and installation of conduiting & wiring for the light points		276	No's	185.00	AED	51,060.00
10.04	Supply and installation of conduiting & wiring for the cove lights		150	Lm	70.00	AED	10,500.00
10.05	Supply & fixing of 1 Gang 1 way white PVC switch (Make: Schneider or equivalent)		17	No's	135.00	AED	2,295.00
10.06	Supply & fixing of 2 Gang 1 way white PVC switch (Make: Schneider or equivalent)		12	No's	150.00	AED	1,800.00
10.07	Supply & fixing of 3 Gang 1 way White PVC switch (Make: MK & Schneider)		6	No's	180.00	AED	1,080.00
10.08	Relocation of existing floor service boxes.		1	Item	6,000.00	AED	6,000.00
10.09	Supply and installation of Electrical Floor box 300x300 mm Make: Conduit- Decoduct PVC, Floor Box: MK (Normal Type)		54	No's	410.00	AED	22,140.00
10.10	Supply and installation of 13 Amp Double power socket with necessary conduiting, wiring as per the design(Conduit: PVC, Wire: Ducab, Switch & Socket: MK White Logic) .		112	No's	280.00	AED	31,360.00
10.11	Supply and installation of 13 Amp single power socket with necessary conduiting, wiring as per the design(Conduit: PVC, Wire: Ducab, Switch & Socket: MK White Logic) .		29	No's	265.00	AED	7,685.00
10.12	Supply and installation of 13A Spur Outlet for extract fan, 24x7 and Access control points with necessary conduiting, wiring as per the design.		3	Nos.	345.00	AED	1,035.00
10.13	Supply and installation of 20 Amp DP switch for FACP with necessary conduiting, wiring as per the design.		1	Nos.	670.00	AED	670.00
10.14	Supply and installation of 16A Industrial Socket for the Server Rack including conduiting and wiring.		1	Nos.	725.00	AED	725.00
10.15	Supply and installation of isolator with necessary conduiting, wiring as per the design.		2	Nos.	550.00	AED	1,100.00
10.16	Testing and commissioning of Electrical system.		1	Ls	3,000.00	AED	3,000.00
10.17	Allow sum for associated civil works (Floor and wall cutting and chipping for related pvc piping for Electrical works)		1	Ls	10,000.00	AED	10,000.00
	Note: 1) We consider that there is enough available load at site to suit the proposed design, if additional load is required it will require an NOC from the landlord and DEWA. It would also incur an additional cost. 2) Existing electrical DEWA approved load schedule to be provided by client.						

HTI CONTRACTING LLC
PO Box :390737
506 - Binary Tower , Business bay
Dubai , United Arab Emirates
www.hashtaginteriors.com

ARCHITECTURAL WORKS:			QTY	UNIT	RATE	AMOUNT	
ITEM	DESCRIPTION OF WORKS				AED	AED	
	LIGHTING:						
10.18	Supply and Installation of 60x60 LED panel light Material : Aluminum | Finish : White Light Source : Samsung Wattage : 40W CRI : 85 | CCT : To be confirmed Power Supply : Constant Current LED Driver Dimmable : No | Protection : IP44 Size : W 595mm X L 595mm X H 8mm **Location: Toilets & Store Rooms**		24	Nos.	250.00	AED	6,000.00
10.19	Supply and installation full length 1600 mm linear light with fixture Model Chip Cree USA, COB CCT 5500°K Driver On/off Driver Finish Black/silver/white IP20 **Location: Workstation Area**		20	Nos.	410.00	AED	8,200.00
10.20	Supply and installation full length 2000 mm linear light with fixture Model Chip Cree USA, COB CCT 5500°K Driver On/off Driver Finish Black/silver/white IP20 **Location: Workstation Area**		12	Nos.	540.00	AED	6,480.00
10.20	Supply & fixing of light LED Directional Spotlight Material : Die Cast Aluminium Finish : White Reflector : Anodized Aluminium Diffuser : Clear Glass Light Source : Cree Power consumption : 10WCCT : To be confirmed CRI : 90+ | Beam Angle : 45°Power Supply : Constant Current LED DriverDimmable : No | Size : D104 x H94 x C92 mm Protection : IP40 **Location: All Area**		128	Nos.	255.00	AED	32,640.00
10.21	Supply and installation of decorative pendant light. **Location: 4pax meeting room**		4	Nos.	4,025.00	AED	16,100.00
10.22	Supply and installation of decorative pendant circular light 600 dia **Location: 8 pax meeting room**		2	Nos.	1,070.00	AED	2,140.00
10.23	**Custom Light:** Supply and installation of locally customized MDF wooden frame light box in veneer finish with acrylic diffuser as per proposed design theme. Size: 50W x 100H mm **Location: Reception** **Manufacture : Joinery Item**		15	Lm	650.00	AED	9,750.00
10.24	Supply and installation custom made linear light with fixture. Model Chip Cree USA, COB CCT 5500°K Driver On/off Driver Finish Black/silver/white IP20 **Location: Auditorium, Conference & 8 pax Meeting Room**		22	Lm	445.00	AED	9,790.00

ARCHITECTURAL WORKS:			QTY	UNIT	RATE	AMOUNT	
ITEM	DESCRIPTION OF WORKS				AED	AED	
10.25	Supply and installation of decorative pendant light. **Location: Pantry Hot Desk**		2	Nos.	650.00	AED	1,300.00
10.26	Supply and installation of track Recessed Magnetic Track LIGHTING ACCESSORIES Dimension Of W72.3xH46.9x1000mm Made With Material Die-Cast Aluminum In Black Finish **Location: Workstation**		17	Lm	95.00	AED	1,615.00
10.27	Supply and installation of track linear light Size: 600L x22Wx43H mm mm with Magnetic Driver. **Location: Workstation**		8	Nos.	235.00	AED	1,880.00
10.28	Supply and installation of 2cm acrylic linear diffuser led light.		150	Lm	75.00	AED	11,250.00
10.29	Supply and installation of LIGHTING SENSOR as per lighting layout.		26	Nos.	1,025.00	AED	26,650.00
	IT STRUCTURE:						
10.30	Supply and installation of 20 mm PVC conduit for network cable.		223	Nos.	75.00	AED	16,725.00
10.31	Supply and installation of 50 mm PVC conduit for HDMI cable.		9	Nos.	280.00	AED	2,520.00
	TOTAL AMOUNT FOR ELECTRICAL AND LIGHTING WORKS					**AED**	**319,490.00**
11.00	**HVAC WORKS:**						
11.01	Modification of existing ductwork to suite new layout - for existing 9 nos FCU		1	Ls	92,600.00	AED	92,600.00
11.02	Supply and install GI Ring, VCD with flexible ductwork						
11.03	Supply and install Linear slot grills, round diffusers and support						
11.04	Air balancing and report by in house						
11.05	Supply and install NEW FCU machine with capacity of 35 tonnage inclduing installation, chemical flushing etc.		7	Nos.	16,580.00		RATE ONLY
11.06	Supply and install 500 CFM ventilation fan for the pantry. Ductwork connected to nearest main vent duct		1	Item	2,395.00	AED	2,395.00
11.07	**If Required:** Supply and install By pass VAV for closed cabins		6	Nos.	3,265.00		RATE ONLY
	Dedicated Server room Split AC						
11.08	Supply and install 2TR Decorative Split indoor and outdoor unit with welded Stand . Make- Carrier		2	Nos.	17,600.00	AED	17,600.00
11.09	Refrigerant piping from indoor to outdoor, Control wiring, Insulation, Apply canvas cloth and foster		1	Item			
11.10	leak test, Vaccum, Gas chaging, Testing and commissioning		1	Item			
11.11	Drainage piping works and pipe connected to nearest drain point.		1	Item			

HTI CONTRACTING LLC
PO Box :390737
506 - Binary Tower , Business bay
Dubai , United Arab Emirates
www.hashtaginteriors.com

ARCHITECTURAL WORKS:			QTY	UNIT	RATE	AMOUNT	
ITEM	DESCRIPTION OF WORKS				AED	AED	
	Note: 1) Relocation of existing FCU are excluded. 2) Replacing of existing Valve packages and Piping works are excluded. 3) Chiller pipe modification and additional piping are excluded. 4) Chiller line Chemical flushing works and report are excluded. 5) BMS Control modification and 3rd Party report and programming are excluded. 6) Supply and install VAV are excluded.						
	TOTAL AMOUNT FOR PLUMBING & SANITARY WORKS					**AED**	**112,595.00**
12.00	**FIRE FIGHTING AND FIRE ALARM WORKS:**						
12.01	Supply and Installation of Fire Alarm Control Panel		1	Nos.	15,000.00	AED	15,000.00
12.02	Relocation, Supply and Installation of Smoke Detector with base		29	Nos.	1,545.00	AED	44,805.00
12.03	Supply and Installation of Heat Detector with Base		1	Nos.	1,545.00	AED	1,545.00
12.04	Supply and Installation of Manual Call Point with Back Box		2	Nos.	1,515.00	AED	3,030.00
12.05	Supply and Installation of Sounder with Back Box		2	Nos.	1,610.00	AED	3,220.00
12.06	Supply and Instalation of Interfacing Control Output Modules for Building and 24×7 Output		2	Nos.	1,650.00	AED	3,300.00
12.07	Supply and Installation of Interface Monitor Input Modules for Building Interface (Fire and Fault)		1	Nos.	2,070.00	AED	2,070.00
12.08	Supply and Installation of Self Contained Emergency Light with 3 Hours Battery Backup		15	Nos.	910.00	AED	13,650.00
12.09	Supply and Installation of Self Contained Exit Light with 3 Hours Battery Backup		6	Nos.	870.00	AED	5,220.00
12.10	Supply and Installation of Pendent Sprinkler with Cup using 1" GI pipies , fittings and accessories		8	Nos.	745.00	AED	5,960.00
12.11	Relocation of Existing Pendent Sprinkler with GI pipies , fittings and accessories.		45	Nos.	550.00	AED	24,750.00
12.12	Supply and Installation of 5kg CO2 Fire Extinguisher		3	Nos.	280.00	AED	840.00
12.13	Supply and Installation of DCP - 4KG Fire Extinguisher		3	Nos.	125.00	AED	375.00
12.14	Relocation of Existing Ceiling Speaker		4	Nos.	420.00	AED	1,680.00
12.15	Cancellation of Existing Fire Alarm Devices		20	Nos.	420.00	AED	8,400.00
12.16	Programming for Unit Fire Alarm Control Panel and Devices		1	Nos.	6,670.00	AED	6,670.00
12.17	Programming for Building Main Control Panel with Unit Panel Interface		1	Nos.	6,500.00	AED	6,500.00
12.18	Testing and Commissioning for Fire Alarm, Emergency and Exit Light System		1	Nos.	1,465.00	AED	1,465.00
12.19	Pressure Testing of Sprinkler Line		1	Nos.	4,530.00	AED	4,530.00
12.20	DCD Certificates-Supply, Warranty and Installation		1	Nos.	1,465.00	AED	1,465.00
	TOTAL AMOUNT FOR FIRE FIGHTING AND FIRE ALARM WORKS					**AED**	**154,475.00**
13.00	**PLUMBING & SANITARY WORKS:**						
13.01	Charges for Supply and Installation of water supply & drainage Lines Connections using UPVC Pipe Lines, tapping nearest stub point for the pantry.		1	Ls	7,200.00	AED	7,200.00
13.02	Supply and installation of water heater		5	Nos.	1,200.00	AED	6,000.00
	SANITARY ITEMS:						
13.03	Supply and installation of calcium silicate box to conceal the flush tank and granite ledge. Size: L 1000mm x W 250 x H 1100mm		5	Nos.	2,650.00	AED	13,250.00
13.04	Supply and installation of tile cladding to the cistern box with new tile matching to the existing tile.		1	Ls	4,500.00	AED	4,500.00
13.05	Supply and installation of Wall hung WC with seat, Flush plate with concealed cistern		5	Nos.	2,285.00	AED	11,425.00

HTI CONTRACTING LLC
PO Box :390737
506 - Binary Tower , Business bay
Dubai , United Arab Emirates
www.hashtaginteriors.com

ARCHITECTURAL WORKS:			QTY	UNIT	RATE	AMOUNT	
ITEM	DESCRIPTION OF WORKS				AED	AED	
13.06	Supply and installation of ss sink with bottle trap.		1	Nos.	1,860.00	AED	1,860.00
13.07	Supply and installation of ss sink mixer with angle valve and hose pipes.		1	Nos.	670.00	AED	670.00
13.08	Supply and installation of floor drain.		1	Nos.	180.00	AED	180.00
	TOTAL AMOUNT FOR PLUMBING & SANITARY WORKS					**AED**	**45,085.00**
14.00	**MISCELLANEOUS WORKS:**						
14.01	Allow sum for the supply and installation of artificial plants		1	Ls	35,000.00	AED	35,000.00
	TOTAL AMOUNT FOR MISCELLANEOUS WORKS					**AED**	**35,000.00**
15.00	**CLOSE-OUT FORMALITIES:**						
15.01	Charges for the close-out formalities.		1	Job	10,000.00	AED	10,000.00
	TOTAL AMOUNT FOR CLOSE-OUT FORMALITIES					**AED**	**10,000.00**
16.00	**LIFT LOBBY WORKS:**						
16.01	**SPC Flooring -** Supply and installation of high grade 118x22 size premium quality herringbone wooden texture design SPC plank flooring with underlay as per proposed design scheme. **Location: Lift Lobby Area** Sample and Specification Sheet to be Submitted for approvals.		33	Sqm	190.00		**RATE ONLY**
16.02	**Wooden Wall Cladding:** Supply and installation of plain wooden cladding in veneer finish with grroves as per proposed design scheme. **Location: Lift Lobby Area** Manufacture : Joinery Item		50	Sqm	1,025.00		**RATE ONLY**
	TOTAL AMOUNT FOR LIFT LOBBY WORKS						**RATE ONLY**
	TOTAL AMOUNT FOR ARCHITECTURAL WORKS					**AED**	**1,650,250.00**

HTI CONTRACTING LLC
PO Box :390737
506 - Binary Tower , Business bay
Dubai , United Arab Emirates
www.hashtaginteriors.com

COMMERCIAL PROPOSAL - R1
FOR
(FURNITURE)

LEANTECH SYSTEMS INFORMATION TECHNOLOGY LLC

1ST FLOOR, NASEEMA TOWER
SHEIKH ZAYED ROAD, DUBAI - UAE

To:
Ms. Ivana Popadic
Level 2, GV 8
Dubai fianacial Centre
Dubai -United Arab Emirates

Date:
May 3, 2025
Reference No.:
QTN-032/SU-0425-R1

HTI CONTRACTING LLC
PO Box :390737
506 - Binary Tower , Business bay
Dubai , United Arab Emirates
www.hashtaginteriors.com

General Terms & Conditions

Payment Terms: 50% Advance Payment against order confirmation and release of purchase order.
25% 1st progressive payment upon completion of 40% of works.
20% 2nd progressive payment upon completion of 70% of works.
5% upon completion and handover to client.
Performa invoice must be approved by client within 7 days from submission.

Project Timeline: Production: 5-6 weeks from the date of order confirmation, Advance payment & finishes approval.
Shipping & installation: 6 Weeks
Total : 11-12 Weeks from the date of receipt of order confirmation.

Validity: Our quote is valid for a period of 30 days from hereof.

Warranty: As per manufacturer warranty period of 3 years structure applies against faulty workmanship
Note: Warranty excludes normal wear and tear

Insurance: Project insurance to be obtain as per company policy if required by any party.

We trust that you will find the attached quotation in line with your requirements, and shall look forward to your earliest response.

Yours faithfully
For HTI Contracting LLC

Suraj M Roy
roy@hashtaginteriors.com

Special Note and Exclusion:

- ***a.*** *Scope is limited to BOQ*
- ***b.*** *Any additional works will be charged as variation.*
- ***c.*** *Feel/Charges to approval authorities/mall management to be paid by client on actuals,*
- ***d.*** *Any specific requirements arise after project award by any statutory authority/client will be charged as variation.*
- ***e.*** *Variation to be approved prior to start of works and 100% payment to be cleared by the client upon confirmation.*
- ***f.*** *Incase of cancellation of project the client will be charged a fee of 25% of the project value.*
- ***g.*** *Delay in work by any 3rd party appointed by consultant/building management/client. HTI will not be held responsible.*
- ***h.*** *Any delay in payment, finishes approval, from approval authority or due to natural calamities HTI will not be held responsible.*

HTI CONTRACTING LLC
PO Box :390737
506 - Binary Tower , Business bay
Dubai , United Arab Emirates
www.hashtaginteriors.com

FURNITURE WORKS:			QTY	UNIT	RATE	AMOUNT	
ITEM	DESCRIPTION OF WORKS				AED	AED	
1.00	**CLOSED MEETING AND OFFICE:**						
1.01	**Rectangular Office / Meeting Table** Size/mm: 1600W*900D*750H House special curved 60*30mm metal leg profile with powder coat; 25mm laminated desktop with scallop cut/Power access cutout.		1	Nos.	1,890.00	AED	1,890.00
2.00	**STAFF WORKSTATIONS:**						
2.01	**HEIGHT ADJUSTABLE WORKSTATION IN ENGINEERING AREA:** InterAction B2B sit standing workstation Size/mm: 1200W*1200D*640-1290H Top: 25mm thickness laminated with scallop cut Frame:metal with powder coat; Leg Orientation:Square/Rectangle column; Height Range:640~1290mm; Speed:40mm/s; Max Loading: 150kg; With Timotion Dual motor; SAA/UL/CE approved;with cable duct	 	13	Set	4,925.00	AED	64,025.00
2.02	InterAction Profile screen Size/mm: 1200W*32D*600H 32mm thick Alu alloy frame fabric upholstery screen with bracket;		13	Nos.	455.00	AED	5,915.00
2.03	Flip cover to cable magement accessable from table top white/light grey finish.		26	Nos.	75.00	AED	1,950.00
2.04	PVC vertical cable management for clean cable treatment below the tables for staff, manager cabins, meeting rooms.		26	Nos.	135.00	AED	3,510.00
2.05	**CLUSTER OF 3 PAX WORKSTATION ISLAND INLINE** Size/mm: W3600*D600*H750 (table top size 1200*600 with metal leg with powder coat; 25mm thick laminated desktop size 1200*600 with scallop cut/Power access cutout; Height adjust feet; with aluminum screen slot.		2	Nos.	2,820.00	AED	5,640.00
2.06	**CLUSTER OF 6 PAX WORKSTATION ISLAND FACE TO FACE** Size/mm: W3600*D1200*H750 (table top size 1200*600 with metal leg with powder coat; 25mm thick laminated desktop size 1200*600 with scallop cut/Power access cutout; Height adjust feet; with aluminum screen slot.		5	Nos.	4,213.00	AED	21,065.00
2.07	**CLUSTER OF 2 PAX WORKSTATION ISLAND INLINE** Size/mm: W2400*D600*H750 (table top size 1200*600 with metal leg with powder coat; 25mm thick laminated desktop size 1200*600 with scallop cut/Power access cutout; Height adjust feet; with aluminum screen slot.		3	Nos.	1,955.00	AED	5,865.00

HTI CONTRACTING LLC
PO Box :390737
506 - Binary Tower , Business bay
Dubai , United Arab Emirates
www.hashtaginteriors.com

FURNITURE WORKS:			QTY	UNIT	RATE	AMOUNT
ITEM	DESCRIPTION OF WORKS				AED	AED
2.08	**CLUSTER OF 4 PAX WORKSTATION ISLAND FACE TO FACE** Size/mm: W2400*D600*H750 (table top size 1200*600 with metal leg with powder coat; 25mm thick laminated desktop size 1200*600 with scallop cut/Power access cutout; Height adjust feet; with aluminum screen slot.		4	Nos.	2,890.00	AED 11,560.00
	HEIGHT ADJUSTABLE WORKSTATION FACE TO FACE SET OF 2 InterAction B2B sit standing workstation Size/mm: 1200W*1200D*640-1290H Top: 25mm thickness laminated with scallop cut Frame:metal with powder coat; Leg Orientation:Square/Rectangle column; Height Range:640~1290mm; Speed:40mm/s; Max Loading: 150kg; With Timotion Dual motor; SAA/UL/CE approved;with cable duct	 	21	Set	4,925.00	RATE ONLY
	HEIGHT ADJUSTABLE WORKSTATION INLINE OF 2 AND 3: InterAction B2B sit standing workstation Size/mm: 1200W*1200D*640-1290H Top: 25mm thickness laminated with scallop cut Frame:metal with powder coat; Leg Orientation:Square/Rectangle column; Height Range:640~1290mm; Speed:40mm/s; Max Loading: 150kg; With Timotion Dual motor; SAA/UL/CE approved;with cable duct	 	12	Nos.	2,965.00	RATE ONLY
	InterAction Profile screen Size/mm: 1200W*32D*600H 32mm thick Alu alloy frame fabric upholstery screen with bracket;		33	Nos.	455.00	RATE ONLY
	Flip cover to cable magement accessable from table top white/light grey finish.		55	Nos.	75.00	RATE ONLY
	PVC vertical cable management for clean cable treatment below the tables for staff, manager cabins, meeting rooms.		55	Nos.	135.00	RATE ONLY
2.09	3-Drawer 0.7mm high quality powder coated metal, three drawer full spread rails, interlock device, fifth wheel design incuding plastic pen box, B/B/F for A4/F4 hanging file holder. Size: W40 x D50 x H60 cm Color: Black/Grey		76	Nos.	465.00	AED 35,340.00
2.10	Desk mounted sound absorbing felt ACOUSTIC screen with 9+9mm with brackets and connector with desk size 1200 fabric to be approved by client .		31	Nos.	335.00	AED 10,385.00

FURNITURE WORKS:			QTY	UNIT	RATE	AMOUNT	
ITEM	DESCRIPTION OF WORKS				AED	AED	
2.11	Cable tray for cable management in powder coated metal finish accessable from table top.		50	Nos.	110.00	AED	5,500.00
2.12	Flip cover to cable magement accessable from table top white/light grey finish.		50	Nos.	75.00	AED	3,750.00
2.13	PVC vertical cable management for clean cable treatment below the tables for staff, manager cabins, meeting rooms.		50	Nos.	95.00	AED	4,750.00
2.14	**STAFF CHAIR** Adjustable headrest; Grey nylon frame; Adjustable lumbar support; PP fixed armrest; High density sponge for seating pad with bottom cover; Single mechanism with tilting back and right position knocking; 85mm size black gas lift; 350mm size chromed base; Nylon castor 55mm size; 3D Adjustable Armrest ; 3 Tilt Locking Position; Adjustable Headrest & Lumbar Support; Syncro Tilt with Adjustable Tilt Tension **WARRANTY - 3 YEARS**		76	Nos.	535.00	AED	40,660.00
3.00	**MEETING , COLLAB/DISCUSSION TABLE:**						
3.01	**4 PAX MEETING TABLE: S**ize/mm: φ1200*750H metal leg profile with powder coat; 25mm laminated desktop with scallop cut/Power access cutout; Black Powder coated frame		3	Nos.	985.00	AED	2,955.00
3.02	**Contemporary Designer Chair** Scandinavian minimalist chair with allpurpose work and office design. Comfortable, stylish, and truly unique, this chair is crafted with premium-grade PU leather and reinforced stitching, balancing style and durability. Upholstery Material: PU Leather Color: Black Seat with White Frame LegFrame: Chrome Aluminum		4	Nos.	680.00	AED	2,720.00
3.03	**Fab Meeting Table** Size/mm: 2400W*800D*1050H House special curved 60*30mm metal leg profile with powder coat; 25mm laminated desktop with scallop cut/Power access cutout; Height adjust feet;		1	Nos.	2,850.00	AED	2,850.00
3.04	Power module with 2 universal socket, 2 data, 1HDMI and 1 VGA point including cable manager cord for each table with flip cover.		2	Nos.	950.00	AED	1,900.00

HTI CONTRACTING LLC
PO Box :390737
506 - Binary Tower , Business bay
Dubai , United Arab Emirates
www.hashtaginteriors.com

FURNITURE WORKS:			QTY	UNIT	RATE	AMOUNT
ITEM	DESCRIPTION OF WORKS				AED	AED
4.00	**ALL HANDS, PNATRY AND OTHER AREAS**					
4.01	Esy lounge sofa chair Size/mm: 840Q*820D*700H Sturdy solid timber frame; High density foam; Fabric upholstery; **Location : All hands**		2	Nos.	1,335.00	AED 2,670.00
4.02	Shell easy lounge chair without arm in fabric seat and back with birch wood finish legs as per image. **Location : All hands**		2	Nos.	1,990.00	AED 3,980.00
4.03	Round shape coffee table on metal base and melamine wooden finish top size dia 600*370 Model: ARC070		2	Nos.	910.00	AED 1,820.00
4.04	Pouf MDF frame ·Fabric or PU upholstery ·High density foam **Location : All hands, Breakout areas**		14	Nos.	445.00	AED 6,230.00
4.05	Single seater high sofa in fabric finish with sponge seat, wooden frame, stainless steel leg the steel can use either black lacquered steel or polish stainless steelframe. 980*800*680 **Location : Reception**		2	Nos.	2,090.00	AED 4,180.00
5.00	**ALL HANDS, PNATRY AND OTHER AREAS**					
5.01	Telephone box Size/mm:W1000*D1000*H2250 Full steel frame structure, the external full steel sheet plate electrostatic spraying (censored), built-in PET sound-absorbing board, 10 mm glass backboard and door plank, mesa of MDF powder, metal table (excluding chairs), LED canister light suction a top, 86 five holes with USB socket, infrared sensing and manual control switch, outside the top integrated fan, T16210 carpet on the ground. Shipment in a closed wooden box		2	Nos.	16,200.00	AED 32,400.00
5.02	Communication box Size/mm:W2200*D1500*H2250 All-steel frame structure, external all-steel table plate electrostatic spraying (with muffler board), built-in PET sound-absorbing board, 10mm glass back board and door panel, top middle steel plate light with LED top strip light, 86 five-hole socket with USB port, infrared sensor and manual dual control switch, top external integrated exhaust fan, T16210 carpet floor (not including sofa and negotiation table) should be selected separately. Shipment in two closed wooden cases		1	Nos.	37,300.00	AED 37,300.00

HTI CONTRACTING LLC
PO Box :390737
506 - Binary Tower , Business bay
Dubai , United Arab Emirates
www.hashtaginteriors.com

FURNITURE WORKS:			QTY	UNIT	RATE	AMOUNT
ITEM	DESCRIPTION OF WORKS				AED	AED
6.00	CABINET AND STORAGES:					
6.01	Brian Storage Size/mm: W800*D400*H1100 E0 grade 25mm +16mm MFC board; Planter cabinet:300mmH; Cabinet with 1 adjustable shelf ; Beveled edge handles; With 25mmH base.		8	Nos.	1,030.00	AED 8,240.00
6.02	Brian Full height Storage Size/mm: W800*D400*H2200 E0 grade 25mm +16mm MFC board; Cabinet with 5 adjustable shelf ; Beveled edge handles; With 25mmH base. **Location : Staff and Engineering Area**		11	Nos.	1,980.00	AED 21,780.00
					TOTAL AMOUNT FOR FURNITURE WORKS	**AED 350,830.00**