PROPOSED INTERIOR FITOUT WORKS AT

ROOM 1202 -OPUS TOWER

DUBAI, UAE

Interiors

31.10.2024

DATE : 31/10/2024

Subject : Commercial Proposal for Interior Fit-out works

PROJECT : ROOM 1202 -OPUS TOWER - DUBAI, UAE

We are pleased to present our proposal for your review against the Fit-out works for **ROOM 1202 -OPUS TOWER - DUBAI, UAE.** Please find herewith our competitive offer as per the attached bill of quantities amounting as below.

GRAND TOTAL FROM SUMMARY		**829,743.00**
	VAT 5%	41,487.15

Completion : to be discussed.

Validity : 20 days from the date above.

Payment terms :
50% Advance against LPO,
40% Progressive Progress payment.
10% on Completion.

Notes & exclusion –As per Notes and exclusions sheet.

Thank you for the opportunity to participate in this tender. If you have any questions, please don't hesitate to get in contact with us. we hope our offer is in line with your requirement and look forward to working with you directly.

Thank you and best regards,

Chris Service
Managing Director | CS Interiors

DATE : 31/10/2024

Subject : Commercial Proposal for Interior Fit-out works

PROJECT : ROOM 1202 -OPUS TOWER - DUBAI, UAE

NOTES AND EXCLUSIONS

General Notes

1 Submitted BOQ is based on the layout, site visit & instructions

2 Any changes to the work, pertaining to the instructions from mall management/authorities/employer will have an additional cost implication and to be agreed upon finalizing of details.

3 We do not received any specification for the pricing and we assume and allocate the material cost to match render picture. During costruction we will propose the materials within our budget allocation. If any selection beyond the cost will submit the cost implication.

4 New gypsum ceiling considered only for **Conference room, Meeting room, Focus booth, Print station and Server room**. **Byron's office and Closed office** area ceiling considered as refurbishing the existing gypsum ceiling.

5 We do not received any details for Signage and art works. So we have considered only as psum. Price will vary when the design finalized.

6 We do not received any details for Artificial plants. So we have considered only as psum. Price will vary when the design finalized.

7 We have considered fixed phone boths. And there is an option considered for Movable phone booths under Loose furniture. (Option total not included in grand total)

Exclusions

1 Any scope related to non scope of areas.

2 Any scope not mentioned in BOQ

Interiors

PROPOSED INTERIOR FITOUT WORKS AT ROOM 1202 -OPUS TOWER - DUBAI, UAE

31/10/2024

Sl NO.	DESCRIPTION	AMOUNT
1	PRELIMINARIES	58,500.00
2	CIVIL AND DEMOLITION WORKS	7,369.00
3	FLOOR FINISH	52,520.00
4	WALLS AND WALL FINISHES	58,088.00
5	CEILING FINISHES	26,298.00
6	GLASS WORKS AND DOORS	68,085.00
7	WINDOW BLINDS	1,000.00
8	SIGNAGE AND ART WORKS	10,000.00
9	TV, VIDEO CONFERENCE SYSTEM AND PRINTER	20,796.00
10	IT WORKS	10,000.00
11	BAR AREA WHITE GOODS	4,344.00
12	LIGHT FITTINGS	41,294.00
13	ARTIFICIAL PLANTS	5,000.00
14	LOOSE FURNITURE	136,291.00
15	JOINERY WORKS	196,017.00
16	MEP WORKS	134,141.00
	Total Amount (Excluding VAT)	**829,743.00**
	VAT 5%	**41,487.15**

Interiors

PROPOSED INTERIOR FITOUT WORKS AT ROOM 1202 -OPUS TOWER - DUBAI, UAE

					31/10/2024
Sl No	**Item Description**	**Qty**	**Unit**	**Rate**	**Amount**
1.00	**PRELIMINARIES**				
1.01	**SITE MANAGEMENT** Provision for site management, including staff and facilities necessary for the efficient execution and supervision of the works.	1	Item	15,000.00	15,000.00
1.02	**MOBILIZATION & DEMOBILIZATION** Allow sum for mobilization & demobilization including supply and installation of temporary DB,Hoarding, adequate lighting, fire fighting equipment / extinguishers, cleaning / clearing of site on daily basis & upon project completion and provision for protection of finished goods, site safety, First Aid kits as well as security.	1	Item	4,000.00	4,000.00
1.03	**AUTHORITY APPROVALS** Obtaining and maintaining necessary permits, licenses, and approvals from relevant authorities(Dubai Development Authority DDA & DEWA) throughout the duration of the project. (All kind of payments and security deposits have been considered separately under below item a, b & c)	1	Psum	13,500.00	13,500.00
a	Fees for local authority approvals for complete approval process from Civil defence, Tecom, DEWA and Dubai municipality.	1	Item		To be paid by Client
b	Payment and Deposit	1	Item		To be paid by Client
c	Allow sum for building management approval-fees for drawing approvals as listed in the tenants manual.	1	Item		To be paid by Client
1.04	**INSURANCE** Provision of all required insurance policies, including but not limited to public liability, employer's liability, and contract works insurance, as per the contract requirements.	1	Item	3,000.00	3,000.00
1.05	**HEALTH & SAFETY PROTECTION** Implementation of health and safety measures, including site inductions, provision of personal protective equipment (PPE), first aid facilities, fire prevention equipment, and site security measures in accordance with applicable regulations and standards.	1	Item	2,000.00	2,000.00
1.06	**SITE CLEARANCE** Clearing and removal of all debris, vegetation, and existing structures from the site, including the disposal of waste materials in accordance with legal requirements and best practices.	1	Item	3,000.00	3,000.00

Interiors

PROPOSED INTERIOR FITOUT WORKS AT ROOM 1202 -OPUS TOWER - DUBAI, UAE

					31/10/2024
Sl No	**Item Description**	**Qty**	**Unit**	**Rate**	**Amount**
1.07	**TEMPORARY WATER & ELECTRICITY** Provision and maintenance of temporary water and electricity supplies for the site, including connections, distribution, and metering, as required for the construction works.	1	Item		By Client
1.08	**SHOP DRAWING** Preparation, submission, and coordination of detailed architectural and MEP shop drawings in accordance with the design specifications and applicable standards, incorporating any revisions and obtaining necessary approvals from the relevant authorities and consultants.	1	Item	10,000.00	10,000.00
1.09	**SCAFFOLDING** Permanent scaffolding provided for this project.	1	Item	4,500.00	4,500.00
1.10	**FINAL CLEANING** Carrying out a thorough final cleaning of the entire project site, including the removal of construction debris, dust, and any leftover materials. The cleaning process should cover all internal and external areas, ensuring that the completed facility is in a clean and presentable condition, ready for handover to the client.	1	Item	3,500.00	3,500.00
				SUB TOTAL CARRIED TO SUMMARY	**58,500.00**
2.00	**CIVIL AND DEMOLITION WORKS**				
2.01	**Demolition:** Demolish and cart away of existing interior elements including Existing Ceiling, Existing Floor and Wall finishes, Existing Partitions.	1	Job	7,369.00	7,369.00
				SUB TOTAL CARRIED TO SUMMARY	**7,369.00**

Interiors

PROPOSED INTERIOR FITOUT WORKS AT ROOM 1202 -OPUS TOWER - DUBAI, UAE

					31/10/2024
Sl No	**Item Description**	**Qty**	**Unit**	**Rate**	**Amount**
3.00	**FLOOR FINISH**				
3.01	**Raised Floor:** Psum allowed for repurposed raised access floor.	1	Psum	3,000.00	3,000.00
3.02	**LVT Flooring:** Supply and installation of LVT flooring including the glue or other fixing materials as per requirement. Location: Bar area, Dining area, Walkway and Print station	81	Sqm	148.00	11,988.00
OPTION	**Moicrocement Floor:** Supply and Installation of Microcement concrete texture finish on floor as per the requirements. Location: Bar area, Dining area, Walkway and Print station	81	Sqm	18,270.68	
3.03	**Carpet Flooring:** Supply and installation of 50 X 50 carpet tile flooring including underlay, adhesives, and other fixing accessories as per the requirement. Location: Open workstation, Hotdesk area, Informal seating area, Conference room, Meeting room, Focus booth, Server room, Closed office, Byron's office and Phone booths	209	Sqm	166.00	34,694.00
3.04	**Floor profile:** Supply and installation of SS floor profile between different floor finishes.	33	Rm	86.00	2,838.00
				SUB TOTAL CARRIED TO SUMMARY	**52,520.00**

Interiors

PROPOSED INTERIOR FITOUT WORKS AT ROOM 1202 -OPUS TOWER - DUBAI, UAE

31/10/2024

Sl No	Item Description	Qty	Unit	Rate	Amount
4.00	**WALLS AND WALL FINISHES**				
4.01	**Skirting:** Supply and installation of 100mm thick MDF skirting, PU painted to the desired color. All work will be executed in compliance with industry standards and manufacturer's recommendations.	96	Rm	53.00	5,088.00
4.02	**Gypsum Partition:** Supply and installation of Gypsum wall partition - 15cm thick - GI stud and track framing system. Height: 3.6m Location: Conference room, Meeting room, Focus booth, Print station area, Closed office, Byron's office, Phone booths and Open workstation area near the bar	155	Sqm	166.00	25,730.00
4.03	**Gypsum Baffle:** Supply & installation of gypsum Baffle over glass (300mm) partition with necessary fittings. Location : Above the glass partition	17	Rm	106.00	1,802.00
4.04	**Fenomastic Wall paint:** Supply and apply of Jotun fenomastic Wall paint inlcuding the base coats. Location: Meeting room, Focus booth, Print station, Server room and Closed office	256	Sqm	37.00	9,472.00
4.05	**Texture paint:** Supply and Apply two coats of texutre paint with all necessary base coats to Walls. Location : Dining area	20	Sqm	76.00	1,520.00
4.06	**Writable Glass:** Supply and Installation of Writable glass as per the requirements. Height: 1.5m Location: Conference room and Focus booth	11	Sqm	1,316.00	14,476.00
4.07	**Fabric panels:** Supply and Installation of fabric panels including the fixing materials as per requirements. Location: Conference room, Closed office and Byron's office	26	Sqm	-	**Included in Joinery**
4.08	**Wrapping:** Supply and Installation of Wrapping including the fixing materials as per requirements. Location: Informal seating, Conference room, Meeting room, Focus booth, Closed office and Byron's Office	74	Sqm	-	**Included in Joinery**
				SUB TOTAL CARRIED TO SUMMARY	**58,088.00**

Interiors

PROPOSED INTERIOR FITOUT WORKS AT ROOM 1202 -OPUS TOWER - DUBAI, UAE

					31/10/2024
Sl No	**Item Description**	**Qty**	**Unit**	**Rate**	**Amount**
5.00	**CEILING FINISHES**				
5.01	**Refurbishing the existing ceiling:** Provision for refurbishing the existing ceiling. Including the repainting works and Patching works. Location: Byron's office and Closed office area	35	Sqm	46.00	1,610.00
5.02	**Gypsum Ceiling:** Supply and installation of 12.5mm thick regular gypsum board ceiling on GI suspension system. Location: Conference room, Meeting room, Focus booth, Server room, Print station and Phone booths	54	Sqm	151.00	8,154.00
5.03	**Ceiling paint:** Supply and application of Jotun fenomastic Ceiling paint inlcuding the base coats. Dark Grey Emulsion Location: New gypsum ceiling areas	54	Sqm	43.00	2,322.00
5.04	**Open Ceiling paint:** Supply and application of fenomastic spray paint on slab with necessary base coats. (Including MEP services) Location: Open workstation, Informal seating area, Bar area, Dining area and Hot desk area	209	Sqm	68.00	14,212.00
				SUB TOTAL CARRIED TO SUMMARY	**26,298.00**

Interiors

PROPOSED INTERIOR FITOUT WORKS AT ROOM 1202 -OPUS TOWER - DUBAI, UAE

					31/10/2024
Sl No	**Item Description**	**Qty**	**Unit**	**Rate**	**Amount**
6.00	**GLASS WORKS AND DOORS**				
6.01	**AcousticGlass Partition:** Supply and installation of (Acoustic) single glazed 12mm thick clear tempered fixed straight glass partition with powder-coated 20x30mm concealed aluminum U channel, ensuring glass-to-glass silicone joints for seamless appearance and stability. (Upto 33dB) Height: 3m Location: Conference room, Meeting room, Focus booth, Closed office and Byron's office	51	Sqm	695.00	35,445.00
6.02	**Acoustic Glass door:** Supply and installation Framed Axile Clarity single glazed swing door in 12mm thick normal clear tempered glass door panel with complete ironmongeries and accessories including Standard 600mm long non lockable H type pull handle. All aluminium door frame and hardware's are in Standard Powder Coated Finish. (Upto 32 dB) Door Size : 0.8m X 3m H Location : Phone booths	2	Nos	6,945.00	13,890.00
6.03	**Wooden Door:** Frame in Solid Beech Wood, Door Leaf in 44mm thick Solid Chip Board Pressed with Veneer with all around 10mm Solid Wood Lipping. All Finishing in Natural/Stained as per approved Sample. Including Normal set of Ironmongery. Location: Conference room, Meeting room, Focus booth, Closed office and Byron's office	5	Nos	3,750.00	18,750.00
OPTION	**Smart Glass:** Supply and Fixing of smart film application for glass partition. Location: Conference room, Meeting room and Byron's office	37	Sqm	48,962.41	
				SUB TOTAL CARRIED TO SUMMARY	**68,085.00**
7.00	**WINDOW BLINDS**				
7.01	Provision for the protection for the Existing blinds and reuse.	1	Psum	1,000.00	1,000.00
				SUB TOTAL CARRIED TO SUMMARY	**1,000.00**
8.00	**SIGNAGE AND ART WORKS**				
8.01	Provision for the signage works.	1	Psum	8,000.00	8,000.00
8.02	Provision for the Art works.	1	Psum	2,000.00	2,000.00
				SUB TOTAL CARRIED TO SUMMARY	**10,000.00**

PROPOSED INTERIOR FITOUT WORKS AT ROOM 1202 -OPUS TOWER - DUBAI, UAE

					31/10/2024
Sl No	**Item Description**	**Qty**	**Unit**	**Rate**	**Amount**
9.00	**TV, VIDEO CONFERENCE SYSTEM AND PRINTER**				
9.01	Supply and Installation of TV. Brand: 65" Samsung Location: Informal seating area, Conference room, Meeting room, Byron's office, Open workstation and Hot desk area	6	Nos	2,152.00	12,912.00
9.02	Supply and Installation of Group Video conferencing system with Expansion Mics. Brand: Logitech Location: Conference room and Meeting room	2	Nos	3,942.00	7,884.00
				SUB TOTAL CARRIED TO SUMMARY	**20,796.00**
10.00	**IT WORKS**				
10.01	**<u>IT works:</u>** Provision for the IT works.	1	Psum	10,000.00	10,000.00
				SUB TOTAL CARRIED TO SUMMARY	**10,000.00**
11.00	**BAR AREA WHITE GOODS**				
11.01	Provision for the white goods including: **Coffee machine (Philips)** **Microwave (Samsung)** **Fridge (Samsung)**	1	Item	4,344.00	4,344.00
				SUB TOTAL CARRIED TO SUMMARY	**4,344.00**

Interiors

PROPOSED INTERIOR FITOUT WORKS AT ROOM 1202 -OPUS TOWER - DUBAI, UAE

					31/10/2024
Sl No	**Item Description**	**Qty**	**Unit**	**Rate**	**Amount**
12.00	**LIGHT FITTINGS**				
12.01	Provision for the Lights fittings (Excluding the Linear lights)	1	Item	37,594.00	37,594.00
12.02	Provision for refurbishing works on the existing linear lights and re use.	1	Psum	3,700.00	3,700.00
				SUB TOTAL CARRIED TO SUMMARY	**41,294.00**
13.00	**ARTIFICIAL PLANTS**				
13.01	Provision for Supply and Installation of artificial plants.	1	Psum	5,000.00	5,000.00
				SUB TOTAL CARRIED TO SUMMARY	**5,000.00**
	TOTAL AMOUNT				**363,294.00**

PROPOSED INTERIOR FITOUT WORKS AT ROOM 1202 -OPUS TOWER
DUBAI, UAE - LOOSE FURNITURE

						31/10/2024
Sl NO.	**DESCRIPTION**		**QTY**	**UNIT**	**RATE**	**AMOUNT**
	LOOSE FURNITURE					
	BAR AREA					
1.00	**Shell Padded Modern Bar Stool** Fully Upholstered Bentwood Seat Structure. Black Powder Coated Steel Frame. Padded Leather Seat. Upholstery Material: Genuine Leather LeatherColor: Black BlackFrame Base: Black Powder Coated Size-450mm L x 450mm w x1035mm H		4	Nos	693.00	2,772.00
2.00	Chairs chair in light beige fabric and black metal base 600mm L x 570mm W x 700mm H		1	Nos	663.00	663.00
	DINING AREA					
3.00	**Milan Round Table** The Milan table is remarkably designed with a stainless steel round flat disc base and a variety of German made worktop finishes. Worktop Finish: Starke® Pro Black Frame Color: Powder Coated Matt Black Desk Dimension: Dia.90 x H74 cm		2	Nos	1,213.00	2,426.00
4.00	**Duoblock Multi-Purpose Designer Chair** Size: W44.5 x D50 x H82 cm Back Color: White Seat Color: White		8	Nos	574.00	4,592.00
	SEATING AREA					
5.00	**Milan Round Table** The Milan table is remarkably designed with a stainless steel round flat disc base and a variety of German made worktop finishes. Worktop Finish: Starke® Pro Black Frame Color: Powder Coated Matt Black Desk Dimension: Dia.90 x H74 cm		2	Nos	1,213.00	2,426.00
6.00	**SYS Series CH-6 Arm Chair** Size: W57 x D62 X H83 cm Fabric Color: HY-5028 Blue Green Leg: White		2	Nos	1,454.00	2,908.00
7.00	**Vino Minimalist Round Coffee Table** Aesthetic chamfered veneer coffee table with a design of simple lines steel tube base with full round seamless end caps. The table top diameter is 40cm made up of plywood red oak veneer, oiled finished with natural color. Size: H 50.5 x W50 x Dia 50 cm		2	Nos	1,000.00	2,000.00

PROPOSED INTERIOR FITOUT WORKS AT ROOM 1202 -OPUS TOWER
DUBAI, UAE - LOOSE FURNITURE

31/10/2024

SI NO.	DESCRIPTION		QTY	UNIT	RATE	AMOUNT
	BREAK-OUT COLLAB					
8.00	**Turin Round Table** Turin series designed for maximum space efficiency with unique tilt and stack function. Worktop Finish: Starke® Pro Black Frame Color: Chrome Desk Dimension: Dia.70 x H43 cmProduction		3	Nos	1,193.00	3,579.00
9.00	**Mars Lounge Chair** Size: H 62 x W 73 x D 52 Color: Orange		9	Nos	1,462.00	13,158.00
	COLLAB/HOTDESK AREA					
10.00	**Kas Modular Minimalist Low Back Sofa** soft upholstered sofa KAS Model: KAS-SO-02F abric Color: LIDO-40 Light Gray Size: W160 x D80 x H68 cm		1	Nos	3,393.00	3,393.00
11.00	**Kas Modular Minimalist Low Back Sofa** soft upholstered sofa KAS Model: KAS-SO-04 Fabric Color: LIDO-40 Light Gray Size: W98 x D80 x H68 cm		3	Nos	2,262.00	6,786.00
12.00	**Cliff Stone Top Coffee Table Set** Minimalist style and sophisticated look for interior, this coffee table set is made up of solid iron with matte black stand and made by sintered stone marble top. The set includes large table with 80cm diameter and 39cm in height while medium size table has 60cm diameter and 45cm in height.		1	Nos	2,747.00	2,747.00
13.00	**Knot Minimalist Coffee Table** Aesthetic chamfered veneer coffee table with a design of simple lines steel tube base with full round seamless end caps. The table top diameter is 40cm made up of plywood red oak veneer, oiled finished with natural color Size: H 50.5 x W 40-42 x Dia 40 cm		2	Nos	739.00	1,478.00
14.00	**Vino Minimalist Round Coffee Table** Aesthetic chamfered veneer coffee table with a design of simple lines steel tube base with full round seamless end caps. The table top diameter is 40cm made up of plywood red oak veneer, oiled finished with natural color. Size: H 50.5 x W50 x Dia 50 cm		1	Nos	1,000.00	1,000.00
15.00	**Shell Padded Modern Bar Stool** Fully Upholstered Bentwood Seat Structure. Black Powder Coated Steel Frame. Padded Leather Seat. Upholstery Material: Genuine Leather LeatherColor: Black BlackFrame Base: Black Powder Coated Size-450mm L x 450mm w x1035mm H		5	Nos	1,019.00	5,095.00

PROPOSED INTERIOR FITOUT WORKS AT ROOM 1202 -OPUS TOWER
DUBAI, UAE - LOOSE FURNITURE

						31/10/2024
Sl NO.	**DESCRIPTION**		**QTY**	**UNIT**	**RATE**	**AMOUNT**
	BYRON'S OFFICE					
16.00	**AVA Series Rectangular Executive Desk** Worktop Finish: Starke® Pro White Frame Color: Powder Coated Matt White Cable Management: 1x Rectangular Grommet Desk Dimension: W180 x D60 x H75 cm Production		1	Nos	2,020.00	2,020.00
17.00	**GEO Black Ergonomic Executive Chair** Chair Ergonomics: ▪ Soft PU 3D adjustable armrests ▪ 3 Tilt Locking Position ▪ Adjustable Headrest & Lumbar Support ▪ Syncro Tilt ▪Adjustable seat		1	Nos	831.00	831.00
18.00	**Aria Visitor Mesh Chair** Mesh back, Grey fabric seat, Armrest with padding, Black powder coated cantilever base, Adaptive back tilt tension Size: H 86 x W 54 x D 58 cm		2	Nos	724.00	1,448.00
19.00	**Kas Modular Minimalist Low Back Sofa** soft upholstered sofa KAS Model: KAS-SO-02F abric Color: LIDO-40 Light Gray Size: W160 x D80 x H68 cm		1	Nos	3,393.00	3,393.00
20.00	**EDGE Series Chamfered Low Height 2 Door White Cabinet** The sleek chamfered edge design in dark grey color is exclusive, intelligent and innovative. Durable commercial grade frame with white finish that resists scratches, stains and wear. Offers two push to open doors with adjustable shelf. Starke® soft close door hinges for smooth and quiet operation. Body & Edge Color : White Worksurface Finish : Starke® Pro White Dimension : W100 x D40 x H85 cm		2	Nos	1,350.00	2,700.00

PROPOSED INTERIOR FITOUT WORKS AT ROOM 1202 -OPUS TOWER
DUBAI, UAE - LOOSE FURNITURE

						31/10/2024
Sl NO.	**DESCRIPTION**		**QTY**	**UNIT**	**RATE**	**AMOUNT**
	CLOSED OFFICE					
21.00	**AVA Series Cluster of 2x Face to Face Workstation** Worktop Finish: Starke® Pro White Frame Color: Powder Coated Matt White Cable Management: 1x Round Grommets (middle) Size per User: W160 x D74 cm Screen Panel: Grey	 	1	Nos	3,336.00	3,336.00
22.00	**Saber Dual Arm Monitor Desk Mount Stand** Color: White		2	Nos	309.00	618.00
23.00	**GEO Silver Grey Ergonomic Executive Chair** Chair Ergonomics: ▪ Soft PU 3D adjustable armrests ▪ 3 Tilt Locking Position ▪ Adjustable Headrest & Lumbar Support ▪ Syncro Tilt ▪Adjustable seat		2	Nos	862.00	1,724.00
24.00	**Milan Round Meeting Table** Worktop Finish: Starke® Pro Black Frame Color: Powder Coated Matt Black Desk Dimension: Dia.80 x H74 cm		1	Nos	1,213.00	1,213.00
25.00	**Marics Black Task Chair** nylon arms and frame, wintex fabric back and seat, and height-adjustable mechanism. Size: W59 x D54 x H85-105 cmDelivery		2	Nos	847.00	1,694.00
26.00	**EDGE Series Chamfered Low Height 2 Door White Cabinet** The sleek chamfered edge design in dark grey color is exclusive, intelligent and innovative. Durable commercial grade frame with white finish that resists scratches, stains and wear. Offers two push to open doors with adjustable shelf. Starke® soft close door hinges for smooth and quiet operation. Body & Edge Color : White Worksurface Finish : Starke® Pro White Dimension : W100 x D40 x H85 cm		1	Nos	1,350.00	1,350.00
	PHONE BOOTH 1,2&3					
27.00	**Mantle Modern Office Bar Stool** Featuring a perfectly integrated pad upholstered with fabric, with a slim skid frame metal base and 3 bars connected in front for stability. Size: H 109 x W 52 x D 51 cm		1	Nos	1,170.00	1,170.00

PROPOSED INTERIOR FITOUT WORKS AT ROOM 1202 -OPUS TOWER
DUBAI, UAE - LOOSE FURNITURE

						31/10/2024
Sl NO.	**DESCRIPTION**		**QTY**	**UNIT**	**RATE**	**AMOUNT**
	METING ROOM					
28.00	**Stellar Chrome Designer Round Meeting Table** Worktop Finish: Starke® Germany Pro White Frame Color: Chrome + Black Dimension Dia.110 x H74 cm		1	Nos	2,908.00	2,908.00
29.00	**Marics Black Task Chair** Nylon arms and frame wintex fabric back and seat height-adjustable mechanism. Size: W59 x D54 x H85-105 cm		6	Nos	847.00	5,082.00
	BOARD ROOM					
30.00	**Ace Series Steel Frame Meeting Table** Worktop Finish: Starke® Germany Frame Color: Powder Coated Matt White/Black Cable Management: 2x Flip Rectangular Grommets Desk Dimension: W300 x D120 x H75 cmProduction		1	Nos	3,537.00	3,537.00
31.00	**Simon Black Genuine Leather Designer Chair** chair made of Top Grade Aniline Italian Leather with a polished aluminum frame. Featuring height adjustable and integrated reclining Donati mechanism. Upholstery Material: Aniline Leather Color: Black		10	Nos	954.00	9,540.00

PROPOSED INTERIOR FITOUT WORKS AT ROOM 1202 -OPUS TOWER
DUBAI, UAE - LOOSE FURNITURE

31/10/2024

SI NO.	DESCRIPTION		QTY	UNIT	RATE	AMOUNT
	WORKSTATION					
32.00	**AVA Series Cluster of 6x Face to Face Workstation Desk** Worktop Finish: Starke® Germany Frame Color: Powder Coated Matt White Cable Management: 2x Round Grommets Size per User: W140 x D74 cm Screen Panel: PET Acoustic Partition with innovative technology which dampens sound and ensures persona		2	Nos	7,973.00	15,946.00
33.00	**AVA Series Cluster of 6x Face to Face Workstation Desk** Worktop Finish: Starke® Germany Frame Color: Powder Coated Matt White Cable Management: 2x Round Grommets Size per User: W120 x D60 cm Screen Panel: PET Acoustic Partition with innovative technology which dampens sound and ensures persona		1	Nos	6,624.00	6,624.00
34.00	**Saber Dual Arm Monitor Desk Mount Stand** Color: White		12	Nos	308.00	3,696.00
35.00	**Sharp Ergonomic Medium Back Executive Chair** Sit comfortably with considerate ergonomic functions and excellent experience. Sharp ergonomic chair is combined with mesh backrest and fabric seat cover with nylon base. Headrest and lumbar support can be adjusted according to your needs. This chair also comes with upward and downward armrest adjustment. It has also lockable and adjustable tilt function that increases stability and control in different seating position. Dimension : W65 x D56 x H115-124 cm Chair Ergonomics : ▪1 Tilt Locking Position ▪3D Adjustable Armrest ▪Adjustable Lumbar Support ▪Synchro Tilt ▪Tilt with Adjustable Tilt TensionDelivery		18	Nos	616.00	11,088.00
	PRINT STATION					
36.00	**EDGE Series Chamfered Low Height 2 Door White Cabinet** The sleek chamfered edge design in dark grey color is exclusive, intelligent and innovative. Durable commercial grade frame with white finish that resists scratches, stains and wear. Offers two push to open doors with adjustable shelf. Starke® soft close door hinges for smooth and quiet operation. Body & Edge Color : White Worksurface Finish : Starke® Pro White Dimension : W100 x D40 x H85 cm		1	Nos	1,350.00	1,350.00
OPTION	**Phone booth** ▪ LED lighting ▪ Intelligent fan ▪ USB Socket ▪ Human sensor system ▪Size: 1100 x 1100 x 2200 mm		2	Nos	73,078.00	Assumed built in
					SUB TOTAL CARRIED TO SUMMARY	**136,291.00**

Interiors

PROPOSED INTERIOR FITOUT WORKS AT ROOM 1202 -OPUS TOWER - DUBAI, UAE

31/10/2024

Sl No	Item Description	Ref Image	Qty	Unit	Rate	Amount
1	**JOINERY WORKS**					
	BAR AREA					
1.01	**Supply and installation of Bar Back Wall Open Cabinet-** Base Unit Carcass, Shelf in 18mm thick MR Melamine MDF with PVC edge Lipping, Shutter, Panel and Open Shelf in 18mm thick MDF with Veneer Finish. Counter top in Black Marble. Including LED Strip Lights. Size- 2800mm L x 600mm W x 3100mm H		1	Nos	18,781.00	18,781.00
1.02	**Supply and installation of Bar Cabinet-** Structures in Plywood and Solid Wood cladded with Procelian tile on top, Fascia. Including LED Strip Light. Size- 3900mm L x 800mm W x 1100mm H		1	Nos	14,852.00	14,852.00
1.03	**Supply and installation of Pantry Cabinet and Back Wall Shelf** Carcass, Shelf, Drawers, Fascia in 18mm thick MR Melamine MDF, Shutters in Veneer/PU Paint Finish and Counter top in Black Porcelain tile finish as per approved sample. Including Pull Handle, Soft Closing Hinges, Drawer Rails. Size- 2900 mm L x 600mm W x 900mm H		1	Nos	15,146.00	15,146.00
1.04	**Supply and installation of Hidden Door** Shutters in MDF with Veneer finish as per approved sample. Including Custom made Pocket Sliding System. Size- 4000 mm L x 1500mm H		1	Nos	24,517.00	24,517.00
	SEATING AREA					
1.04	**Supply and installation of Bench seating** Structures in Solid White Wood and Top and Exposed area in MDF with Veneer /PU Paint Finish. Seating Upholstery Fabric Finish over Medium Density Foam. Back wall in MDF with Bodaq wrapping Finish as per approved sample. Size- 4342+3167mm L x 520mm W x 700mm H		1	Nos	30,968.00	30,968.00
1.05	**'Supply and installation of Wooden Wall Panel For TV area** In 9mm thick MDF with Bodaq Wrapping Finish Fixed Direct on to the Wall. Size- 4100mm L x 3600mm H.		1	Nos	6,300.00	6,300.00
1.06	**'Supply and installation of Wooden Wall Panel For TV area** In 9mm thick MDF with Bodaq Wrapping Finish Fixed Direct on to the Wall. Size- 3500mm L x 3600mm H.		1	Nos	5,775.00	5,775.00
	MEETING ROOM					
1.07	**'Supply and installation of Wooden Wall Panel For TV area** In 9mm thick MDF with Bodaq Wrapping Finish Fixed Direct on to the Wall. Size- 3300mm L x 3600mm H.		1	Nos	5,617.00	5,617.00
	CONFERENCE ROOM					
1.08	**'Supply and installation of Wooden Wall Panel For TV area** In 9mm thick MDF with Bodaq Wrapping Finish Fixed Direct on to the Wall. Size- 3500mm L x 3600mm H.		1	Nos	5,775.00	5,775.00
1.09	**Wooden Wall Panel** Supply and installation of 12mm thick MDF with Bodaq Wrapping Finish.		15	Sqm	647.00	9,705.00
	COLLAB/HOTDESK					
1.10	**Supply and installation of Table Ledge** Wooden top and base leg in Melamine MDF. Ledge thickness 36mm. Size- 4238mm L x 600mm W x 750mm H		1	Nos	5,899.00	5,899.00

Interiors

PROPOSED INTERIOR FITOUT WORKS AT ROOM 1202 -OPUS TOWER - DUBAI, UAE

						31/10/2024
Sl No	**Item Description**	**Ref Image**	**Qty**	**Unit**	**Rate**	**Amount**
1.11	**'Supply and installation of Wooden Wall Panel For TV area** In 9mm thick MDF with Bodaq Wrapping Finish Fixed Direct on to the Wall. Size- 5200mm L x 3600mm H.		1	Nos	8,022.00	8,022.00
1.12	**'Supply and installation of Readymade Movable TV Stand** In MS Powder coated Finish. including Rotary Wheels. Size- 1700mm L x 1500mm H.		1	Nos	1,614.00	1,614.00
	BYRON'S OFFICE					
1.13	**Supply and installation of Display unit** Carcass, Shelf and Panel in 18mm thick MDF with Veneer/ Bodaq Wrapping Finish. Including Soft Closing Hinges and LED Strip Light. Size-1780mm L x 600mm W x 3600mm H		1	Nos	13,441.00	13,441.00
1.14	**'Supply and installation of Wooden Wall Panel For TV area** In 9mm thick MDF with Bodaq Wrapping Finish Fixed Direct on to the Wall. Size- 3300mm L x 3600mm H.		1	Nos	5,617.00	5,617.00
	CLOSED OFFICE					
1.15	**Wooden Wall Panel** Supply and installation of 12mm thick MDF with Bodaq Wrapping Finish.		12	Sqm	647.00	7,764.00
	POD ROOM					
1.16	**Wall Fabric Cladding** Supply and installation of acoustic grooved panel fixed direct on the gypsum wall with necessary adhesives. Note- There will be a hairline joint @ 2400mm H and 1200mm Length. (Due to the available size of Sheet) Brand-Acoustic.ae. Material- 100% Polyester fiber including 60% regenerated Fibers. Thickness-12mm Density-200 Kg/cubic.m Color- as per selection from Catalog. Ceiling Height-3000mm.		20	Sqm	632.00	12,640.00
	FOCUS BOOTH					
1.16	**Supply and installation of Seating & Wrapping** Structures in Solid White Wood and exposed area in MDF with Veneer /PU Paint Finish. Seating Upholstery Fabric Finish over Medium Density Foam. Size- 1200mm L x 600mm W x 750mm H		1	Nos	3,584.00	3,584.00
				TOTAL AED		**196,017.00**

Interiors

PROPOSED MEP WORKS FOR ROOM 1202 -OPUS TOWER - DUBAI, UAE

31/10/2024

Sl NO.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	MEP WORKS				
1.00	**ELECTRICAL WORK**				
	Sub Main Distribution Boards (MDB/SMDB/DB)				
1.001	Modification of DBs	1	Nos.	4,286.00	4,286.00
1.002	Temporary power service and lights for construction Note:- Any additional charge from DEWA / FM team to be paid by client	1	Item	2,143.00	2,143.00
1.003	Approval Note:- Any additional charge from the DEWA / FM team is to be paid by the client We have assumed that DEWA approval is not required if required we have add in the cost Note: We have excluded the Power upgradation Additional payment by the client Main armoured cable	1	Item	6,429.00	Rate Only
	Containment				
1.004	**HDGI Cable tray and trunking including necessary supports, accessories etc. all in accordance with the drawings** H/L and L/L Cable trunking for Lighting & Power	1	Item	2,572.00	2,572.00
	Supply and Install power points with PVC Conduits, PVC Wiring, containment & accessories including final termination for the following as per the drawings, specification and regulations.				
1.005	13A Switch socket, Twin white PVC	13	Nos.	415.00	5,395.00
1.006	13A Switch socket, Single white PVC	6	Nos.	315.00	1,890.00
1.007	Relocation of floor box	6	Nos.	358.00	2,148.00
1.008	Floor box (2 Twin socket and 4 data)	8	Nos.	715.00	5,720.00
1.009	HDMI point for TV point	2	Nos.	358.00	716.00
1.010	Power for server rack	1	Nos.	429.00	429.00
1.011	Power Switch with Flex-Outlet for AC	1	Nos.	572.00	572.00
1.012	power isolator for Coffice machine	1	Nos.	572.00	572.00
1.013	Power for Pantry equipments	4	Nos.	572.00	2,288.00
1.014	16A SPN isolator with Timer for Signages	2	Nos.	572.00	1,144.00
	Supply and install Lighting power points with Wiring, PVC Conduiting & final circuit PVC wiring including termination for the followings - (Supply of Light Fixture Excluded in this price)				
1.015	Install Light fixture with containment, cabling and termination hanging and spot lights and wall light power points	50	Nos.	205.00	10,250.00
1.016	Install Light fixture with containment, cabling and termination Decorative power points	3	Nos.	286.00	858.00
1.017	Install Light fixture with containment, cabling and termination LED light power points (Ceilling cove,Curtains and joinerys)	10	Nos.	172.00	1,720.00
1.018	Supply and installation of Lighting Switches (MK)	5	Nos.	286.00	1,430.00
	Supply and Installation of only PVC conduits, containments for the MEP Services as per the design requirements (Final confirmation subject to cofirmation on scope)				
1.019	Data/Voice Twin outlet (RJ-45)				
1.02	Security System(Access Control)	1	Items	2,858.00	2,858.00
1.021	AV system				
1.022	Wi Fi system				
	Testing & commissioning				
1.023	Testing & commissioning of Electrical System	1	Items	3,572.00	3,572.00
				SUB TOTAL CARRIED TO SUMMARY	**50,563.00**

Interiors

PROPOSED MEP WORKS FOR ROOM 1202 -OPUS TOWER - DUBAI, UAE

31/10/2024

Sl NO.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
2.00	**FIRE PROTECTION WORKS**				
	Fire Alarm Works				
	Supply and installation of Fire alarm Devices with necessary fire rated cables, clips and other accessories as per the drawings and specifications as per the new design requirement.				
2.01	Supply and Installation of Addressable Smoke Detector	3	Nos.	1,072.00	3,216.00
2.02	Relocation of existing Smoke	7	Nos.	429.00	3,003.00
2.03	Relocation of Break Glass Unit	1	Nos.	500.00	500.00
2.04	Relocation of Fire Alarm Sounder	1	Nos.	500.00	500.00
2.05	Supply and Installation of Inter Face Unit control module	2	Nos.	1,143.00	2,286.00
2.06	Supply and Installation of FA cables 1.5mmx2C red colour	1	Items	2,572.00	2,572.00
2.07	Supply and installation of fire alram panel FACP Note:We have assumed that the existing panel has space to add the new device	1	Nos.	12,858.00	Rate only
2.08	Testing and commissioning of Fire Alarm System	1	Item	7,572.00	7,572.00
	Emergency Lighting System				
2.09	Supply and Installation of Emergency Light self contained	4	Nos.	586.00	2,344.00
2.10	Supply and Installation of Emergency Exit Light	4	Nos.	586.00	2,344.00
2.11	Allow sum for testing, addressing, programming and commissioning of Emergency Lighting System	1	Item	1,429.00	1,429.00
	Fire Fightings system				
2.11	Supply and installtion of springkler in ceilling area	5	Nos.	643.00	3,215.00
2.12	Relocation of springkler	10	Nos.	358.00	3,580.00
2.13	CO2 fire extinguishers (5 kg)	2	Nos.	366.00	732.00
2.14	Dry Chemical powder extinguisher (6 kg)	2	Nos.	304.00	608.00
2.15	Fire Blanket	1	Nos.	212.00	212.00
	FF isolation charge				
2.16	Isolation of FA and FF system charge to paid for FLS maintenance team	1	Item	2,858.00	2,858.00
2.17	Charge for DCD inspection certificate	1	Item	1,143.00	1,143.00
2.18	Testing and commissioning of Fire Fighting System	1	Item	2,143.00	2,143.00
				SUB TOTAL CARRIED TO SUMMARY	**40,257.00**

Interiors

PROPOSED MEP WORKS FOR ROOM 1202 -OPUS TOWER - DUBAI, UAE

					31/10/2024
Sl NO.	**DESCRIPTION**	**QTY**	**UNIT**	**RATE**	**AMOUNT**
3.00	**HVAC WORKS**				
3.01	Service the existing AC	4	Nos.	500.00	2,000.00
3.02	Relocation of thermostat	4	Nos.	558.00	2,232.00
	Duct work including Plenum Boxes, elbows, bends, tees, junctions, belmouths, access doors, connection to equipments and air out lets as per the drawings and specifications.				
3.03	Modification of existing ducts ,Fabrication and installation of Supply Air Duct (PI Ducting) forfor FCUs based on proposed drawings	1	Items	17,000.00	17,000.00
3.04	Flexible duct (consider each 1.5m) with round damper, rings & jubilee clips as per design	1	Item	3,572.00	3,572.00
3.05	Supply & installation of Volume Control Dampers control the air flow	1	Item	3,572.00	3,572.00
3.06	Supply & installation of acoustic insulation control the airflow noise	1	Item	3,572.00	3,572.00
	Grilles and Diffusers				
3.07	Supply and installation of Grills and Diffusers including fittings, supports, and other materials required to complete installation as specified and shown on the drawing. Grills Type:Flow Bar diffuser for linear grills and diffuser in open ceilling	1	Item	8,515.00	8,515.00
	Testing & Commissioning				
3.08	Testing, commissioning & air balancing	1	Item	2,858.00	2,858.00
				SUB TOTAL CARRIED TO SUMMARY	**43,321.00**

Exclution:

1.We have excluded combined two Units as per the DEWA standard
2.We have excluded Power upgradation
3.We have excluded the IT works ,We have consider the contaiament for IT works
4. We have excluded the Lighting control system,we have consider ON/ OFF switches
5. We have excluded the BMS system
6. We have excluded the FM200 for sever room
7. We have assumed that the existing AC is in working condition

	TOTAL MEP	**134,141.00**