Design Infinity LLC

Interior Turnkey Solutions

COMMERCIAL PROPOSAL

AWARDED Superbrands WORLDWIDE 2022

Level 2, Unit 202 Burj Daman Building, DIFC,
DI/GN/391/R0/2023
28.08.2023

Design Infinity LLC
Interior Turnkey Solutions

Beyond Imagination ...

Date:28/08/2023

REF :DI/GN/391/R0/2023

To,

Dear Sir/Madam,

Sub: Interior FITOUT WORK Level 2, Unit 202 Burj Daman Building, DIFC

We thank you for giving us an opportunity to offer our proposal for Interior FITOUT WORK Level 2, Unit 202 Burj Daman Building, DIFC
Please find herewith our competitive offer as per the attached bill of quantities amounting as below.

Total for Fit out + Loose Furniture	**2,967,174.00**
VAT As per UAE Laws	**148,358.70**

Completion: To be Discussed

Validity: 30 days from the above date.

Payment Terms: 25% advance Payment against Order confirmation , 65% Progressive payment,5% on completion 5% retention against security check

Encl. : 1) Annexure I Notes and Exclusion
2) Annexure II BOQ

We look forward to establishing a constructive dialogue with you at all stages of your evaluation process. Assuring you of our best services at all times.

We hope our offer is in line with your requirement and look forward to working with you.

Thank you and best regards,

Geetha Nayak
Managing Partner

P.O. Box 62522 | Dubai | UAE
Tel: +971 4 3795902
Fax: +971 4 3795903
Email: info@design-infinity.com

P.O. Box 62560 | Abu Dhabi | UAE
Tel: +971 2 448 2286
Fax: +971 4 3795903
Email: info@design-infinity.com

www.design-infinity.com

Date:28/08/2023

REF :DI/GN/391/R0/2023

Sub: Interior FITOUT WORK Level 2, Unit 202 Burj Daman Building, DIFC

NOTES AND EXCLUSION

1 Government fees & deposit to the concerned authority/ building management to be paid by the client on actuals.

2 Any major changes to the work, pertaining to the instructions from Building management/authorities/employer will have an additional cost implication and to be agreed upon finalizing of details.

3 Water & electricity charges during the fit out period will be provided by the client.

4 Required power and Chilled water provision to be provided by the Landlord

5 We considered only the containment work for IT Works ,

EXCLUSIONS

1 Electrical Load Upgradation
2 Any IT CCTV , Acess control and AV BGM
3 Artficial and natural plnts
4 White hoods
5 FM 200
6 Any modification of existing MEP stubout
7 BMS & BTU meter
2 VAT

SN	DESCRIPTION	AMOUNT (LATEST)
	FIT-OUT WORKS	
A	PRELIMINARIES	75,000.00
B	FLOOR WORKS	166,355.00
C	WALL PARTITIONS	162,271.00
D	WALL FINISHES	437,102.00
E	CEILING WORKS	159,895.00
F	DOORS & SIGNAGE WORKS	246,438.00
G	JOINERY WORKS	291,010.00
H	LOOSE FUNITURE / ITEMS	200,000.00
I	SUPPLY & FIXING OF LIGHT FIXTURES	240,260.00
	MEP WORKS	
J	ELECTRICAL WORKS	291,559.00
K	FIRE ALARM WORKS	132,858.00
L	FIRE FIGHTING	142,858.00
M	EMERGENCY & EXIT LIGHT SYSTEM	29,221.00
N	AIR CONDITIONING WORKS	345,204.00
O	Plumbing - Water Supply & Drainage Works	37,013.00
P	IT /AV Works(Only Containment)	10,130.00
Q	ACCESS CONTROL SYSTEM (Make- ZKTeco)	Excluded
R	CCTV SYSTEM (Make- HIK VISION)	Excluded
S	IT SYSTEM (Make-SCHNEIDER ELECTRIC)	Excluded
T	BMS Works [Provisional Sum]	Excluded
	TOTAL FIT-OUT WORKS (AED)	**2,967,174.00**

Note: Total Amount Excluding VAT.

SN	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	FIT-OUT WORKS				
A	PRELIMINARIES				
1	**AUTHORITY APPROVALS:** Obtaining Authority Approvals; Dubai Municipality & Dubai Civil Defense Dubai Electricity & Water Authority Obtaining Approvals & Work Permit from Building Management Preparation of Drawings & Documents Inspection Appointments & Completion Certificates	1			-
2	**MAINTENANCE & PROTECTION OF SITE:** Temporary protection & maintenance of the general area of site. First Aid Box & Safety Equipment, Temporary Fire Extinguishers	1			-
3	**SUPERVISION & SECURITY:** Coordination and Site Supervision team stationed at site during the working hours & ensure the safety. (To protect the site from unauthorized entry & trespassing)	1			-
4	**TEMPORARY FACILITIES:** Mobilization, temporary fittings (Light, DB, water supply, safety equipment, tools, transportation, coverage of corridors and protection of surfaces, etc.. Points for temporary power and lighting tap off to be provided by client.	1	Item	75,000.00	75,000.00
5	**PROJECT MANAGEMENT & COORDINATION:** Liaising with the Building Management, Consultant or Client during execution Preparation of execution schedule & plan.	1			-
6	**SITE CLEANING:** Removal & Cleaning of all debris from site to the approved municipality dump yard as per the regulations. Temporary Skips & Dust Bins at Site of Daily Cleaning. Final Deep cleaning of the site including removal of all Contractor materials before the handover of the site.	1			-
7	**EQUIPMENT & TOOLS:** Carrying out all the required equipment & tools for the execution of works. To ensure all the equipment's are in good condition.	1			-
8	AUTHORITY APPROVALS AND DEPOSIT FEES - IS TO BE PAID BY CLIENT BY ACTUALS				By Client
	Sub Total				**75,000.00**
B	FLOOR WORKS				
1	Allowance for removal, modification, supply and installation of New Mechanical Raised Access Floor due to damage and design changes.. **Location: All Area**	1	Ls	60,780.00	60,780.00
2	**Anti Static Raised Access Floor:** Supply and installation of Anti-Static Raised Access Floor for the server room. sample to submit for approval. **Location: Server Room**	1	Ls	4,500.00	4,500.00
3	**Waterproofing:** Supply and laying of Two layers of 4mm thick bitumen membrane type water proofing. including perimeter wall & columns up to 300mm height above finish floor level. With necessary surface preparation. **Location: Powder Room at Director Room & Pantry Area**	1	Ls	3,500.00	3,500.00
	FLOORING FINISHES				
4	**FL-01 LVT Plank:** Supply and installation of LVT Plank FF-01 including wastage with all necessary accessories as per the flooring layout drawing & specification. HTS will provide the materials for client approval. **Location: Director 1-2 Room, Meeting and Lounge, Reception area**	140	m2	262.00	36,680.00
5	**FL-02 LVT Plank:** Supply and installation of LVT Plank FF-01 including wastage with all necessary accessories as per the flooring layout drawing & specification. HTS will provide the materials for client approval **Location: Pantry area**	1	Ls	262.00	262.00
6	**FL-03 Vinyl Tiles:** Supply and installation of Vinyl Tiles including wastage with all necessary accessories as per the flooring layout drawing & specification. HTS will provide the materials for client approval. **Location: Storage 1 & 2**	15	m2	204.00	3,060.00
7	**FL-04 -Carpet Tile Flooring**: Supply & installation of Carpet Tile flooring including all necessary accessories. HTS to provide sample for client approval - **Location: Open Workstation**	40	m2	208.00	8,320.00
8	**FL-05 - Carpet Tile Flooring (Type 1)**: Supply & installation of carpet tile flooring including all necessary accessories. HTS to provide sample for client approval - **Location: Sr. Executive Room 1 & 2**	1	Ls	208.00	208.00
9	**FL-06 - Carpet Planks Flooring (Type 2)**: Supply & installation of carpet planks flooring including all necessary accessories. HTS to provide sample for client approval - **Location: Demo/Presentation Room**	70	m2	234.00	16,380.00
10	**FL-07 - Porcelain Marble Look Tiles Flooring**: Supply & installation of Porcelain Marble Look Tiles Flooring including all necessary accessories. HTS to provide sample for client approval - **Location: Powder Room at Directors Area**	1	Ls	1,500.00	1,500.00
11	**Stage at Demo/Presentation Stage**: Supply & installation of Stage at Demo/Presentation Stage made of metal structure including all necessary wooden support - **Location: Demo/Presentation room**	1	Ls		Excluded
12	**Self Leveling:** Supply and installation if self leveling	275	m2	72.00	19,800.00
13	**MDF Skirting**: Supply & Installation of MDF Skirting.	155	Lm	59.00	9,145.00
14	**SS Strips:** Supply & Installation of SS transition strip Profile including required adhesives. Location: between different floor finish.	20	Lm	111.00	2,220.00
					166,355.00
C	WALL PARTITIONS				

SN	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
1	**FR Gypsum Partition:** Supply and installation of **100mm gypsum wall** with necessary GI framing and 1x12.5mm Normal FR gypsum board (Knauf Brand) on both sides **including mineral wool insulation** complete with jointing, taping and ready to receive final finish. Till 4000 mm height only .Location: As per partition Lay-out	332	m2	130.00	43,160.00
2	**Cement Board Partition:** Supply & Install of 100mm Thick cement board partition including taping & Joinery, ready to receive the finish. Till 3.6m height only Location: Powder Room & Pantry (only at Wet Area)	1	Ls	208.00	208.00
3	**FR Gypsum Cladding:** Supply and installation of Liner Wall cladding to the existing wall with necessary GI framing and 12.5mm FR gypsum board on one sides complete with jointing, taping and ready to receive final finish.	84	m2	111.00	9,324.00
4	**Glass Partition (Single Glazed):** Supply and installation Single Glazing system comprising of 1x10mm tempered glass with 35x21mm head and bottom channels in Silver Anodized finish including dummy frame.. Tape Jointed. Partition Height till 2700mm. Note: We considered normal tempered glass only. Any DB certificate is excluded **Location: Sr. Executive Room 1 & 2 only**	8	m2	338.00	2,704.00
5	**Vinyl Sticker:** Supply and installation of Vinyl Sticker.	8	m2	1,500.00	1,500.00
6	Allow for the above **gypsum baffle** above the glass partition **including mineral wool insulation** complete with jointing, taping and ready to receive final finish.	15	Lm	130.00	1,950.00
7	**MDF Cladding:** Supply and installation of **MDF Liner Wall cladding to the existing façade as per site survey** with necessary GI framing including mineral wool insulation on one sides complete with jointing, taping and ready to receive final finish.	35	Lm	2,955.00	103,425.00
					162,271.00
D	**WALL FINISHES**				
1	**WF-01 Paint:** Supply & Application of **Fenomastic Jotun Paint** finish including application of stucco & Primer Paint. Location: As per the wall finishes layout	598	m2	39.00	23,322.00
2	**WF-02 Textured Paint:** Supply & Application of Textured Paint finish including backing application of stucco & Primer Paint. Location: Reception Area	30	m2	163.00	4,890.00
3	**WF-03 Wall Paper (Type 1):**Supply & installation of Wallpaper fixed directly on the proposed wall as per the wall finishes. Location: **Director Room 1 & 2, Reception & Meeting/Lounge Area Walls**	180	m2	119.00	21,420.00
4	**WF-03 Wall Paper (Type 2) :** Supply & installation of Wallpaper fixed directly on the proposed wall as per the wall finishes. **Location: Pantry**	45	m2	119.00	5,355.00
5	**WF-04 Fabric Acoustic Wall Panel** : Supply & Installation of Fabric Acoustic Wall Panel at Demo/Presentation Room. Height of the panel is 3000mm	20	m2	1,949.00	38,980.00
6	**WF-05 MDF Veneer Wall Cladding**: Supply & Installation of MDF wall cladding in veneer finish. Location: Director Room 1 & 2, Reception & Meeting/Lounge Area	65	m2	1,819.00	118,235.00
7	**WF-06 MDF Slats @ Back of Reception:** Supply and installation of MDF slats in veneer finishes	9	m2	1,819.00	16,371.00
8	**WF-07 Porcelain Marble Look Tiles:** Supply and installation of Porcelain Marble Look Tiles. Location: Powder Room & Director 2 Area	45	m2	812.00	36,540.00
9	**WF-08 Writable Glass**: Supply and installation of writable back painted glass	18	m2	780.00	14,040.00
10	Allow for supply and installation of wall SS strip in black color as per the 3D.	1	Ls	845.00	845.00
11	Supply & Installation of **manual operated sun screen fabric roller blinds** including required support and accessories.	86	m2	1,299.00	111,714.00
12	Supply & Installation of **Automatic roller blinds (black out)** including required support and accessories. **Location: Demo Room only**	30	m2	1,513.00	45,390.00
					437,102.00

SN	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
E	CEILING WORKS				
1	**CF-01 Normal Gypsum Ceiling:** Supply & Installation of Normal Non-FR Gypsum board ceiling using singe layer of 12mm gypsum board including necessary GI suspension system & joint taped and finished ready to receive the paint. Location: As per the Ceiling Layout	275	m2	111.00	30,525.00
2	**Wooden Ceiling:** Supply & Installation of MDF wooden laminate matching veneer ceiling including necessary. Location: Director 1 Room	50	m2	1,949.00	97,450.00
3	**Stretch Ceiling:** Supply & Installation of Stretch Ceiling including necessary. Location: Reception Area	22	m2	2,900.00	Option only
4	Supply & Installation of gypsum coving as required including support & accessories	60	Lm	195.00	11,700.00
5	Supply & Installation of gypsum pelmet as required including support & accessories	36	Lm	195.00	7,020.00
6	Allow for cutting the ceiling to received the concealed lights including strips as per the 3D.	1	Lm	2,500.00	2,500.00
7	**Ceiling paint:** Supply & Application of 2 Coats for Fenomastic Jotun Paint including application of 2 Coats for Primer/Stucco on the Gypsum Ceiling, Pelmet & bulkhead.	275	m2	33.00	9,075.00
8	Supply & Installation of 600mmx600mm Access Panel including required support & accessories	5	nos.	325.00	1,625.00
					159,895.00
F	DOORS & SIGNAGE WORKS				
1	**FR Door @ Entrance:** Supply and installation of FR rated Glass Door	1	Nos.	161,039.00	161,039.00
2	**Glass Door @ Cabin** Supply & Installation of Normal Tempered glass door.	3	Nos.	3,247.00	9,741.00
3	**Double Wooden Door:** Supply and installation of Normal Wooden Door at Location: Meeting & Lounge	1	Nos.	10,390.00	10,390.00
4	**Wooden Door:** Supply and installation of Normal Wooden Door at Location: Director 1 & 2, Reception & Entrance to Demo Room	4	Nos.	3,897.00	15,588.00
5	**Normal Wooden Door:** Supply and installation of Normal Wooden Door at Location: Storage Area & Pantry Door	5	Nos.	3,767.00	18,835.00
6	**FR Wooden Door:** Supply and installation of Normal Wooden Door at Server Room Note: 60 minute FR	1	Nos.	5,845.00	5,845.00
	Signage Works			-	-
7	Allowance for signage at Reception	1	Nos.	25,000.00	25,000.00
					246,438.00
G	JOINERY WORKS				
1	**Reception Counter:** Fabricate, supply and installation of Reception Counter at internal carcass in MDF and as per the drawings.	1	Nos.	15,585.00	15,585.00
2	**Reception Metal Shelves:** Fabricate, supply and installation of Reception Metal Shelvs sand as per the drawings.	4	Nos.	LS	7,500.00
3	**Open Plan Workspace Table** Fabricate, supply and installation of Table at internal carcass in MDF Veneer and table top will be Veneer as per the drawing. Size: 1400mm L	6	Nos.	7,511.00	45,066.00
4	**Director 1 Desk :** Fabricate, supply and installation of Director Desk as per the 3D.	1	Nos.	25,975.00	25,975.00
5	**Director 1 behide Metal Shelves:** Fabricate, supply and installation of Director Metal Shelves as per the 3D.	1	Ls	19,286.00	19,286.00
6	**Director 1 Customized Table:** Fabricate, supply and installation of Customized Table as per the 3D.	1	Nos.	31,585.00	31,585.00
7	**Director 1 Vanity Counter:** Fabricate, supply and installation of Vanity Counter as per the 3D.	1	Nos.	8,117.00	8,117.00
8	**Director 2 L-Shape Desk :** Fabricate, supply and installation of Director Desk as per the 3D.	1	Nos.	11,299.00	11,299.00
9	**Meeting Room Coffee Counter** Fabricate, supply and installation of Coffee Counter at internal carcass in MDF laminate and shutter to laminate MDF and table top will be Marble Look Tiles. Size: 3200mm L	1	Nos.	19,221.00	19,221.00
10	**Demo/Presentation U Shape Desk - Type 1** Fabricate, supply and installation of Demo/Presentation U Shape Desk metal leg & table top will be MDF laminate finish Size: 7200 mm L	1	Nos.	47,241.00	47,241.00
11	**Demo/Presentation U Shape Desk - Type 2** Fabricate, supply and installation of Demo/Presentation U Shape Desk metal leg & table top will be MDF laminate finish. Size: 2300mm L	1	Nos.	13,247.00	13,247.00
12	**Demo/Presentation U Shape Desk - Type 3** Fabricate, supply and installation of Demo/Presentation U Shape Desk metal leg & table top will be MDF laminate finish. Size: 3600mm L	1	Nos.	21,299.00	21,299.00

SN	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
13	**Podium Stand at Demo/Presentation.** Fabricate, supply and installation of Demo/Presentation Podium metal leg & table top will be Solid Surface. Size: 3600mm L	1	Nos.	-	Excluded
14	**Pantry Counter** Fabricate, supply and installation of Pantry Counter at internal carcass in MDF laminate and shutter to laminate MDF and table top will be Solid Surface. Size: 2000mm L	1	Nos.	10,390.00	10,390.00
15	Allowance for TV wall support and backing	3	Nos.	780.00	2,340.00
16	Allowance for Video Conferencing extra support and backing	1	Nos.	1,949.00	1,949.00
17	**DB/FACP Cabinet** Supply & Installation of DB cabinet as per the drawing & specification.	1	Nos.	5,455.00	5,455.00
18	**Director 2 Customized Console** Fabricate, supply and installation of Customized Console.	1	Nos.	5,455.00	5,455.00
					291,010.00
H	**LOOSE FUNITURE / ITEMS**				
1	FF-01 - Task Chair	9	Nos.	-	-
2	FF-02 - Chair at Presentation Room	16	Nos.	-	-
3	FF-03 - Director Chair	1	Nos.	-	-
4	FF-04 Lounge Chair	15	Nos.	-	-
5	FF-05 Arm Chair	2	Nos.	-	-
6	FF-06 Arm Chair at Lounge	4	Nos.	-	-
7	FF-07 Sofa	1	Nos.	Provional sum	200,000.00
8	FF-08 Pantry Chair	4	Nos.	-	-
9	FF-09 Side Table	3	Nos.	-	-
10	FF-10 Coffee Table	2	Nos.	-	-
11	FF-11 Table	1	Nos.	-	-
12	FF-12 Task Table at Se. Executive 1 & 2	2	Nos.	-	-
13	**Director 1 Customized Working Desk:** Fabricate, supply and installation of Customized Working Desk as per the 3D.	2	Nos.		Excluded
	Note: All Furniture will be provided by HTS for client approval				
					200,000.00
I	**SUPPLY & FIXING OF LIGHT FIXTURES**				
1	LF-01 - Suspended Linear Light Type 1	1	Ls	-	-
1	LF-03 - Downlight	1	Ls	-	-
2	LF-04 - Recessed LED lights	1	Ls	-	-
3	LF-05 - Track Light	1	Ls	-	-
4	LF-05 B- Track	1	Ls	-	-
5	LF-06 & 07 -Pendant Lights	1	Ls	240,260.00	240,260.00
6	LF-08 - Pin light	1	Ls	-	-
7	LF-09 - Concealed Led Lights	4	no.	-	-
8	Decorative Lights @ Reception	1	Ls	-	-
9	LED Strip Lights	1	item	-	-
9	Supply of Dimming Panel	1	item	-	-
10	Allow for LCS system as per building requirments	1	item	-	-
					240,260.00
	MEP WORKS				
J	**ELECTRICAL WORKS**				
1	Modification of existing DB as per the new power and lighting layout with all new accessories, new cabling, etc	1	Nos	-	-
2	Supply and install GI cable tray and trunking for the power and lighting cables	1	Item	-	-
	13 Amps Single Sockets (MK-White PVC)			-	-
3	Supply and installation of single pole sockets outlets 13A - 250 V , conventional earth pin release shutter dual earth terminal OR equivalent, with wiring, PVC conduiting & connections as per the design requirements in the proposed Interior layout.	11	Nos	-	-
	13 Amps Single Socket for VAV			-	-
4	Supply and installation of single pole sockets outlets 13A - 250 V , conventional earth pin release shutter dual earth terminal OR equivalent, with wiring, PVC conduiting & connections as per the design requirements in the proposed Interior layout.	7	Nos	-	-
	13 Amps Dual Sockets			-	-
5	Supply and installation of dual pole sockets outlets 13A - 250 V , conventional earth pin release shutter dual earth terminal OR equivalent, with wiring, PVC conduiting & connections as per the design requirements in the proposed Interior layout.	15	Nos	-	-
	13 Amps Spur outlets			-	-
6	Supply and installation of 13Amps spur outlet with wiring, conduiting & connections as per the site requirements	1	No	-	-
	15 Amps Switched Sockets			-	-
7	Supply and installation of 15Amps switched socket with wiring, conduiting & connections as per the site requirements	5	No	241,559.00	241,559.00
	20 Amps switched Sockets			-	-
8	Supply and installation of 20Amps switched socket with wiring, conduiting & connections as per the site requirements	5	No	-	-
	20 Amps isolator for FTU			-	-
9	Supply and installation of 20Amps isolator for FTU with wiring, conduiting & connections as per the site requirements	17	No	-	-
	Floor Boxes			-	-
10	Supply and installation of floor boxes with accessories including conduits for electrical sockets as per the design requirements in the Proposed Interior layout. Floor boxes to be grey framed, flush mounted in existing floor and with carpet infill to the lids..	15	No	-	-
	Conduting and cabling works for the light fittings			-	-
11	Connection to lights including cables, conduits and necessary fittings in conceal/ expose, connections, terminations, wiring ,fixings and fittings,ceiling rose (where required), complete all in accordance with detail drawings and Specifications.	40	No	-	-
12	Supply & installation of 2 gang light switch , White PVC	2	Nos	-	-
13	Supply & installation of 3 gang light switch , White PVC	4	Nos	-	-
	Testing and commissioning:			-	-
14	Testing and commissioning including Megger test,Live test,Cold test	1	Item	-	-

SN	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	Lighting control system:			-	-
15	Supply and installation of cables and containments for Dali dimmable standalone lighting control system for the reception area and meeting rooms only.	1	Item	-	-
16	Interfacing of perimeter light with the building System	1	Item	PS	50,000.00
	te: 1)We have not considered any power upgradation works. 2) Any kind of work in the electrical room is not considered 3) New cable from electrical room to DB not considered.4) We have considered 1FB shared by 2 persons for the open workstation area. 5) We have not considered any UPS power.				
					291,559.00
K	**FIRE ALARM WORKS**				
1	Supply and installation of new FACP with voice evacuation	1	Nos	-	-
2	Interface module with 24/7 DCD, building panel & building system	10	Nos	-	-
3	Supply of new smoke detector	15	Nos	-	-
4	Supply of new heat detector	1	Nos	-	-
5	Suppy of new void detectors with indicator	16	Nos	132,858.00	132,858.00
6	Charges for cancelling the existing fire alarm devices	8	Nos	-	-
7	Supply of control/Monitor module	20	Nos	-	-
8	Supply of addressable pull station with sounder	3	No	-	-
9	Installation of fire alarm devices	61	No	-	-
10	Testing, commissioning & programming of building FACP	1	No	-	-
					132,858.00
L	**FIRE FIGHTING**				
1	Supply and installation of new sprinklers heads with piping	1	Ls	-	-
2	Pressure test for the new sprinkler line	1	Item	-	-
3	Supply & Installation of 5 KG CO2 Fire Extinguisher	2	nos	71,429.00	142,858.00
4	Supply & Installation of 4 KG DCP Fire Extinguisher	2	nos	-	-
5	DCD Certification charges	1	Item	-	-
					142,858.00
M	**EMERGENCY & EXIT LIGHT SYSTEM**				
1	Supply & installation of emergency light (Self Continued type with 3 Hrs battery backup)	8	Nos	-	-
2	Supply and installation of new directional exit lights	4	No	29,221.00	29,221.00
3	Supply and installation of emergency control panel	1	No	-	-
4	Testing, commissioning & programming	1	Item	-	-
					29,221.00
N	**AIR CONDITIONING WORKS**				
	Duct Works				
1	Supply of Floor Terminal Unit (TU4) inclusive of two centrifugal fans, motorized damper, multifunctional electronic controller with "bus" communication card, air discharge and intake floor grills, 5m power connection cable with British Standard fused plug. This unit has an LCD Screen for reading all necessary data and easily changing them if required. Manufacturer: AET, UK	17	Nos	11,429.00	194,293.00
2	Installation of Floor Unit (TU4) inside the Raised Access Floor, supply & installation of all necessary data (bus communication) cabling & RJ45. Power supply to the TU4 and preparation of the raised floor to receive the unit is not included in our price. - 17 nos	1	Item	66,234.00	66,234.00
3	Supply of floor grille	1	Item	5,065.00	5,065.00
4	Allow for all necessary works for FTU	1	Item	42,598.00	42,598.00
5	Supply & Installation of Duct Sealants, 1 inch Gasket tape, 2 inch Aluminium tape, Duct Connectors etc.	1	Item	6,494.00	6,494.00
6	Supply and installation of new BTU Meter as per the building requirements	1	Item	24,026.00	24,026.00
7	Allow for Civil work for FTU	17	Nos	6,494.00	6,494.00
					345,204.00
O	**Plumbing - Water Supply & Drainage Works**				
1	Supply & installation of Water Supply PPR / Pex pipes as required			-	-
2	Supply & installation of UPVC Drainage piping works as required			-	-
3	Supply & installation of Floor trap & Clean out as required			-	-
4	Supply & Installation of Isolation valves, angle valves, traps & Flexible connections			-	-
5	Connecting the Water Supply & Drain Pipes to base build Stub out	1	LS	37,013.00	37,013.00
6	Pressure Test for Water Supply line, gravity flow test for drain for new works			-	-
7	Supply & installation of water heater 30 ltr			-	-
8	Supply & installation of water Meter as per building requirement			-	-
9	Chlorination for the new water supply line			-	-
					37,013.00

SN	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
P	**IT /AV Works(Only Containment)**				
1	Supply and installation of 25mm PVC Conduiting/trunking for IT, CCTV,Access Control system;	1	item	10,130.00	10,130.00
2	Supply and installation of 50mm dia conduit for the A/V connection	1	item	-	-
					10,130.00
Q	**ACCESS CONTROL SYSTEM (Make- ZKTeco)**				
					Excluded
R	**CCTV SYSTEM (Make- HIK VISION)**				
					Excluded
S	**IT SYSTEM (Make-SCHNEIDER ELECTRIC)**				
					Excluded
T	**BMS Works [Provisional Sum]**				
1	Supply and installation of BMS system as per the building requirement for the HVAC system. (1 FCUs and BTU meter)	1	item		Excluded Provisional Price only
2	Interfacing the HVAC system with building BMS system.				
					Excluded