Design Infinity

WWW.DESIGN-INFINITY.COM

COMMERCIAL PROPOSAL

PARADYM OPUS TOWER

LOCATION: DUBAI

Table of CONTENTS

1. Cover Letter with Notes & Exclusions
2. Bill of Quantities
3. Contact Person

Design Infinity

COVER LETTER

Design Infinity *Beyond Imagination …*

Date: 01/11/2024

REF: DI/SA/2024/R0

Dear Sir

SUB : INTERIOR FITOUT WORKS FOR PARADYM

We thank you for allowing us to offer for INTERIOR FITOUT WORKS FOR PARADYM
Please find herewith our offer as per the attached amounting as below.

TOTAL FOR FIT OUT	**891,688.00**

VAT 5% AED : As per UAE law

Completion: To be discussed

Validity: 30 days from the above date.

Payment Terms: 25% advance against confirmation,s,65% interim payment upon site progress,5% on completion &5% retention against bank guarantee cheque

We look forward to establishing a constructive dialogue with you at all stages of your evaluation process. Assuring you of our best services at all times.

We hope our offer is in line with your requirement and look forward to working with you.

Thank you and best regards,

SHOAIB ANSARI
BUSINESS DEVELOPMENT MANAGER

P.O. Box. 62522 | Dubai | UAE
Tel: +971 4 3795902
Fax: +971 4 3795903
Email: info@design-infinity.com

P. O. Box. 62560 | Abu Dhabi | UAE
Tel: +971 2 4482286
Fax: +971 2 4482287
Email: info@design-infinity.com

www.design-infinity.com

SUB : INTERIOR FITOUT WORKS FOR PARADYM

NOTES AND EXCLUSION

1 All Government/ Municipal/Civil defence fees, deposits, building deposits are to be paid by the Client on actuals.

2 Any changes to the work, on the instructions from building management/authorities/employer, will have an additional cost implication and to be agreed upon finalizing of details.

3 We have assumed that we have enough chilled water flow rate as per the given as-built layouts. And also we assumed that existing FCU units are available in our provisional premises.

4 The light fitting considered in our proposal are Non-dimmable lights
Make : Creta

5 Any additional charges/ fees for any third party shall be paid by the client.

6 Civil defence final price subjected to final design.

7 We have assumed that existing emergency lights are self-contained system with any DCD Approved contractor can carried out the works

8 Upright sprinklers & void detectors will be not part of our scope. proposed ceiling void is less than 800MM

9 We have not considered any water provision for the BAR area

10 Assumed that existing FACP to be reused and in good working condition

EXCLUSIONS

1 IT Works
2 Signage
3 Live / Artificial Plants and planter box
5 Plumbing work
6 White goods
7 New HVAC Machines
8 Electrical Meter arrangements
9 Power upgradation related work

9 Power upgradation related work
10 New FACP
11 Water meters
12 Av, BGM, TV, Wifi
13 Third party charges for Civil defense
14 VAT

P.O. Box. 62522 | Dubai | UAE
Tel: +971 4 3795902
Fax: +971 4 3795903
Email: info@design-infinity.com

P. O. Box. 62560 | Abu Dhabi | UAE
Tel: +971 2 4482286
Fax: +971 2 4482287
Email: info@design-infinity.com

www.design-infinity.com

BILL OF QUANTITIES

Design Infinity LLC
Interior Turnkey Solutions
Beyond Imagination ...
P. O. Box. 62522 | Dubai | UAE
Tel: +971 4 3795902
Fax: + 971 4 3795903
Email: info@design-infinity.com

PARADYM - OPUS TOWER

DI/JS//2024/R0 **Date 31/10/2024**

Item	DESCRIPTION	Qty	Unit	Amount (Dhs.)	TOTAL (Dhs.)
1	**PRELIMINERIES**				
1.01	Mobilization work and demobilization of site workers &equipment's		Job		-
1.02	Preparation of drawings		Job		-
1.03	Allow for necessary scaffolding		Job		-
1.03	Provision, site supervision including project manager, site supervisor and site personnel's.		Job		-
1.04	Provide Cleaning of site on regular basis.		Job	55,000.00	55,000.00
1.05	Insurance for office interior work (CAR) Coverage asper the DI standards		Job		-
	Note : Authority Approval Fees shall be paid by client on actuals				
	TOTAL-PRELIMINARIES				**55,000.00**
2	**CIVIL WORKS**				
2.01	Demolition of existing partition , flooring , ceiling mep fixtures cart way the same to municipality dump stations.	1	Job	18,025.00	18,025.00
2.02	Re arraging of existing raised floor as per the new flooring and partition alyout	1	Job	12,875.00	12,875.00
	TOTAL-CIVIL WORKS				**30,900.00**
3	**FLOOR FINISHES**				
3.01	Supply and installation of carpet tile flooring as per the design Brand : PC RATE AED 90 / sqm **Location : Work station area , Informal seating , phone booth**	130	sqm	147.00	19,110.00
3.02	Supply and installation of carpet tile flooring as per the design Brand : PC RATE AED 90 / sqm **Location : Byrons Office , Closed office , , 6 pax meeting room , 10pax meeting room**	65	sqm	147.00	9,555.00

Design Infinity LLC
Interior Turnkey Solutions
Beyond Imagination ...
P. O. Box. 62522 | Dubai | UAE
Tel: +971 4 3795902
Fax: + 971 4 3795903
Email: info@design-infinity.com

PARADYM - OPUS TOWER

DI/JS//2024/R0 **Date 31/10/2024**

Item	DESCRIPTION	Qty	Unit	Amount (Dhs.)	TOTAL (Dhs.)
3.03	Supply and installation of LVT flooring as per the design Brand : PC RATE AED 100 / sqm **Location : Walkway clearence , Dining , bar area**	76	sqm	160.00	12,160.00
3.04	Supply andinstallation of fibrebond self levelling	76	sqm	160.00	12,160.00
3.04	Supply and installation of HPL raised floor Location : Server Room	4	sqm	LS	3,500.00
	TOTAL-FLOOR FINISHES				**56,485.00**
4	**CEILING FINISHES**				
4.01	Supply and installation of regular plain gypsum board ceiling with necessary fittings **Location : Byrons's Office , Closed , iformal seating ,**	155	m2	103.00	15,965.00
4.02	Supply and apply of white Fenomastic paint for the proposed gypsum ceiling	200	m2	30.00	6,000.00
4.03	Supply and installation of gypsum perforated ceiling **Location : 10pax meeting room , 6 pax meeting**	45	m2	181.00	8,145.00
4.04	Supply and appalication of white fenomastic paint for open ceiling area	80	m2	46.00	3,680.00
4.05	Supply and installation 80mm high cove bulkhead including paint	26	Lmt	142.00	3,692.00
4.06	Supply & installation of gypsum access panel	8	Nos	232.00	1,856.00
4.07	Supply and installation of curtain pelmet	35	mtr	142.00	
	Wexisting curtain pelmet ewill be reatined as it is				
	TOTAL-CEILING FINISHES				**39,338.00**
5	**WALLS & WALL FINISHES**				
5.01	Supply and installation of single layer NFR gypsum board dry wall partition with necessary fittings **Location :**	162	m2	116.00	18,792.00
5.01	Supply and installation of 12mm single glazed Straight Glass fix partition 30x20mm Aluminum U channel_ powder coated finish **Location :**	40	m2	367.00	14,680.00

Design Infinity LLC
Interior Turnkey Solutions
Beyond Imagination ...
P. O. Box. 62522 | Dubai | UAE
Tel: +971 4 3795902
Fax: + 971 4 3795903
Email: info@design-infinity.com

PARADYM - OPUS TOWER

DI/JS//2024/R0 **Date 31/10/2024**

Item	DESCRIPTION	Qty	Unit	Amount (Dhs.)	TOTAL (Dhs.)
5.01	Supply and installation of baffle wall above the glass partition **Location :**	20	m	116.00	2,320.00
5.01	Supply & installation of glass frosting.1200mm height **MAKE-METAMARC**	24	m2	110.00	2,640.00
5.02	Supply and installation of accoustic fabric wall panel made of MDF backing with 10mm thk fabric cladding (PC rate- 100Aed/Lm) Location:Phone booth & Focus room	33	m3	993.00	32,769.00
5.03	Supply & installation of fenomastic paint to walls. Make : jotun fenomastic	70	m2	33.00	2,310.00
5.04	Supply and installation of wall paper as per the layout Location : PC rate : AED 45 / sqm	84	m2	99.00	8,316.00
5.05	Supply and installation of back painted glass Location :	35	m2	644.00	22,540.00
5.06	Supply and installation of graphic panel	30	m2	155.00	4,650.00
5.07	Supply and fixing of manual roller blinds Make-Global shades	115	m2	97.00	EXCLUDED
5.08	Supply and installation mdf veneer skirting	95	m	58.00	5,510.00
	TOTAL-WALL FINISHES				**114,527.00**
6	**DOORS**				
6.01	Supply and installation of frameless single leaf swing door using 12mm thick clear tempered glass with powder coated aluminium outer frame (100x50mm), fitted with GEZE Floor spring, standard patch fittings, bottom lock and standard 'H' type 600mm long handle. (32mm dia handle, 400mm C/C). All fittings are in powder coated finish.	7	Nos	2,447.00	17,129.00

Design Infinity LLC
Interior Turnkey Solutions
Beyond Imagination ...
P. O. Box. 62522 | Dubai | UAE
Tel: +971 4 3795902
Fax: + 971 4 3795903
Email: info@design-infinity.com

PARADYM - OPUS TOWER

DI/JS//2024/R0 **Date 31/10/2024**

Item	DESCRIPTION	Qty	Unit	Amount (Dhs.)	TOTAL (Dhs.)
6.02	Supply & install of 60 minutes FR wooden door made in wood frame & architrave . Shutter to have 54 mm thk flush door shutter in both side in PU finish. Size: 1000mmL x 2200 mm Ht Location :Server room	1	Nos	5,279.00	5,279.00
	TOTAL- DOORS				**22,408.00**
	Note : Entrance door will be keeping as it is				
7	**JOINERY WORKS**				
7.01	**PANTRY COUNTER**, bottom and top full ht unit made of MR MDF green PU paint finish shutter and laminated MDF carcass and the counter made of white marble top (PC rate- 350AED/Sqm) Size-6900x600x800 mm HT + 2430x400x1800 mm ht.	1	No.	24,801.00	24,801.00
7.02	**PANTRY ISLAND UNIT** made of MDF PU paint flutted end panel with facia white sticher finish and counter top in white marble finish (PC Rate- 350AED/Sqm) Size-3900 x600x9000mm ht.	1	Nos.	13,111.00	13,111.00
7.03	**BANQUETTE SEATING** made of MDF Veneer finish base and upholstered seating (Fabric pc rate- 100AED/Lm) . Size-8000x600x450/800mm ht.	1	No.	24,820.00	24,820.00
7.04	**TV WALL I** , made of MDF Veneer finish wall cladding with necessary wooden backing including TV metal support. Size-1500x150x2400 mm ht. Near Collab & Dining	1	No.	4,642.00	4,642.00
7.05	**TV WALL II** , made of MDF Veneer flutted design finish wall cladding with necessary wooden backing including TV metal support. Size-3650x150x2400 mm ht. Location - Board Room	1	No.	9,748.00	9,748.00
#REF!	**STORAGE** made of MDF veneer shutter with laminated MDF carcass . Size -1000x600x2400mm ht. Location - Print Station.	1	No.	3,965.00	3,965.00

Design Infinity LLC
Interior Turnkey Solutions
Beyond Imagination ...
P. O. Box. 62522 | Dubai | UAE
Tel: +971 4 3795902
Fax: + 971 4 3795903
Email: info@design-infinity.com

PARADYM - OPUS TOWER

DI/JS//2024/R0 **Date 31/10/2024**

Item	DESCRIPTION	Qty	Unit	Amount (Dhs.)	TOTAL (Dhs.)
#REF!	**SEATING** made of metal base with upholstered seating fabric PC rate considered- 100AED/LM. Size 1200x600x450/400mm ht. Location - Phone Booth.	2	No.	3,972.00	7,944.00
#REF!	**SEATING II** made of metal base with upholstered seating fabric PC rate considered- 100AED/LM. Size 1600x600x450/400mm ht. Location - Focus Booth.	1	No.	4,096.00	4,096.00
#REF!	**DISPLAY UNIT WITH STORAGE** made of MDF veneer bottom unit with top open shelves in MDF veneer with glass . Size 4100x600x800mm ht. + 4150x350x1800 mm HT Location -Closed office 2 pax.	1	No.	23,138.00	23,138.00
#REF!	**TABLE LEDGE** made of MDF PU paint table top with bottom MDF PU paint design panel Size - 4150x500x750/50 mm HT.	1	No.	8,687.00	8,687.00
					124,952.00
8	**LIGHTING WORKS.**				
	Supply of Light fittings / fixtures as per received proposed drawings / all in accordance with design visual :				
8.01	LT-01 - Recessed Led linear light (light source)	14	Mtrs	335.00	4,690.00
8.02	LT-02 - Suspended Led linear light	6	Mtrs	451.00	2,706.00
8.03	LT-03 - Recessed twin light	25	Nos	335.00	8,375.00
8.04	LT-05 - Decortaive pendant lights	3	Nos	773.00	2,319.00

Design Infinity LLC
Interior Turnkey Solutions
Beyond Imagination ...
P. O. Box. 62522 | Dubai | UAE
Tel: +971 4 3795902
Fax: + 971 4 3795903
Email: info@design-infinity.com

PARADYM - OPUS TOWER

DI/JS//2024/R0 **Date 31/10/2024**

Item	DESCRIPTION	Qty	Unit	Amount (Dhs.)	TOTAL (Dhs.)
8.05	LT-07 - Cylindrical light surface mounted/ suspended	20	Nos	335.00	6,700.00
8.06	LT-08 - Led downlight	6	Nos	142.00	852.00
8.07	LT-09 - Led striplight 	100	Mtrs	84.00	8,400.00
8.08	LT-10 - Decortaive hanging light 2.5m 	1	Nos	2,575.00	2,575.00
	SUB TOTAL-LIGHTING WORKS				**36,617.00**
9	**ELECTRICAL POWER WORKS.**				
	Power distribution SMDB / DB works:				
9.1	Modification of existing **DB**	1	Nos	3,219.00	3,219.00
	Power cabling works :				
9.2	4C x 35mm XLPE/SWA/PVC+1C x 16 mm ECC from new SMDB to DB-01			-	N/A
	Cable tray and trunking works for Power cables:				
9.21	Modification of existing cable tray for incoming power cables	1	Item	-	-
9.22	Modification of existing cable tray for the **Data cables** from IT cabinet at High level.	1	Item	-	-
9.23	Modification of existing cable trunking for **Power** distributions at **high level**.	1	Item	10,944.00	10,944.00
9.24	Modification of existing cable trunking for **Power** distributions at **low level**.	1	Item	-	-
9.25	Modification of existing cable trunking for **Light** distributions at **high level.**	1	Item	-	-
9.26	Supply and installation of cable trunking for **ELV** distributions at **high level.**	1	Item	-	-
9.3	**Light Installation works**				
9.31	Supply and installation of Conduit and wiring for the light fixtures	100	Nos	181.00	18,100.00

Design Infinity LLC
Interior Turnkey Solutions
Beyond Imagination ...
P. O. Box. 62522 | Dubai | UAE
Tel: +971 4 3795902
Fax: + 971 4 3795903
Email: info@design-infinity.com

PARADYM - OPUS TOWER

DI/JS//2024/R0 **Date 31/10/2024**

Item	DESCRIPTION	Qty	Unit	Amount (Dhs.)	TOTAL (Dhs.)
9.32	Supply and installation of Conduit and wiring for the Strip light	100	Mtr	58.00	5,800.00
9.33	Installation of technical light fixtures	96	Nos	39.00	3,744.00
9.34	Installation of LED strip lights	100	Mtr	33.00	3,300.00
9.35	Installation of Magnetic tracks	20	Mtr	20.00	400.00
9.36	Installation of Pendant lights	4	Nos	78.00	312.00
9.37	Removal and relocation of existing lights	25	Nos	219.00	5,475.00
9.4	**Switches Installation & Supply of lighting control system works:**			-	-
9.41	Supply and installation of **1 Gang 1 Way** Switch *Brand : Schneider/ MK/ equivalent* *Finishes: PVC finish*	5	Nos	181.00	905.00
9.42	Supply and installation of **2 Gang 1 Way** Switch *Brand : Schneider/ MK/ equivalent* *Finishes: PVC finish*	3	Nos	206.00	618.00
9.43	Supply and installation of **3 Gang 1 Way** Switch *Brand : Schneider/ MK/ equivalent* *Finishes: PVC finish*	2	Nos	239.00	478.00
9.44	Supply and installation of **8/12 gang 1 Way** Switch *Brand : LG/ MK/ equivalent* *Finishes: PVC finish*	2	Nos	1,095.00	2,190.00
9.5	**Power Sockets Installation works**			-	-
9.51	Supply & installation of **13A Single power** socket with necessary conduiting, wiring and accessories. *Brand : Schneider/ MK/ equivalent* *Finishes: PVC Finish*	8	Nos	335.00	2,680.00
9.52	Supply & installation of **13A twin power** socket with necessary conduiting, wiring and accessories for TVs(3) Amplifier(1), LED video wall controllers *Brand : Schneider/ MK/ equivalent* *Finishes: PVC Finish*	15	Nos	361.00	5,415.00
9.53	Supply & installation of **FB2** Three Compartment Floor box, including wiring and PVC coated GI flexibles / PVC flexibles Config: 2 Nos. - 13A Twin Socket outlets, spaces for 2 nos. data outlets. *Brand : MK/ equivalent*	6	Nos	760.00	4,560.00
9.54	Relocation of exsting Floor box	13	Nos	515.00	6,695.00

Design Infinity LLC
Interior Turnkey Solutions
Beyond Imagination ...
P. O. Box. 62522 | Dubai | UAE
Tel: +971 4 3795902
Fax: + 971 4 3795903
Email: info@design-infinity.com

PARADYM - OPUS TOWER

DI/JS//2024/R0 **Date 31/10/2024**

Item	DESCRIPTION	Qty	Unit	Amount (Dhs.)	TOTAL (Dhs.)
9.55	Supply and installation of **15A Single** sockets with necessary wiring and conduiting for Kitchen equipments - Fridge	1	Nos	387.00	387.00
9.56	Supply and installation of **3Ph Isolator** sockets with necessary wiring and conduiting for Kitchen equipments - Coffee machine	1	Nos	1,545.00	1,545.00
9.57	Supply and installation of **13A switched fused spur outlet** including containment and wiring for FACP, 24/7 DCD panel, Emergency panel.	3	Nos	387.00	1,161.00
9.58	Supply and installation of **20A DP switched outlet** including containment and wiring for Water heater	1	Nos	490.00	490.00
9.59	Allow cost for power supply for **FCUs**	4	Nos	387.00	1,548.00
9.6	Allow cost for power supply for **VAVs**	2	Nos	387.00	774.00
9.61	Allow cost for power supply for exhaust fan	1	Nos	387.00	387.00
				-	-
9.6	**Power Sockets Installation works**			-	-
9.61	Supply and installation of PVC Conduit for **IT Data** points	25	Nos	116.00	2,900.00
9.62	Supply and installation of PVC Conduit for **HDMI** points	6	Nos	155.00	930.00
9.63	Supply and installation of PVC Conduit for **Access** points	2	Nos	155.00	310.00
9.64	Supply and installation of PVC Conduit for **Wi-fi** points	5	Nos	116.00	580.00
9.65	Supply and installation of PVC Conduit for **Camera**	6	Nos	116.00	696.00
9.66	Supply and installation of PVC Conduit for **AV** works like speakers, Projectors, Room booking system etc.	20	Nos	116.00	2,320.00
9.67	PVC Conduiting works involved in carrying **Fiber optic** cabling Works from building IT room to proposed premises.	1	Item	773.00	773.00
9.7	**Sundries**				
9.71	Allow for **testing and commissioning** of electrical services (Any 3rd party testing and certifications excluded)	1	Item	644.00	644.00
9.72	Allow for documents submissions like shop drawings, As-built **drawings,** operating instructions and maintenance manuals **(O&Ms**) as per built specifications.	1	Item		Included

Design Infinity LLC
Interior Turnkey Solutions
Beyond Imagination ...
P. O. Box. 62522 | Dubai | UAE
Tel: +971 4 3795902
Fax: + 971 4 3795903
Email: info@design-infinity.com

PARADYM - OPUS TOWER

DI/JS//2024/R0 **Date 31/10/2024**

Item	DESCRIPTION	Qty	Unit	Amount (Dhs.)	TOTAL (Dhs.)
9.73	**Civil works** related with MEP works such as chasing and chipping on wall and floor, Wall & ceiling cutting for services to install and making ready to receive final finishes, AC grill cutting and its related finishing civil works etc.	1	Item	1,288.00	1,288.00
9.74	Allow for identification **labels** including plates, discs, labels, charts and color coding for electrical services.	1	Item	-	Included
9.75	Co-ordination charges for DEWA approvals	1	Item	1,932.00	1,932.00
	SUB TOTAL-ELECTRICAL WORKS				**93,500.00**
10	**HVAC WORKS**				
10.1	Modification of existing PI rectangular duct work with necessary fittings and accessories for the for Supply Air Ducting	60	Sq.M	206.00	12,360.00
10.11	Modification of existing GI Duct work with necessary fittings and accessories for the fresh air system.	20	Sq.M	232.00	4,640.00
10.12	Supply & installation of VAV with thermostat for the Board room & Meeting room (BMS Not considered)	2	Nos	3,026.00	6,052.00
10.13	Supply and installation of VCDs with necessary fittings and accessories	40	Nos	116.00	4,640.00
10.14	Supply and installation of flexible duct including necessary fixtures	30	Nos	8,575.00	8,575.00
10.15	Supply and installation of Plenum box including necessary fixtures	36	Sqm		
10.16	Supply and installation of Linear diffuser for Supply/Return with necessary supports and accessories	60	Mtr	232.00	13,920.00
10.17	Supply and installation of Round diffuser for Supply air for Open ceiling area with necessary supports and accessories	10	Nos	322.00	3,220.00
10.18	Supply and installation of Fresh Air Bellmouth with necessary supports and accessories	1	Item	464.00	464.00
10.19	Air Balancing for the FCU (Consider Existing FCU will be retained in the same location)	1	Item	3,219.00	3,219.00

Design Infinity LLC
Interior Turnkey Solutions
Beyond Imagination ...
P. O. Box. 62522 | Dubai | UAE
Tel: +971 4 3795902
Fax: + 971 4 3795903
Email: info@design-infinity.com

PARADYM - OPUS TOWER

DI/JS//2024/R0 **Date 31/10/2024**

Item	DESCRIPTION	Qty	Unit	Amount (Dhs.)	TOTAL (Dhs.)
	Note : 1. Any modification to the existing Chilled water/Condensate pipe not considered 2. Individual AC control considered only for Board room & meeting room				
	SUB TOTAL-HVAC WORKS				**57,090.00**
11	**CIVIL DEFENCE WORKS**				
11.1	**FIRE ALARM WORKS**				
11.11	Supply and installation of New FACP for the space **Note : Existing to be reused**	1	Nos	15,450.00	RATE ONLY
11.12	Supply and Installation of new addressable optical **smoke** detectors with built in isolator base.	10	Nos	1,005.00	10,050.00
11.13	Relocation of existing Smoke detectors	8	Nos	515.00	4,120.00
11.14	Supply and Installation of new addressable optical **Heat** detectors with built in isolator base.	1	Nos	1,005.00	1,005.00
11.15	Supply and Installation of Addressable **Void** smoke detector				N/ A
11.16	Supply and Installation of new **remote indicators** for Void smoke detector				N/A
11.17	Supply & Installation of Addressable **break glass / Manual call point** with cover	1	Nos	1,005.00	1,005.00
11.18	Supply & Installation of Addressable **sounder / Flasher**	6	Nos	1,005.00	6,030.00
11.19	Supply and Installation of Interface module with Necessary Wiring and accessories for interfacing with Music system, Access door(2), Building FACP(2), SIV(1)	2	Nos	1,417.00	2,834.00
11.2	Supply and Installation of IFU with Necessary Wiring and accessories for DCD panel	1	Item	1,417.00	1,417.00
11.21	Testing & Re-Programming of fire alarm panel	1	Item	7,725.00	7,725.00
11.22	Disconnection and Connection charges to building Main FACP	1	Item	1,932.00	1,932.00
11.23	Relocation of existing ceiling speakers & Fire devices	1	Item	1,933.00	1,933.00
11.2	**EMERGENCY AND EXIT LIGHT WORKS**				
11.21	Supply & Installation of Self Contained New Emergency with necessary wiring and accessories	13	Item	773.00	10,049.00

Design Infinity LLC
Interior Turnkey Solutions
Beyond Imagination ...
P. O. Box. 62522 | Dubai | UAE
Tel: +971 4 3795902
Fax: + 971 4 3795903
Email: info@design-infinity.com

PARADYM - OPUS TOWER

DI/JS//2024/R0 **Date 31/10/2024**

Item	DESCRIPTION	Qty	Unit	Amount (Dhs.)	TOTAL (Dhs.)
11.22	Relocation of exiting Emergency light	2	Nos	773.00	1,546.00
11.23	Supply & Installation of New Self-contained Exit Light with necessary wiring and accessories	1	Nos	837.00	837.00
11.24	Supply & Installation of New Self-contained Directional Exit Light with necessary wiring and accessories	2	Nos	741.00	1,482.00
11.25	Supply & Installation of New Emergency Monitoring Panel	1	Nos	8,369.00	RATE ONLY
11.3	**FIRE FIGHTING WORKS**				
11.31	Supply & installation pendent sprinkler with associated pipe and fittings.	23	Nos	741.00	17,043.00
11.32	Relocation of existing Sprinklers	12			N/A
11.33	Supply & installation of upright sprinkler with associated pipe and fittings.		Set	-	-
11.34	Supply & installation of 6 kg DCP fire extinguisher	1	Set	309.00	309.00
11.35	Supply & installation of 5 kg CO2 fire extinguisher	1	Nos	232.00	232.00
11.36	Supply & installation of fire blanket	1	LS	194.00	194.00
11.37	Charges for Zone control valve closing and pressure test	1	Item	3,219.00	3,219.00
11.38	Pressure testing	1	Item	4,507.00	4,507.00
	TOTAL FOR CIVIL DEFENCE WORK				**77,469.00**
13	**LOOSE FURNITURE**				
1	Installation,Programming and Testing Commissioning Charges	1	Nos	183,402.00	183,402.00
	TOTAL-LOOSE FURNITURE WORKS				**183,402.00**

Design Infinity LLC
Interior Turnkey Solutions
Beyond Imagination ...
P. O. Box. 62522 | Dubai | UAE
Tel: +971 4 3795902
Fax: + 971 4 3795903
Email: info@design-infinity.com

PARADYM - OPUS TOWER

DI/JS//2024/R0 **Date 31/10/2024**

Item	DESCRIPTION	Qty	Unit	Amount (Dhs.)	TOTAL (Dhs.)
	SUMMARY				
1	PRELIMINERIES				55,000.00
2	CIVIL WORKS				30,900.00
3	FLOOR FINISHES				56,485.00
4	CEILING FINISHES				39,338.00
5	WALLS & WALL FINISHES				114,527.00
6	DOORS				22,408.00
7	JOINERY WORKS				124,952.00
8	LIGHTING WORKS.				36,617.00
9	ELECTRICAL WORKS				93,500.00
10	HVAC WORKS				57,090.00
11	CIVIL DEFENCE WORK				77,469.00
12	LOOSE FURNITURE				183,402.00
				TOTAL	**891,688.00**

CONTACT PERSON

SHOAIB ANSARI
BUSINESS DEVELOPMENT MANAGER

CONTACT DETAILS:

T: 04 379 5902

M: 055 375 41 69

E: shoaib@design-infinity.com

DUBAI (HEAD OFFICE) ADDRESS:
UNIT 201-203, 212-213 & 301-303
HAMSAH BUILDING, O-BLOCK
PO BOX 62522, AL KARAMA
DUBAI, UNITED ARAB EMIRATES
T: 04 379 5902

DUBAI BRANCH – OFFICE & WAREHOUSE
JOINERY, GLASS & METAL DIVISION
DUBAI INVESTMENT PARK 2
PLOT NUMBER: 597-813
TEL: 971 4 321 6946

ABU DHABI OFFICE
OFFICE NO. M1, P/181 BUILDING
PO BOX 62560, AL MUROOR
ABU DHABI, UNITED ARAB EMIRATES
T: 02 448 2286

WWW.DESIGN-INFINITY.COM