PROPOSED INTERIOR FITOUT WORKS FOR

ELECTROLUX MIDDLE EAST

29th FLOOR-FORTUNE TOWER, JLT, DUBAI - UAE

Interiors

04.08.2025

DATE : 04/08/2025

Subject : Commercial Proposal for Interior Fit-out works

PROJECT : PROPOSED INTERIOR FITOUT WORKS FOR ELECTROLUX MIDDLE EAST
29TH FLOOR, FORTUNE TOWER, JLT - DUBAI UAE

We are pleased to present our proposal for your review against the Fit-out works for **ELECTROLUX MIDDLE EAST 29TH FLOOR, FORTUNE TOWER, JLT - DUBAI, UAE.** Please find herewith our competitive offer as per the attached bill of quantities amounting as below.

GRAND TOTAL FROM SUMMARY		**1,628,949.63**
	VAT 5%	**81,447.48**

Completion : to be discussed.

Validity : 20 days from the date above.

Payment terms :
50% Advance payment
40% Progress payment
10% on Completion

Notes & exclusion –As per Notes and exclusions sheet.

Thank you for the opportunity to participate in this tender. If you have any questions, please don't hesitate to get in contact with us. we hope our offer is in line with your requirement and look forward to working
with you directly.

Thank you and best regards,

Chris Service
Managing Director | CS Interiors

DATE : 04/08/2025

Subject : Commercial Proposal for Interior Fit-out works

PROJECT : PROPOSED INTERIOR FITOUT WORKS FOR ELECTROLUX MIDDLE EAST

NOTES AND EXCLUSIONS

General Notes

1 Submitted BOQ is based on the layout, site visit & instructions

2 Any changes to the work, pertaining to the instructions from mall management/authorities/employer will have an additional cost implication and to be agreed upon finalizing of details.

Exclusions

1 Any scope related to non scope of areas.

2 Any scope not mentioned in BOQ

Interiors

PROPOSED INTERIOR FITOUT WORKS FOR ELECTROLUX MIDDLE EAST
29TH FLOOR, FORTUNE TOWER, JLT - DUBAI UAE

		04/08/2025
Sl NO.	**DESCRIPTION**	**AMOUNT**
1	PRELIMINARIES	94,550.00
2	CIVIL WORKS	38,073.00
3	FLOOR FINISH	62,078.00
4	WALLS AND WALL FINISHES	79,567.07
5	CEILING FINISHES	63,410.40
6	GLAZING WORKS	76,759.16
7	SANITARY FITTINGS & FIXTURES	23,618.00
8	WINDOW BLINDS	15,015.00
9	IT WORKS	12,000.00
10	PANTRY APPLIANCES AND FITTINGS	10,476.00
11	MISCELLANEOUS	53,148.00
12	LIGHT FITTINGS	47,864.00
13	LOOSE FURNITURE	150,677.00
14	JOINERY WORKS	426,350.00
15	MEP WORKS	475,364.00
	TOTAL (EXCLUDING VAT)	**1,628,949.63**
	VAT 5%	**81,447.48**

PROPOSED INTERIOR FITOUT WORKS FOR ELECTROLUX MIDDLE EAST
29TH FLOOR, FORTUNE TOWER, JLT - DUBAI UAE

04/08/2025

Sl No	Item Description	Qty	Unit	Rate	Amount
1.00	**PRELIMINARIES**				
1.01	**SITE MANAGEMENT** Provision for site management, including staff and facilities necessary for the efficient execution and supervision of the works.	1	Item	48,000.00	48,000.00
1.02	**MOBILIZATION & DEMOBILIZATION** Allow sum for mobilization & demobilization including supply and installation of temporary DB, Hoarding, adequate lighting, fire fighting equipment / extinguishers, cleaning / clearing of site on daily basis & upon project completion and provision for protection of finished goods, site safety, First Aid kits as well as security.	1	Item	5,850.00	5,850.00
1.03	**AUTHORITY APPROVALS** Obtaining and maintaining necessary permits, licenses, and approvals from relevant authorities throughout the duration of the project. (All kind of payments and security deposits have been considered separately under below item a, b & c)	1	Psum	26,500.00	26,500.00
a	Fees for local authority approvals for complete approval process from Civil defence, Tecom, DEWA and Dubai municipality.	1	Item	-	**By Client**
b	Payment and security deposit to Building management(If Required)	1	Item	-	**By Client**
c	Allow sum for building management approval-fees for drawing approvals as listed in the tenants manual.	1	Item	-	**By Client**
1.04	**INSURANCE** Provision of all required insurance policies, including but not limited to public liability, employer's liability, and contract works insurance, as per the contract requirements.	1	Item	2,500.00	2,500.00
1.05	**HEALTH & SAFETY PROTECTION** Implementation of health and safety measures, including site inductions, provision of personal protective equipment (PPE), first aid facilities, fire prevention equipment, and site security measures in accordance with applicable regulations and standards.	1	Item	2,000.00	2,000.00
1.06	**SITE CLEARANCE** Site clearing, removal of construction debris from time to time including the disposal of waste materials in accordance with legal requirements and best practices.	1	Item	3,200.00	3,200.00
1.07	**TEMPORARY WATER & ELECTRICITY** Provision and maintenance of temporary water and electricity supplies for the site, including connections, distribution, and metering, as required for the construction works.	1	Item	-	**By Client**
1.08	**SHOP DRAWING** Preparation, submission, and coordination of detailed architectural and MEP shop drawings in accordance with the design specifications and applicable standards, incorporating any revisions and obtaining necessary approvals from the relevant authorities and consultants.	1	Item	2,500.00	2,500.00
1.09	**SCAFFOLDING** Movable scaffolding provided for this project.	1	Item	2,000.00	2,000.00
1.10	**FINAL CLEANING** Carrying out a thorough final cleaning of the entire project site, including the removal of construction debris, dust, and any leftover materials. The cleaning process should cover all internal and external areas, ensuring that the completed facility is in a clean and presentable condition, ready for handover to the client.	1	Item	2,000.00	2,000.00
				SUB TOTAL CARRIED TO SUMMARY	**94,550.00**

PROPOSED INTERIOR FITOUT WORKS FOR ELECTROLUX MIDDLE EAST
29TH FLOOR, FORTUNE TOWER, JLT - DUBAI UAE

04/08/2025

Sl No	Item Description	Qty	Unit	Rate	Amount
2.00	**CIVIL WORKS**				
2.01	**Waterproofing:** Supply and installation of Cementitious Water proofing. Location: Pantry and Toilets	83	Sqm	74.00	6,142.00
2.02	**Floor Modification:** Modification of existing floor (Where the new floor boxes installation)	1	Lsum	2,000.00	2,000.00
2.03	**Demolition** Provision for removal of the existing ceiling, existing Joinery elements, existing partitions and existing sanitaryware.				
a	Toilet floor and wall tiles	68	Sqm	27.00	1,836.00
b	Skirting	40	Lm	14.00	560.00
c	Ceiling tiles	409	Sqm	27.00	11,043.00
d	Partition with wall tiles	271	Sqm	34.00	9,214.00
e	Glass partition for toilet	1	Lsum	534.00	534.00
f	Joinery Elements	1	Lsum	1,534.00	1,534.00
g	Sanitary fixture	1	Lsum	534.00	534.00
h	Wooden & glass Doors	14	Nos.	334.00	4,676.00
				SUB TOTAL CARRIED TO SUMMARY	**38,073.00**
3.00	**FLOOR FINISH**				
3.01	**Screed** Supply and installation of 100mm ht Concrete screed to receive final floor finishes. Location: Toilets	24	Sqm	94.00	2,256.00
3.02	**LVT Flooring** Supply and installation of LVT flooring including the glue or other fixing materials as per requirement to be install on top of the existing floor tile. Location: Meeting rooms, Pantry, Reception, GM room and Passage area	132	Sqm	131.00	17,292.00
3.03	**Carpet Flooring** Supply and installation of 50 X 50 carpet tile flooring including underlay, adhesives, and other fixing accessories as per the requirement to be install on top of the existing floor tile. Location: Workstation areas, Hot desk area, Server room, Store room and Focus POD	171	Sqm	147.00	25,137.00
3.04	**Tile Flooring** Supply and Installation of 60 x 60 Porcelain Tile Flooring with adhesive, grout and other necessary accessories. Location: Toilets	35	Sqm	183.00	6,405.00
3.05	**Tile Flooring** Supply and Installation of Porcelain Tile Flooring with adhesive, grout and other necessary accessories. Location: Window Step areas	20	Sqm	202.00	4,040.00
3.06	**Threshold** Supply and installation of Threshold. Location : Toilets, Server Room & Store Room	4	Nos	267.00	1,068.00
3.07	**Transition Strip** Supply and installation of transition strip in SS finish. Location : Between different floor finishes	49	Lm	120.00	5,880.00
				SUB TOTAL CARRIED TO SUMMARY	**62,078.00**

	PROPOSED INTERIOR FITOUT WORKS FOR ELECTROLUX MIDDLE EAST 29TH FLOOR, FORTUNE TOWER, JLT - DUBAI UAE				
					04/08/2025
Sl No	**Item Description**	**Qty**	**Unit**	**Rate**	**Amount**
4.00	**WALLS AND WALL FINISHES**				
4.01	**Skirting:** Supply and installation of 100mm thick waterproof composite skirting, painted to the desired color. All work will be executed in compliance with industry standards and manufacturer's recommendations.	235.1	Rm	47.00	11,049.70
4.02	**Gypsum Board Partition** Supply & installation of 100mm thick normal gypsum board partition for the proposed partition as shown in the layout including 0.5 mm thk G.I. Studs, Rockwool insulation, to minimize the sound transmission and improve the quality of the sound proofing with-in the room. Location: As per the proposed layout	138.75	Sqm	140.00	19,425.00
4.03	**Fire-rated Gypsum Board Partition** Supply & installation of 150mm thick fire rated gypsum board partition for the proposed partition as shown in the layout including 0.5 mm thk G.I. Studs, Rockwool insulation, to minimize the sound transmission and improve the quality of the sound proofing with-in the room. Location: Server Room	29.1	Sqm	160.00	4,656.00
4.04	**Cement Board Partition** Supply & installation of 100mm thick cement board partition for the proposed partition as shown in the layout. Location: Toilet Area	51	Sqm	174.00	8,874.00
4.05	**Porcelain Wall Tiles** Supply & Installation of 60 x 60 Porcelain wall tiles including the glue or other fixing materials as per requirement. Location: Toilets	88	Sqm	183.00	16,104.00
4.06	**Green wall** Provision for supply and installation green wall as per required. Location: To be confirmed (Reception back wall, GM Cabin and Step seating area back wall)	30	Sqm	134.00	4,020.00
4.07	**Gypsum Baffle:** Supply & installation of gypsum Baffle over glass (300mm) partition with necessary fittings. Location : Above the glass partition	21.6	Rm	103.00	2,224.80
4.08	**Fenomastic Wall Paint:** Supply and apply of Jotun fenomastic Wall paint inlcuding the base coats. Location: All area walls except the board rooms, GM room walls and Toilet walls	412.924	Sqm	32.00	13,213.57
				SUB TOTAL CARRIED TO SUMMARY	**79,567.07**

	PROPOSED INTERIOR FITOUT WORKS FOR ELECTROLUX MIDDLE EAST 29TH FLOOR, FORTUNE TOWER, JLT - DUBAI UAE				
					04/08/2025
Sl No	**Item Description**	**Qty**	**Unit**	**Rate**	**Amount**
5.00	**CEILING FINISHES**				
5.01	**Plain Gypsum Ceiling** Supply and installation of 12.5mm thick ordinary gypsum board false ceiling on GI suspension system. Location: Reception, Meeting rooms, Server room, Focus POD, GM room and Store room	140.1	Sqm	127.00	17,792.70
5.02	**MR Gypsum Ceiling** Supply and installation of 12.5mm thick MR gypsum board false ceiling on GI suspension system. Location: Toilets & Pantry	29	Sqm	140.00	4,060.00
5.03	**Light Cove** Supply & installation of gypsum board straight/curved light cove including necessary internal frame works at Reception waiting lounge area. Location **:** GM Cabin and Focus POD	57.3	Rm	100.00	5,730.00
5.04	**Ceiling Paint:** Supply and application of Jotun fenomastic Ceiling paint inlcuding the base coats. Location: Gypsum ceilings	169.1	Sqm	32.00	5,411.20
5.05	**Open Ceiling Paint:** Supply and application of fenomastic spray paint on slab with necessary base coats. (Including MEP services) Location: Workstations, Pantry, and Reception	239.5	Sqm	67.00	16,046.50
5.06	**Rockwool** Supply and Installation of rockwool on the slab sofit. Location: Workstations, Pantry, and Reception	239.5	Sqm	60.00	14,370.00
				SUB TOTAL CARRIED TO SUMMARY	**63,410.40**

PROPOSED INTERIOR FITOUT WORKS FOR ELECTROLUX MIDDLE EAST
29TH FLOOR, FORTUNE TOWER, JLT - DUBAI UAE

04/08/2025

Sl No	Item Description	Qty	Unit	Rate	Amount
6.00	**GLAZING WORKS**				
6.01	**Glazed Partition** Supply and install Single Glazed partitions using 12mm thick normal clear tempered glass panel in Tape glass to glass joints. Comprising of channels: 26x26mm top, bottom and wall aluminium channels. All aluminium sections in Standard Powder Coated finish. Location: As per the proposed layout	51.84	Sqm	467.00	24,209.28
6.02	**Normal Glass Door:** Supply and installation of Framed Single Leaf Swing glass door using 12mm thk clear tempered glass with necessary fittings , ironmongeries and handle. Door Size : 1000mmL x 2200mmH Location : As per the proposed layout	5	Nos	3,267.00	16,335.00
6.03	**Acoustic Glass door:** Supply and installation Framed Axile Clarity single glazed swing door in 12mm thick normal clear tempered glass door panel with complete ironmongeries and accessories including Standard 600mm long non lockable H type pull handle. All aluminium door frame and hardware's are in Standard Powder Coated Finish. (Upto 32 dB) Door Size : 1000mmL x 2200mmH Location : PODS	2	Nos	7,334.00	14,668.00
6.04	**Bifolding Glass Door:** Supply and installation of bifolding glass door (4 leaf) using 12mm thk clear tempered glass with necessary fittings and ironmongeries. Door Size : 3600mmL x 2400mmH Location : As per the proposed layout	1	Psum	16,000.00	16,000.00
6.05	**Manifestation on Glass Partition** Supply and installation of manifestation bands on glass partition. Location : Glass partitions (Full height)	51.84	Sqm	107.00	5,546.88
				SUB TOTAL CARRIED TO SUMMARY	**76,759.16**
7.00	**SANITARY FITTINGS & FIXTURES**				
7.01	Wall mounted WC with seat cover	3	Nos	2,875.00	8,625.00
7.02	Cistern and Flush plate				
7.03	Shattaf	3	Nos	232.00	696.00
7.04	Toilet roll holder	3	Nos	175.00	525.00
7.05	Wash basin	3	Nos	525.00	1,575.00
7.06	Wash basin mixer	3	Nos	1,194.00	3,582.00
7.07	Hand Dryer	3	Nos	2,257.00	6,771.00
7.08	Floor drain	3	Nos	175.00	525.00
7.09	Pantry sink	1	Nos	950.00	950.00
7.10	Sink mixer	1	Nos	369.00	369.00
				SUB TOTAL CARRIED TO SUMMARY	**23,618.00**
8.00	**WINDOW BLINDS**				
8.01	**Manual Blinds** Supply and installation of manually operated window blinds.	1	Psum	15,015.00	15,015.00
				SUB TOTAL CARRIED TO SUMMARY	**15,015.00**
9.00	**IT WORKS**				
9.01	**CCTV, Wifi, Telephones and Access control** Provision for the IT works.	1	Psum	12,000.00	12,000.00
				SUB TOTAL CARRIED TO SUMMARY	**12,000.00**

	PROPOSED INTERIOR FITOUT WORKS FOR ELECTROLUX MIDDLE EAST 29TH FLOOR, FORTUNE TOWER, JLT - DUBAI UAE				
					04/08/2025
Sl No	**Item Description**	**Qty**	**Unit**	**Rate**	**Amount**
10.00	**PANTRY APPLIANCES AND FITTINGS**				
	White goods Supply & installation of White Goods or equivalent kitchen appliances as per the design				
10.01	Microwave Oven	1	Item	400.00	400.00
10.02	Coffee machine	1	Item	3,292.00	3,292.00
10.03	Fridge	1	Item	2,386.00	2,386.00
10.04	Water dispenser	3	Item	1,466.00	4,398.00
				SUB TOTAL CARRIED TO SUMMARY	**10,476.00**
11.00	**MISCELLANEOUS**				
11.01	**Signage** Provision for supply and installation of signage as per renders for client's approval. Location **:** To be confirmed by the client	1	Psum	15,000.00	15,000.00
11.02	**HPL DOOR + PANEL** Provision for Supply and installation of 12mm thk HPL door and panel with divider complete with necessary fittings and accessries. Location **:** Gents & Ladies Toilet	1	Psum	15,550.00	15,550.00
11.03	**Artificial Plants and Planter box** Provision for supply and installation of Artificial plants and Planter boxes as per required. - Butterfly palm-2 nos; dragon tree- 4 nos; peace lily-4 nos. Location: To be confirmed by the client	1	Psum	15,000.00	15,000.00
11.04	**TV** Supply & Installation of 55" Samsung TV. Location : 6 pax meeting rooms and 8 pax meeting rooms	3	Nos	1,600.00	4,800.00
11.05	**TV** Supply & Installation of 43" Samsung TV. Location : 5 pax meeting room and GM room	2	Nos	1,399.00	2,798.00
				SUB TOTAL CARRIED TO SUMMARY	**53,148.00**
	TOTAL AMOUNT				**528,694.63**

PROPOSED INTERIOR FITOUT WORKS AT ELECTROLUX
DUBAI, UAE

04/08/2025

Sl NO.	DESCRIPTION	IMAGES	QTY	UNIT	RATE	AMOUNT
	LIGHT FITTINGS					
1.00	Description :Track Mounted Light none dimmable Wattage :10w Brand- Luz Finish - black / white		8	Nos	222.00	1,776.00
2.00	Track Mounted Light none dimmable Wattage :10w Brand- Luz Finish - black / white		15	Nos	222.00	3,330.00
3.00	Magnetic Track Brand- Luz Finish - black / white		25	Lm	136.00	3,400.00
4.00	Trimless spot light Cc-3000k Ip44 Watts-6-9w Lumen-100lm/w Cri-90 (tl m) Dia-75mm Ctout-70mm Finish-black / white Voltyag-220-240vac		84	Nos	138.00	11,592.00

PROPOSED INTERIOR FITOUT WORKS AT ELECTROLUX
DUBAI, UAE

04/08/2025

Sl NO.	DESCRIPTION	IMAGES	QTY	UNIT	RATE	AMOUNT
5.00	LED Round Downlight		12	Nos	458.00	5,496.00
6.00	pendant light		8	Nos	429.00	3,432.00
7.00	Decorative pendant light light Size - 12000mm Dia		2	Nos	4,429.00	8,858.00
8.00	Decorative liner light Size - 1000mm L		2	Nos	3,286.00	6,572.00
9.00	Table Lamp		2	Nos	443.00	886.00
10.00	Wall Light		2	Nos	286.00	572.00
11.00	Led Strip light		30	Rm	65.00	1,950.00

Please note, This Price will vary based on the final design, material selection and Final quantity To be confirmed.

	SUB TOTAL CARRIED TO SUMMARY	**47,864.00**

PROPOSED INTERIOR FITOUT WORKS FOR ELECTROLUX MIDDLE EAST
29TH FLOOR, FORTUNE TOWER, JLT - DUBAI UAE

04/08/2025

S/N	DESCRIPTION		QTY	UNIT	RATE	AMOUNT
13.00	**LOOSE FURNITURE**					
13.01	**6 PAX MEETING ROOM TABLE**		2	Nos	3,000.00	6,000.00
13.02	**6 PAX MEETING ROOM CHAIR**		12	Nos	643.00	7,716.00
13.03	**5 PAX MEETING ROOM TABLE**		1	Nos	2,000.00	2,000.00
13.04	**5 PAX MEETING ROOM CHAIR**		5	Nos	1,215.00	6,075.00
13.05	**8 PAX MEETING ROOM TABLE**		1	Nos	2,572.00	2,572.00
13.06	**8 PAX MEETING ROOM CHAIR**		8	Nos	1,786.00	14,288.00
13.07	**GM CABIN TABLE**		1	Nos	3,715.00	3,715.00
13.08	**GM CABIN TABLE**		1	Nos	2,286.00	2,286.00
13.09	**GM CABIN CHAIR**		1	Nos	2,286.00	**Excluded Considered Re using the Existing**
13.10	**GM CABIN VISITORS TABLE**		1	Nos	2,000.00	2,000.00

S/N	DESCRIPTION		QTY	UNIT	RATE	AMOUNT
13.11	GM CABIN VISITORS CHAIR		3	Nos	1,215.00	Excluded Considered Re using the Existing
13.12	FOCUS POD TABLE		2	Nos	929.00	1,858.00
13.13	FOCUS POD CHAIR		2	Nos	929.00	Excluded Considered Re using the Existing
13.14	LOUNGE AREA 2 SEATER SOFA		1	Nos	1,715.00	1,715.00
13.15	LOUNGE AREA 1 SEATER SOFA		1	Nos	1,215.00	1,215.00
13.16	LOUNGE AREA COFFEE TABLE		1	Nos	929.00	929.00
13.17	RECEPTION CHAIR		1	Nos	1,786.00	Excluded Considered Re using the Existing
13.18	4 PAX WORKSTATION TABLE		6	Nos	6,858.00	41,148.00
13.19	5 PAX WORKSTATION TABLE		1	Nos	8,572.00	8,572.00
13.20	10 PAX WORKSTATION TABLE		1	Nos	17,143.00	17,143.00

S/N	DESCRIPTION		QTY	UNIT	RATE	AMOUNT
13.21	**6 PAX WORKSTATION TABLE**		2	Nos	10,286.00	20,572.00
13.22	**2 PAX WORKSTATION TABLE**		2	Nos	3,429.00	6,858.00
13.23	**WORKSTATION CHAIRS**		55	Nos	543.00	**Excluded Considered Re using the Existing**
13.24	**HOT DESK TABLE**		1	Nos	2,643.00	2,643.00
13.25	**HOT DESK CHAIR**		6	Nos	1,072.00	**Excluded Considered Re using the Existing**
13.26	**PANTRY AREA ROUND TABLE**		2	Nos	686.00	1,372.00
13.27	**PANTRY AREA ROUND TABLE CHAIR**		4	Nos	643.00	**Excluded Considered Re using the Existing**
13.28	**PANTRY AREA HIGH CHAIR**		6	Nos	929.00	**Excluded Considered Re using the Existing**
					SUB TOTAL CARRIED TO SUMMARY	**150,677.00**

Interiors

PROPOSED INTERIOR FITOUT WORKS AT ELECTROLUX - DUBAI, UAE

04/08/2025

Sl No	Item Description	Reference Image	Qty	Unit	Rate	Amount
1.00	**JOINERY WORKS**					
1.01	**Fabrication, supply and installation of pantry unit-** Carcass, shelves in 18 mm thick MR white melamine MDF finish. Shutters in 18 mm thick MDF with Oak veneer natural/stained finish. Including LED strip light, quartz finish counter top and 100 mm high back splash, soft closing hinges and all related works. **Note: Excluding sink, mixer and all appliance.** Pantry size: (2226+1782) mm L x 600 mm D x 2400 mm H Location: Pantry		1	No	30,945.00	30,945.00
1.02	**Fabrication, supply and installation of high table-** Made of 50 mm thick MDF framed table top with Oak veneer natural/stained finish. Table leg made of MDF with Oak veneer natural/stained finish. Including metal supports, necessary, fixing, fittings and all related works. Size: 5492 mm L x 800 mm D x 1070 mm H Location: Pantry		1	No	12,895.00	12,895.00
1.03	**Fabrication, supply and installation of TV wooden panel cladding-** Panels 18 mm thick MDF with Oak veneer natural/stained finish as per approved sample. Including grooves, structural work, necessary fittings and all related works. Size: 3050 mm L x 2400 mm H Location: Near step seating area		1	No	9,300.00	9,300.00
1.04	**Fabrication, supply and installation of step seating with storage and planter box-** Made of MDF with a veneer finish and supported by a metal / wood frame backing. Includes pouf seating, storage compartments, planter box and all associated works. Size: 5315 mm L x 900 mm H Location: Step seating area		1	No	52,735.00	52,735.00
1.05	**Fabrication, supply and installation of wooden ribbed panel with plain panel cladding-** Panels in 18 mm thick MDF with Oak veneer natural/stained finish. Including wooden structure, necessary fixing, fittings and all related works. Ribbed panel size: 3300 mm L x 2400 mm H Plain panel size: 2015 mm L x 2400 mm H Location: Back wall- step seating area		1	No	18,675.00	18,675.00
1.06	**Fabrication , supply and installation of full height storage unit-** Carcass, panels and shelves in 18 mm thick MDF with white melamine finish. Shutters in 18 mm thick MDF with 30% or less gloss PU paint finish. Including soft closing hinges, handles and all related works. Size: (2211+2232) mm L x 600 mm D x 2400 mm H Location: Store room		1	No	18,565.00	18,565.00
1.07	**Fabrication, Supply and installation of vanity counter with mirror-** Structure in ply wood with metal angle supports. Drawer fascia in 18 mm thick MR MDF Oak veneer natural/stained finish. Drawers in 12 mm thick MR white melamine MDF finish. Back paneling in 9 mm thick MR MDF white melamine finish. Counter top with quartz finish. Including 6 mm thick mirror cladding with MDF back paneling, LED strip light, necessary fixing, fittings and all related works. Vanity counter size: 2400 mm L x 600 mm D x 750 mm H Mirror size: 700 mm L x 1500 mm H (3 Nos) Location: Ladies toilet		1	No	13,965.00	13,965.00
1.08	**Fabrication, supply and installation of bench-** Made of cement board panels, supported by a metal frame work. Size: 1900 mm L x 600 mm D x 450 mm H Location: Ladies toilet		1	No	2,645.00	2,645.00
1.09	**Fabrication, Supply and installation of vanity counter with mirror-** Structure in ply wood with metal angle supports. Drawer fascia in 18 mm thick MR MDF Oak veneer natural/stained finish. Drawers in 12 mm thick MR white melamine MDF finish. Back paneling in 9 mm thick MR MDF white melamine finish. Counter top with quartz finish. Including 6 mm thick mirror cladding with MDF back paneling, LED strip light, necessary fixing, fittings and all related works. Vanity counter size: 2100 mm L x 800 mm D x 750 mm H Mirror size: 900 mm L x 1500 mm H (2 Nos) Location: Gents toilet		1	No	12,370.00	12,370.00

Interiors

PROPOSED INTERIOR FITOUT WORKS AT ELECTROLUX - DUBAI, UAE

04/08/2025

Sl No	Item Description	Reference Image	Qty	Unit	Rate	Amount
1.10	**Fabrication, supply and installation of bench-** Made of cement board panels, supported by a metal frame work. Size: 1000 mm L x 600 mm D x 450 mm H Location: Ladies toilet		1	No	1,575.00	1,575.00
1.11	**Fabrication , supply and installation of full height storage unit-** Carcass, panels and shelves in 18 mm thick MDF with white melamine finish. Shutters in 18 mm thick MDF with 30% or less gloss PU paint finish. Including soft closing hinges, handles and all related works. Size: 1300 mm L x 600 mm D x 2400 mm H Location: Janitor		1	No	5,610.00	5,610.00
1.12	**Fabrication , supply and installation of full height wooden DB unit-** Carcass, panels and shelves in 18 mm thick MDF with white melamine finish. Shutters in 18 mm thick MDF with Oak veneer natural/stained finish. Including soft closing hinges and all related works. Size: 3537 mm L x 415 mm D x 2400 mm H Location: Wide passage		1	No	15,750.00	15,750.00
1.13	**Fabrication , supply and installation of full height wooden printer bay and storage unit-** Carcass, panels and shelves in 18 mm thick MDF with white melamine finish. Shutters in 18 mm thick MDF with Oak veneer natural/stained finish. Including soft closing hinges, LED strip light and all related works. Size: 5645 mm L x 415 mm D x 2400 mm H Location: Wide passage		1	No	28,590.00	28,590.00
1.14	**Fabrication , supply and installation of full height wooden display unit-** Carcass, panels and shelves in 18 mm thick MDF with white melamine finish. Shutters in 18 mm thick MDF with Oak veneer natural/stained finish. Including soft closing hinges, LED strip light and all related works. Size: 2479 mm L x 600 mm D x 2400 mm H Location: Wide passage		1	No	12,735.00	12,735.00
1.15	**Fabrication, supply and installation of wooden ribbed panel cladding-** Panels in 18 mm thick MDF with Oak veneer natural/stained finish. Plain panel cladding on both sides of ribbed panel. Including grooves, LED strip light, necessary fittings and all related works. Size: 2100 mm L x 2400 mm H Location: Reception		1	No	12,200.00	12,200.00
1.16	**Fabrication and supply of reception desk with curved edges-** The structure will be made of plywood and solid white wood. The inside unit carcass, shelf, and drawer box in white melamine MDF finish. Shutters and fascia will be made from 18mm thick MDF with a Oak veneer natural/stained finish. The counter fascia will be made of ribbed MDF with Oak veneer natural/stained finish. Countertop with quartz finish. The desk will include LED strip lighting, soft-closing hinges, soft-closing drawer runners, fittings, and all related works. Size: 2100 mm L x 800 mm D x 1100 mm H Location: Reception		1	No	26,345.00	26,345.00
1.17	**Fabrication, Supply and installation of divider-** Divider made of MDF with Oak veneer natural/stained finish. Including base and top wooden support, necessary fixing, fitting and all related works as per approved sample. Size: 1188 mm L x 2400 mm H (we consider 12 fins) Location: Reception		1	No	8,440.00	8,440.00
1.18	**Fabrication, Supply and installation of divider-** Divider made of MDF with Oak veneer natural/stained finish. Including base and top wooden support, necessary fixing, fitting and all related works as per approved sample. Size: 1300 mm L x 2400 mm H (we consider 13 fins) Location: Near focus POD and workstation area opposite to Boardroom		3	Nos	9,145.00	27,435.00
1.19	**Fabrication , supply and installation of ledge table and storage above-** Carcass, panels and shelves in 18 mm thick MDF with white melamine finish. Shutters in 18 mm thick MDF with Oak veneer natural/stained finish as per approved sample. Including soft closing hinges and all related works. Ledge in MDF with Oak veneer natural/stained finish as per approved sample. Including metal L angle supports. Ledge Size: 1800 mm L x 600 mm D x 750 mm H Cabinet Size: 1800 mm L x 350 mm D x 900 mm H Location: POD Focus		2	No	8,100.00	16,200.00

Interiors

PROPOSED INTERIOR FITOUT WORKS AT ELECTROLUX - DUBAI, UAE

04/08/2025

Sl No	Item Description	Reference Image	Qty	Unit	Rate	Amount
1.20	**Fabrication , supply and installation of full height wooden printer bay and storage unit-** Carcass, panels and shelves in 18 mm thick MDF with white melamine finish. Shutters in 18 mm thick MDF with Oak veneer natural/stained finish. Including soft closing hinges, LED strip light and all related works. Size: 1045 mm L x 400 mm D x 2400 mm H Location: Near POD Focus		1	No	7,235.00	7,235.00
1.21	**Fabrication, supply and installation of wooden featured wall panel cladding-** Panels in 18 mm thick MDF with 30% or less gloss PU paint finish as per approved sample. Including grooves, wooden structure, necessary fittings. Size: 5550 mm L x 2400 mm H Location: Boardroom		1	No	17,535.00	17,535.00
1.22	**Fabrication , supply and installation of full height storage unit-** Carcass, panels and shelves in 18 mm thick MDF with white melamine finish. Shutters in 18 mm thick MDF with 30% or less gloss PU paint finish. Including soft closing hinges, LED strip light and all related works. Size: 3200 mm L x 600 mm D x 2400 mm H Location: Boardroom		1	No	17,400.00	17,400.00
1.23	**Fabrication, supply and installation of TV wooden panel cladding-** Ribbed panels in top and bottom made of 18 mm thick MDF with Oak veneer natural/stained finish as per approved sample. Including wallpaper cladding with MDF backing, wooden structure, grooves, LED strip light, necessary fittings and all related works. Size: 3050 mm L x 2400 mm H Location: Boardroom		1	No	11,075.00	11,075.00
1.24	**Fabrication , supply and installation of TV wall with full height storage unit-** Carcass, panels and shelves in 18 mm thick MDF with white melamine finish. Shutters and TV back wall in 18 mm thick MDF with 30% or less gloss PU/textured paint finish. Including soft closing hinges, handles and all related works. Size: 3182 mm L x 600 mm D x 2400 mm H Location: Meeting room 6 PAX		1	No	15,190.00	15,190.00
1.25	**Fabrication, supply and installation of 60 minute single leaf FR door-** Made of 54mm thick Halspan fire-rated core and 15 mm thick solid wood lipping, providing certified 60 minutes of fire resistance in accordance with applicable fire safety standards. The shutter is faced on both sides with 0.6mm natural Beech veneer. All finishing in Oak veneer natural/stained finish. Including normal butt hinges and ironmongeries. Size: 1000 mm L x 2100 mm H Location: Storage room		1	No	5,625.00	5,625.00
1.26	**Fabrication, supply, and installation of single leaf door-** Made of High Pressure Laminate (HPL) panel. Including normal butt hinges and ironmongeries. Size: 800 mm x 2100 mm H Location: Ladies and gents toilet		5	No	2,813.00	14,065.00
1.27	**Fabrication, supply and installation of single leaf door-** Made of 33mm Hollow Core Pressed with 6mm thick MDF on Both sides and Solid Wood Lipping. Frame and architrave in solid beech wood. All finishing in Oak veneer natural/stained finish. Including normal butt hinges and ironmongeries. Size: 1000 mm L x 2100 mm H Location: Ladies and gents toilet door, Store room		3	No	3,750.00	11,250.00
		TOTAL AMOUNT				**426,350.00**

Interiors

PROPOSED INTERIOR FITOUT WORKS AT ELECTROLUX
MEP WORKS

					04/08/2025
Sl NO.	**DESCRIPTION**	**QTY**	**UNIT**	**RATE**	**AMOUNT**
	MEP WORKS				
1.00	**ELECTRICAL WORK**				
	Sub Main Distribution Boards (MDB/SMDB/DB)				
1.001	Modification of DBs Adds the breaker for new power and termination	2	Nos.	3,867.00	7,734.00
1.002	Temporary power service and lights for construction Note:- Any additional charge from DEWA / FM team to be paid by client	1	Item	2,000.00	2,000.00
1.003	Approval Note:- Any additional charge from the DEWA / FM team is to be paid by the client We have assumed that DEWA approval is not required if required we have add in the cost	1	Item	6,000.00	Rate Only
	Note: We have excluded the Power upgradation Additional payment by the client				
	Containment				
	HDGI Cable tray and trunking including necessary supports, accessories etc. all in accordance with the drawings				
1.004	H/L and L/L Cable trunking for Lighting & Power	1	Item	5,200.00	5,200.00
0.001	H/L and L/L Cable tray for IT & Power	1	Item	4,400.00	4,400.00
	Supply and Install power points with PVC Conduits, PVC Wiring, containment & accessories including final termination for the following as per the drawings, specification and regulations.				
1.005	13A Switch socket, Twin white PVC	34	Nos.	334.00	11,356.00
1.006	13A Switch socket, Single white PVC	13	Nos.	260.00	3,380.00
1.007	Supply and installation of Floor box (2 Twin socket and 4 data)	40	Nos.	634.00	25,360.00
1.008	HDMI point for TV point	5	Nos.	334.00	1,670.00
1.009	Power for server rack	3	Nos.	400.00	1,200.00
1.010	Power Switch with Flex-Outlet for AC	8	Nos.	530.00	4,240.00
1.011	Power For display	3	Nos.	531.00	1,593.00
1.012	power isolator for Coffee machine	1	Nos.	530.00	530.00
1.013	power isolator for screen	1	Nos.	531.00	531.00
1.014	Power for Pantry equipment	8	Nos.	530.00	4,240.00
1.015	Power for VAV	5	Nos.	467.00	2,335.00
1.016	Power for FACP panel	1	Nos.	467.00	467.00
1.017	Power for exhaust fan	3	Nos.	467.00	1,401.00
	Supply and install Lighting power points with Wiring, PVC Conduiting & final circuit PVC wiring including termination for the followings - (Supply of Light Fixture Excluded in this price)				
1.018	Install Light fixture with containment, cabling and termination hanging and spot lights and wall light ,table lamp power points	100	Nos.	187.00	18,700.00
1.019	Install Light fixture with containment, cabling and termination Decorative liner,pendant light and light power points	12	Nos.	240.00	2,880.00
1.020	Install Light fixture with containment, cabling and termination Magnetic track light power points	23	Nos.	240.00	5,520.00
1.021	Install Light fixture with containment, cabling and termination LED light power points (Ceiling cove, Curtains and joinery)	30	Nos.	200.00	6,000.00
1.022	Supply and installation of Lighting Switches (MK)	15	Nos.	267.00	4,005.00
	Supply and Installation of only PVC conduits, containments for the MEP Services as per the design requirements (Final confirmation subject to confirmation on scope)				
1.023	Data/Voice Twin outlet (RJ-45)	1	Items	6,667.00	6,667.00
1.024	Security System(Access Control)				
1.025	AV system				
1.026	Wi Fi system				
	Testing & commissioning				
1.027	Testing & commissioning of Electrical System	1	Items	4,000.00	4,000.00
				SUB TOTAL CARRIED TO SUMMARY	**125,409.00**

Interiors

PROPOSED INTERIOR FITOUT WORKS AT ELECTROLUX
MEP WORKS

					04/08/2025
Sl NO.	**DESCRIPTION**	**QTY**	**UNIT**	**RATE**	**AMOUNT**
2.00	**FIRE PROTECTION WORKS**				
	Fire Alarm Works				
	Supply and installation of Fire alarm Devices with necessary fire rated cables, clips and other accessories as per the drawings and specifications as per the new design requirement.				
2.01	Supply and Installation of Addressable Smoke Detector	5	Nos.	1,143.00	5,715.00
2.02	Relocation of the existing Smoke detector	18	Nos.	400.00	7,200.00
2.03	Supply and installation of Heat detector	4	Nos.	1,067.00	4,268.00
2.04	Relocation of Break Glass Unit	2	Nos.	467.00	934.00
2.05	Supply and installation of Fire Alarm Sounder	2	Nos.	600.00	1,200.00
2.06	Relocation of voice Excavation	2	Nos.	467.00	934.00
2.07	Supply and Installation of Inter Face Unit control module	4	Nos.	2,000.00	8,000.00
2.08	Supply and Installation of FA cables 1.5mmx2C red color	1	Items	2,667.00	2,667.00
2.09	Supply and installation of a fire alarm panel FACP Note: Reuse the existing; we have assumed that the existing is working condition	1	Nos.	12,000.00	Rate only
2.10	Reprogramming, Testing, and Commissioning of Fire Alarm System	1	Item	7,067.00	7,067.00
	Emergency Lighting System				
2.11	Supply and Installation of Emergency Light self contained	17	Nos.	560.00	9,520.00
2.12	Supply and Installation of Emergency Exit Light	6	Nos.	560.00	3,360.00
2.13	Allow sum for testing, addressing, programming and commissioning of Emergency Lighting System	1	Item	1,600.00	1,600.00
	Remove the existing central battery lights and bay bass the existing line	1	Item	2,134.00	2,134.00
	Fire Fighting system				
2.13	Supply and installation of sprinkler	10	Nos.	600.00	6,000.00
2.14	Relocation of sprinkler	43	Nos.	334.00	14,362.00
2.15	CO2 fire extinguishers (5 kg)	4	Nos.	400.00	1,600.00
2.16	Dry Chemical powder extinguisher (6 kg)	4	Nos.	334.00	1,336.00
2.17	Fire Blanket	1	Nos.	200.00	200.00
2.18	FM200 system for the server room	1	Items	29,334.00	Rate only
	FF isolation charge				
2.19	Isolation of FA and FF system charge to paid for FLS maintenance team	1	Item	3,334.00	3,334.00
2.20	Charge for DCD inspection certificate and handing over to Concordia for inspection	1	Item	1,334.00	1,334.00
2.21	Testing and commissioning of Fire Fighting System	1	Item	2,000.00	2,000.00
				SUB TOTAL CARRIED TO SUMMARY	**84,765.00**

PROPOSED INTERIOR FITOUT WORKS AT ELECTROLUX
MEP WORKS

Interiors

					04/08/2025
Sl NO.	**DESCRIPTION**	**QTY**	**UNIT**	**RATE**	**AMOUNT**
3.00	**HVAC WORKS**				
3.01	Remove the existing FCUs & Supply and installation of new FCU	8	Nos.	6,000.00	48,000.00
3.02	Supply and installation of VAV for meeting rooms	5	Nos.	2,400.00	12,000.00
3.03	Supply and installation of thermostat	13	Nos.	400.00	5,200.00
3.04	Remove the existing CHW pipes, Supply and Installation of CHW pipes,25mm rubber insulation, and necessary support	1	Items	30,934.00	30,934.00
3.05	Supply and installation of CHW valve packaged (PICV valve,Gate valve, stainer,test point and Ect..)	8	Items	3,734.00	29,872.00
3.06	Supply and installation of condensate drain pipe connecting to the drain line p for the FCU units	8	Nos.	200.00	1,600.00
	Duct work including Plenum Boxes, elbows, bends, tees, junctions, belmouths, access doors, connection to equipment and air out lets as per the drawings and specifications.				
3.07	Remove the existing ducts, Fabrication and installation of Supply Air Duct (PI Ducting) for FCUs based on proposed drawings	1	Items	46,286.00	46,286.00
3.08	Flexible duct (consider each 1.5m) with round damper, rings & jubilee clips as per design	1	Item	6,667.00	6,667.00
3.09	Supply & installation of Volume Control Dampers control the air flow	1	Item	6,667.00	6,667.00
3.10	Supply & installation of acoustic insulation control the airflow noise	1	Item	6,000.00	6,000.00
	Grilles and Diffusers				
3.11	Supply and installation of Grills and Diffusers, including fittings, supports, and other materials required to complete installation as specified and shown on the drawing. Grill Type: Flow Bar Grill and diffuser	1	Item	22,858.00	22,858.00
	Testing & Commissioning				
3.12	Testing, commissioning & air balancing	1	Item	4,000.00	4,000.00
0.01	CHW Chemical flushing	2	Item	6,000.00	12,000.00
				SUB TOTAL CARRIED TO SUMMARY	**232,084.00**
4.00	**PLUMBING WORKS**				
4.01	Sanitary fitting installation	1	Item	5334	5334.00
4.03	Supply and installation of PPR domestic Cold pipes including fittings, accessories, hangers and support; scope up to the building line.	1	Item	6140	6140.00
4.04	All hot and cold water pipes vertical drops concealed in block work walls below ceiling in cross linked polyethylene piping (PEX) complete with connectors and accessories	1	Item	1627	1627.00
4.05	Supply and installation of Water Heater - 50 Ltr	3	Item	1600	4800.00
4.06	Supply and Installation of Water hammer Arrestor	5	Item	200	1000.00
4.07	Cold and Hot water gate valve	8	Item	200	1600.00
4.08	Supply and installation of UPVC waste pipes including hangers, supports, fittings, and accessories bathrooms waste pipes and soil pipes	1	Item	6800	6800.00
4.09	Supply and Installation of Floor Trap	8	Nos	267	2136.00
4.10	Supply and Installation of Clean Outs	3	Nos	334	1002.00
4.11	Testing and Commissioning Plumbing system (Pressure test , Gravity and slope test)	1	Item	2667	2667.00
				SUB TOTAL CARRIED TO SUMMARY	**33,106.00**

Exclusion:

1.We have excluded combined two Units as per the DEWA standard
2.We have excluded Power upgradation
3.We have excluded the IT works ,We have consider the containment for IT works
4. We have excluded the Lighting control system, we have consider ON/ OFF switches
5. We have excluded the BMS system
6. We have excluded the FM200 for sever room
7. We have excluded the FACP panel

475,364.00