INTERIORS
HAPPINESS TO SPACES

QUOTATION *for* FIT OUT & MEP WORKS

NSATS

TURNKEY FIT-OUT SERVICES OF NSATS OFFICE

Level 2, Unit 202 Burj Daman Building, DIFC, Dubai

Qtn Ref.: HTS/INT/QN/2023/2735/R1

Prepared by:

HTS Interiors
Interior: Architects: Engineers
www.htsinteriors.com

Date: 14 July 2023

HTS INTERIORS

HAPPINESS TO SPACES

QTN REF NO: HTS/INT/QN/2023/2735/R1 **DATE: 14 July 2023**

Attn: Mr. Halen Rodda
Managing Partner
Project People

SUBJECT: DESIGN & BUILD FOR NSAT RHQ OFFICE AT BURJ DAMAN, DIFC, DUBAI

Dear Halen,

We thank you for inviting us for the above-mentioned project and we are pleased to submit our revised commercial offer for your review.

We have prepared this offer based upon the Value Engineering of concept design intent for the NSAT office, our analysis of the site, and the following notes and considerations as per T&C:

Please find included our lump sum offer as shown below.

TOTAL FIT-OUT WORKS	1,555,249.00
SPECIAL CORPORATE DISCOUNT	-55,249.00
TOTAL AMOUNT AFTER DISCOUNT	1,500,000.00

The offer covers all areas of the project aligned to your shared design intent, brief and currently available information, and is broken down further for your understanding.

We are happy to discuss any clarifications you require and look forward to partnering with you to deliver a successful project.

Kind regards,

Mr. Nitin Nadukandy

CEO

P.O Box 124791 DUBAI U.A.E
HTS INTERIOR DESIGN L.L.C.

Project : TURNKEY FIT-OUT SERVICES OF NSATS OFFICE Level 2, Unit 202 Burj Daman Building, Difc, Dubai

Subject : Interior Fitout Works

Qtn Ref.: HTS/INT/QN/2023/2735/R1

HTS INTERIORS

SN	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	FIT-OUT WORKS				
A	**PRELIMINARIES**				
1	**AUTHORITY APPROVALS:** Obtaining Authority Approvals; Dubai Municipality & Dubai Civil Defense Dubai Electricity & Water Authority Obtaining Approvals & Work Permit from Building Management Preparation of Drawings & Documents Inspection Appointments & Completion Certificates	1	Item	59,500.00	59,500.00
2	**MAINTENANCE & PROTECTION OF SITE:** Temporary protection & maintenance of the general area of site. First Aid Box & Safety Equipment, Temporary Fire Extinguishers	1			
3	**SUPERVISION & SECURITY:** Coordination and Site Supervision team stationed at site during the working hours & ensure the safety. (To protect the site from unauthorized entry & trespassing)	1			
4	**TEMPORARY FACILITIES:** Mobilization, temporary fittings (Light, DB, water supply, safety equipment, tools, transportation, coverage of corridors and protection of surfaces, etc.. Points for temporary power and lighting tap off to be provided by client.	1			
5	**PROJECT MANAGEMENT & COORDINATION:** Liaising with the Building Management, Consultant or Client during execution Preparation of execution schedule & plan.	1			
6	**SITE CLEANING:** Removal & Cleaning of all debris from site to the approved municipality dump yard as per the regulations. Temporary Skips & Dust Bins at Site of Daily Cleaning. Final Deep cleaning of the site including removal of all Contractor materials before the handover of the site.	1			
7	**EQUIPMENT & TOOLS:** Carrying out all the required equipment & tools for the execution of works. To ensure all the equipment's are in good condition.	1			
8	**AUTHORITY APPROVALS AND DEPOSIT FEES - IS TO BE PAID BY CLIENT BY ACTUALS**				By Client
	Sub Total				**59,500.00**
B	**FLOOR WORKS**				
1	Allowance for removal, modification, supply and installation of New Mechanical Raised Access Floor due to damage and design changes.. **Location: All Area**	1	Ls	29,295.00	29,295.00
2	**Anti Static Raised Access Floor:** Supply and installation of Anti-Static Raised Access Floor for the server room. sample to submit for approval. **Location: Server Room**	1	Ls	2,100.00	2,100.00
3	**Waterproofing:** Supply and laying of Two layers of 4mm thick bitumen membrane type water proofing. including perimeter wall & columns up to 300mm height above finish floor level. With necessary surface preparation. **Location: Powder Room at Director Room & Pantry Area**	1	Ls	2,940.00	2,940.00
	FLOORING FINISHES				
4	**FL-01 LVT Plank:** Supply and installation of LVT Plank FF-01 including wastage with all necessary accessories as per the flooring layout drawing & specification. HTS will provide the materials for client approval. **Location: Director 1-2 Room, Meeting and Lounge, Reception area**	140	m2	140.00	19,600.00
5	**FL-02 LVT Plank:** Supply and installation of LVT Plank FF-01 including wastage with all necessary accessories as per the flooring layout drawing & specification. HTS will provide the materials for client approval **Location: Pantry area**	1	Ls	2,100.00	2,100.00
6	**FL-03 Vinyl Tiles:** Supply and installation of Vinyl Tiles including wastage with all necessary accessories as per the flooring layout drawing & specification. HTS will provide the materials for client approval. **Location: Storage 1 & 2**	15	m2	147.00	2,205.00
7	**FL-04 -Carpet Tile Flooring**: Supply & installation of Carpet Tile flooring including all necessary accessories. HTS to provide sample for client approval - **Location: Open Workstation**	40	m2	133.00	5,320.00
8	**FL-05 - Carpet Tile Flooring (Type 1)**: Supply & installation of carpet tile flooring including all necessary accessories. HTS to provide sample for client approval - **Location: Sr. Executive Room 1 & 2**	1	Ls	2,100.00	2,100.00
9	**FL-06 - Carpet Planks Flooring (Type 2)**: Supply & installation of carpet planks flooring including all necessary accessories. HTS to provide sample for client approval - **Location: Demo/Presentation Room**	70	m2	147.00	10,290.00
10	**FL-07 - Porcelain Marble Look Tiles Flooring**: Supply & installation of Porcelain Marble Look Tiles Flooring including all necessary accessories. HTS to provide sample for client approval - **Location: Powder Room at Directors Area**	1	Ls	3,850.00	3,850.00
11	**Stage at Demo/Presentation Stage**: Supply & installation of Stage at Demo/Presentation Stage made of metal structure including all necessary wooden support - **Location: Demo/Presentation room**	1	Ls	6,075.00	6,075.00

Project : TURNKEY FIT-OUT SERVICES OF NSATS OFFICE Level 2, Unit 202 Burj Daman Building, Difc, Dubai

Subject : Interior Fitout Works

Qtn Ref.: HTS/INT/QN/2023/2735/R1

HTS INTERIORS

SN	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
12	**Self Leveling:** Supply and installation if self leveling	275	m2	49.00	13,475.00
13	**MDF Skirting**: Supply & Installation of MDF Skirting.	155	Lm	95.00	14,725.00
14	**SS Strips:** Supply & Installation of SS transition strip Profile including required adhesives. Location: between different floor finish.	20	Lm	77.00	1,540.00
					115,615.00
C	**WALL PARTITIONS**				
1	**FR Gypsum Partition:** Supply and installation of **100mm gypsum wall** with necessary GI framing and 1x12.5mm Normal FR gypsum board (Knauf Brand) on both sides **including mineral wool insulation** complete with jointing, taping and ready to receive final finish. Till 4000 mm height only .Location: As per partition Lay-out	281	m2	140.00	39,340.00
2	**Cement Board Partition:** Supply & Install of 100mm Thick cement board partition including taping & Joinery, ready to receive the finish. Till 3.6m height only Location: Powder Room & Pantry (only at Wet Area)	1	Ls	8,400.00	8,400.00
3	**FR Gypsum Cladding:** Supply and installation of Liner Wall cladding to the existing wall with necessary GI framing and 12.5mm FR gypsum board on one sides complete with jointing, taping and ready to receive final finish.	84	m2	119.00	9,996.00
4	**Glass Partition (Single Glazed):** Supply and installation Single Glazing system comprising of 1x10mm tempered glass with 35x21mm head and bottom channels in Silver Anodized finish including dummy frame.. Tape Jointed. Partition Height till 2700mm. Note: We considered normal tempered glass only. Any DB certificate is excluded	42	m2	560.00	23,520.00
5	**Vinyl Sticker:** Supply and installation of Vinyl Sticker.	72	m2	100.00	7,200.00
6	Allow for the above **gypsum baffle** above the glass partition **including mineral wool insulation** complete with jointing, taping and ready to receive final finish.	15	Lm	140.00	2,100.00
7	**MDF Cladding:** Supply and installation of **MDF Liner Wall cladding to the existing façade as per site survey** with necessary GI framing including mineral wool insulation on one sides complete with jointing, taping and ready to receive final finish.	35	Lm	210.00	7,350.00
					97,906.00
D	**WALL FINISHES**				
1	**WF-01 Paint:** Supply & Application of **Fenomastic Jotun Paint** finish including application of stucco & Primer Paint. Location: As per the wall finishes layout	598	m2	37.00	22,126.00
2	**WF-03 Wall Paper (Type 1):**Supply & installation of Wallpaper fixed directly on the proposed wall as per the wall finishes. Location: Director Room 1 & 2, Reception & Meeting/Lounge Area Walls	130	m2	120.00	15,600.00
3	**WF-03 Wall Paper (Type 2) :** Supply & installation of Wallpaper fixed directly on the proposed wall as per the wall finishes. **Location: Pantry**	45	m2	120.00	5,400.00
4	**WF-04 Fabric Acoustic Wall Panel** : Supply & Installation of Fabric Acoustic Wall Panel at Demo/Presentation Room. Height of the panel is 3000mm	20	m2	680.00	13,600.00
5	**WF-05 MDF Laminate (matching veneer) Wall Cladding:** Supply & Installation of MDF wall cladding in Laminate (matching veneer). Location: Director Room 1 & 2, Reception & Meeting/Lounge Area	80	m2	680.00	54,400.00
6	**WF-06 MDF Slats @ Back of Reception:** Supply and installation of MDF slats in veneer finishes	9	m2	1,150.00	10,350.00
7	**WF-07 Porcelain Marble Look Tiles:** Supply and installation of Porcelain Marble Look Tiles. Location: Powder Room	20	m2	750.00	15,000.00
8	**WF-08 Porcelain Marble Look Tiles Cladding:** Supply and installation of Porcelain Marble Look Tiles Cladding. Location: Director 2 Area	1	Ls	3,780.00	3,780.00
9	Allow for supply and installation of wall SS strip in black color as per the 3D.	1	Ls	8,780.00	8,780.00
10	Supply & Installation of **manual operated sun screen fabric roller blinds** including required support and accessories.	116	m2	160.00	18,560.00
					167,596.00
E	**CEILING WORKS**				
1	**CF-01 Normal Gypsum Ceiling:** Supply & Installation of Normal Non-FR Gypsum board ceiling using singe layer of 12mm gypsum board including necessary GI suspension system & joint taped and finished ready to receive the paint. Location: As per the Ceiling Layout	275	m2	140.00	38,500.00
2	Supply & Installation of gypsum coving as required including support & accessories	60	Lm	102.00	6,120.00
3	Supply & Installation of gypsum pelmet as required including support & accessories	36	Lm	102.00	3,672.00
4	Allow for cutting the ceiling to received the concealed lights including strips as per the 3D.	1	Lm	7,700.00	7,700.00
5	**Ceiling paint:** Supply & Application of 2 Coats for Fenomastic Jotun Paint including application of 2 Coats for Primer/Stucco on the Gypsum Ceiling, Pelmet & bulkhead.	275	m2	35.00	9,625.00
6	Supply & Installation of 600mmx600mm Access Panel including required support & accessories	5	nos.	245.00	1,225.00
					66,842.00
F	**DOORS & SIGNAGE WORKS**				

Project : TURNKEY FIT-OUT SERVICES OF NSATS OFFICE Level 2, Unit 202 Burj Daman Building, Difc, Dubai

Subject : Interior Fitout Works

Qtn Ref.: HTS/INT/QN/2023/2735/R1

HTS INTERIORS

SN	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
1	**FR Door @ Entrance:** Supply and installation of FR rated Glass Door	1	Nos.	30,800.00	Rate Only if Needed
2	**Glass Door @ Cabin** Supply & Installation of Normal Tempered glass door.	9	Nos.	4,200.00	37,800.00
3	**Normal Wooden Door:** Supply and installation of Normal Wooden Door at Storage Area & Pantry Door	4	Nos.	5,600.00	22,400.00
4	**FR Wooden Door:** Supply and installation of Normal Wooden Door at Server Room	1	Nos.	6,300.00	6,300.00
	Signage Works				
5	Allowance for signage at Reception	1	Nos.	3,500.00	3,500.00
					70,000.00
G	**JOINERY WORKS**				
1	**Reception Counter:** Fabricate, supply and installation of Reception Counter at internal carcass in MDF and as per the drawings.	1	Nos.	15,530.00	15,530.00
2	**Reception Metal Shelves:** Fabricate, supply and installation of Reception Metal Shelvs sand as per the drawings.	4	Nos.	880.00	3,520.00
3	**Open Plan Workspace Table** Fabricate, supply and installation of Table at internal carcass in MDF laminate and table top will be laminate as per the drawing. Size: 1400mm L	6	Nos.	5,270.00	31,620.00
4	**Director 1 Desk :** Fabricate, supply and installation of Director Desk as per the 3D.	1	Nos.	16,540.00	16,540.00
5	**Director 1 behide Metal Shelves:** Fabricate, supply and installation of Director Metal Shelves as per the 3D.	4	Nos.	1,150.00	4,600.00
6	**Director 1 Customized Working Desk:** Fabricate, supply and installation of Customized Working Desk as per the 3D.	2	Nos.	9,510.00	Excluded
7	**Director 1 Customized Table:** Fabricate, supply and installation of Customized Table as per the 3D.	1	Nos.	14,180.00	14,180.00
8	**Director 1 Vanity Counter:** Fabricate, supply and installation of Vanity Counter as per the 3D.	1	Nos.	10,800.00	10,800.00
9	**Director 2 L-Shape Desk :** Fabricate, supply and installation of Director Desk as per the 3D.	1	Nos.	10,130.00	10,130.00
10	**Meeting Room Coffee Counter** Fabricate, supply and installation of Coffee Counter at internal carcass in MDF laminate and shutter to laminate MDF and table top will be Marble Look Tiles. Size: 3200mm L	1	Nos.	14,830.00	14,830.00
11	**Demo/Presentation U Shape Desk - Type 1** Fabricate, supply and installation of Demo/Presentation U Shape Desk metal leg & table top will be MDF laminate finish Size: 7200 mm L	1	Nos.	17,120.00	17,120.00
12	**Demo/Presentation U Shape Desk - Type 2** Fabricate, supply and installation of Demo/Presentation U Shape Desk metal leg & table top will be MDF laminate finish. Size: 2300mm L	1	Nos.	5,750.00	5,750.00
13	**Demo/Presentation U Shape Desk - Type 3** Fabricate, supply and installation of Demo/Presentation U Shape Desk metal leg & table top will be MDF laminate finish. Size: 3600mm L	1	Nos.	9,000.00	9,000.00
14	**Podium Stand at Demo/Presentation.** Fabricate, supply and installation of Demo/Presentation Podium metal leg & table top will be Solid Surface. Size: 3600mm L	1	Nos.	4,860.00	4,860.00
15	**Pantry Counter** Fabricate, supply and installation of Pantry Counter at internal carcass in MDF laminate and shutter to laminate MDF and table top will be Solid Surface. Size: 2000mm L	1	Nos.	6,700.00	6,700.00
16	Allowance for TV wall support and backing	3	Nos.	680.00	2,040.00
17	Allowance for Video Conferencing extra support and backing	1	Nos.	2,030.00	2,030.00
18	**DB/FACP Cabinet** Supply & Installation of DB cabinet as per the drawing & specification.	1	Nos.	2,500.00	2,500.00
					171,750.00
H	**LOOSE FUNITURE / ITEMS**				
1	FF-01 - Task Chair	9	Nos.	950.00	8,550.00
2	FF-02 - Chair at Presentation Room	16	Nos.	880.00	14,080.00
3	FF-03 - Director Chair	1	Nos.	2,030.00	2,030.00
4	FF-04 Lounge Chair	17	Nos.	1,760.00	29,920.00
5	FF-05 Arm Chair	4	Nos.	2,700.00	10,800.00
6	FF-06 Arm Chair at Lounge	4	Nos.	2,700.00	10,800.00
7	FF-07 Sofa	1	Nos.	5,400.00	5,400.00
8	FF-08 Pantry Chair	4	Nos.	1,150.00	4,600.00
9	FF-09 Side Table	3	Nos.	1,150.00	3,450.00
10	FF-10 Coffee Table	2	Nos.	1,620.00	3,240.00
11	FF-11 Table	1	Nos.	3,780.00	3,780.00
12	FF-12 Task Table at Se. Executive 1 & 2	2	Nos.	3,380.00	6,760.00
	Note: All Furniture will be provided by HTS for client approval				

Project : TURNKEY FIT-OUT SERVICES OF NSATS OFFICE Level 2, Unit 202 Burj Daman Building, Difc, Dubai

Subject : Interior Fitout Works

Qtn Ref.: HTS/INT/QN/2023/2735/R1

HTS INTERIORS

SN	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
					103,410.00
I	**SUPPLY & FIXING OF LIGHT FIXTURES**				
1	LF-01 - Suspended Linear Light Type 1	1	Ls		
1	LF-03 - Downlight	1	Ls		
2	LF-04 - Recessed LED lights	1	Ls		
3	LF-05 - Track Light	1	Ls		
4	LF-05 B- Track	1	Ls		
5	LF-06 & 07 -Pendant Lights	1	Ls	60,750.00	60,750.00
6	LF-08 - Pin light	1	Ls		
7	LF-09 - Concealed Led Lights	4	no.		
8	Decorative Lights @ Reception	1	Ls		
9	Decorative Lights @ Director Room	1	Ls		
10	LED Strip Lights	1	item		
11	Allow for LCS system as per building requirments	1	item	11,480.00	11,480.00
					72,230.00
	MEP WORKS				
J	**ELECTRICAL WORKS**				
1	Modification of existing DB as per the new power and lighting layout with all new accessories, new cabling, etc	1	Nos		
2	Supply and install GI cable tray and trunking for the power and lighting cables	1	Item		
	13 Amps Single Sockets (MK-White PVC)				
3	Supply and installation of single pole sockets outlets 13A - 250 V , conventional earth pin release shutter dual earth terminal OR equivalent, with wiring, PVC conduiting & connections as per the design requirements in the proposed Interior layout.	11	Nos		
	13 Amps Single Socket for VAV				
4	Supply and installation of single pole sockets outlets 13A - 250 V , conventional earth pin release shutter dual earth terminal OR equivalent, with wiring, PVC conduiting & connections as per the design requirements in the proposed Interior layout.	6	Nos		
	13 Amps Dual Sockets				
5	Supply and installation of dual pole sockets outlets 13A - 250 V , conventional earth pin release shutter dual earth terminal OR equivalent, with wiring, PVC conduiting & connections as per the design requirements in the proposed Interior layout.	8	Nos		
	13 Amps Spur outlets				
6	Supply and installation of 13Amps spur outlet with wiring, conduiting & connections as per the site requirements	1	No		
	15 Amps Switched Sockets				
7	Supply and installation of 15Amps switched socket with wiring, conduiting & connections as per the site requirements	5	No		
	20 Amps switched Sockets			105,000.00	105,000.00
8	Supply and installation of 20Amps switched socket with wiring, conduiting & connections as per the site requirements	5	No		
	20 Amps isolator for FTU				
9	Supply and installation of 20Amps isolator for FTU with wiring, conduiting & connections as per the site requirements	17	No		
	Floor Boxes				
10	Supply and installation of floor boxes with accessories including conduits for electrical sockets as per the design requirements in the Proposed Interior layout. Floor boxes to be grey framed, flush mounted in existing floor and with carpet infill to the lids..	13	No		
	Conduting and cabling works for the light fittings				
11	Connection to lights including cables, conduits and necessary fittings in conceal/ expose, connections, terminations, wiring ,fixings and fittings,ceiling rose (where required), complete all in accordance with detail drawings and Specifications.	40	No		
12	Supply & installation of 2 gang light switch , White PVC	2	Nos		
13	Supply & installation of 3 gang light switch , White PVC	4	Nos		
	Testing and commissioning:				
14	Testing and commissioning including Megger test,Live test,Cold test	1	Item		
	Lighting control system:				
15	Supply and installation of cables and containments for Dali dimmable standalone lighting control system for the reception area and meeting rooms only.	1	Item		
16	Interfacing of perimeter light with the building System	1	Item		
	te: 1)We have not considered any power upgradation works. 2) Any kind of work in the electrical room is not considered 3) New cable from electrical room to DB not considered.4) We have considered 1FB shared by 2 persons for the open workstation area. 5) We have not considered any UPS power.				
					105,000.00
K	**FIRE ALARM WORKS**				
1	Supply and installation of new FACP with voice evacuation	1	Nos		
2	Interface module with 24/7 DCD, building panel & building system	10	Nos		
3	Supply of new smoke detector	15	Nos		
4	Supply of new heat detector	1	Nos		
5	Suppy of new void detectors with indicator	16	Nos	119,000.00	119,000.00
6	Charges for cancelling the existing fire alarm devices	8	Nos		
7	Supply of control/Monitor module	20	Nos		
8	Supply of addressable pull station with sounder	3	No		

Project : TURNKEY FIT-OUT SERVICES OF NSATS OFFICE Level 2, Unit 202 Burj Daman Building, Difc, Dubai

Subject : Interior Fitout Works

Qtn Ref.: HTS/INT/QN/2023/2735/R1

HTS INTERIORS

SN	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
9	Installation of fire alarm devices	61	No		
10	Testing, commissioning & programming of building FACP	1	No	21,000.00	21,000.00
					140,000.00
L	**FIRE FIGHTING**				
1	Supply and installation of new sprinklers heads with piping	1	Ls		
2	Pressure test for the new sprinkler line	1	Item	35,000.00	35,000.00
3	Supply & Installation of 5 KG CO2 Fire Extinguisher	2	nos		
4	Supply & Installation of 4 KG DCP Fire Extinguisher	2	nos		
5	DCD Certification charges	1	Item		
					35,000.00
M	**EMERGENCY & EXIT LIGHT SYSTEM**				
1	Supply & installation of emergency light (Self Continued type with 3 Hrs battery backup)	8	Nos		
2	Supply and installation of new directional exit lights	4	No		
3	Supply and installation of emergency control panel	1	No		
4	Testing, commissioning & programming	1	Item	39,000.00	39,000.00
					39,000.00
N	**AIR CONDITIONING WORKS**				
	Duct Works				
1	Supply of Floor Terminal Unit (TU4) inclusive of two centrifugal fans, motorized damper, multifunctional electronic controller with "bus" communication card, air discharge and intake floor grills, 5m power connection cable with British Standard fused plug. This unit has an LCD Screen for reading all necessary data and easily changing them if required. Manufacturer: AET, UK	17	Nos	10,080.00	171,360.00
2	Installation of Floor Unit (TU4) inside the Raised Access Floor, supply & installation of all necessary data (bus communication) cabling & RJ45. Power supply to the TU4 and preparation of the raised floor to receive the unit is not included in our price. - 17 nos	1	Item		
3	Supply of floor grille	1	Item	70,000.00	70,000.00
4	Allow for all necessary works for FTU	1	Item		
5	Supply & Installation of Duct Sealants, 1 inch Gasket tape, 2 inch Aluminium tape, Duct Connectors etc.	1	Item		
6	Supply and installation of new BTU Meter as per the building requirements	1	Item		
7	Allow for Civil work for FTU	17	Nos	1,120.00	19,040.00
					260,400.00
O	**Plumbing - Water Supply & Drainage Works**				
1	Supply & installation of Water Supply PPR / Pex pipes as required				
2	Supply & installation of UPVC Drainage piping works as required				
3	Supply & installation of Floor trap & Clean out as required				
4	Supply & Installation of Isolation valves, angle valves, traps & Flexible connections				
5	Connecting the Water Supply & Drain Pipes to base build Stub out	1	LS	37,000.00	37,000.00
6	Pressure Test for Water Supply line, gravity flow test for drain for new works				
7	Supply & installation of water heater 30 ltr				
8	Supply & installation of water Meter as per building requirement				
9	Chlorination for the new water supply line				
					37,000.00
P	**IT /AV Works(Only Containment)**				
1	Supply and installation of 25mm PVC Conduiting/trunking for IT, CCTV,Access Control system;	1	item	14,000.00	14,000.00
2	Supply and installation of 50mm dia conduit for the A/V connection	1	item		
					14,000.00
Q	**ACCESS CONTROL SYSTEM (Make- ZKTeco)**				
					Excluded
R	**CCTV SYSTEM (Make- HIK VISION)**				
					Excluded
S	**IT SYSTEM (Make-SCHNEIDER ELECTRIC)**				
					Excluded
T	**BMS Works [Provisional Sum]**				
1	Supply and installation of BMS system as per the building requirement for the HVAC system. (1 FCUs and BTU meter)	1	item	30,800.00	Excluded Provisional Price only
2	Interfacing the HVAC system with building BMS system.				
					Excluded

P.O Box 124791 DUBAI U.A.E
HTS INTERIOR DESIGN L.L.C.

Project : TURNKEY FIT-OUT SERVICES OF NSATS OFFICE Level 2, Unit 202 Burj Daman Building, Difc, Dubai

Subject : Interior Fitout Works

Qtn Ref.: HTS/INT/QN/2023/2735/R1

INTERIORS
HAPPINESS TO SPACES

SN	DESCRIPTION	AMOUNT (LATEST)
	FIT-OUT WORKS	
A	PRELIMINARIES	59,500.00
B	FLOOR WORKS	115,615.00
C	WALL PARTITIONS	97,906.00
D	WALL FINISHES	167,596.00
E	CEILING WORKS	66,842.00
F	DOORS & SIGNAGE WORKS	70,000.00
G	JOINERY WORKS	171,750.00
H	LOOSE FUNITURE / ITEMS	103,410.00
I	SUPPLY & FIXING OF LIGHT FIXTURES	72,230.00
	MEP WORKS	
J	ELECTRICAL WORKS	105,000.00
K	FIRE ALARM WORKS	140,000.00
L	FIRE FIGHTING	35,000.00
M	EMERGENCY & EXIT LIGHT SYSTEM	39,000.00
N	AIR CONDITIONING WORKS	260,400.00
O	Plumbing - Water Supply & Drainage Works	37,000.00
P	IT /AV Works(Only Containment)	14,000.00
Q	ACCESS CONTROL SYSTEM (Make- ZKTeco)	Excluded
R	CCTV SYSTEM (Make- HIK VISION)	Excluded
S	IT SYSTEM (Make-SCHNEIDER ELECTRIC)	Excluded
T	BMS Works [Provisional Sum]	Excluded
	TOTAL FIT-OUT WORKS (AED)	**1,555,249.00**

Note: Total Amount Excluding VAT.

P.O.Box 124791
DUBAI U.A.E
HTS INTERIOR DESIGN L.L.C.

GENERAL TERMS & CONDITIONS

Project	TURNKEY FIT-OUT SERVICES OF NSATS OFFICE	
Subject	Interior Fitout Works	Date: 14 July 2023
Total Project Value	**: AED 1,555,249.00**	Qtn Ref.: HTS/INT/QN/2023/2735/R1

GENERAL NOTES:

1	All charges required by the bldg. management & all Government and Non-Government authorities are provisional sum.
2	Any Special Design/Approval Charges is to be paid by the client as per actuals.
3	Any change in quantity/specifications /size will have additional cost implications and to be agreed upon on finalization of all architectural, MEP plans/drawings, Electrical Load Schedule & Existing panel details, etc..
4	Considered all materials installed on site shall remain the property of HTS until the release of final payment.
5	Project duration shall mutually be agreed upon from date of receipt of confirmation, advance payment, all approvals from client on sample and materials, and all necessary approvals from regulatory bodies, whichever comes latest.
6	HTS reserve the right to re-quote in the event of size, quantity or specification changes requested by the client.
7	Any omissions or discrepancy on the items quoted above due to the human error shall subject to rectification.
8	Assuming sufficient electrical load available at site to meet the design requirements.
9	All MEP services will be terminated to the stub out provide with the premises, as per LOD issued. Any scope building or external area is not considered in our scope.
10	Specifications for Loose Furniture and Lights are considered UAE locally available and brand is from Far East and HTS will provide TDS and photo for Client review and approval.

EXCLUSIONS :

1	FM200 is excluded.
2	Video Conference and meeting room management/booking System
3	Any New Entrance Door
4	Any Access Control, AV , CCTV and IT System.
5	Any BMS Works
6	Fiber cable works from MDF room to site
7	Any items not mentioned in the BOQ

P.O Box 124791 DUBAI U.A.E HTS INTERIOR DESIGN L.L.C.

PAYMENT TERMS & PROJECT COMPLETION SCHEDULE :

* Payment Terms:
TBC

VAT (VALUE ADDED TAX)

* An additional amount of 5% (Or any % specified by the government) will be charged with invoice, according to the government rules and regulations.

VALIDITY :

* This offer is valid only for 40 days upon issue. HTS reserve the rights to revise the rates accordingly after this period