INTERIORS
HAPPINESS TO SPACES

QUOTATION *for* FIT OUT & MEP WORKS

LVMH

ADP & LOEWE ~ D3 OFFICE

DUBAI, UAE

Qtn Ref.: HTS/INT/QN/2023/2764-A/R9

Prepared by:

HTS Interiors
Interior: Architects: Engineers
www.htsinteriors.com

Date: 03 November 2023

Project : Adp & Loewe - D3 Office Dubai, Uae

Subject : Interior Fitout Works

Qtn Ref.: HTS/INT/QN/2023/2764-A/R9

LVMH

HTS INTERIORS HAPPINESS TO SPACES

SN	DESCRIPTION	AMOUNT	REMARKS
	FIT-OUT WORKS		
A	PRELIMINARIES	47,000.00	
B	DEMOLITION WORKS	22,480.00	
C	FLOOR WORKS	45,820.00	
D	WALL PARTITIONS	16,675.00	
E	WALL FINISHES	19,805.00	
F	GLASS PARTITION & GLASS DOOR WORKS	87,435.00	
G	CEILING WORKS	6,400.00	Considered all open ceiling aas per the new 3D.
H	JOINERY WORKS	11,605.00	Priced decreased due to joinery exclusions.
I	SUPPLY OF LIGHT FIXTURES	70,330.00	
	MEP WORKS		
J	ELECTRICAL WORKS	67,430.00	
K	FIRE FIGHTING & FIRE ALARM WORKS	64,750.00	
L	AIR CONDITIONING WORKS	68,440.00	
M	IT SYSTEM (Make-SCHNEIDER ELECTRIC)	Excluded	
N	ACCESS CONTROL SYSTEM (Make- ZKTeco)	Excluded	
O	CCTV SYSTEM (Make- HIK VISION)	Excluded	
	TOTAL FIT-OUT & MEP WORKS	**528,170.00**	

Note: Total Amount Excluding VAT.

ANNEXURE 1

Project : **Adp & Loewe - D3 Office**

Subject : Interior Fitout Works

Qtn Ref.: HTS/INT/QN/2023/2764-A/R9

HTS INTERIORS

SN	DESCRIPTION	IMAGE	QTY	UNIT	RATE	AMOUNT	REMARKS AS PER THE PTC MEETING WITH LVMH DTD 16.10.23
	FIT-OUT WORKS						
A	**PRELIMINARIES**						
1	**AUTHORITY APPROVALS:** Obtaining Authority Approvals; Dubai Municipality & Dubai Civil Defense Dubai Electricity & Water Authority Obtaining Approvals & Work Permit from Building Management Preparation of Drawings & Documents Inspection Appointments & Completion Certificates		1	Item	47,000.00	47,000.00	
2	**DESIGN DEVELOPMENT:** Allow for making Architectural Design Drawings & As-built. Allow for making MEP Design Drawings		1				
3	**MAINTENANCE & PROTECTION OF SITE:** Temporary protection & maintenance of the general area of site. First Aid Box & Safety Equipment, Temporary Fire Extinguishers		1				
4	**SUPERVISION & SECURITY:** Coordination and Site Supervision team stationed at site during the working hours & ensure the safety. (To protect the site from unauthorized entry & trespassing)		1				
5	**Insurance Charges** :- Contractor to get the following insurances for the project. The limit should be as per the mall management requirement. 1. Contractor's All Risk Insurance. 2. Workmen Compensation Policy.		1				
6	**TEMPORARY FACILITIES:** Mobilization, temporary fittings (Light, DB, water supply, safety equipment, tools, transportation, coverage of corridors and protection of surfaces, etc.. Points for temporary power and lighting tap off to be provided by client.		1				
7	**PROJECT MANAGEMENT & COORDINATION:** Liaising with the Building Management, Consultant or Client during execution Preparation of execution schedule & plan.		1				
8	**SITE CLEANING:** Removal & Cleaning of all debris from site to the approved municipality dump yard as per the regulations. Temporary Skips & Dust Bins at Site of Daily Cleaning. Final Deep cleaning **including existing roller blinds** of the site including removal of all Contractor materials before the handover of the site.		1				
9	**EQUIPMENT & TOOLS:** Carrying out all the required equipment & tools for the execution of works. To ensure all the equipment's are in good condition.		1				
	Note: All Security Deposits & Approval Fees to be paid by Client on actuals.						
	Sub Total					**47,000.00**	
B	**DEMOLITION WORKS**						
1	Allow for the Demolition works in the area required for the site condition to proceed with the work.		1	Item	22,480.00	22,480.00	
	Sub Total					**22,480.00**	
C	**FLOOR WORKS**						
	FLOORING FINISHES						
1	**New Concrete Epoxy Flooring:** Supply and installation of new Concrete look to match the existing at **meeting room area.**		40	m2	290.00	11,600.00	
2	**FL-01 Patterned Carpet Flooring:** Supply and installation of FF-01Carpet wastage with all necessary accessories as per the flooring layout drawing & specification. - HTS will provide the materials for client approval. **Location: All Area**		195	m2	248.00	Rate Only per sq.m	Existing flooring to be reused as per the meeting dated 16.10.23
3	**MDF Skirting**: Supply & Installation of 100mm Height MDF Skirting.		50	Lm	87.00	4,350.00	
4	**SS Strips:** Supply & Installation of SS transition strip Profile including required adhesives. Location: between different floor finish.		6	Lm	80.00	Excluded	Not applicable due to retaining of the floor
5	Allowance for modification of the existing floor due to chipping of floor box & electrical work on the floor		1	Ls	29,870.00	29,870.00	
	Sub Total					**45,820.00**	
D	**WALL PARTITIONS**						
1	**Gypsum Partition (Double Layer Gypsum Both Side):** Supply and installation of 100mm gypsum wall with necessary GI framing and 2x12.5mm Normal Non-FR gypsum board (Knauf) on both sides including mineral wool insulation complete with jointing, taping and ready to receive final finish. **Height considered is 3400mm H Slab to Slab partition** .Location: As per partition layout Except Server Room		50	m2	203.00	10,150.00	
2	**Gypsum Cladding:** Supply and installation of Liner Wall cladding to the existing wall with necessary GI framing and 12.5mm **FR gypsum** board on one sides complete with jointing, taping and ready to receive final finish.		1	Ls	3,625.00	3,625.00	
3	Allow for the above gypsum baffle above the glass partition including mineral wool insulation complete with jointing, taping and ready to receive final finish. Height of the baffle wall is 1000mm H		20	Lm	145.00	2,900.00	
						16,675.00	
E	**WALL FINISHES**						
1	**WF-01 Paint:** Supply & Application of **Fenomastic Jotun Paint** finish including application of stucco & Primer Paint as per the wall finishes		405	m2	31.00	12,555.00	

Project :	**Adp & Loewe - D3 Office**						
Subject : Interior Fitout Works							
Qtn Ref.: HTS/INT/QN/2023/2764-A/R9							
SN	**DESCRIPTION**	**IMAGE**	**QTY**	**UNIT**	**RATE**	**AMOUNT**	**REMARKS AS PER THE PTC MEETING WITH LVMH DTD 16.10.23**
2	**WF-02 Wallpaper:** Supply & Installation of Wallpapepr. HTS Will provide sample for approval. Location: As per 3D		105	m2	140.00	Rate Only per sq.m	Show as Rate Only if needed as per PTC meeting dtd 16.10.23
3	**WF-03 MDF Veneer Cladding:** Supply & Installation of MDF Veneer Cladding including all necessary backing Location: As per the 3D		1	Item	8,700.00	Rate Only if needed	
4	**WF-04 Porcelain Marble Look Tiles:** Supply & Installation of Porcelain Marble Look Tiles including all necessary backing Location: As per the 3D		1	Item	5,880.00	Rate Only if needed	
5	**WF-04 Customized Wallpaper:** Supply & Installation of Wallpaper Location: As per the 3D		130	m2	240.00	Rate Only if needed	
6	**Manually Operated Curtain at Meeting Room:** Supply & Installation of manually Operated Curtain. Height considered is 3000mm. HTS to provide the Fabric for client approval.		60	m2	240.00	Rate Only if needed	
7	Allow for rectifying of the existing blinds		1	item	7,250.00	7,250.00	
						19,805.00	
F	**GLASS PARTITION & GLASS DOOR WORKS**						
1	**Glass Partition:** Supply and installation of SINGLE GLAZED 10mm thick clear tempered glass with polished edges panels fixed with normal U channel. (Height -2400mm) . Note: any DB rating certificate is not available for this glass partition system.		35	m2	406.00	14,210.00	
2	**Acoustic Foldable Partition:** Supply and installation of manually foldable partition Panel Frames: Lamb's Wool / Gray / Brown (TBC) with Acoustic rating including above structural support. Note: Finish will be Fabric (HTS will provide fabric sample for client approval)		1	Ls	47,850.00	47,850.00	
3	**D01 Glass Door Type 1:** Supply & Installation of Framed Less Single leaf Swing 10mm thick normal clear tempered glass . Size: 900mmx2400mm. Ironmongery brand: Dorma fittings, US10 Corner lock and normal H Handle 32mm Dia, 1200mm length back-to-back fixing. All Ironmongeries will be powder coated**.**		7	Nos.	3,625.00	25,375.00	
4	**Frosted vinyl sticker:** Supply and application of frosted vinyl sticker for the proposed glass partition & Doors. Height of frosted sticker is 2000mm - Location: Proposed Glass Partition		55	m2	124.00	Rate Only per sq.m	
5	**Smart Film for the Rooms:** Supply and application of Ultra High Tansparency Smart Film Self adhesive with Transformer+ Switch to be fix on the wall.		55	m2	1,080.00	Rate Only per sq.m	Rate Only as per the Email from CD dated 20.10.2023
						87,435.00	
G	**CEILING WORKS**						
1	**Exposed ceiling painting:** Supply & application of Fenomastic paint for the open ceiling area slab including all the exposed MEP services[Except sprinkler pipes].		200	m2	32.00	6,400.00	
						6,400.00	
H	**JOINERY WORKS**						

Project :	**Adp & Loewe - D3 Office**						
Subject : Interior Fitout Works							
Qtn Ref.: HTS/INT/QN/2023/2764-A/R9							
SN	**DESCRIPTION**	**IMAGE**	**QTY**	**UNIT**	**RATE**	**AMOUNT**	**REMARKS AS PER THE PTC MEETING WITH LVMH DTD 16.10.23**
1	**Ledge** Fabricate, supply and installation of Ledge as per the design. (as per the new 3D)		1	Nos.	7,400.00	Rate only	To be removed as per CD email dated 03 November 2023
2	**Low Height Cabinet -Size: 3200mm L x 1200mm H** Fabricate, supply and installation of Storage Cabinet as per the design. (as per new 3D drawings)		1	Nos.	7,620.00	Rate only	To be removed as per CD email dated 03 November 2023
3	**Low Height Cabinet -Size: 1200mm L x 1200mm H** Fabricate, supply and installation of Storage Cabinet as per the design.		1	Nos.	2,610.00	Rate only	To be removed as per CD email dated 03 November 2023
4	**Full Height Cabinet -Size: 2300mm L x 2700mm H** Fabricate, supply and installation of Storage Cabinet as per the design. (as per new 3D drawings)		1	Nos.	10,810.00	Rate only	To be removed as per CD email dated 03 November 2023
5	**Metal Shelves** Fabricate, supply and installation of Shelves as per the 3D.		2	Nos.	7,250.00	Rate only	To be removed as per CD email dated 01 November 2023
6	**DB & SMDB cabinet:** Supply & Installation of DB & SMDB cabinet in FR MDF in laminate finishes.		1	Nos.	2,180.00	2,180.00	
7	**D01 -Acoustic Normal Wooden Door:** Supply & Installation of Acoustic non-fire rated Single Swing Door in paint finish. single swing single leaf door with self closing mechanism. **Location: Entrance**		1	Nos.	9,425.00	9,425.00	
						11,605.00	
I	**SUPPLY OF LIGHT FIXTURES**						
1	LF-01 - Spot Lights		1	Ls			
2	LF-01 - Track		1	Ls			
3	LF-03 - Pendant Light		8	Nos.			
4	LF-04 - Directional Spot Light with Track Light		1	Ls			
5	LF-05 Spot Lights		1	item			
6	Supply of LED strip light for ceiling and joinery items		1	item	70,330.00	70,330.00	
	Note: **HTS Interiors will provide technical data for client approval before proceeding.** **All lights with 5 years warranty**						
						70,330.00	
	MEP WORKS						
J	**ELECTRICAL WORKS**						
1	Modification of existing Electrical Distribution Board based on the design requirement.		2	Nos			
2	Supply & Installation of PVC conduiting, wiring, flexible wire connector including all necessary accessories for light points.		45	Nos			

Project :	**Adp & Loewe - D3 Office**						
Subject : Interior Fitout Works							
Qtn Ref.: HTS/INT/QN/2023/2764-A/R9							
SN	**DESCRIPTION**	**IMAGE**	**QTY**	**UNIT**	**RATE**	**AMOUNT**	**REMARKS AS PER THE PTC MEETING WITH LVMH DTD 16.10.23**
3	Supply and installation of PVC conduit with Required wiring for light switches.		1	Ls			
4	Modification of existing GI Trunking to run the lighting & Power circuits from the existing Distribution Board.		1	Ls	67,430.00	67,430.00	
5	Supply and Installation of 13 A single switched socket with required PVC conduiting and normal cabling.		10	Nos			
6	Supply and Installation of 13 A Dual switched socket with required PVC conduiting and normal cabling.		2	Nos			
7	Supply & Installation of New Floor Boxes with 2 nos Twin socket, Data blank plate with necessary conduiting and wiring for electrical circuit.		12	Nos			
8	Relocation of existing Floor Boxes with 1 no Twin socket, Data blank plate with necessary conduiting and wiring for electrical circuit.		4	Nos			
9	Containment work for the relocation of existing Thermostat		1	Ls			
10	Modification of existing cable tray for IT works (Structured cabling works excluded)		1	Ls			
11	Supply and Installation of 25mm PVC Containment for structured cabling works		1	Ls			
12	Supply and installation of 50mm PVC containment for AV works (AV cabling works excluded)		1	Ls			
13	Testing and Commissioning (Third party Excluded)		1	Ls			
	We have not considered for Load upgradation. Zero kW NOC is not included in our scope, if required to be charged additionally. We have considered for PVC conduits only, if GI Conduits will be required it will be charged additionally. No Modification works considered inside the electrical room. DEWA Estimate charges & Security deposit payment excluded.						
						67,430.00	
K	**FIRE FIGHTING & FIRE ALARM WORKS**						
	FIRE ALARM WORKS						
1	Relocation of existing Smoke detector with necessary wiring & accessories.		5	Nos.			
2	Supply & Installation of New Smoke detector with necessary wiring & accessories.		4	Nos.			
3	Supply and installation of additional Sounder/Flasher with necessary wiring and accessories.		1	No.	27,260.00	27,260.00	
4	Supply and installation of Break glass unit with necessary wiring and accessories.		2	Nos.			
5	Isolation & Energization of Fire Alarm System		1	Ls			
6	All above including testing, commissioning, and programming with DCD attested certificate and attend DCD inspection.		1	Ls			
	FIRE FIGHTING						
7	Relocation of existing pendant sprinklers with head.		20	Nos			
8	Supply and installation of DCP & CO2 extinguishers		15	No			
9	Charges for ZCV closing, draining and Re-energizing the network		2	Set			
10	Charges for doing pressure test for the network		1	Ls	26,250.00	26,250.00	
11	Certification charges		1	Ls			
	EMERGENCY & EXIT LIGHT SYSTEM						
12	Relocation of existing Emergency Light with necessary wiring and accessories.		5	Nos.			
13	Relocation of existing Exit Light with necessary wiring and accessories.		2	Nos.			
14	Supply and installation of additional Emergency Light with necessary wiring and accessories. (Self- Contained)		2	Nos.			
15	All above including testing, commissioning, and programming with DCD attested certificate and attend DCD inspection.		1	Ls	11,240.00	11,240.00	
						64,750.00	
L	**AIR CONDITIONING WORKS**						
	Supply, and installation, of all items listed according to the indicated specifications and design guidelines						
1	Charges for servicing existing indoor units (No repair/replacement of the parts for the unit considered)		7	Nos			
2	Charges for relocation of the existing thermostats		7	Nos			
3	Supply and installation of bypass type VAV (Normal type, Not BMS Compactible)		10	Nos			
4	Modification of FCU Supply Pl Duct with thermobreak insulation including insulation works, hangers, supports and other accessories.		1	Item	68,440.00	68,440.00	
5	Air outlets type as listed. The price includes all required material, plenum boxes, VCD, rings, belt and lock, marking and installation.		1	item			
6	Testing and commissioning work with reports including Air & Water balancing for HVAC system.		10	Nos			
7	Charges for silencer for the FCU units in the open area		1	Nos	2,103.00	Rate Only per no.	
	We are considered to retain all the existing AC units with its valve packages , if the machine, valves found defective will give you revised offer for the same. we have not considered any kind of work related to AC relocation, CHW Piping/Flushing, BMS system etc. for this project.						
						68,440.00	
M	**IT SYSTEM (Make-SCHNEIDER ELECTRIC)**						
						Excluded	
N	**ACCESS CONTROL SYSTEM (Make- ZKTeco)**						
						Excluded	
O	**CCTV SYSTEM (Make- HIK VISION)**						
						Excluded	

GENERAL TERMS & CONDITIONS

Project	Adp & Loewe - D3 Office		
Subject	Interior Fitout Works	November 3, 2023	
Total Project Value	**: AED 528,170.00**	Qtn Ref.: HTS/INT/QN/2023/2764-A/R9	

GENERAL NOTES:

1	All charges required by the bldg. management & all Government and Non-Government authorities are to be paid by the client.
2	All authority Approval Fees, Security Deposit Fees to be paid by the client as per actuals.
3	Any Special Design/Approval Charges is to be paid by the client as per actuals.
4	Any change in quantity/specifications /size will have additional cost implications and to be agreed upon on finalization of all architectural, MEP plans/drawings, Electrical Load Schedule & Existing panel details, etc..
5	Considered all materials installed on site shall remain the property of HTS until the release of final payment.
6	Job duration shall mutually be agreed upon from date of receipt of confirmation, advance payment, all approvals from client on sample and materials, and all necessary approvals from regulatory bodies, whichever comes latest.
7	HTS reserve the right to re-quote in the event of size, quantity or specification changes requested by the client.
8	Any omissions or discrepancy on the items quoted above due to the human error shall subject to rectification.
9	This proposal is based on the design drawings available to us. Any substantial change in those parameters will result in the revision of this offer.
10	Assuming sufficient electrical load available at site to meet the design requirements.
11	All MEP services will be terminated to the stub out provide with the premises, as per LOD issued. Any scope building or external area is not considered in our scope.
12	As per meeting with contract directs, few lights (maybe around 35%) will be reused.

EXCLUSIONS :

1	Other authorities fees not mentioned herewith as per the location requirement.
2	Any Acoustic rating & certification for Glass partition & Doors
3	Lighting control and automation.
4	White goods excluded.
5	Any AV & video conference system.
6	Any BMS works
7	All IT/CCTV Access Control system is excluded [Only containment]
8	power upgradation and busbar modification is excluded.
9	Plumbing works
10	Any attick stock
11	Loose Furniture & Pod
12	FM 200 system
13	Any items not mentioned in the BOQ

PAYMENT TERMS & PROJECT COMPLETION SCHEDULE :

* TBC

VAT (VALUE ADDED TAX)

* An additional amount of 5% (Or any % specified by the government) will be charged with invoice, according to the government rules and regulations.

VALIDITY :

* This offer is valid only for 30 days upon issue. HTS reserve the rights to revise the rates accordingly after this period