INTERIORS
HAPPINESS TO SPACES

QUOTATION *for* FIT OUT & MEP WORKS

LVMH

BPC - D3 OFFICE

DUBAI, UAE

Qtn Ref.: HTS/INT/QN/2023/2764-B/R8

Prepared by:

HTS Interiors
Interior: Architects: Engineers
www.htsinteriors.com

Date: 31 October 2023

Project : Bpc - D3 Office Dubai, Uae

Subject : Interior Fitout Works

Qtn Ref.: HTS/INT/QN/2023/2764-B/R8

LVMH

HTS INTERIORS HAPPINESS TO SPACES

SN	DESCRIPTION	AMOUNT	REMARKS
	FIT-OUT WORKS		
A	PRELIMINARIES	50,000.00	
B	DEMOLITION WORKS	50,750.00	
C	FLOOR WORKS	202,425.00	
D	WALL PARTITIONS	67,222.00	
E	WALL FINISHES	55,295.00	1) Reduced cost because all walls will only need to be painted. 2) Few finishes shown rate only, for future reference for any additional scope.
F	GLASS PARTITION & GLASS DOOR WORKS	106,981.00	
G	CEILING WORKS	98,656.00	
H	JOINERY WORKS	149,595.00	Priced decreased due to joinery exclusions.
I	SUPPLY OF LIGHT FIXTURES	181,250.00	
	MEP WORKS		
J	ELECTRICAL WORKS	191,300.00	
K	FIRE FIGHTING & FIRE ALARM WORKS	169,530.00	
L	AIR CONDITIONING WORKS	200,830.00	
M	IT SYSTEM (Make-SCHNEIDER ELECTRIC)	Excluded	
N	ACCESS CONTROL SYSTEM (Make- ZKTeco)	Excluded	
O	CCTV SYSTEM (Make- HIK VISION)	Excluded	
P	CORRIDOR WORKS	Excluded	
	TOTAL FIT-OUT & MEP WORKS	**1,523,834.00**	

Note: Total Amount Excluding VAT.

ANNEXURE 1

Project : **Bpc - D3 Office**

Subject : Interior Fitout Works

Qtn Ref.: HTS/INT/QN/2023/2764-B/R8

SN	DESCRIPTION	IMAGE	QTY	UNIT	RATE	AMOUNT	REMARKS AS PER THE PTC MEETING WITH LVMH DTD 16.10.23
	FIT-OUT WORKS						
A	**PRELIMINARIES**						
1	**AUTHORITY APPROVALS:** Obtaining Authority Approvals; Dubai Municipality & Dubai Civil Defense Dubai Electricity & Water Authority Obtaining Approvals & Work Permit from Building Management Preparation of Drawings & Documents Inspection Appointments & Completion Certificates		1	Item	50,000.00	50,000.00	
2	**DESIGN DEVELOPMENT:** Allow for making Architectural Design Drawings & As-built. Allow for making MEP Design Drawings		1				
3	**MAINTENANCE & PROTECTION OF SITE:** Temporary protection & maintenance of the general area of site. First Aid Box & Safety Equipment, Temporary Fire Extinguishers		1				
4	**SUPERVISION & SECURITY:** Coordination and Site Supervision team stationed at site during the working hours & ensure the safety. (To protect the site from unauthorized entry & trespassing)		1				
5	**Insurance Charges** :- Contractor to get the following insurances for the project. The limit should be as per the mall management requirement. 1. Contractor's All Risk Insurance. 2. Workmen Compensation Policy.		1				
6	**TEMPORARY FACILITIES:** Mobilization, temporary fittings (Light, DB, water supply, safety equipment, tools, transportation, coverage of corridors and protection of surfaces, etc.. Points for temporary power and lighting tap off to be provided by client.		1				
7	**PROJECT MANAGEMENT & COORDINATION:** Liaising with the Building Management, Consultant or Client during execution Preparation of execution schedule & plan.		1				
8	**SITE CLEANING:** Removal & Cleaning of all debris from site to the approved municipality dump yard as per the regulations. Temporary Skips & Dust Bins at Site of Daily Cleaning. Final Deep cleaning **including exising roller blinds** of the site including removal of all Contractor materials before the handover of the site.		1				
9	**EQUIPMENT & TOOLS:** Carrying out all the required equipment & tools for the execution of works. To ensure all the equipment's are in good condition.		1				
	Note: All Security Deposits & Approval Fees to be paid by Client on actuals.						
	Sub Total					**50,000.00**	
B	**DEMOLITION WORKS**						
1	Allow for the Demolition works in the area required for the site condition to proceed with the work.		1	Item	50,750.00	50,750.00	
	Sub Total					**50,750.00**	
C	**FLOOR WORKS**						
	FLOORING FINISHES						
1	**FL-01 LVT Flooring (4mm thick)**: Supply and installation of FL-01 LVT including wastage with all necessary accessories as per the flooring layout drawing & specification. - HTS will provide the materials for client approval. **Location: Open Workstation, IT Service Room & IT store**		530	m2	145.00	76,850.00	
2	**FL-02 LVT Flooring (4mm thick) :** Supply and installation of FL-02 LVT including wastage with all necessary accessories as per the flooring layout drawing & specification. - HTS will provide the materials for client approval. **Location: Meeting Rooms, IT-01, HR-01, HR-07 & Phone Booth** **Location: SC-01, SC-02, F28, F1,F2,F3,F4**		235	m2	145.00	34,075.00	
3	**FL-03 LVT Flooring in Herringbone Pattern (4mm thick):** Supply and installation of FL-02 LVT including wastage with all necessary accessories as per the flooring layout drawing & specification. - HTS will provide the materials for client approval.		110	m2	196.00	Rate Only per sq.m if needed	
4	**FL-03 Parquet Flooring:** Supply and installation of Parquet Flooring including wastage with all necessary accessories as per the flooring layout drawing & specification. - HTS will provide the materials for client approval. **Location: SC-01, SC-02, F28, F1,F2,F3,F4**		110	m2	551.00	Rate Only per sq.m as per the PTC meeting	
3	**MDF Skirting**: Supply & Installation of 100mm Height MDF Skirting in PU paint finish		200	Lm	87.00	17,400.00	
4	**SS Strips:** Supply & Installation of SS transition strip Profile including required adhesives. Location: between different floor finish.		20	Lm	80.00	1,600.00	
6	Allowance for modification, supply and installation of New Mechanical Raised Access Floor due to damage and design changes.		1	Ls	72,500.00	72,500.00	
	Sub Total					**202,425.00**	
D	**WALL PARTITIONS**						
1	**Gypsum Partition (Double Layer Gypsum Both Side):** Supply and installation of 100mm gypsum wall with necessary GI framing and 2x12.5mm Normal Non-FR gypsum board (Knauf) on both sides including mineral wool insulation complete with jointing, taping and ready to receive final finish. **Height considered is 3400mm H Slab to Slab partition** .Location: As per partition layout Except Server Room		244	m2	203.00	49,532.00	
2	**Gypsum Cladding:** Supply and installation of Liner Wall cladding to the existing wall with necessary GI framing and 12.5mm **FR gypsum** board on one sides complete with jointing, taping and ready to receive final finish.		1	Ls	14,500.00	14,500.00	

Project :	Bpc - D3 Office
Subject : Interior Fitout Works	
Qtn Ref.: HTS/INT/QN/2023/2764-B/R8	

SN	DESCRIPTION	IMAGE	QTY	UNIT	RATE	AMOUNT	REMARKS AS PER THE PTC MEETING WITH LVMH DTD 16.10.23
3	Allow for the above gypsum baffle above the glass partition including mineral wool insulation complete with jointing, taping and ready to receive final finish. Height of the baffle wall is 1000mm H		22	Lm	145.00	3,190.00	
						67,222.00	
E	**WALL FINISHES**						
1	**WF-01 Paint:** Supply & Application of **Fenomastic Jotun Paint** finish including application of stucco & Primer Paint as per the wall finishes		945	m2	31.00	29,295.00	
2	**WF-02 Wallapaper:** Supply & Installation of Wallpaper. HTS will provide sample for client approval. Location: As per the 3D		189	m2	150.00	Rate Only per sq.m	Show as Rate Only if needed as per PTC meeting dtd 16.10.23
3	**WF-03 MDF Veneer Cladding:** Supply & Installation of MDF Veneer Cladding including all nescessary backing Location:As per the 3D		51	m2	730.00	Rate Only per sq.m	Show as Rate Only if needed as per PTC meeting dtd 16.10.23
4	**WF-04 MDF Wooden Slats Cladding:** Supply & Installation of Wooden Slats Cladding in PU paint finish including all nescessary backing Location: **Workstation Area Wall near the moss wall**		18	m2	1,240.00	Rate Only per sq.m	Show as Rate Only if needed as per PTC meeting dtd 16.10.23
5	**WF-05 Writable Glass Board:** Supply & Installation of Writable Glass Board with MDF backing. Height considered is 3000mm **Location: as per the 3D**		81	m2	798.00	Rate Only per sq.m	Show as Rate Only if needed as per PTC meeting dtd 16.10.23
6	**WF-05 Fabric Wall:** Supply & Installation of Fabric with MDF backing. Height considered is 1500mm **Location: IT Service Room**		1	item	7,903.00	Rate Only per sq.m	Show as Rate Only if needed as per PTC meeting dtd 16.10.23
7	**WF-07 Moss Wall:** Supply & Installation of Moss Wall **Location: Works Station**		1	item	21,200.00	Rate Only per sq.m	To reduced the cost and match the budget
8	**Signage at Moss Wall:** Supply and installation of signage reas as " I LVMH Beauty " to be made of 3D backlight signage using 15 mm opal white acrylic diffuser on the back and 2 mm powder coated and 3 cm side molded aluminum front facia. Size: 96 cm(W) x 60 cm(H) - I LVMH Size: 70 cm(W) x 60 cm(H) - Beauty		1	item	7,875.00	7,875.00	To be included as per the PTC Meeting dtd 16.10.23
9	**Manually Operated Curtain at Meeting Room:** Supply & Installation of manually Operated Curtain. Height considered is 3000mm. HTS to provide the Fabric for client approval.		285	m2	240.00	Rate Only per sq.m	
10	**Allow for rectifiying of the existing blinds**		1	item	18,125.00	18,125.00	
						55,295.00	
F	**GLASS PARTITION & GLASS DOOR WORKS**						
1	**Glass Partition:** Supply and installation of SINGLE GLAZED 10mm thick clear tempered glass with polished edges panels fixed with normal U channel. (Height -2400mm) . Note: any DB rating certificate is not available for this glass partition system.		126	m2	406.00	51,156.00	
2	**D01 Glass Door Type** 1: Supply & Installation of Framed Less Single leaf Swing 10mm thick normal clear tempered glass . Size: 900mmx2400mm. Ironmongery brand: Dorma fittings, US10 Corner lock and normal H Handle 32mm Dia, 1200mm length back-to-back fixing. All Ironmongeries will be powder coated.		11	Nos.	3,625.00	39,875.00	
3	**Sliding Glass Window @ IT Service Room:** Supply & Installation of Sliding Window 10mm thick normal clear tempered glass door fixing.		1	Nos.	3,625.00	3,625.00	

Project :	Bpc - D3 Office
Subject : Interior Fitout Works	
Qtn Ref.: HTS/INT/QN/2023/2764-B/R8	

SN	DESCRIPTION	IMAGE	QTY	UNIT	RATE	AMOUNT	REMARKS AS PER THE PTC MEETING WITH LVMH DTD 16.10.23
4	**FR rated Sliding Glass:** Fabrication, Supply and installation of Automatic single leaf framed sliding 60 mins fire rated glass door using 6mm FR glass and steel frame as per standards with normal accessories (Size – 1200x2400mm)		1	Nos.	12,325.00	12,325.00	
4.a	**Option for FR rated Sliding Doors:** Wooden Sliding: Supply of FR rated Sliding Door in solid core wooden door with frame in veneer finish including track system with handle.	**FOR IMAGE PURPOSE ONLY**	1	Nos.	10,150.00	Option only for Sliding glass door	
5	**Frosted vinyl sticker:** Supply and application of frosted vinyl sticker for the proposed glass partition & Doors. Height of frosted sticker is 2000mm - Location: Proposed Glass Partition		178	m2	124.00	Rate Only per sq.m	To reduced the cost and match the budget
5a	**Curtain:** Supply and application of Manual Hand Operated Curtains with heavy duty track fix direcly on the ceiling		1	m2	383.00	Option 2	Per sq.m rate only
5b	**Smart Film for the Rooms:** Supply and application of Ultra High Tansparency Smart Film Self adhesive with Transformer+ Switch to be fix on the wall.		1	m2	1,080.00	Option 3	Per sq.m rate only
						106,981.00	
G	**CEILING WORKS**						
1	**Normal Gypsum Ceiling:** Supply & Installation of Normal Non-FR Gypsum board ceiling using singe layer of 12mm gypsum board including necessary GI suspension system & joint taped and finished ready to receive the paint. Location: As per the Ceiling Layout		228	m2	160.00	36,480.00	
2	**Ceiling paint**: Supply & Application of 2 Coats for Fenomastic Jotun Paint including application of 2 Coats for Primer/Stucco on the Gypsum Ceiling & bulkhead.		228	m2	32.00	7,296.00	
3	**Exposed ceiling painting:** Supply & application of Fenomastic paint for the open ceiling area slab including all the exposed MEP services[Except sprinkler pipes].		395	m2	44.00	17,380.00	
4	Allowance for Existing Slats Removing,Repaiting and Refurbishing.		1	Item	34,310.00	34,310.00	
5	Supply & Installation of 600mmx600mm Access Panel including required support & accessories		11	nos.	290.00	3,190.00	
						98,656.00	
H	**JOINERY WORKS**						
1	**Full Height Cabinet -Size:2500 L x 2700mm H @ HR-07** Fabricate, supply and installation of Full Height Open Cabinet made of MDF laminate matchin veneer as per the design.		1	Nos.	14,690.00	14,690.00	
2	**Full Height Cabinet -Size:4600 L x 2700mm H @ Lounge Area** Fabricate, supply and installation of Full Height Open Cabinet with shelves made of MDF laminate matching veneer as per the design.		1	Nos.	28,820.00	28,820.00	
3	**Full Height Cabinet -Size: 2800 L x 2700mm H @ Breakout Area** Fabricate, supply and installation of Full Height Open Cabinet with shelves made of MDF laminate matching veneer as per the design.		1	Nos.	17,540.00	17,540.00	
4	**Eating Table at Pantry Area - 3000mm L** Fabricate, supply and installation of pantry ledge made of MDF PU Paint		1	Nos.	13,050.00	13,050.00	
5	Modification of existing pantry cabinet.		1	Nos.	8,700.00	8,700.00	
6	Mdification of existing digital screen framing due to relocation		1	Nos.	8,700.00	Excluded as per the PTC meeting dtd 16.10.23	

Project :	Bpc - D3 Office
Subject :	Interior Fitout Works
Qtn Ref.:	HTS/INT/QN/2023/2764-B/R8

SN	DESCRIPTION	IMAGE	QTY	UNIT	RATE	AMOUNT	REMARKS AS PER THE PTC MEETING WITH LVMH DTD 16.10.23
7	Shelves made of MDF PU paint as per the 3D		7	Nos.	660.00	Excluded as per the PTC meeting dtd 16.10.23	
8	**Full Height Cabinet -Size: 4170 L x 2700mm H @ IT Service Room** Fabricate, supply and installation of Full Height Cabinet made of MDF laminate as per the design.		1	Nos.	16,450.00	16,450.00	New detail to be provided or develop by both parties
9	**Low Height Cabinet -Size: 5400+2000+4200 L x 2700mm H @ IT Service Room** Fabricate, supply and installation of Full Height Cabinet made of MDF laminate as per the design.	 	1	Nos.	32,800.00	32,800.00	Sliding door to be considered to maximized the space.
10	Allow for extra back framing support of the TV.		7	Nos.	1,160.00	8,120.00	
11	**DB & SMDB cabinet:** Supply & Installation of DB & SMDB cabinet in FR MDF in laminate finishes.		1	Nos.	2,900.00	2,900.00	
12	**Fire Rated Wooden Door:** Supply & Installation of fire rated Single Swing Door in paint finish. single swing single leaf door with self closing mechanism. **Location: IT Room**		1	Nos.	6,525.00	6,525.00	
						149,595.00	
I	**SUPPLY OF LIGHT FIXTURES**						
1	LF-01 - Linear LED Light		1	item			
2	LF-02 - Magneting LED lights		100	nos.			
3	LF-02A - Track for Magneting Light		1	Ls			
3	LF-03 - Pendant Light		9	nos.			
4	LF-04 - Pendant Light		15	nos.			
5	LF-05 - Directional Spot Light with Track Light		95	nos.			
6	LF-05 Spot Lights		1	item			
7	LF-06 Pendant Light		4	nos.			
8	Supply of LED strip light for ceiling and joinery items		1	item	181,250.00	181,250.00	

Project :	Bpc - D3 Office
Subject : Interior Fitout Works	
Qtn Ref.: HTS/INT/QN/2023/2764-B/R8	

SN	DESCRIPTION	IMAGE	QTY	UNIT	RATE	AMOUNT	REMARKS AS PER THE PTC MEETING WITH LVMH DTD 16.10.23
	Note: **HTS Interiors will provide technical data for client approval before proceeding.** **All lights with 5 years warranty**						
						181,250.00	
	MEP WORKS						
J	**ELECTRICAL WORKS**						
1	Modification of existing Electrical Distribution Board based on the design requirement.		3	Nos			
2	Supply & Installation of PVC conduiting, wiring, flexible wire connector including all necessary accessories for light points.		107	Nos			
3	Supply and installation of PVC conduit with Required wiring for for light switches.		1	Ls			
4	Supply and installation of PVC conduit with Required wiring for for Grid Switchswitches.		2	Nos.			
5	Modification of existing GI Trunking to run the lighting & Power circuits from the existing Distribution Board.		1	Ls	191,300.00	191,300.00	
6	Supply and Installation of 13 A single switched socket with required PVC conduiting and normal cabling.		11	Nos			
7	Supply and Installation of 13 A Dual switched socket with required PVC conduiting and normal cabling.		14	Nos			
8	Relocation of existing Floor Boxes with 2 nos Twin socket, Data blank plate with necessory conduiting and wiring for electrical circuit.		45	Nos			
9	Relocation of existing Floor Boxes with 1 no Twin socket, Data blank plate with necessory conduiting and wiring for electrical circuit.		13	Nos			
10	Containment work for the relocation of existing Thermostat		1	Ls			
11	Modification of existing cable tray for IT works (Structured cabling works excluded)		1	Ls			
12	Supply and Installation of 25mm PVC Containment for structured cabling works		1	Ls			
13	Supply and installation of 50mm PVC containment for AV works (AV cabling works excluded)		1	Ls			
14	Testing and Commissioning (Third party Excluded)		1	Ls			
	We have not considered for Load upgradation. Zero kW NOC is not included in our scope, if required to be charged additionally.We have considered for PVC conduits only, if GI Conduits will be required it will be charged additionally. No Modification works considered inside the electrcial room. **DEWA Estimate charges & Security deposit payment excluded.**						
						191,300.00	
K	**FIRE FIGHTING & FIRE ALARM WORKS**						
	FIRE ALARM WORKS						
1	Relocation of existing Smoke detector with necessary wiring & accessories.		23	Nos.			
2	Supply & Installation of New Smoke detector with necessary wiring & accessories.		9	Nos.			
3	Supply & Installation of New Heat detector with necessary wiring & accessories.		1	Nos.	50,390.00	50,390.00	
4	Supply and installation of Break glass unit with necessary wiring and accessories.		2	Nos.			
5	Isolation & Energization of Fire Alarm System		2	Nos.			
6	All above including testing, commissioning, and programming with DCD attested certificate and attend DCD inspection.		1	Ls			
	FIRE FIGHTING		1	Ls			
7	Pipe modification charges for changing pendant sprinklers into upright sprinklers with head.		36	Nos			
8	Relocation of existing upright sprinklers with head.		8	No			
9	Relocation of existing pendant sprinklers with head.		23	Set			
10	Supply and installation of DCP & CO2 extinguishers		4	Ls			
11	Charges for ZCV closing, draining and Re-energizing the network		1	Ls	82,000.00	82,000.00	
12	Charges for doing pressure test for the network		1				
13	Certification charges		1	Ls			
	EMERGENCY & EXIT LIGHT SYSTEM						
14	Relocation of existing Emergency Light with necessary wiring and accessories.		19	Nos.			
15	Relocation of existing Exit Light with necessary wiring and accessories.		3	Nos.			
16	Supply and installation of additional Emergency Light with necessary wiring and accessories. (Self- Contained)		5	Nos.			
17	Supply and installation of additional Exit Light with necessary wiring and accessories. (Self-Contained)		7	Nos.			
18	All above including testing, commissioning, and programming with DCD attested certificate and attend DCD inspection.		1	Ls	37,140.00	37,140.00	
						169,530.00	
L	**AIR CONDITIONING WORKS**						
	Supply, and installation, of all items listed according to the indicated specifications and design guidelines						
1	Charges for servicing existing indoor units (No repair/replacement of the parts for the unit considered)		14	Nos			
2	Charges for relocation of the existing thermostats		14	Nos			
3	Supply and installation of bypass type VAV (Normal type, Not BMS Compactible)		13	Nos			
4	Modification of FCU Supply PI Duct with thermobreak insulation including insulation works, hangers, supports and other accessories.		1	Item	200,830.00	200,830.00	
5	Air outlets type as listed. The price includes all required material, plenum boxes, VCD, rings, belt and lock, marking and installation.		1	item			
6	Charges for cros talk attenuator		13	Nos			
7	Charges for rectification work for the existing CHW line in the breakout/lounge area. (Only in the leaking area rectification considered)		1	item			
8	Testing and commissioning work with reports including Air & Water balancing for HVAC system.		1	Item			
9	Charges for silencer for the FCU units in the open area		1	Nos	2,103.00	Rate Only per no.	
	We are considered to retain all the exisitng AC units with its valve packages , if the machine, valves found deffective will give you revised offer for the same. we have not considered any kind of work related to AC relocation, CHW Piping/Flushing, BMS system etc for this project.						
						200,830.00	
M	**IT SYSTEM (Make-SCHNEIDER ELECTRIC)**						
						Excluded	
N	**ACCESS CONTROL SYSTEM (Make- ZKTeco)**						
						Excluded	

Project :	**Bpc - D3 Office**						
Subject : Interior Fitout Works							
Qtn Ref.: HTS/INT/QN/2023/2764-B/R8							
SN	**DESCRIPTION**	**IMAGE**	**QTY**	**UNIT**	**RATE**	**AMOUNT**	**REMARKS AS PER THE PTC MEETING WITH LVMH DTD 16.10.23**
O	**CCTV SYSTEM (Make- HIK VISION)**						
						Excluded	
P	**CORRIDOR WORKS**						
1	**FL-01 LVT Flooring:** Supply and installation of FF-01 LVT including wastage with all necessary accessories as per the flooring layout drawing & specification. - HTS will provide the materials for client approval. **Note: LVT will be direct install above the tiles.**		340	m2	182.00	Excluded	
2	Repainting of the existing walls including removal of existing wallpaper.		700	m2	31.00	Excluded	
3	Repainting of the existing ceiling		340	m2	31.00	Excluded	
						-	

GENERAL TERMS & CONDITIONS

Project	Bpc - D3 Office		
Subject	Interior Fitout Works	October 31, 2023	
Total Project Value	**: AED 1,523,834.00**	Qtn Ref.: HTS/INT/QN/2023/2764-B/R8	

GENERAL NOTES:

1	All charges required by the bldg. management & all Government and Non-Government authorities are to be paid by the client.
2	All authority Approval Fees, Security Deposit Fees to be paid by the client as per actuals.
3	Any Special Design/Approval Charges is to be paid by the client as per actuals.
4	Any change in quantity/specifications /size will have additional cost implications and to be agreed upon on finalization of all architectural, MEP plans/drawings, Electrical Load Schedule & Existing panel details, etc..
5	Considered all materials installed on site shall remain the property of HTS until the release of final payment.
6	Job duration shall mutually be agreed upon from date of receipt of confirmation, advance payment, all approvals from client on sample and materials, and all necessary approvals from regulatory bodies, whichever comes latest.
7	HTS reserve the right to re-quote in the event of size, quantity or specification changes requested by the client.
8	Any omissions or discrepancy on the items quoted above due to the human error shall subject to rectification.
9	This proposal is based on the design drawings available to us. Any substantial change in those parameters will result in the revision of this offer.
10	Assuming sufficient electrical load available at site to meet the design requirements.
11	All MEP services will be terminated to the stub out provide with the premises, as per LOD issued. Any scope building or external area is not considered in our scope.
12	Project Schedule to be submitted in MS project format for the duration of the Project.
13	As per meeting with contract directs, few lights (maybe around 35%) will be reused.

EXCLUSIONS :

1	Other authorities fees not mentioned herewith as per the location requirement.
2	Any Roller Blinds (Only modification required)
3	Any Corridor Works as per our meeting.
4	Any Acoustic rating & certification for Glass partition & Door
5	Lighting control and automation.
6	White goods excluded.
7	Any AV & video conference system.
8	Any BMS works
9	All IT/CCTV Access Control system is excluded [Only containment]
10	Fiber cable works from MDF room to site
11	Power upgradation and busbar modification is excluded.
12	Plumbing works
13	Any attick stock
14	Loose Furniture & Pod
15	FM 200 system
16	Any items not mentioned in the BOQ

PAYMENT TERMS & PROJECT COMPLETION SCHEDULE :

* TBC
* Note: Project Schedule to be submitted in MS project format for the duration of the Project.

VAT (VALUE ADDED TAX)

* An additional amount of 5% (Or any % specified by the government) will be charged with invoice, according to the government rules and regulations.

VALIDITY :

* This offer is valid only for 30 days upon issue. HTS reserve the rights to revise the rates accordingly after this period