INTERIORS
HAPPINESS TO SPACES

QUOTATION *for* FIT OUT & MEP WORKS

LVMH

GIVENCHY & KENZO - D3 OFFICE

DUBAI, UAE

Qtn Ref.: HTS/INT/QN/2023/2764-C/R9

Prepared by:

HTS Interiors
Interior: Architects: Engineers
www.htsinteriors.com

Date: 03 November 2023

Project : Givenchy & Kenzo - D3 Office Dubai, Uae

Subject : Interior Fitout Works

Qtn Ref.: HTS/INT/QN/2023/2764-C/R9

LVMH

HTS INTERIORS HAPPINESS TO SPACES

SN	DESCRIPTION	AMOUNT	REMARKS
	FIT-OUT WORKS		
A	PRELIMINARIES	62,000.00	
B	DEMOLITION WORKS	28,500.00	
C	FLOOR WORKS	129,005.00	Changing from Parquet to LVT caused the price to drop.
D	WALL PARTITIONS	35,815.00	
E	WALL FINISHES	84,465.00	1) Reduced cost because all walls will only need to be painted. 2) Few finishes shown rate only, for future reference for any additional scope. 3) Slatted wall added at Entrance Wall & Experience Room
F	GLASS PARTITION & GLASS DOOR WORKS	81,200.00	Proposed Smart Switchable Glass for the meeting room only.
G	CEILING WORKS	219,721.00	Slated Metal Ceiling is included
H	JOINERY WORKS	65,710.00	
I	SUPPLY OF LIGHT FIXTURES	125,650.00	
	MEP WORKS		
J	ELECTRICAL WORKS	86,420.00	
K	FIRE FIGHTING & FIRE ALARM WORKS	107,530.00	
L	AIR CONDITIONING WORKS	150,880.00	
M	IT SYSTEM (Make-SCHNEIDER ELECTRIC)	Excluded	
N	ACCESS CONTROL SYSTEM (Make- ZKTeco)	Excluded	
O	CCTV SYSTEM (Make- HIK VISION)	Excluded	
	TOTAL FIT-OUT & MEP WORKS	**1,176,896.00**	

Note: Total Amount Excluding VAT.

ANNEXURE 1

Project : **Givenchy & Kenzo - D3 Office**

Subject : Interior Fitout Works

Qtn Ref.: HTS/INT/QN/2023/2764-C/R9

HTS INTERIORS

SN	DESCRIPTION	IMAGE	QTY	UNIT	RATE	AMOUNT	AMOUNT
	FIT-OUT WORKS						
A	**PRELIMINARIES**						
1	**AUTHORITY APPROVALS:** Obtaining Authority Approvals; Dubai Municipality & Dubai Civil Defense Dubai Electricity & Water Authority Obtaining Approvals & Work Permit from Building Management Preparation of Drawings & Documents Inspection Appointments & Completion Certificates		1	Item	62,000.00	62,000.00	
2	**DESIGN DEVELOPMENT:** Allow for making Architectural Design Drawings & As-built. Allow for making MEP Design Drawings		1				
3	**MAINTENANCE & PROTECTION OF SITE:** Temporary protection & maintenance of the general area of site. First Aid Box & Safety Equipment, Temporary Fire Extinguishers		1				
4	**SUPERVISION & SECURITY:** Coordination and Site Supervision team stationed at site during the working hours & ensure the safety. (To protect the site from unauthorized entry & trespassing)		1				
5	**Insurance Charges** :- Contractor to get the following insurances for the project. The limit should be as per the mall management requirement. 1. Contractor's All Risk Insurance. 2. Workmen Compensation Policy.		1				
6	**TEMPORARY FACILITIES:** Mobilization, temporary fittings (Light, DB, water supply, safety equipment, tools, transportation, coverage of corridors and protection of surfaces, etc.. Points for temporary power and lighting tap off to be provided by client.		1				
7	**PROJECT MANAGEMENT & COORDINATION:** Liaising with the Building Management, Consultant or Client during execution Preparation of execution schedule & plan.		1				
8	**SITE CLEANING:** Removal & Cleaning of all debris from site to the approved municipality dump yard as per the regulations. Temporary Skips & Dust Bins at Site of Daily Cleaning. Final Deep cleaning **including exising roller blinds** of the site including removal of all Contractor materials before the handover of the site.		1				
9	**EQUIPMENT & TOOLS:** Carrying out all the required equipment & tools for the execution of works. To ensure all the equipment's are in good condition.		1				
	Note: All Security Deposits & Approval Fees to be paid by Client on actuals.						
	Sub Total					**62,000.00**	
B	**DEMOLITION WORKS**						
1	Allow for the Demolition works in the area required for the site condition to proceed with the work.		1	Item	28,500.00	28,500.00	
	Sub Total					**28,500.00**	
C	**FLOOR WORKS**						
	FLOORING FINISHES						
1	**FL-01 Vinly Flooring:** Supply and installation of FF-01 Vinyl including wastage with all necessary accessories as per the flooring layout drawing & specification. - HTS will provide the materials for client approval. **Location: Open Workstation & Pantry Area**		265	m2	116.00	30,740.00	
2	**FL-02 LVT Flooring (4mm thick) :** Supply and installation of FL-02 LVT including wastage with all necessary accessories as per the flooring layout drawing & specification.. - HTS will provide the materials for client approval. **Location: Managers Cabins & Meeting Room** **Location: SC-01, SC-02, F28, F1,F2,F3,F4**		190	m2	145.00	27,550.00	
3	**FL-03 LVT Flooring in Herringbone Pattern (4mm thick):** Supply and installation of FL-02 LVT including wastage with all necessary accessories as per the flooring layout drawing & specification. - HTS will provide the materials for client approval. **Location: SC-01, SC-02, F28, F1,F2,F3,F4**		95	m2	196.00	Rate only if needed	
3	**FL-03 Parquet Flooring:** Supply and installation of Parquet Flooring including wastage with all necessary accessories as per the flooring layout drawing & specification. - HTS will provide the materials for client approval. **Location: General Manager Room**		27	m2	580.00	Rate Only	Rate Only per sq.m as per the PTC meeting
3	**MDF Skirting**: Supply & Installation of 100mm Height MDF Skirting.		135	Lm	87.00	11,745.00	
4	**SS Strips:** Supply & Installation of SS transition strip Profile including required adhesives. Location: between different floor finish.		20	Lm	80.00	1,600.00	
6	Allowance for modification, supply and installation of New Mechanical Raised Access Floor due to damage and design changes.		1	Ls	57,370.00	57,370.00	
	Sub Total					**129,005.00**	
D	**WALL PARTITIONS**						

Project :	Givenchy & Kenzo - D3 Office
Subject : Interior Fitout Works	
Qtn Ref.: HTS/INT/QN/2023/2764-C/R9	

HTS INTERIORS

SN	DESCRIPTION	IMAGE	QTY	UNIT	RATE	AMOUNT	AMOUNT
1	**Gypsum Partition (Double Layer Gypsum Both Side):** Supply and installation of 100mm gypsum wall with necessary GI framing and 2x12.5mm Normal Non-FR gypsum board (Knauf) on both sides including mineral wool insulation complete with jointing, taping and ready to receive final finish. **Height considered is 3400mm H Slab to Slab partition** .Location: As per partition layout Except Server Room		125	m2	203.00	25,375.00	
2	**Gypsum Cladding:** Supply and installation of Liner Wall cladding to the existing wall with necessary GI framing and 12.5mm **FR gypsum** board on one sides complete with jointing, taping and ready to receive final finish.		1	Ls	7,250.00	7,250.00	
3	Allow for the above gypsum baffle above the glass partition including mineral wool insulation complete with jointing, taping and ready to receive final finish. Height of the baffle wall is 1000mm H		22	Lm	145.00	3,190.00	
						35,815.00	
E	**WALL FINISHES**						
1	**WF-01 Paint:** Supply & Application of **Fenomastic Jotun Paint** finish including application of stucco & Primer Paint as per the wall finishes		620	m2	31.00	19,220.00	
2	**WF-02 Wallpaper:** Supply & installation of Wallpaper. HTS interiors will provide sample for approval. Location: Managers Cabin, 13 pax meeting room, GM & pantry column		90	m2	150.00	Rate Only per sq.m	Show as Rate Only if needed as per PTC meeting dtd 16.10.23
3	**WF-03 MDF Veneer Cladding:** Supply & Installation of MDF Veneer Cladding including all nescessary backing Location: Meeting Room 1,2 & 3		40	m2	730.00	Rate Only per sq.m	Show as Rate Only if needed as per PTC meeting dtd 16.10.23
4	**WF-04 MDF Wooden Slats Cladding:** Supply & Installation of Wooden Slats Cladding in PU paint finish including all nescessary backing	 	38	m2	1,240.00	47,120.00	Area Considered is Entrance Wall & Experience Room Only. As per CD email dated 01 November 2023
5	**WF-05 Writable Glass Board:** Supply & Installation of Writable Glass Board with MDF backing. Height considered is 3000mm **Location: 13 pax Meeting Room**		14	m2	798.00	Rate Only per sq.m	Show as Rate Only if needed as per PTC meeting dtd 16.10.23
6	**WF-06 Mirror:** Supply & Installation of Mirror with MDF backing. Height considered is 3000mm		4.5	m2	435.00	Rate Only per sq.m	Shown in the new 3D
7	**Manually Operated Curtain at Meeting Room:** Supply & Installation of manually Operated Curtain. Height considered is 3000mm. HTS to provide the Fabric for client approval.		100	m2	240.00	Rate Only if needed	
8	**Allow for rectifiying of the existing blinds**		1	item	18,125.00	18,125.00	
						84,465.00	
F	**GLASS PARTITION & GLASS DOOR WORKS**						
1	**Glass Partition:** Supply and installation of SINGLE GLAZED 10mm thick clear tempered glass with polished edges panels fixed with normal U channel. (Height -2400mm) . Note: any DB rating certificate is not available for this glass partition system.		60	m2	406.00	24,360.00	
2	**D01 Glass Door Type 1:** Supply & Installation of Framed Less Single leaf Swing 10mm thick normal clear tempered glass . Size: 900mmx2400mm. Ironmongery brand: Dorma fittings, US10 Corner lock and normal H Handle 32mm Dia, 1200mm length back-to-back fixing. All Ironmongeries will be powder coated.		8	Nos.	3,625.00	29,000.00	
3	**D02 Sliding Glass Door Type 2:** Supply & Installation of Sliding Door 10mm thick normal clear tempered glass door fixing.		2	Nos.	4,495.00	8,990.00	
4	**Smart Film at 13 pax Meeting Room:** Supply and installation of smart film at 13 pax meeting room with Transformer+ Switch to be fix on the wall. Approximate area 15 sq.m		1	item	18,850.00	18,850.00	
5	**Frosted vinyl sticker:** Supply and application of frosted vinyl sticker for the proposed glass partition & Doors. Height of frosted sticker is 2000mm - Location: Proposed Glass Partition		1	m2	124.00	Excluded	Rate only per sq.m , if needed
						81,200.00	
G	**CEILING WORKS**						
1	**Normal Gypsum Ceiling:** Supply & Installation of Normal Non-FR Gypsum board ceiling using singe layer of 12mm gypsum board including necessary GI suspension system & joint taped and finished ready to receive the paint. Location: As per the Ceiling Layout		148	m2	160.00	23,680.00	

Project :	Givenchy & Kenzo - D3 Office
Subject :	Interior Fitout Works
Qtn Ref.:	HTS/INT/QN/2023/2764-C/R9

HTS INTERIORS

SN	DESCRIPTION	IMAGE	QTY	UNIT	RATE	AMOUNT	AMOUNT
2	**Ceiling paint**: Supply & Application of 2 Coats for Fenomastic Jotun Paint including application of 2 Coats for Primer/Stucco on the Gypsum Ceiling & bulkhead.		148	m2	32.00	4,736.00	
3	**Exposed ceiling painting:** Supply & application of Fenomastic paint for the open ceiling area slab including all the exposed MEP services[Except sprinkler pipes].		245	m2	44.00	10,780.00	
4	**Slats Ceiling in Metal :** Supply and installation of Slats Ceiling in Metal with insert acoustic rockwool and necessary suspension system		245	m2	725.00	177,625.00	To include, as per CD email dated 01 Nov. 2023
5	Supply & Installation of 600mmx600mm Access Panel including required support & accessories		10	nos.	290.00	2,900.00	
						219,721.00	
H	**JOINERY WORKS**						
1	**Open Shelve Cabinet @ Meeting Room** Fabricate, supply and installation of Open Shelve Cabinet made of MDF laminate as per the design.		1	Nos.	10,440.00	10,440.00	
2	**GM Cabinet- Size: 3600mm L x 2400mm H @ GM Office** Fabricate, supply and installation of GM Cabinet made of MDF Veneer as per the design.		1	Nos.	15,660.00	15,660.00	
3	**Overhead Cabinet at Printer Area - 1150mm L x 900mm H** Fabricate, supply and installation of overhaed cabinet made of MDF laminate finish including nesseasry support.		1	Nos.	2,900.00	2,900.00	
4	**Pantry Counter with Shelves - Overall Size: 1800mm L x 2700mm H** Fabricate, supply and installation of Pantry Cabinet as per the 3D.		1	Nos.	12,910.00	12,910.00	
5	**MDF Shelves at Columns** Fabricate, supply and installation of Shelves as per the 3D.		3	Nos.	2,180.00	6,540.00	
6	Allow for extra back framing support of the TV.		3	Nos.	1,160.00	3,480.00	
7	**DB & SMDB cabinet:** Supply & Installation of DB & SMDB cabinet in FR MDF in laminate finishes.		1	Nos.	2,180.00	2,180.00	
8	**D01 - Normal Wooden Door:** Supply & Installation of normal non-fire rated Single Swing Door in paint finish. single swing single leaf door with self closing mechanism. **Location: Pantry & Entrance**		2	Nos.	5,800.00	11,600.00	
						65,710.00	
I	**SUPPLY OF LIGHT FIXTURES**						
1	LF-01 - Linear LED Light		20	Nos.			
2	LF-02 - Magneting LED lights		1	Ls			
3	LF-02A - Track for Magneting Light		1	Ls			
3	LF-03 - Pendant Light		10	Nos.			

Project :	Givenchy & Kenzo - D3 Office
Subject : Interior Fitout Works	
Qtn Ref.: HTS/INT/QN/2023/2764-C/R9	

HTS INTERIORS

SN	DESCRIPTION	IMAGE	QTY	UNIT	RATE	AMOUNT	AMOUNT
4	LF-04 - Directional Spot Light with Track Light		1	Ls			
5	LF-05 - Suspended Lights		50	Nos.			
6	LF-05 Spot Lights		7	Nos.			
7	Supply of LED strip light for ceiling and joinery items		1	item	125,650.00	125,650.00	
	Note: **HTS Interiors will provide technical data for client approval before proceeding.** **All lights with 5 years warranty**						
						125,650.00	
	MEP WORKS						
J	**ELECTRICAL WORKS**						
1	Modification of existing Electrical Distribution Board based on the design requirement.		2	Nos			
2	Supply & Installation of PVC conduiting, wiring, flexible wire connector including all necessary accessories for light points.		106	Nos			
3	Supply and installation of PVC conduit with Required wiring for for light switches.		1	Ls			
4	Modification of existing GI Trunking to run the lighting & Power circuits from the existing Distribution Board.		1	Ls	86,420.00	86,420.00	
5	Supply and Installation of 13 A single switched socket with required PVC conduiting and normal cabling.		13	Nos			
6	Supply and Installation of 13 A Dual switched socket with required PVC conduiting and normal cabling.		8	Nos			
7	Supply & Installation of New Floor Boxes with 1 no Twin socket, Data blank plate with necessory conduiting and wiring for electrical circuit.		4	Nos			
8	Relocation of existing Floor Boxes with 2 nos Twin socket, Data blank plate with necessory conduiting and wiring for electrical circuit.		15	Nos			
9	Relocation of existing Floor Boxes with 1 no Twin socket, Data blank plate with necessory conduiting and wiring for electrical circuit.		7	Nos			
10	Containment work for the relocation of existing Thermostat		1	Ls			
11	Modification of existing cable tray for IT works (Structured cabling works excluded)		1	Ls			
12	Supply and Installation of 25mm PVC Contaiment for structured cabling works		1	Ls			
13	Supply and installation of 50mm PVC containment for AV works (AV cabling works excluded)		1	Ls			
14	Testing and Commissioning (Third party Excluded)		1	Ls			
	We have not considered for Load upgradation. Zero kW NOC is not included in our scope, if required to be charged additionally.We have considered for PVC conduits only, if GI Conduits will be required it will be charged additionally. No Modification works considered inside the electrcial room. **DEWA Estimate charges & Security deposit payment excluded.**						
						86,420.00	
K	**FIRE FIGHTING & FIRE ALARM WORKS**						
	FIRE ALARM WORKS						
1	Relocation of existing Smoke detector with necessary wiring & accessories.		18	Nos.			
2	Supply & Installation of New Smoke detector with necessary wiring & accessories.		3	Nos.			
3	Supply & Installation of New Heat detector with necessary wiring & accessories.		1	Nos.	32,940.00	32,940.00	
4	Supply and installation of Break glass unit with necessary wiring and accessories.		2	Nos.			
5	Isolation & Energization of Fire Alarm System		1	Ls			
6	All above including testing, commissioning, and programming with DCD attested certificate and attend DCD inspection.		1	Ls			
	FIRE FIGHTING						
7	Pipe modification charges for changing pendant sprinklers into upright sprinklers with head.		20	Nos			
8	Relocation of existing pendant sprinklers with head.		15	No			
9	Supply and installation of DCP & CO2 extinguishers		2	Set			
10	Charges for ZCV closing, draining and Re-energizing the network		1	Ls	53,490.00	53,490.00	
11	Charges for doing pressure test for the network		1	Ls			
12	Certification charges		1	Ls			
	EMERGENCY & EXIT LIGHT SYSTEM						
13	Relocation of existing Emergency Light with necessary wiring and accessories.		15	Nos.			
14	Relocation of existing Exit Light with necessary wiring and accessories.		3	Nos.			
15	Supply and installation of additional Emergency Light with necessary wiring and accessories. (Self- Contained)		5	Nos.			
16	All above including testing, commissioning, and programming with DCD attested certificate and attend DCD inspection.		1	Ls	21,100.00	21,100.00	
						107,530.00	
L	**AIR CONDITIONING WORKS**						
	Supply, and installation, of all items listed according to the indicated specifications and design guidelines						
1	Charges for servicing existing indoor units (No repair/replacement of the parts for the unit considered)		7	Nos			
2	Charges for relocation of the existing thermostats		7	Nos			
3	Supply and installation of bypass type VAV (Normal type, Not BMS Compactible)		10	Nos			

Project :	Givenchy & Kenzo - D3 Office
Subject : Interior Fitout Works	
Qtn Ref.: HTS/INT/QN/2023/2764-C/R9	

SN	DESCRIPTION	IMAGE	QTY	UNIT	RATE	AMOUNT	AMOUNT
4	Modification of FCU Supply Pl Duct with thermobreak insulation including insulation works, hangers, supports and other accessories.		1	Item	150,880.00	150,880.00	
5	Air outlets type as listed. The price includes all required material, plenum boxes, VCD, rings, belt and lock, marking and installation.		1	item			
6	Charges for cros talk attenuator		10	Nos			
7	Testing and commissioning work with reports including Air & Water balancing for HVAC system.		1	Item			
8	Charges for silencer for the FCU units in the open area		1	Nos	2,083.00	Rate Only per no.	
	We are considered to retain all the exisitng AC units with its valve packages , if the machine, valves found deffective will give you revised offer for the same. we have not considered any kind of work related to AC relocation, CHW Piping/Flushing, BMS system etc for this project.						
						150,880.00	
M	**IT SYSTEM (Make-SCHNEIDER ELECTRIC)**						
						Excluded	
N	**ACCESS CONTROL SYSTEM (Make- ZKTeco)**						
						Excluded	
O	**CCTV SYSTEM (Make- HIK VISION)**						
						Excluded	

GENERAL TERMS & CONDITIONS

Project	Givenchy & Kenzo - D3 Office		
Subject	Interior Fitout Works	November 3, 2023	
Total Project Value	**: AED 1,176,896.00**	Qtn Ref.: HTS/INT/QN/2023/2764-C/R9	

GENERAL NOTES:

1	All charges required by the bldg. management & all Government and Non-Government authorities are to be paid by the client.
2	All authority Approval Fees, Security Deposit Fees to be paid by the client as per actuals.
3	Any Special Design/Approval Charges is to be paid by the client as per actuals.
4	Any change in quantity/specifications /size will have additional cost implications and to be agreed upon on finalization of all architectural, MEP plans/drawings, Electrical Load Schedule & Existing panel details, etc..
5	Considered all materials installed on site shall remain the property of HTS until the release of final payment.
6	Job duration shall mutually be agreed upon from date of receipt of confirmation, advance payment, all approvals from client on sample and materials, and all necessary approvals from regulatory bodies, whichever comes latest.
7	HTS reserve the right to re-quote in the event of size, quantity or specification changes requested by the client.
8	Any omissions or discrepancy on the items quoted above due to the human error shall subject to rectification.
9	This proposal is based on the design drawings available to us. Any substantial change in those parameters will result in the revision of this offer.
10	Assuming sufficient electrical load available at site to meet the design requirements.
11	All MEP services will be terminated to the stub out provide with the premises, as per LOD issued. Any scope building or external area is not considered in our scope.
12	Project Schedule to be submitted in MS project format for the duration of the Project.
13	As per meeting with contract directs, few lights (maybe around 35%) will be reused.

EXCLUSIONS :

1	Other authorities fees not mentioned herewith as per the location requirement.
2	Any Roller Blinds
3	Any Acoustic rating & certification for Glass partition & Door
4	Lighting control and automation.
5	White goods excluded.
6	Any AV & video conference system.
7	Any BMS works
8	All IT/CCTV Access Control system is excluded [Only containment]
9	Fiber cable works from MDF room to site
10	power upgradation and busbar modification is excluded.
11	Plumbing works
12	Any attick stock
13	Loose Furniture & Pod
14	FM 200 system
15	Any items not mentioned in the BOQ

PAYMENT TERMS & PROJECT COMPLETION SCHEDULE :

* TBC
* Note: Project Schedule to be submitted in MS project format for the duration of the Project.

VAT (VALUE ADDED TAX)

* An additional amount of 5% (Or any % specified by the government) will be charged with invoice, according to the government rules and regulations.

VALIDITY :

* This offer is valid only for 30 days upon issue. HTS reserve the rights to revise the rates accordingly after this period