INTERIORS
HAPPINESS TO SPACES

LEAN TECH OFFICE - NASSIMA TOWER LEVEL 1

Fitout and MEP Works

Reference No: 3040 R1

Commercial Proposal

HTS Interiors

3 May 2025

Project :	**LEAN TECH OFFICE - NASSIMA TOWER LEVEL 1**
Subject :	**Fitout and MEP Works**
Qtn Ref.:	**HTS/INT/QN/2025/3040 R1**

SN	DESCRIPTION	AMOUNT (AED)
	ANNEXURE 1	
	ID WORKS	
A	PRELIMINARIES	72,500.00
B	DEMOLITION WORKS	37,500.00
C	FLOORING WORKS	170,596.00
D	PARTITION WORKS	59,477.00
E	GLASS PARTITION & DOOR WORKS	130,712.00
F	WALL FINISHES	106,242.00
G	CEILING WORKS	207,636.00
H	JOINERY WORKS	260,985.00
I	LIGHT FITTINGS	63,909.00
J	SANITARY FITTINGS	32,730.00
	MEP WORKS	
K	HVAC WORKS	162,435.00
L	ELECTRICAL WORKS	215,283.00
M	FIRE ALARM SYSTEM	73,611.00
M	EMERGENCY LIGHT WORKS	58,323.00
N	FIRE FIGHTING WORKS	61,843.00
O	PLUMBING WORKS	43,218.00
	TOTAL FIT-OUT WORKS (AED)	**1,757,000.00**

Note: Total Amount Excluding VAT.

ANNEXURE 1

Project :	**LEAN TECH OFFICE - NASSIMA TOWER LEVEL 1**
Subject :	**Fitout and MEP Works**
Qtn Ref.:	**HTS/INT/QN/2025/3040 R1**

SN	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
A	**PRELIMINARIES**				
1	**COORDINATION FOR APPROVALS:** Coordination charges for authority Approvals; Dubai Municipality, DDA, DCD & DEWA Coordination Approvals & Work Permit from Building Management Preparation of Drawings & Documents Inspection Appointments & Completion Certificates	1	Item	7,500.00	7,500.00
2	**DETAILED DESIGN:** Develop a shop drawings as per design from client. Prepare a full detailed furniture layout. Produce a detailed drawing for the partitions positioning, types, and details. Develop finishes layouts as per the approved design with the required details. Prepare list and schedule to the finishes, light fixtures, Furniture, Equipment as per the approved design. Allow for making MEP Design Drawings	1	Ls		Included
3	**MAINTENANCE & PROTECTION OF SITE:** Temporary protection & maintenance of the general area of site. First Aid Box & Safety Equipment, Temporary Fire Extinguishers	1	Ls		
4	**Insurance Charges :**- Contractor to get the following insurances for the project. The limit should be as per the mall management requirement. 1. Contractor's All Risk Insurance. 2. Workmen Compensation Policy.	1	Ls		
5	**SUPERVISION & SECURITY:** Coordination and Site Supervision team stationed at site during the working hours & ensure the safety. (To protect the site from unauthorized entry & trespassing)	1	Ls		
6	**TEMPORARY FACILITIES:** Mobilization, temporary fittings (Light, DB, water supply, safety equipment, tools, transportation, coverage of corridors and protection of surfaces, etc.. Points for temporary power and lighting tap off to be provided by client.	1	Ls	65,000.00	65,000.00
7	**PROJECT MANAGEMENT & COORDINATION:** Liaising with the Building Management, Consultant or Client during execution Preparation of execution schedule & plan.	1	Ls		
8	**SITE CLEANING:** Removal & Cleaning of all debris from site to the approved municipality dump yard as per the regulations. Temporary Skips & Dust Bins at Site of Daily Cleaning. Final Deep cleaning of the site including removal of all Contractor materials before the handover of the site.	1	Ls		
9	**EQUIPMENT & TOOLS:** Carrying out all the required equipment & tools for the execution of works. To ensure all the equipment's are in good condition.	1	Ls		
10	Authority fees (Note : Fee to be paid by the Client against actual bill)		Item	18,000.00	Rate only
	TOTAL FOR PRELIMINARIES				**72,500.00**
B	**DEMOLITION WORKS**				
	Allow charges for demolition/removal of following items and cart away the debris.				
1	Existing floor finishes	1	Item		
2	Existing partition	1	Item		
3	Existing wall finishes	1	Item		
4	Existing false ceiling	1	Item	37,500.00	37,500.00
5	Existing doors	1	nos		
6	Existing loose furniture/joinery items	1	Item		
7	Allow charges for removal of existing MEP services and equipment's	1	Item		
	Total for DEMOLITION WORKS				**37,500.00**
C	**FLOORING WORKS**				
1	**Screed** Supply and installation of cement sand screed (100 mm high) for the new pantry area.	1	Item	2,250.00	2,250.00
2	**Waterproofing** Supply and application of cementitious waterproofing for the we area floor and wall perimeter (1200 mm high for cistern and 300 mm for remaining area)	119	m2	68.00	8,092.00
3	**Raised Floor Modification** Allow charges for removal and reinstallation of existing raised access flooring as per the new proposed design.	1	Item	41,250.00	41,250.00
4	**Self Levelling** Supply and application of 2-3 mm thick self levelling on the raised access floor to receive proposed LVT flooring.	272	m2	53.00	14,416.00

Project :	**LEAN TECH OFFICE - NASSIMA TOWER LEVEL 1**
Subject :	**Fitout and MEP Works**
Qtn Ref.:	**HTS/INT/QN/2025/3040 R1**

SN	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
5	**FL 01 Carpet** Supply and installation of carpet tile flooring as per the proposed design. Size : 500x500 mm Location : Open workstation area (61 pax) *Note : HTS will provide sample for the Client approval.*	201	m2	132.00	26,532.00
6	**FL 02 Carpet** Supply and installation of carpet tile flooring as per the proposed design. Size : 500x500 mm Location : Meeting room & Closed offices**.** *Note : HTS will provide sample for the Client approval.*	125	m2	132.00	16,500.00
7	**FL 03 LVT Type 1** Supply and installation of luxury vinyl tile concrete look as per the proposed design. Location : Corridor *Note : HTS will provide sample for the Client approval.*	112	m2	141.00	15,792.00
8	**FL 04 LVT Type 2** Supply and installation of luxury vinyl tile wooden/terrazzo look as per the proposed design. Location : Opwn workstation area (workstation 19 pax), All hand area, Dining and pantry. *Note : HTS will provide sample for the Client approval.*	160	m2	141.00	22,560.00
9	**Ceramic Tile Flooring** Supply and installation of ceramic tile flooring using standard glue and grout. Size : 400x400 mm Location : Toilets *Note : HTS will provide sample for the Client approval.*	23	m2	165.00	3,795.00
10	**Porcelain Tile Flooring** Supply and installation of 800x800 mm tile flooring at lift lobby. *Note : HTS will provide sample for the Client approval.*	32	m2	173.00	5,536.00
11	**MDF skirting** Supply and installation of 100 mm high, 12 mm thick MDF skiting with PU paint finish.	170	m	60.00	10,200.00
12	**Transition strip** Supply and installation of transition strip between LVT and carpet floor termination.	43	m	61.00	2,623.00
13	**Threshold** Supply and installation of marble threshold for toilet entrance.	2	nos	525.00	1,050.00
	Total for FLOORING WORKS				**170,596.00**
D	**PARTITION WORKS**				
1	**Gypsum Partition** Supply and installation of single layer 100 mm thick partition with necessary GI framing and 1 x 12.5mm fire rated gypsum board on both sides complete with jointing, taping and ready to receive final finish. Partition height considered is slab to slab	104	m2	143.00	14,872.00
2	**Gypsum Cladding** Supply and installation of single layer gypsum cladding with necessary GI framing and 1 x 12.5mm fire rated gypsum board on single sides complete with jointing, taping and ready to receive final finish. Location : All existing perimeter wall and column. Partition height considered is slab to slab	440	m2	98.00	43,120.00
3	**Gypsum Baffle Wall** Supply and installation of single layer gypsum baffle wall with necessary GI framing and 1 x 12.5mm fire rated gypsum board on single sides. Location : Above glass partition and door up to slab sofit.	11	m2	135.00	1,485.00
	Total for PARTITION WORKS				**59,477.00**
E	**GLASS PARTITION & DOOR WORKS**				
1	**Glass Partition - Acoustic 32 dB** Supply and installation of acoustic glass partition with powder coated coated aluminium profile. Clarity of Glass: Clear Glass (Regular) Type of Glass: 12mm Head Channel Dimension: 26mm x 23mm Bottom Channel Dimension: 26mm x 23mm Acoustic Rating: 32dB Aluminium Profile Finish: RAL powder coated Height : 2800 mm Location : As per the proposed design.	64	m2	635.00	40,640.00

Project :	**LEAN TECH OFFICE - NASSIMA TOWER LEVEL 1**				
Subject :	**Fitout and MEP Works**				
Qtn Ref.:	**HTS/INT/QN/2025/3040 R1**				
SN	**DESCRIPTION**	**QTY**	**UNIT**	**RATE**	AMOUNT
2	**Glass Door - : Acoustic 34 dB** Supply and installation of acoustic glass door. Type of Glass: 12mm Acoustic Rating: 34dB Leaf Configuration: Single Leaf Clarity of Glass: Clear Glass (Regular) Aluminium Profile Finish: RAL 9005 Height of Door: 2700 mm Width of Door: 1074 mm Door Handle: 1200mm H Type - Round Accessories: Pivots + Floor Spring + Raven Drop Seal + Door stop	9	nos	7,425.00	66,825.00
3	**Manifestation** Supply and installation of frosted glass sticker. Height considered : 1500 mm	64	m2	115.00	7,360.00
4	**Smart Glass - Rate Only** Supply and installation of laminated glass partition with smart film insert. Partition height : 2800 mm		m2	1,283.00	Rate only if required
5	**Double Glaze Glass Door** Supply and installation of double glazed door with necessary external façade modification. Location : Door from dining area to external Height considered : L 900 x H 2400 mm		Rate only/ no	11,475.00	Rate only if required
6	**Automatic Sliding Door With Fixed Partition** Supply and installation of 12 mm thick glass door and partition with black powder coated U channel all around. Door size : L 2000 x H 2400 mm Fixed Partition : L 400 x H 2400 mm x 2 no	1	Item	15,887.00	15,887.00
	Total for GLASS PARTITION & DOOR WORKS				**130,712.00**
F	**WALL FINISHES**				
1	**Wall Paint** Supply & application of 2 Coats for Fenomastic Jotun Paint including application of 1 Coats for Primer and 2 coat of stucco on the Gypsum partition.	527	m2	30.00	15,810.00
2	**Branding Wall** Supply and installation of vinyl printed graphics wall as per the proposed design. Height considered 2800 mm	46	m2	169.00	7,774.00
3	**Texture Paint** Supply and installation of texture paint finish on the wall as per the proposed design. Height considered 2800 mm	73	m2	162.00	11,826.00
4	**Wall tile at toilet** Supply and installation of 400x400 mm wall tile at toilet using standard glue and grout. *Note : HTS will provide sample for the Client approval.*	82	m2	173.00	14,186.00
5	**Reusing Existing Roller Blinds** Allow charges for removal and reinstallation of existing roller blinds.	1	Item	16,200.00	16,200.00
6	**Roller Blinds** Supply and installation of manually operated roller blinds for the external windows.		Rate only/ m2	90.00	Rate only if required
7	**Steel Curtain** Supply and installation of steel curtain. Siz3 : L 3600 x H 2600 mm *Note : HTS will provide sample for the Client approval.*	2	no	4,914.00	9,828.00
8	**Acoustic Wall Cladding** Supply and installation of PET panel acoustic wall cladding with CNC cut pattern. *Note : HTS will provide sample for the Client approval.*	54	m2	567.00	30,618.00
	Total for WALL FINISHES				**106,242.00**
G	**CEILING WORKS**				
1	**Gypsum Ceiling - Regular** Supply and installation of gypsum board ceiling using singe layer of 12.5 mm regular gypsum board including necessary GI suspension system & joint taped and finished ready to receive the paint. Location: As per the Ceiling Layout	260	m2	128.00	33,280.00
2	**Gypsum Ceiling - Moisture Resistant** Supply and installation of gypsum board ceiling using singe layer of 12.5 mm MR gypsum board including necessary GI suspension system & joint taped and finished ready to receive the paint. Location: As per the Ceiling Layout	22	m2	150.00	3,300.00
3	**Open Ceiling Paint** Supply and application of open ceiling paint above the baffle ceiling slab sofit and wall perimeter	733	m2	48.00	35,184.00
4	**Gypsum Bulkhead** Supply and installation of 100 mm thick bulkhead as per the proposed design.	89	m	113.00	10,057.00
5	**Gypsum Light Cove** Supply and installation of 50x100 mm light cove as per the proposed design.	89	m	128.00	11,392.00

Project :	**LEAN TECH OFFICE - NASSIMA TOWER LEVEL 1**				
Subject :	**Fitout and MEP Works**				
Qtn Ref.:	**HTS/INT/QN/2025/3040 R1**				
SN	**DESCRIPTION**	**QTY**	**UNIT**	**RATE**	AMOUNT
6	**Ceiling paint** Supply & Application of 2 Coats for Fenomastic Jotun Paint including application of 2 Coats for Primer/Stucco on the Gypsum Ceiling, Pelmet & bulkhead.	851	m2	33.00	28,083.00
7	**Acoustic Ceiling - Baffle** Supply and installation of hanging 12 mm thick PET acoustic ceiling. *Note : HTS will provide sample for the Client approval.* 	24	m2	1,035.00	24,840.00
8	**Acoustic Ceiling - Hanging** Supply and installation of hanging 12 mm thick PET acoustic ceiling. Location : Above workstation *Note : HTS will provide sample for the Client approval.* 	82	m2	750.00	61,500.00
	Total for CEILING WORKS				**207,636.00**
H	**JOINERY WORKS**				
1	**J01 Pantry cabinet - Bottom Unit** Supply and installation of pantry cabinet to be made of moisture resistant MDF. Shutter and all outer visible area to be in laminate finish and inner carcass to be in prelaminated MDF. All the visible edges to be lipped with PVC edge band. Counter top top be in 12 mm thick solid surface. Location : Pantry Size : L 3650 x W 600 x H 900 mm 	1	nos	12,566.00	12,566.00
2	**J02 Ledge Table With Steel Support** Supply and installation of pantry cabinet to be made of moisture resistant MDF with laminate finish. Including metal leg. Location : Dining area Size : L 3750 x W 600 x H 1100 mm	1	nos	4,219.00	4,219.00
3	**J03 Seating Bench** Supply and installation of seating bench to be made of non fire rated MDF with laminate finish (wooden look) with upholstered seating (Artificial leather). Location : Dining area Size : L 5000 x W 450 x H 900 mm	1	nos	10,838.00	10,838.00
4	**J04 Storage for Sliding Folding Partition** Supply and installation of sliding folding partition to be made of prelaminated MDF on both outer and inner visible area. Location : Dining area Size : L 1250 x W 400 x H 2800 mm	1	nos	4,909.00	4,909.00
5	**J05 Movable Podium** Supply and installation of movable podium to be made of non fire rated MDF with LVT finish. Including necessary wooden frame work and heavy duty wheel. Location : Collaboration area Size : L 3450 x W 1200 x H 200 mm 	1	nos	3,168.00	3,168.00
6	**J06 Step Seating** Supply and installation of step seating unit to be made of non fire rated MDF with wooden look laminate finish. Including necessary wooden frame work. Size : L 7800+4775 x H 900 mm Location : Collaboration area 	1	Item	28,050.00	28,050.00
7	**J07 Storge Unit** Supply and installation of storage unit with PU paint finish. Location : Collaboration area Size : L 3500 x W 500 x H 2800 mm 	1	Item	18,118.00	18,118.00

Project :	**LEAN TECH OFFICE - NASSIMA TOWER LEVEL 1**
Subject :	**Fitout and MEP Works**
Qtn Ref.:	**HTS/INT/QN/2025/3040 R1**

SN	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
8	**J09 TV Unit** Supply and installation of TV unit wall with PU paint finish Size : L 2200 x H 2800 mm Location : 16 pax & 8 pax meeting room 	2	nos	5,498.00	10,996.00
9	**J10 Storage Cabinet** Supply and installation of storage cabinet with Back painted glass shutter and PU paint finish outer visible area. Inner carcass will be prelaminated MDF finish. Location : 16 pax & 8 pax meeting room Size : L 5100 x W 500 x H 2800 mm 	1	nos	32,773.00	32,773.00
10	**J11 Reception Back Wall** Supply and installation of reception back wall to be made of non fire rated fluted non fire rated MDF with PU paint finish. Size : L 2300 x H 2800 mm 	1	Item	7,801.00	7,801.00
11	**J12 Reception Counter** Supply and installation of reception counter to be made of non fire rated MDF. Counter top to be in 12 mm thick solid surface finish and PU paint finishes front fascia. Including SS skirting. Size : L 2000 x W 800 x H 1200 mm 	1	Item	15,300.00	15,300.00
12	**J13 Printer Cabinet Unit** Supply and installation of printer cabinet to be made of moisture resistant MDF. Shutter and all outer visible area to be in laminate finish and inner carcass to be in prelaminated MDF. All the visible edges to be lipped with PVC edge band. Location : Copy room Size - Bottom cabinet : L 1200 x W 700 x H 900 mm Size - Over head cabinet : L 1200 x W 400 x H 1200 mm	2	Item	4,590.00	9,180.00
13	**J14 Storage Unit With Planter Box** Supply and installation of storage unit with planter box. Item to be made of non fie rated MDF with laminate finish. Location : Workstation area Size : L 1800 x W 400 x H 900 mm 	2	nos	2,066.00	4,132.00
14	**J15 Cabinet Unit With Storage** Supply and installation of TV unit with shelving to be made of non fire rated MDF. Shutter and all outer visible area to be in laminate finish and inner carcass to be in prelaminated MDF. All the visible edges to be lipped with PVC edge band. Location : Business development workstation area Size : L 3400 x W 500 x H 2800 mm	1	Item	16,994.00	16,994.00

Project :	**LEAN TECH OFFICE - NASSIMA TOWER LEVEL 1**
Subject :	**Fitout and MEP Works**
Qtn Ref.:	**HTS/INT/QN/2025/3040 R1**

SN	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
15	**J16 Open Pantry Unit** Item to be made of non fire rated MDF with PU paint finish outer visible area and prelaminated MDF inner carcass. Including wooden grain laminate finish open shelf and solid surface counter top. Location : Collaboration area Bottom cabinet Size : L 2300 x W 600 x H 9000 Open Shelf : L 1500 x W 300 mm x 50 mm thk	1	nos	9,244.00	9,244.00
16	**J17 Column Planter Unit** Item to be made of non fire rated MDF with PU paint/ wooden finish laminate finish. Location : Workstation area Size : L 2500 x W 700 x H 900 mm		Rate only/ no	3,305.00	Rate only if required
17	**J18 Ledge Table with Steel Support** Supply and installation of ledge unit to be made of moisture resistant MDF with wooden look laminate finish and black steel support. Location Pantry Size : L (3000+1250) x W 500 x 1200 mm 	1	Item	8,129.00	8,129.00
18	**J19 TV Wall unit (Bottom cabinet + Open shelf)** Supply and installation of TV wall unit to be made of moisture resistant MDF with laminate finish in outer visible area and prelaminated MDF in inner carcass. Location : Dining area Bottom cabinet : L 2600 x W 400 x H 900 mm 	1	Item	5,636.00	5,636.00
19	**Bench with Fabric Backing** Supply and installation of bench with storage unit to be made of non fire rated MDF with PU paint finish. Including upholstered seat and back rest. Gypsum light cover Bench size : L 1200 x W 400 x H 450 mm Back rest : L 1200 x H 1500 mm 		Rate only/ no	3,960.00	Rate only if required
20	Allow charges for vinyl wrapping for existing doors	7	nos	1,800.00	12,600.00
21	Sliding folding partition - MDF with laminate/ PU paint finish	1	Item	23,250.00	23,250.00
22	**Vanity Counter** Supply and installation of vanity counter with solid surface finish. Size : L 2000 x W 500 x H 300 mm	2	no	3,900.00	7,800.00
23	**Writing Board 1** Supply and installation of 6 mm thick back painted glass. Size : L 1200 x H 1000 mm	4	no	1,080.00	4,320.00
24	**Writing Board** Supply and installation of 6 mm thick back painted glass. Size : L 2000 x H 1000 mm	2	no	1,305.00	2,610.00
25	**Janitor Cabinet** Supply and installation of cabinet with prelaminated MDF finish. Size : L 1200 x W 600 x H 2400 mm	1	nos	4,752.00	4,752.00
26	**FACP panel Cabinet** Supply and installation of FACP panel cabinet. Size : L 1000 x H 1000 mm	1	nos	1,350.00	1,350.00
27	**DB & SMDB panel Cabinet** Supply and installation of DB & SMDB panel cabinet. Size : L 600 x H 600 mm	2	nos	1,125.00	2,250.00
	Total for JOINERY WORKS				**260,985.00**
I	**LIGHT FITTINGS**				
1	Supply and installation of following light fittings	1	Item	63,909.00	63,909.00
1.1	*LT-01 SUSPENDED, LINEAR LIGHT*	*43*	*nos*		
1.2	*LT-02 & LT-05 CYLINDRICAL LED PENDANT LIGHT*	*53*	*nos*		
1.3	*LT-03 CEILING MOUNTED CYLINDRICAL LED LIGHT*	*30*	*nos*		

Project :	**LEAN TECH OFFICE - NASSIMA TOWER LEVEL 1**
Subject :	**Fitout and MEP Works**
Qtn Ref.:	**HTS/INT/QN/2025/3040 R1**

SN	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
1.4	*LT-04 RECESSED CIRCULAR LED DOWNLIGHT*	*30*	*nos*		
1.5	*LT-06 RECESSED CIRCULAR LED DOWNLIGHT*	*37*	*nos*		
1.6	*LT-07 RECESSED CIRCULAR LED DOWNLIGHT*	*10*	*nos*		
1.7	*LT-08 SUSPENDED, LOW OUT PUT DECORATIVE, PENDENT LIGHT - 2*	*4*	*nos*		
1.8	*LT-09 DECORATIVE LIGHT*	*4*	*nos*		
	Total for LIGHT FITTINGS				**63,909.00**
J	**SANITARY FITTINGS**				
1	Supply of following sanitary fittings. Brand : RAK or equivalent.	1	Item	32,730.00	32,730.00
1.1	*Wall mounter water closet*	*4*	*nos*		
1.2	*Concealed cistern unit*	*4*	*nos*		
1.3	*Flush plate*	*4*	*nos*		
1.4	*Bidet spray*	*4*	*nos*		
1.5	*Toilet roll holder*	*4*	*nos*		
1.6	*Counter top wash basin*	*4*	*nos*		
1.7	*Basin mixer*	*4*	*nos*		
1.8	*Tissue paper dispenser*	*4*	*nos*		
1.9	*Waste bin*	*8*	*nos*		
1.10	*Hand dryer*	*2*	*nos*		
1.11	*Rob hook*	*4*	*nos*		
1.12	*Floor drain*	*8*	*nos*		
1.13	*Sink at pantry*	*1*	*nos*		
1.14	*Mixer at pantry*	*1*	*nos*		
1.15	*Urinal unit*	*3*	*nos*		
1.16	*Urinal partition*	*2*	*nos*		
	Total for SANITARY FITTINGS				**32,730.00**
K	**HVAC WORKS**				
1	Modification of existing chilled water MS pipes with black rubber insulation covered with canvas cloths and Foster adhesive coating	1	LS		
2	Pressure testing of chilled water pipe line and Chemical flushing. flushing of the chilled water circuit with approved flushing chemical vendor.	1	Item		
3	Supply and installation of the new thermostat for the FCU with control wires	8	Nos		
4	Supply & Installation of 20mm thick phenolic Pre Insulated sheet indoor ducts with VCD,necessary supports for FCU,Fresh air & Extract air as per havoc design	1	Item	162,435.00	162,435.00
5	Supply and installation of 12mm thick Internal acoustic lining insulation for initial 1.5 meter for FCU	40	M2		
6	Supply & Installation of stand alone Bypass type VAV boxes with digital thermostat and control wires in each enclosed offices.	8	Nos		
7	Supply & Installation of Cross-talk Sound attenuator in each enclosed offices.	8	Nos		
8	Supply & Installation of Motorized Fire damper for supply & Return duct to IT room as per ADCD regulation	2	Nos		
9	Supply & Installation of linear grills and square diffusers, Round diffusers with plenum boxes, flexible duct and VCD rings.	1	Item		
10	Third party air balancing, Testing & Commissioning of HVAC system as per ASHRAE standard Specification: a) Adjusting Air Flow in each room as per approved HVAC design b)Arrangement of VCD to maintain air flow. c)Duct air leak/Lose analysis and rectification d)Water balancing of CHW flow as per approved CHW layout	1	Item		
	Total for HVAC WORKS				**162,435.00**
L	**ELECTRICAL WORKS**				
1	Relocation with Modification of Existing Sub Main Distribution Board based on the design requirement.	1	No		
2	Supply, Installation, Testing and Commissioning of wall mounted Electrical Distribution Board, 240 Volts, Surface/Recess, complete suitable size with GI insulated Copper Conductor up to terminal blocks, tinned copper bus bar, Neutral links, Earth bar, Glanding plate, interconnections with Din bar for mounting 40Amp main breaker and outgoing circuits for light, power & FCU	2	Nos		
3	Supply and install 4C x 16 mm.sq XLPE/SWA/GI armoured cable from the new SMDB to the new DB's complete	25	Lam		
4	Supply and install 1C x 16mm. Sq ECC Cable earth wire from the new SMDB to the new SMDB to the new DB's complete	25	Lam		
5	Supply and install 4C x 35 mm.sq XLPE/SWA/GI armoured cable from the new SMDB to the new DB's complete	32	Lam		
6	Supply and install 1C x 16mm. Sq ECC Cable earth wire from the new SMDB to the new SMDB to the new DB's complete	32	Lam		
7	Supply & Installation of New Cable Tray for above cabling works	40	Lam		
8	Supply & Installation of PVC conduiting, wiring, flexible wire connector including all necessary accessories for light points.	325	Nos		
9	Supply and installation of PVC conduit with wiring for for light switches/ Grid Switch.	1	Ls		
10	Supply and Installation of 13 A single switched socket with required PVC conduiting and normal cabling.	18	Nos		
11	Supply and Installation of 13 A Flex outlet socket with required PVC conduiting and normal cabling (FACP)	2	Nos		

Project :	**LEAN TECH OFFICE - NASSIMA TOWER LEVEL 1**
Subject :	**Fitout and MEP Works**
Qtn Ref.:	**HTS/INT/QN/2025/3040 R1**

SN	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
12	Supply and Installation of 13 A Dual switched socket with required PVC conduiting and normal cabling.	9	Nos		
13	Supply and Installation of 20 Amp SP Isolator/ Commando Socket for Server rack (2 nos)	1	Item	215,283.00	215,283.00
14	Supply and Installation of Power Outlet for FCU / VAV	16	Nos.		
15	Supply and installation of 20Amp DP Switch & 13 Amp Flex Outlet for fridge, water dispenser	2	Nos		
16	Supply and installation of 20Amp DP Switch & 15 Amp Socket for Oven-02 nos. ,Dishwasher Coffee Machine, Water Heater.	5	Nos		
17	Supply & Installation of New Floor Boxes with 1 nos Twin socket, Data blank plate with necessary conduiting and wiring for electrical circuit. (Sharing Floor Boxes)	30	Nos		
18	Supply & Installation of New Floor Boxes with 2 nos Twin socket, Data blank plate with necessary conduiting and wiring for electrical circuit. (Sharing Floor Boxes)	37	Nos		
19	Supply & Installation of GI Trunking for Each DB (2 nos.) for Power & Light Circuits	1	Ls		
20	Supply & Installation of conduit for Thermostat	1	Ls		
21	Supply & Installation of cable tray for IT works (Structured cabling works excluded)	1	Ls		
22	Supply and Installation of 25mm PVC Containment for structured cabling works	1	Ls		
23	Supply and installation of 50mm PVC containment for AV works (AV cabling works excluded)	1	Ls		
24	Testing and Commissioning (Third party Excluded)	1	Ls		
	Total for ELECTRICAL WORKS				**215,283.00**
M	**FIRE ALARM SYSTEM**				
1	Relocation of existing Smoke detector with necessary wiring & accessories.	29	Nos.		
2	Supply & Installation of New Smoke & Heat detector with necessary wiring & accessories.	12	Nos.		
3	Relocation of existing Speaker with necessary wiring and accessories.	5	Nos.		
4	Relocation of existing Break Glass with necessary wiring and accessories.	4	Nos.		
5	Supply & Installation of Break glass unit with necessary wiring and accessories.	1	Nos.		
6	Relocation of existing Fire Alarm control panel & cancellation of 01 existing FACP	1	No.		
7	Supply & Installation of Sounder unit with necessary wiring and accessories. (4 nos)	1	item	73,611.00	73,611.00
8	Containment & Cabling works for existing & all new devices	1	Ls		
9	Relocation of existing IFU Module for 24X7 DCD panel with office fire alarm panel.	2	Nos		
10	Supply & Installation of Interfacing module for Access Control system- 3 nos. with office fire alarm panel with necessary wiring and accessories.	3	Nos.		
11	Isolation & Energization of Fire Alarm System	1	Ls		
12	All above including testing, commissioning, and programming with DCD attested certificate and attend DCD inspection.	1	Ls		
	Total for FIRE ALARM SYSTEM				**73,611.00**
M	**EMERGENCY LIGHT WORKS**				
1	Supply and installation of Emergency Light with necessary wiring and accessories. (Self- Contained)	41	Nos.		
2	Supply and installation of additional Emergency Light with necessary wiring and accessories. (Self- Contained)	9	Nos.		
3	Containment & Cabling works for existing & all new devices	1	Ls	58,323.00	58,323.00
4	Isolation & Energization of Emergency Light System	1	Ls		
5	All above including testing, commissioning, and programming with DCD attested certificate and attend DCD inspection.	1	Ls		
	Total for EMERGENCY LIGHT WORKS				**58,323.00**
N	**FIRE FIGHTING WORKS**				
1	Relocation of existing Pendent sprinklers	68	Nos		
2	Supply & Installation of new pendant sprinkler	5	Nos		
3	Supply and installation of DCP & CO2 extinguishers	6	Set		
4	Fire Blanket	1	Set		
5	Charges for existing line modification works	1	Ls	61,843.00	61,843.00
6	Charges for ZCV closing, draining and Re-energizing the network	1	Ls		
7	Charges for doing pressure test for the network	1	Ls		
8	Certification charges	1	Ls		
	Total for FIRE FIGHTING WORKS				**61,843.00**
O	**PLUMBING WORKS**				
1	Supply & installation of PPR water supply pipes	1	L.S		
2	supply & installation of HDPE drainage piping.	1	L.S		
3	Supply & Installation of PEX pipes	24	Mtr		
4	Supply & Installation of Valves and accessories	1	L.S		
5	supply & installation of water heater (80 L)	2	Nos		
6	Installation of sanitary fixtures	1	L.S	43,218.00	43,218.00

Project :	**LEAN TECH OFFICE - NASSIMA TOWER LEVEL 1**
Subject :	**Fitout and MEP Works**
Qtn Ref.:	**HTS/INT/QN/2025/3040 R1**

SN	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
7	Supply & installation of floor trap gratings	8	Nos		
8	Supply and installation of Water hammer arrester	2	Nos		
9	Gravity testing of drainage line	1	Item		
10	Testing and commissioning of plumbing drainage system	1	Item		
	Total for PLUMBING WORKS				**43,218.00**

GENERAL TERMS & CONDITIONS

Project	LEAN TECH OFFICE - NASSIMA TOWER LEVEL 1
Subject	Fitout and MEP Works
Total Project Value	**1,757,000.00**
Date:	03 May 2025
Qtn Ref.:	HTS/INT/QN/2025/3040 R1

GENERAL NOTES:

1	All charges required by the bldg. management & all Government and Non-Government authorities are provisional sum.
2	Any Special Design/Approval Charges is to be paid by the client as per actuals.
3	Any change in quantity/specifications /size will have additional cost implications and to be agreed upon on finalization of all architectural, MEP plans/drawings, Electrical Load Schedule & Existing panel details, etc..
4	Considered all materials installed on site shall remain the property of HTS until the release of final payment.
5	Project duration shall mutually be agreed upon from date of receipt of confirmation, advance payment, all approvals from client on sample and materials, and all necessary approvals from regulatory bodies, whichever comes latest.
6	HTS reserve the right to re-quote in the event of size, quantity or specification changes requested by the client.
7	Any omissions or discrepancy on the items quoted above due to the human error shall subject to rectification.
8	Assuming sufficient electrical load available at site to meet the design requirements.
9	All MEP services will be terminated to the stub out provide with the premises, as per LOD issued. Any scope building or external area is not considered in our scope.
10	We have not considered any smoke control system since there is no details available in the given drawings. If it's required as per Authority, it will be considered as variation.
11	We have not considered for Load upgradation. Consider existing Meter & CT Meter provision in the Electrical room , if required it will be change additional.
12	DCD Certificate considered only for new items.
13	We have not considered any new FCUs for the office area as per the scope of work document provided by the client. We assume that the existing FCUs have sufficient capacity to support the proposed area.
14	All the existing FCU to be serviced and given in good condition by Landlord
15	Specifications for All Finishes, Loose Furniture and Lights are to be supplied by HTS for Client review and approval.

EXCLUSIONS :

1	Third party acoustic consultant
2	BTU Meter, and any BMS Integration Works
3	Chilled water rectification works along with insulations.
4	Any works related to lighting control system and motion sensor
5	FM 200 for IT room
6	All kinds of IT/AV/Access control/CCTV works
7	All active components/Screen/Computer arm etc.
8	We have not considered for Load upgradation. DEWA Estimate charges & Security deposit payment excluded.
9	Any items not mentioned in the BOQ

PAYMENT TERMS :

*
1) 40% Advance upon confirmation.
2) 25% On Completion of MEP first fix.
3) 25% On Completion of Finishing Works
4) 10% On Project Handover (TOC/Beneficial Occupancy)
5) Or to be discussed and Agreed upon

Note: We would like to propose payment milestone & payment should be released within 2 weeks from the date of invoice.

PROGRAMME

* As per the attached project programmed.

VAT (VALUE ADDED TAX)

* An additional amount of 5% (Or any % specified by the government) will be charged with invoice, according to the government rules and regulations.

VALIDITY :

* This offer is valid only for 40 days upon issue. HTS reserve the rights to revise the rates accordingly after this period