INIS INTERIORS

Bill of Quantities	Our Ref :	IIID-071-Rev.00
	Attention to :	David Cook
	Date :	October 30, 2024

COMMERCIAL PROPOSAL FOR:

Quotation for Interior Fitout Works - Unit 1202B - Tower B - Opus

Presented to:

David Cook
Contractors Direct
Dubai

Presented By:

Stephen Duffy
Inis Interiors
Dubai

Ref No.	IIID-071-R00
Project:	Unit 1202B - Tower B - Opus
Attention:	David Cook
P.O. Box	Dubai
Subject:	Fitout Works
Date	October 30, 2024

ITEM	DESCRIPTION	QTY.	UNIT	RATE	AMOUNT
	BILLS OF QUANTITES				
1	**SUBMISSION OF DRAWINGS**				
1.01	Preparation of architectural and technical submission drawings and obtain necessary authorities approval. The drawings will include, plans, sections, elevations and all construction drawings, necessary to build the office space. Note: (All required deposits, Concerned Authorities & Building Management fees including fees & deposits for the temporary services like water and electricity from the Building Management shall be paid by client on actuals.)	1	L/s	20,000.00	20,000.00
	SUB-TOTAL: SUBMISSION OF DRAWINGS				**20,000.00**
2	**PRELIMINARIES**				
2.01	Allow for site supervision, site management during execution period	1	L/s	15,000.00	15,000.00
2.02	Allow for preliminaries generally including mobilization and demobilization	1	L/s		
2.03	First aid kits and necessary safety equipment to comply with the health and safety regulations for the duration of the contract.	1	L/s		
2.04	Provision of fire extinguishers for the duration of the works to each area. In compliance with Health and Safety regulations	1	L/s		
2.05	All ladders/scaffolding and access staging necessary to carry out the works.	1	L/s		
2.06	Power hand tools and scaffoldings.	1	L/s		
2.07	Preliminary protection for existing finished wall and floor from the guidance of building management and mobilization & demobilization	1	L/s		
2.08	Contractor's All Risk Insurance policy and Workmen Compensation Insurance policy limited to Inis Interiors policy.	1	L/s		
2.09	Regular cleaning of site during construction period.	1	L/s		
	SUB-TOTAL: PRELIMINARIES				**15,000.00**
3	**DEMOLITION WORKS**				
	All Areas				
3.01	Demolition of existing MEP services all as per drawings including disposal of material to designated location provided by local authority. This includes chasing the floor to accommodate the new floor boxes.	1	L/s	20,355.00	20,355.00
	SUB-TOTAL: DEMOLITION WORKS				**20,355.00**
4	**CEILING**				
	Suspended Ceiling Finishes				
4.01	Supply & installation of 12mm thickness gypsum ceiling including all necessary fittings. Material: Kanuf or Equivelant **Location: As per drawing**	86	M²	165.00	14,190.00
4.02	Supply & installation of 12mm thickness gypsum bulkhead (without cove) including all necessary fittings. Material: Kanuf or Equivelant **Location: Curtain Palmet & above Glass Partitions**	58	LM	110.00	6,380.00
4.03	Supply & installation of 12mm thickness gypsum bulkhead (with cove) including all necessary fittings. Material: Kanuf or Equivelant **Location: Meeting Rooms & Phone Booths & Private Office**	52	LM	125.00	6,500.00
4.04	Supply and installation of access panels of 600 x 600 in the gypsum ceiling for future maintenances of FCU's services above the ceiling.	6	No	225.00	1,350.00
4.05	Supply and installation of access panels of 450 x 450 in the gypsum ceiling for future maintenances of other services above the ceiling.	2	No	200.00	400.00
4.06	Supply and installation of access panels of 450 x 450 in the gypsum ceiling for future maintenances of other services above the ceiling.	2	No	200.00	400.00
	Ceiling Finishes				-
4.07	Supply & application of 1 coat of primer & 2x coats of paint including preparation of gypsum Ceiling complete as per the layout. **Location: Closed Cabins Meeting Rooms Phone & Booths**	86	M²	45.00	3,870.00
4.08	Supply and applying of Industrial paint to existing ceiling slab in the areas as indicated below and in the layout and composed as follows: - Primer - Paint 1st and 2nd coat **Note: Includes MEP Services**	186	M²	65.00	12,090.00
	SUB-TOTAL: CEILING				**45,180.00**
5	**FLOORING**				
	Sub-Flooring				
5.01	Supply and installation of liquid waterproofing (2x coats) Material: Weberdry **Location: Pantry Area**	15	M²	100.00	1,500.00
5.02	Supply and installation of Self Leveling Material: Mapei **Location: Pantry Area**	435	M²	50.00	Rate Only
	Flooring Finishes				
5.03	**FL-01** Supply and installation of Carpet tiles as per design. Size (60cm x 60cm) **Location: Open Workstations, Closed Cabins And Social Area**	200	M²	150.00	30,000.00
5.04	**FL-02** Supply and installation of Herringbone LVT as per design. Size (TBC) **Location: Pantry and walkways**	78	M²	185.00	14,430.00

5.05	Supply and installation of SS transition strip (10mm T profile black powder coated) **Location:**	52	LM	80.00	4,160.00
	Skirting Finishes				
5.06	Supply and installation of woodne black skirting. Size 12mm x 100mm **Location: All Areas**	104	LM	80.00	8,320.00
	SUB-TOTAL: FLOORING				**58,410.00**
6	**PARTITIONS**				
	Gypsum & Glass				
6.01	**Double Layer NFR Gypsum (122mm)**: Supply and installation of 2600mm H Drywall **Gypsum partitions** with 12.5mm thick regular gypsum plasterboards double layer both sides with necessary framework and accessories complete with taping and jointing. **Location: Closed Csbins as per design**	107	M²	180.00	**19,260.00**
6.02	**TV supports:** Supply and installation of 18mm mdf support for TV brackets. **Location: As per design**	6	No	550.00	**3,300.00**
6.03	**Glass:** Supply and installation of Single glazed 12 mm thick clear tempered glass having Alpha 23 - 33dB Gemino system with head Channel Dimension: 26mm x 23mm and Bottom Channel Dimension: 26mm x 23mm finished with Aluminium Profile Finish: RAL 9005 Height of Partition: 2600 mm **Location: Closed Cabins as per design**	58	M²	600.00	**34,800.00**
	SUB-TOTAL: PARTITIONS				**57,360.00**
7	**WALL FINISHES**				
7.01	**W-01** Paint (Color TBC) Material: Jotun brand considered **Location: as per drawing**	184	M²	35.00	6,440.00
7.02	**W-02** Back Painted Glass (White) Material: Jotun brand considered **Location: Board Room** (writing glass)	10	M²	650.00	6,500.00
7.03	**W-03** Ceramic Tile Material: Brand considered RAK or Equivelant **Location: Pantry**	4	M²	375.00	1,500.00
	Acoustics				
7.04	**W-04** Supply and Installation of PET Acoustic wall panel Fixing with silicon/adhesive directly on wall as per design. • Polyester Acoustic Panel • 3D Type- Embossed (Curved surface) • Thickness: 12mm • Panel size: 1220x2440mm **Height considered for up to - 2600 mm** **Location: Phone booths & Meeting Room TV Walls** 	34	M²	750.00	25,500.00
	Windows & Blinds				-
7.05	Supply and installation of new full height roller blinds as per approved sample & in the below mentioned areas.	125	M²	120.00	Rate Only
	SUB-TOTAL: WALL FINISHES				**39,940.00**
8	**DOORS**				
	Framed Glass Doors				
8.01	**D-01** Supply and Installation of 12 mm thick framed glass door with Aluminum powder coated black finish including 600x32mm H handle, door stop, locks concealed in frame, locally sourced floor spring,pivots and raven drop seal. **Size:1074x2700 mm** **Location - All Closed Cabins excluding the Server Room**	7	No.	5,135.00	35,945.00
8.02	**D-02** Supply & installation of Non Fire-rated wooden access panel doors in paint finish. All complete as per the design with required hardwires, adhesive etc. **Server Room**	1	No.	4,500.00	4,500.00
	SUB-TOTAL: DOORS				**40,445.00**
9	**JOINERY**				
	Phone Booth				
	Pantry				
9.01	Pantry Counter:Supply and installation of the straight pantry base counter, Overhead counter, and Tall cabinet) with the carcass and shelves made with 18mm thick white Melamine MR.MDF and the finger pull shutters in New Mika laminate finish (external area only) including provisions for LED light at the bottom of the overhead cabinet (led by others) and space for fridge. The countertop and 40mm high fascia and 100mm high backsplash will be in a white Solid surface finish with necessary fittings including a pull-out drawer for the waste bin and Niche for fridge with overhead cabinet above the fridge as per the layout and image **Overall size: 15300 W x 650/400 D x 2400mm Ht.** 	1	No	28,750.00	28,750.00

9.02	Supply and installation of Bar height Island counter + one end open shelf with metal framing. The bar height Island counter is made with a 40mm thick tabletop + fascia in a white Solid surface finish with bottom side laminate finish and legs in one side solid surface finish with MDF structure and modesty panel with New mika laminate cladding on both sides including 50mm Dia SS brush finished footrest. The open shelf with metal frame, 25 x 25 x 2mm M.S metal tube frame with grey powder-coated finish including 1no shelf and 100mm high base in New Mika laminate finish with necessary fittings as per the layout and image **Overall Size: 4416 L x 900 D x 1050mm Ht** 	1	No	18,665.00	18,665.00
	Social Seating				
9.03	3-Level Step Seating: Supply and installation of seating made out of custom made mdf sofa complete with cushion with necessary fittings as per the layout and image **Overall size : 8000 L x D x 650mm Ht** 	1	No	19,500.00	19,500.00
	Collab Works Bench				
9.04	Supply and installation of custom made collab workspace bench made pout of emilam in wood finish. This is complete with necessary supports. Size: 4200mm x 600mm x 2600mm H 	1	No	7,630.00	7,630.00
	Private Office				
9.05	Supply and installation of custom made display cabinet with storage. Cabinet is made out emilam in wood finish and LED is included. Size: 4200mm x 400mm x 2600mm H 	1	No	14,200.00	14,200.00
9.06	Provision to supply and installation of TV wall with decorative wall paneling as per final design. Size: 4200mm x 400mm x 2600mm H 	1	No	12,555.00	12,555.00
	Boardroom TV Wall				
9.07	Provision to supply and installation of TV wall with decorative wall paneling as per final design. Size: 3700mm x 400mm x 2600mm H 	1	No	11,000.00	11,000.00
	Cloed Office				
9.07	Provision to supply and storage cabinet made out of melamine. Finish TBC Size: 1600mm x 400mm x 2600mm H 	1	No	4,200.00	4,200.00
	Printer Room				

9.08	Provision to supply and printer cabinet made out of melamine. Finish TBC Size: 1100mm x 400mm x 2600mm H 	1	No	2,800.00	2,800.00
	SUB-TOTAL: FIXED JOINERY				**119,300.00**
10	**LIGHTS**				
10.01	**Suspended LED Cylinder Light** Supply & installation of Suspended LED Cylinder Light with electronic ballast of color 4000 kelvin OR equivalent, all including PVC conduiting, wiring, flexible wire connector including all necessary accessories with white switches, as per the approved layout and design. Power: 20Watts Output Lumen: 1800Lm Size: D93XH150mm Control Gear: Non-Dimmable 4000K,Grey finish **Location - Reception,Workstations,Social Hub, Zen corner, Pantry**	20	Nos	385.00	7,700.00
10.02	**Recessed LED Spot Light** Supply & installation of Recessed LED dual spot Light with electronic ballast of color 4000 kelvin OR equivalent, all including PVC conduiting, wiring, flexible wire connector including all necessary accessories with white switches, as per the approved layout and design. Recessed LED spot Light Power: 12Watts Output Lumen: 1080Lm Control Gear: Non Dimmable 4000K,White **Location - Closed Cabins**	18	Nos	360.00	6,480.00
10.03	**Attic Conic Pendant Light** Supply & installation of Attic Conic Pendant Light with electronic ballast of color 4000 kelvin OR equivalent, all including PVC conduiting, wiring, flexible wire connector including all necessary accessories with white switches, as per the approved layout and design. Attic Conic Pendant Light Power: 12Watts Size: Dia 240mm Control Gear: Non-Dimmable 4000K,Black **Location - Workstation area**	4	Nos	936.00	3,744.00
10.04	**Suspended LED Linear Light** Supply & installation of Suspended LED Linear Light with electronic ballast of color 4000 kelvin OR equivalent, all including PVC conduiting, wiring, flexible wire connector including all necessary accessories with white switches, as per the approved layout and design. Suspended LED Linear Light Power: 68Watts Output Lumen: 5440Lm Size: L2100XW50XH75mm Control Gear: Non-Dimmable 4000K,grey **Location - Workstation Area**	9	Nos	811.00	7,299.00
10.05	**Flexible LED Strips** Supply & Installation of flexible LED strips with conduiting, wiring, including all necessary accessories, as per the approved layout and design. Power: 14.5 Watts/Mtr Output Lumen: 2100 Lm/mtr Aluminum Profile W/ Diffuser Size: 17x15 Diffuser: Frosted Constant Voltage Driver Control Type:No-Dimmable output Voltage: 24V/DC **Location - wall washing light for boardroom, meeting rooms, Reception, creator studio, phonebooths,meeting pod** & collaboration area	52	Lm	180.00	9,360.00
10.06	**LED Track Spot Light** Supply & installation of LED Track Spot Light with electronic ballast of color 4000 kelvin OR equivalent, all including PVC conduiting, wiring, flexible wire connector including all necessary accessories with white switches, as per the approved layout and design. LED Track Spot Light Power: 20Watts Output Lumen: 1800Lm Control Gear: Non Dimmable Osram Driver 	6	No's	385.00	2,310.00
10.07	3 Line single Phase Track Rail Power Supply: One Side Endcap: One side	12	Lm	250.00	3,000.00
10.08	3 Line Single Phase Internal Connector				
10.09	3 Line Single Phase Right Angle Connector				
10.10	Track Rail Suspension Kit				
10.11	**Location - Creator studio**				

10.12	Supply & installation of light control pole push switch 10 A - 250 V, Conforns to BS EN 60669 -1 : 2000 OR equivalent, in standard WHITE PVC. and: MK or Legrand	3	Nos	450.00	1,350.00
10.13	Supply & installation of light control pole push switch 10 A - 250 V, Conforns to BS EN 60669 -1 : 2000 OR equivalent, in standard WHITE PVC.	8	Nos	550.00	4,400.00
10.14	Supply & installation of light control pole push switch 10 A - 250 V, Conforns to BS EN 60669 -1 : 2000 OR equivalent, in standard WHITE PVC.	8	Nos	575.00	4,600.00
10.15	Supply & installation of GI tray above the ceiling for lighting with required supports and suspension.	45	Lm	100.00	4,500.00
	SUB-TOTAL: LIGHTS				**54,743.00**
11	**HVAC WORKS**				
	FCU UNITS				
11.01	Relocation of Exiting FCUs	1	Nos	3,250.00	Rate Only
11.02	Performance test for Existing FCUs	1	Item	4,000.00	4,000.00
11.03	Supply and Installation of Thermostat (Honeywell)	4	Nos	350.00	1,400.00
11.04	Exiting chilled water pipe insulation is damaged- If required to change	1	Item	8,600.00	Rate Only
11.05	Supply and Installation of By Pass Type VAV's if required for Closed Cabins and Meeting room (BetaCad)	4	Nos	3,600.00	Rate Only
	DUCTING				
11.06	Modifiction of Duct works to suit the new Layout (Assumed whole office is Ceiling) by reusing existing main ducts only branches modified and Return Ducts	1	Item	36,500.00	36,500.00
11.07	Modification of Fresh Air Ducting (If the Machines are relocated)	1	Item	4,750.00	4,750.00
11.08	Supply and Installation of Volume Control Damper (Desert Air)	1	Item	5,900.00	5,900.00
11.09	Supply and Installation Plenium Box	1	Ls	3,000.00	3,000.00
11.10	Supply and Installation of Flexible duct & Acoustic Linear	1	Ls	2,400.00	2,400.00
	DIFFUSERS & GRILLS				
11.11	Supply and Installation of Air Outlet(Supply & Return) - Winner (Assumed All are Sauare Diffusers)	1	Item	11,500.00	11,500.00
	Testing & commissioning				-
11.12	Pressure Test - If Machines are relocated	1	Item	2,300.00	Rate Only
11.13	Chemical flushing - If Machines are relocated	1	Item	12,000.00	Rate only
11.14	Air Balancing	1	Item	3,000.00	3,000.00
	SUB-TOTAL: HVAC WORKS				**72,450.00**
12	**ELECTRICAL**				
	SMDB & DB				
12.01	Modification of DB	1	Nos	4,200.00	4,200.00
	SWITCH GEAR				
12.02	Supply and Installation of Power for FCUs & FACP	5	Nos	450.00	2,250.00
12.03	Supply and installation of 13A single switched socket(MK- PVC)	15	Nos	450.00	6,750.00
12.04	Supply and installation of 13A Twin Socket (MK- PVC)	20	Nos	475.00	9,500.00
12.05	Supply and Installation of Floor Box (2 Twin 4 Data) (, Workstation, Offices, Meeting Room)	20	Nos	850.00	17,000.00
12.06	Allow cost for power provision to the lighitng with necessary accessories(PVC Conduit PVC Wires) Internal Lighting Only	125	Nos	250.00	31,250.00
12.07	Allow cost for installation of lighting	125	Nos	20.00	2,500.00
12.08	Supply and installation of Switches	12	Nos	375.00	4,500.00
	Cable Tray & Trunking				
12.09	Allow cost for the cable tray & trunking - Lighting	1	Item	4,750.00	4,750.00
12.10	Allow cost for the cable tray & trunking - Power	1	Item	4,750.00	4,750.00
12.11	Allow cost for ELV Trays and Trunking	1	Item	4,200.00	4,200.00
	DATA & CCTV (Containment Only)				
12.12	Allow conduiting for the Telephone & Data points	1	Item	3,500.00	3,500.00
12.13	Allow cost for CCTV,speakers	1	Item	3,000.00	3,000.00
	Sundries				

12.14	Testing and Commissioning	1	Item	4,200.00	4,200.00
12.15	DEWA Approvals	1	Item	5,200.00	Rate Only
	Subtotal - Electrical				**102,350.00**
13	**Fire Fighting & Fire Alarm**				
13.01	Fire alarm control panel with voice evacuation	1	No	Excluded until Fire Fighting & Fire Alarm drawing is approved by Civil Defense (DCD)	
13.02	Control module with back box for interfacing with 24x7 DCD Panel	6	No		
13.03	Monitor module with back box for interfacing with Building FACP	4	No		
13.04	new smoke detectors with standard base	2	No		
13.05	new Void smoke detectors with LED indicator	9	No		
13.06	manual call point with back box	2	No		
13.07	Speaker with flasher with back box	2	No		
13.08	Sounder with back box	1	No		
13.09	Installation of FACP	1	No		
13.10	Installation of above FAS devices with cable & accessories	26	No		
13.11	Relocation of Existing smoke detector-14, speaker-2, Sounder-1	17	No		
13.12	Programming, Testing & Commissioning	1	No		
13.13	DCD Certificate Charges	1	No		
	Subtotal - Fire Fighting				**-**
14	**PLUMBING WORKS**				
14.01	Supply and installation of PPR / Pex pipes for water supply to Kitchen Sink	7	mts	85.00	595.00
14.02	Supply and installation of UPVC piping for Drainage piping works.	7	mts	115.00	805.00
14.03	Supply & Installation of isolation valves, traps & flexible connections.	1	Ls	1,600.00	1,600.00
14.04	Supply and installation water Hammer Aristor	1	No	555.00	555.00
14.05	Installation of below quoted Sink and mixer	1	No	850.00	850.00
14.06	Pressure test for Water supply lines & gravity flow test for drain lines-new piping work	1	Ls	975.00	975.00
14.07	Testing & Commissioning of Plumbing system.	1	Ls	1,650.00	1,650.00
14.08	Supply of Kitchen Sik including accessories - Pantry	1	Ls	2,250.00	2,250.00
	Note :Gravity test included. Coring works excluded.				
	Subtotal - Plumbing				**9,280.00**
15	**IT WORKS**				
	Structured cabling System for all service CAT 6 for DATA, Voice and WIFI CCTV and Access Controller (Brand - DATACOM)				
15.01	Supply Installation of CAT 6 Cable Face Pale and CAT 6 JACK, Connecters, Both Side Termination and Testing , levelling (DATA and Voice) DATACOM Brand 25 year Warranty AVG 70 meter length	40	No.	218.00	8,720.00
15.02	Supply and installation of conduiting for Data and Voice for the above mentined points including the required points.	20	No.	150.00	3,000.00
15.03	Supply & installation of GI tray for the data cables with required supports and suspension.	40	No.	100.00	4,000.00
15.04	DATACOM CAT 6 24 Port patch Panel shielded with full Load	3	No.	270.00	Rate Only
15.05	1 meter Cat.6 DATACOM 23 AWG PVC Patch Cord	162	No.	11.00	Rate Only
15.06	2 Meter Cat.6 DATACOM 23 AWG PVC Patch Cord	162	No.	14.00	Rate Only
15.07	Supply Installation of 42 U Server Rack 800 x 1000 rack with, 1 Shelf,	1	No.	3,600.00	Rate Only
15.08	Power PDU 12 BAY Vertical DATACOM 32 A	1	No.	233.00	Rate Only
15.09	1 U Cable manager. DATACOM	3	No.	38.00	Rate Only
15.10	ISP FIber Cable Single Mode 6 Coe Fiber Cabling from Main Server room to Client IT Room Including Cable Supply, with all Fiber accessories, Pigtile,SC APC Module, Patch panel, ODF box, Fiber patch Cord, Including Fiber Splicing and Testing	1	No.	3,750.00	Rate Only
	SUB-TOTAL: IT WORKS				**15,720.00**
	SUMMARY TOTAL WORKS				
1	**SUBMISSION OF DRAWINGS**				**20,000.00**
2	**PRELIMINARIES**				**15,000.00**
3	**DEMOLITION WORKS**				**20,355.00**
4	**CEILING**				**45,180.00**
5	**FLOORING**				**58,410.00**
6	**PARTITIONS**				**57,360.00**
7	**WALL FINISHES**				**39,940.00**
8	**DOORS**				**40,445.00**
9	**JOINERY**				**119,300.00**
10	**LIGHTS**				**54,743.00**
11	**HVAC WORKS**				**72,450.00**
12	**ELECTRICAL**				**102,350.00**
13	**FIRE FIGHTING**	**Excluded until Fire Fighting & Fire Alarm drawing is approved by Civil Defense (DCD)**			
14	**PLUMBING WORKS**				**9,280.00**
15	**IT WORKS**				**15,720.00**
		GRAND TOTAL (EXCL VAT)			**670,533.00**

PAYMENT TERMS

50% Advance Payment upon order confirmation
25% Progress payment upon 50% project completion
20% Progress payment upon 80% project completion
5% Upon 100% project delivery and handing over Completion Certificate.
*5% VAT to be added to the invoice
*Advance payment is an immediate payment and to be made within three (3) days of our invoice submission.
*All payments except for the advance payment must be made within seven (7) days of the receipt of our invoices.

TERMS AND CONDITION

1	We reserve the right to requote in case any material change, size Quantity or Specs, additional works not included in the above works will be
2	All Samples and Material List to be checked and approved by Client prior working on site
3	Power and Water consumption during the project to be paid by client
4	Our offer excludes all approval related fees and gate passes
5	Additional requirements will be subjected to resonable additional costs.
6	One Year Defect Liability period to be included in the contract
7	Loose Furniture, Appliances, Glass fascade, External Signage and Coring are excluded
8	All kitchen equipment is excluded from our scope and to be executed by client
9	Pantry design not confirmed but we have provided alternative option within the same budget
10	Electrical Exclusions: Power Upgrade, Motion Sensors
11	Fire Fighting Works is excluded from this quotation. Once FF/FA drawing is approved we can proivde accurate cost
12	IT some rates provided but excluded from this Quote
13	Office Deep Cleaning is not included from our scope.
14	Frosting & Smart Film is excluded from this Quote
15	Ceiling suspended panel & planter box dividers removed from scope to achieve budget

for Inis Interiors
Stephen Duffy
Office 101, Building A1, Silicone Oasis
Dubai | U.A.E.
Mobile: +971 551037822
Email: stephen@inisinterior.com

Client Approval:
Name:
Signature
Date
Company Stamp: