Friday, October 06, 2023

LVMH Beauty
Dubai, United Arab Emirates

FTAO: Ms. Viktoriia Aseeva

Dear Ms. Viktoriia Aseeva,

LVMH BEAUTY, D3, DUBAI, UAE
INTERIOR FITOUT & MEP WORKS QUOTATION, REVISION 1

With reference to our previous offer reference number LVMH231002quotsp0 – K2795 dated 02nd October 2023, we hereby submit our Offer (VE Offer) for the sum of:

Total Amount AED: 4,150,089.00

Four Million One Hundred Fifty Thousand and Eight-Nine Dirhams Only

Our Offer excludes VAT and is valid for 30 days only.

We would welcome the opportunity to discuss the project further and where necessary to alter our proposal to meet your exact requirements and budget.

If you should require anything further, please do not hesitate to contact me.

Yours sincerely,

For and on behalf of KOJ Interiors LL

Warren L Gemlik FRICS FCIOB MCIArb
Group Development Director

warren.gemlik@kojamjoom.com
+971 50 435 4882

Project Ref No.: K2795

Date: Friday, October 6, 2023

Revision: 1

Issued by: Shiju Purayil

BILL OF QUANTITIES

For the

M/s. LVMH BEAUTY

Interior Fitout & MEP works at LVMH Beauty

At

D3, Dubai, UAE.

By

KOJ Interiors LLC
Office 1704, 17th Floor
Festival Tower, DFC
Dubai,
UAE

Email: info@kojinteriors.com
Web: www.kojinteriors.com

TENDER DOCUMENT

INDEX

1 Annexure 1 - Bill Of Quantities

2 Annexure 2 - Qualifications & Exclusions

3 Annexure 3 - VE Options

BILL OF QUANTITIES

MAIN SUMMARY **Rev 1- VE**

SL #	Item Description	Quantity	Unit	Rate	Amount (AED)
	MAIN SUMMARY				
	Total for ADP-LOEWE Area				732,650.00
	Total for BPC area				1,851,113.00
	Total for Givenchy & Kenzo				1,235,244.00
	Preliminaries				331,082.00
	GRAND TOTAL VE				**4,150,089.00**

SL #	Item Description	Quantity	Unit	Rate	Amount (AED)
	Demolition Works				
A	Allow for removing, packing and shifting of existing loose furniture and Office furniture to the Client's storage area within the Dubai.	1	L/s	Excluded as per RFI Reply	
B	Allow for removal of existing Gypsum Partitions and cart away the debris to the Municipality dump yard.	1	L/s		
C	Allow for removal of the existing Fitted Furniture and cart away the debris to the Municipality dump yard.	1	L/s		
D	Allow for removal of Existing Floor Finishes and cart away the debris to the Municipality dump yard.	1	L/s		
E	Allow for removal existing Ceiling finishes and cart away the debris to the Municipality dump yard.	1	L/s	16,657.00	16,657.00
F	Allow for removal existing Roller Blinds and cart away the debris to the Municipality dump yard.	1	L/s		
G	Allow for removal existing Light fittings and cart away the debris to the Municipality dump yard.	1	L/s		
H	Allow for making new Window Opening as per the layout.	1	L/s		
J	Allow for modification of existing Raised Access Floor to receive new floor finishes.	1	L/s		
	Carried to the Summary (AED)				**16,657.00**

SL #	Item Description	Quantity	Unit	Rate	Amount (AED)
	Floor Finishes				
	Supply and Installation of Carpet Flooring with glue on existing raised flooring.				
A	To ADP-LOEWE Area.	191	sqm	179.00	34,189.00
	Wall Finishes.				
	Supply and Installation of Printed Wallpaper to the Walls.(Design to be provided by the client)				
B	To walls	48	sqm	185.00	8,880.00
	Supply and Application of White Fenomastic Paint to the new and existing walls at Proposed Area and Corridor wall				
C	To wall	93	sqm	25.00	2,325.00
	Supply and application of Special Paint.				
D	To existing columns & Loewe Manager Rm	30	sqm	149.00	4,470.00
	Supply and Installation of Green PU painted MDF cladding including all necessary accessories and supports.				
E	To the meeting entrance area.	5	sqm	612.00	3,060.00
	Supply and Installation of Fabric Padded Paneling with LED strip Lights including all necessary backing.				
F	to MFK Manager Room, Size : 2700 x 2600mm H	1	No	5,248.00	5,248.00
	Supply and Installation of MDF Skirting with PU Painted finish and Aluminium U Channel.				
G	100mm high Skirting	66	Lm	101.00	6,666.00
	Carried to the Summary (AED)				**64,838.00**

SL #	Item Description	Quantity	Unit	Rate	Amount (AED)
	Ceiling Finishes				
	Supply and installation of Gypsum ceiling using 12.5mm thick Gypsum on GI Metal suspension system including white Fenomastic paint.				
A	Gypsum Plain ceiling to entire area	191	sqm	163.00	31,133.00
B	Recessed Light Cove 75 x 100mm H	167	Lm	82.00	13,694.00
C	Gypsum Pelmet	20	Lm	95.00	1,900.00
	Wall Partitions				
	Supply and installation of Glass Partitions with aluminium frame in Black paint including all supports. (All doors are measured separately)				
D	2600mm high.	25	sqm	541.00	13,525.00
E	1200mm high.	13	sqm	541.00	7,033.00
F	to the meeting rooms with Smart glass ; 2600mm high	14	sqm	2,230.00	31,220.00
	Supply and Installation Gypsum Partition using 12.5mm thick Gypsum board in GI metal frame. (Finishes measured separately)				
G	100mm thick Gypsum Partitions.	51	sqm	203.00	10,353.00
H	Allow for closing the existing door openings.	1	Item	676.00	676.00
	Supply and Installation of Operable Partition Series 631 – nominally 76mm thick panel with Acoustic Rating of 51 STC based on laboratory test results.				
J	Partition with Green PU Painted MDF , Size : 5160 x 2600mm H.	1	No	59,058.00	59,058.00
	Carried to the Summary (AED)				**168,592.00**

SL #	Item Description	Quantity	Unit	Rate	Amount (AED)
	Doors and windows				
	Supply and Installation of Glass Door with Aluminium frame in black paint finish including the hardware.				
A	Size : 800 x 2400mm H	6	no	3,784.00	22,704.00
B	to the Meeting Room with Smart Glass Size : 900mm x 2400mm H	2	no	6,757.00	13,514.00
	Suply and installation of Single Leaf Wooden door with handle and all necessary hardware				
C	Size : 1000mm x 2400mm H	1	no	4,606.00	4,606.00
	Supply and Installation of Glass Window with Aluminium frame in black paint finish including the hardware.				
D	Size : 1900 x 1200mm H	3	no	1,352.00	4,056.00
	Carried to the Summary (AED)				**44,880.00**

SL #	Item Description	Quantity	Unit	Rate	Amount (AED)
	Joinery Works				
	Supply and Installation of Full height Storage Cabinet using with MDF in Green PU Painted shutters and white melamine carcass including LED Strip Lights in the open shelves all necessary accessories.				
A	Size : 2430mm x 450 x 2400mm H	2	No	7,405.00	14,810.00
	Supply and Installation of Low height Storage Cabinet using with MDF in Oak/wenge Veneer Finish including all necessary accessories.				
B	at Main Entrance 3230 x 450 x 900mm H	1	No	5,114.00	5,114.00
C	For the Workstations ; Size : 1500 x 400 x 900mm H	5	No	2,375.00	11,875.00
D	For the Workstations ; Size : 2420 x 400 x 900mm H	1	No	3,832.00	3,832.00
E	Loewe Manager ; Size : 2215 x 400 x 900mm H	1	No	3,507.00	3,507.00
F	HR & MFK Manager ; Size : 1200 x 400 x 900mm H	2	No	1,900.00	3,800.00
	Supply and Installation of Wall hung shelves MDF with PU Paint including all necessary supports and accessories. (All Display items and Artworks are excluded)				
G	200mm Wide	5	Lm	504.00	2,520.00
	Supply and Installation of Full height Storage Cabinet using with Grooved MDF in Stained in mtaching to veneer finish shutters including all necessary accessories.				
H	535 + 1930 x 450 x 2600mm H	1	No	10,147.00	10,147.00
	Carried to the Summary (AED)				**55,605.00**

SL #	Item Description	Quantity	Unit	Rate	Amount (AED)
	Joinery Works (Cont'd...)				
	Supply and Installation Curved Wooden cladding to the existing column using Grooved MDF stained in Matching to veneer finish Including white Corian counter and LED strips				
A	Overall Size : 1610 dia x 1000mm H	1	no	7,172.00	7,172.00
	Supply and Installation of Decorative Open shelf using Metal in Black PVD finish and PU Painted MDF including LED Strip Lights. (All Display items and Artworks are excluded)				
B	To General Manager Room; Size : 2200mm W x 2600mm H	1	No	11,845.00	11,845.00
	Roller Blinds				
C	Supply and Installation of Manually Operated Roller Blinds	61	m2	102.00	6,222.00
	Signage Works				
D	Signage 'Maison Fondee en-2009' Size : 800 x 250mm H	1	No	4,055.00	4,055.00
	Carried to the Summary (AED)				**29,294.00**

SL #	Item Description	Quantity	Unit	Rate	Amount (AED)
	Light Fittings **Supply of Lights. All cabling and fixing works are considered separately)**				
A	Downlight For Meeting Rooms Power：15W; CCT：4000K CRI： ≥ 90;Beam angle：24o Input Voltage：48V;IP Rate ： IP20 Dimension: L2400mm;Material Quality: AL Dimmable.	12	Sets	541.00	6,492.00
B	Downlight Power：15W; CCT：4000K;CRI： ≥ 90 IP Rate ： IP20;Input Voltage：185-265V Dimension: Φ100mm x H90MM; Material Quality: AL	32	no	399.00	12,768.00
C	Downlight 300mm Long Power：8W;CCT：4000K;CRI： ≥ 90;Beam angle：60°;IP Rate ： IP20;Input Voltage：24V;Dimension: L300mm;Material Quality: AL	60	no	263.00	15,780.00
D	Hanging Pendant Lights Power：28W*2 CCT：4000K CRI： ≥ 90•Beam angle：36° Input Voltage：185-265V Dimension: Φ300mm Dimmer:ON/OFF Material Quality: AL4PCS*	6	no	359.00	2,154.00
E	Hanging Pendant Lights -2Nos Power：28W*2;CCT：4000K;CRI： ≥ 90;Beam angle：36°;Input Voltage：185-265V;Dimension: Φ300mm;Dimmer:ON/OFF;Material Quality: AL	4	Sets	1,055.00	4,220.00
F	Linear Profile Lights	21	m	609.00	12,789.00
	Carried to the Summary (AED)				**54,203.00**

SL #	Item Description	Quantity	Unit	Rate	Amount (AED)
	MEP WORKS				
	MECHANICAL, ELECTRICAL AND PLUMBING Misc				
A	Builders works in connection with MEP works, chasing, making good etc	1	item	6,258.00	6,258.00
	ELECTRICAL WORKS				
	SWITCHGEARS				
B	Modification of existing DB (power upgradation excluded)	1	no.	4,106.00	4,106.00
	CABLE TRAY & TRUNKING				
	Supply & Installation of HDGI cabletray & trunkig as per drawings including all the required accessaries				
C	100 X 50mm tray for data	30	m.	73.00	2,190.00
D	50 X 50mm trunking for lights & power	30	m.	95.00	2,850.00
	SMALL POWER OUTLET				
	Supply and installation of small power outlets as shown on the drawings and as specified including the necessary copper insullated wire and 25mm PVC conduits				
E	Floorbox (1 twin socket +2 data provision)	3	no.	822.00	2,466.00
F	Floorbox (2 twin socket +4 data provision)	17	no.	941.00	15,997.00
G	13A Single switch socket - PVC white finish	4	no.	318.00	1,272.00
H	13A twin switch socket - PVC white finish	2	no.	371.00	742.00
J	13A single switch socket with USB outlet-floor mounted	1	no.	729.00	729.00
K	13A spur outlet	2	no.	490.00	980.00
	Carried to the Summary (AED)				**37,590.00**

SL #	Item Description	Quantity	Unit	Rate	Amount (AED)
	Install Light fixtures and associated items as per the drawings with plug in type ceilig rose and 2.5mm copper insulated wire and 20 mm pvc conduit				
A	Installation of ceiling lights	1	item	18,541.00	18,541.00
	LIGHTING SWITCHES				
B	1 Gang 1 way switches	6	no.	153.00	918.00
C	2 Gang 1 way switches	2	no.	179.00	358.00
D	Supply & installation of stand alone PIR sensors in the open space & offices	12	no.	808.00	9,696.00
E	Supply & Installation of touch panel in the meeting rooms	1	item	52,973.00	52,973.00
	ELV Containments				
	Supply & Installation of 25mm pvc conduits for the ELV system				
F	Data points	73	no.	133.00	9,709.00
G	AV points on meeting room	2	no.	133.00	266.00
	AIR CONDITIONING WORKS				
	HVAC UNITS				
	We assume that the existing FCU have enough capacity to cool the area and not cosnider any new FCU				
H	Relocation of existing FCU	3	nos	3,179.00	9,537.00
J	Perfomance testing for existing AC machines	3	nos	1,855.00	5,565.00
K	Thermostat for new VAV	6	no.	676.00	4,056.00
L	New VAV -bypass type for all closed rooms	6	no.	4,106.00	24,636.00
	Carried to the Summary (AED)				**136,255.00**

SL #	Item Description	Quantity	Unit	Rate	Amount (AED)
	DUCT WORKS **Modification of existing ductwork with insulated angles,elbows,reducers,supports and all other items required .**				
A	Modification of existimng supply & return air	1	Item	17,482.00	17,482.00
B	Flexible duct & plenum boxes	1	item	1,987.00	1,987.00
	DUCT CONTROL DEVICES				
	Supply & Installation of Volume control Dampers for supply,fresh &extract ducts				
C	Supply& Installation of VCD	1	item	4,238.00	4,238.00
	GRILLS & DIFFUSERS				
D	Supply & Installation of grills & diffusers	1	item	8,344.00	8,344.00
	FIRE ALARM DETECTION & ALARM SYSTEM				
E	Supply and install new smoke detector	7	no.	1,690.00	11,830.00
F	Relocation of smoke detector	5	no.	609.00	3,045.00
G	Supply and install new sounder with flasher	1	no.	2,163.00	2,163.00
H	Supply and Install manual call point/break glass	1	no.	1,757.00	1,757.00
J	Supply & Installation of new FACP without network card		no.	18,919.00	Rate only
L	Integration of new FACP to the existing FACP	1	Item	9,460.00	9,460.00
M	Supply, installation and connection of I/O module interface - 1 INPUT and 1 OUTPUT signal.	1	no.	1,419.00	1,419.00
N	Testing & Commisioning	1	no.	9,460.00	9,460.00
	Carried to the Summary (AED)				**71,185.00**

SL #	Item Description	Quantity	Unit	Rate	Amount (AED)
	FIRE FIGHTING SYSTEM				
	It is assumed that the landlord can provide isolation of the system, without cost, for any modications				
A	Fire extinguisher set, attached to wall on brackets.5 kilogram of dry powder and 5 kilograms of CO2 within electrical room	2	set	888.00	1,776.00
B	Co2 Extinguisher	2	no.	609.00	1,218.00
C	Install new pendnet fire sprinkler heads, valves and supplies,	12	no.	1,149.00	13,788.00
D	Relocation of existing sprinkler	8	no.	744.00	5,952.00
E	Opening and closing of the Zone Control Valve	1	Item	6,757.00	6,757.00
	EMERGENCY EXIT LIGHTING				
	(If KOJI are allowed to supply and install as per KOJI standards)				
F	Supply & Installation of new Emergency light,self contained	4	no.	1,217.00	4,868.00
G	Supply & Installation of new Exit light,self contained	2	no.	1,487.00	2,974.00
	COMMISSIONING				
H	Testing and commissioning of Electrical works	1	item	1,352.00	1,352.00
J	Testing and commissioning of air conditioning	1	item	10,811.00	10,811.00
K	Testing and commissioning of fire fighting	1	item	4,055.00	4,055.00
	Carried to the Summary (AED)				**53,551.00**

SL #	Item Description	Quantity	Unit	Rate	Amount (AED)
	Summary				
	Page 1				16,657.00
	Page 2				64,838.00
	Page 3				168,592.00
	Page 4				44,880.00
	Page 5				55,605.00
	Page 6				29,294.00
	Page 7				54,203.00
	Page 8				37,590.00
	Page 9				136,255.00
	Page 10				71,185.00
	Page 11				53,551.00
	Carried to the Main Summary (AED)				**732,650.00**

SL #	Item Description	Quantity	Unit	Rate	Amount (AED)
	Demolition Works				
A	Allow for removing, packing and shifting of existing loose furniture and Office furniture to the Client's storage area within the Dubai.	1	L/s	Excluded as per RFI Reply	
B	Allow for removal of existing Gypsum Partitions and cart away the debris to the Municipality dump yard.	1	L/s		
C	Allow for removal of the existing Fitted Furniture and cart away the debris to the Municipality dump yard.	1	L/s		
D	Allow for removal of Existing Floor Finishes and cart away the debris to the Municipality dump yard.	1	L/s		
E	Allow for removal existing Ceiling finishes and cart away the debris to the Municipality dump yard.	1	L/s	45,270.00	45,270.00
F	Allow for removal existing Roller Blinds and cart away the debris to the Municipality dump yard.	1	L/s		
G	Allow for removal existing Light fittings and cart away the debris to the Municipality dump yard.	1	L/s		
H	Allow for modification of existing Raised Access Floor to receive new floor finishes.	1	L/s		
	Carried to the Summary (AED)				**45,270.00**

SL #	Item Description	Quantity	Unit	Rate	Amount (AED)
	Floor Finishes				
	Supply and Installation of 18mm thick Engineered Wood Flooring on exsiting raised flooring.				
A	Oak Finish to SC1, SC2, F1, F3, F4, F8, Meeting Rooms, IT Store, IT1 & HR Rooms.	237	sqm	218.00	51,666.00
B	to Break out, Lounge and Common Areas.	483	sqm	218.00	105,294.00
	Supply and Installation SS Metal Floor Trim in PVD finish to the Door opening				
C	Metal Floor Trim	16	Lm	109.00	1,744.00
	Wall Finishes				
D	Supply and Installation 100mm High using MDF with PU Painted finish including Aluminium Channel.	175	Lm	101.00	17,675.00
E	Supply and Application of Fenomastic Paint to the existing and proposed Walls.	431	sqm	25.00	10,775.00
F	Supply and Application of Special Paint to the existing coloumns and Meeting Room Including Gypsum Lining.	127	sqm	149.00	18,923.00
	Supply and installation of veneered MDF Cladding Including all necessary supports and accessories.				
G	to HR7, HR6, IT1, F1, F4, SC1	70	sqm	699.00	48,930.00
	Supply and Installation of MDF with PU Paint finish cladding including all necessary supports and accessories.				
H	to Small Meeting Room with Glossy finish.	48	sqm	612.00	29,376.00
J	Fluted Cladding	30	sqm	1,080.00	32,400.00
	Supply and Installation of Wallcovering including Gypsum Lining.				
K	To Lounge Area	6		273.00	1,638.00
	Carried to the Summary (AED)				**318,421.00**

SL #	Item Description	Quantity	Unit	Rate	Amount (AED)
	Ceiling Finishes				
	Supply and installation of Gypsum ceiling using 12.5mm thick Gypsum on GI Metal suspension system including white Fenomastic paint.				
A	Gypsum Plain Ceiling To SC1, SC2, F1, F2, F3, F4, F8, Meeting Rooms, It Store, IT1 & HR Rooms.	237	sqm	163.00	38,631.00
B	Recessed Light Cove 75 x 100mm H	176	Lm	82.00	14,432.00
C	Gypsum Pelmet	96	Lm	95.00	9,120.00
	Supply and Installation of 40 x 100mm Wooden Slat Ceiling at 100mm c/c using Veneered MDF including all suspensions.				
D	Wooden Slat Ceiling to Break out & Lounge area.	121	sqm	1,080.00	130,680.00
	Supply and application of White Fenomastic paint to the Open ceiling and all the MEP services.				
E	White Paint to Break out, lounge & common areas.	483	sqm	60.00	28,980.00
	Wall Partitions				
	Supply and installation of Glass Partitions with aluminium frame in Black paint including all supports. (All doors are measured separately)				
F	2600mm high.	150	sqm	595.00	89,250.00
G	1200mm high.	6	sqm	541.00	3,246.00
H	to the meeting rooms with Smart glass ; 2600mm high	5	sqm	2,230.00	11,150.00
J	Big Meeting & Adjust Meeting Room Partitions & Doors	1	Item	Existing to be retained	
	Carried to the Summary (AED)				**325,489.00**

SL #	Item Description	Quantity	Unit	Rate	Amount (AED)
	Wall Partitions (Cont'd…)				
	Supply and Installation Gypsum Partition using 12.5mm thick Gypsum board in GI metal frame. (Finishes measured separately)				
A	100mm thick Gypsum Partitions.	250	sqm	203.00	50,750.00
	Doors and Windows				
	Supply and Installation of Glass Door with Aluminium frame in black paint finish including the hardware.				
B	Size : 800 x 2400mm H	12	no	3,784.00	45,408.00
C	with Smart Glass Size : 800 x 2400mm H	1	no	6,757.00	6,757.00
	Supply and Installation of Automatic Sliding Glass Door using 10mm thick Tempered Glass including the hardware.				
D	Size : 1000 x 2600mm h	1	no	22,298.00	22,298.00
E	Main Entrance Doors	1		to be retained the existing.	
	Joinery Works				
F	Allow for the repair of existing Pantry cabinet .	1	Item	900.00	900.00
	Supply and installation of Shelf using veneered MDF including all necessary supports and accessories				
G	Open shelf to HR7 Room Size : 2430 x 450 x 2600mm H	1	No	6,820.00	6,820.00
H	To F1, F3, Meeting Room, Wall Hung Shelf 300mm Wide	9	Lm	504.00	4,536.00
J	To Lounge Area 4610 x 500 x 2400mm H	1	No	15,128.00	15,128.00
K	To break out area 2830 x 450 x 2400mm H	1	No	9,287.00	9,287.00
	Carried to the Summary (AED)				**161,884.00**

SL #	Item Description	Quantity	Unit	Rate	Amount (AED)
	Joinery Works (Cont'd…)				
	Supply and Installation High Table using Marble counter Top and cladding and Veneered MDF in accordance with the provided 3D.				
A	To break out area; Size : 3050 x 1010 x 900mm H	1	No	9,784.00	9,784.00
	Supply and Installation Storage Cabinet using Veneered MDF including all necessary accessories and Supports.				
B	Full height to IT service Room ; Size : 4170 x 600 x 2600mm H	2	No	14,824.00	29,648.00
	Supply and Installation Storage Cabinet using Laminated MDF including all necessary accessories and Supports.				
C	Low height to IT service Room ; Size : 4400 x 600 x 1000mm H	1	No	5,700.00	5,700.00
D	Low height to IT service Room ; Size : 5360 x 600 x 1000mm H	1	No	6,943.00	6,943.00
E	Low height to IT service Room ; Size : 2000 x 600 x 1000mm H	1	No	2,591.00	2,591.00
	Roller Blinds				
F	Supply and Installation of Manually Operated Roller Blinds	310	m2	102.00	31,620.00
	Signage Works				
G	Signage 'LVMH Beauty' Location : Near SC30 Workstation Size : 1700 x 500mm H	1	No	6,757.00	6,757.00
	Carried to the Summary (AED)				**93,043.00**

SL #	Item Description	Quantity	Unit	Rate	Amount (AED)
	Light Fittings **Supply of Lights. All cabling and fixing works are considered separately)**				
A	Decorative Pendant Light Power：20W;CCT：4000K;CRI： ≥ 90;Beam angle：60°;Input Voltage：185-265V;IP Rate : IP20;Dimension: Φ600mm;Material Quality: AL （Inner & outer WhiteMatte）	14	Nos	2,028.00	28,392.00
B	Downlight 300mm Long Power：8W;CCT：4000K;CRI： ≥ 90;Beam angle：60°;IP Rate : IP20;Input Voltage：24V;Dimension: L300mm; Material Quality : AL	150	no	181.00	27,150.00
C	Track -4 Nos With Track Light (4600mm Length) - Magnetic type Power：12W;CCT：4000K;CRI： ≥ 90;Beam angle：24°;Input Voltage：48V;IP Rate : IP20;Dimension: L4600mm.	30	no	2,343.00	70,290.00
D	Hanging Linear Light 4600mm Long Power：30W/M;CCT：4000K;CRI： ≥ 90•Beam angle：36°;Input Voltage：24V;Dimension: L4600mm;W80;H75mm;Dimmer:ON/OFF;Material Quality: AL	20	no	1,891.00	37,820.00
E	Hanging Pendant Light Power：10W;CCT：4000K;CRI： ≥ 90;Beam angle：36°;Input Voltage：185-265V;Dimension: Φ200mm;Dimmer:ON/OFF;Material Quality: Glass	14	no	528.00	7,392.00
F	Linear continuos Light ower：40W/M;CCT：4000K;CRI： ≥ 90;Beam angle：120°;Input Voltage：185-265V;Dimension: L1200mm*W100*H40mm;Dimmer:ON/OFF;Material Quality: iron	16	no	406.00	6,496.00
G	Allow for Dimmable drivers for the Meeting Rooms.	1	Item	6,352.00	6,352.00
	Carried to the Summary (AED)				**183,892.00**

SL #	Item Description	Quantity	Unit	Rate	Amount (AED)
	MEP WORKS				
	MECHANICAL, ELECTRICAL AND PLUMBING Misc				
A	Builders works in connection with MEP works, chasing, making good etc	1	item	6,258.00	6,258.00
	ELECTRICAL WORKS				
	SWITCHGEARS				
B	Modification of existing DB (power upgradation excluded)	2	no.	4,238.00	8,476.00
	CABLE TRAY & TRUNKING				
	Supply & Installation of HDGI cabletray & trunkig as per drawings including all the required accessaries				
C	100 X 50mm tray for data	65	m.	73.00	4,745.00
D	50 X 50mm trunking for lights & power	65	m.	95.00	6,175.00
	SMALL POWER OUTLET				
	Supply and installation of small power outlets as shown on the drawings and as specified including the necessary copper insullated wire and 25mm PVC conduits				
E	Floorbox (1 twin socket +2 data provision)	23	no.	822.00	18,906.00
F	Floorbox (2 twin socket +4 data provision)	41	no.	941.00	38,581.00
G	13A Single switch socket - PVC white finish	14	no.	318.00	4,452.00
H	13A twin switch socket - PVC white finish	17	no.	371.00	6,307.00
J	13A single switch socket with USB outlet-floor mounted	3	no.	729.00	2,187.00
K	13A spur outlet	8	no.	490.00	3,920.00
	Carried to the Summary (AED)				**100,007.00**

SL #	Item Description	Quantity	Unit	Rate	Amount (AED)
A	15A socket for Cofee machine	1	no.	596.00	596.00
	LIGHT FIXTURES				
	Install Light fixtures and associated items as per the drawings with plug in type ceilig rose and 2.5mm copper insulated wire and 20 mm pvc conduit				
B	Installation of ceiling lights	1	item	35,545.00	35,545.00
	LIGHTING SWITCHES				
C	1 Gang 1 way switches	14	no.	153.00	2,142.00
D	2 Gang 1 way switches	4	no.	179.00	716.00
E	Supply & installation of stand alone PIR sensors in the open space & offices	41	no.	808.00	33,128.00
F	Supply & Installation of touch panel in the meeting rooms	1	item	66,217.00	66,217.00
	ELV Containments				
	Supply & Installation of 25mm pvc conduits for the ELV system				
G	Data points	210	no.	133.00	27,930.00
H	AV points on meeting room	6	no.	133.00	798.00
	Carried to the Summary (AED)				**167,072.00**

SL #	Item Description	Quantity	Unit	Rate	Amount (AED)
	AIR CONDITIONING WORKS				
	HVAC UNITS				
	We assume that the existing FCU have enough capacity to cool the area and not cosnider any new FCU				
A	Relocation of existing FCU	3	nos	3,179.00	9,537.00
B	Perfomance testing for existing AC machines	15	nos	1,855.00	27,825.00
C	Thermostat for new VAV	15	no.	676.00	10,140.00
D	New VAV -bypass type for all closed rooms	15	no.	4,106.00	61,590.00
	DUCT WORKS				
	Supply and install ductwork insulated angles,elbows,reducers,supports and all other items required .				
E	Modification of existimng supply & return air	1	Item	72,605.00	72,605.00
F	Flexible duct & plenum boxes	1	item	10,396.00	10,396.00
	DUCT CONTROL DEVICES				
	Supply & Installation of Volume control Dampers for supply,fresh &extract ducts				
G	Supply& Installation of VCD	1	item	8,476.00	8,476.00
	GRILLS & DIFFUSERS				
H	Supply & Installation of grills & diffusers	1	item	38,936.00	38,936.00
	Carried to the Summary (AED)				**239,505.00**

SL #	Item Description	Quantity	Unit	Rate	Amount (AED)
	FIRE ALARM DETECTION & ALARM SYSTEM				
A	Supply and install new smoke detector	17	no.	1,690.00	28,730.00
B	Relocation of smoke detector & sounder	17	no.	609.00	10,353.00
C	Supply and install new sounder with flasher	2	no.	2,163.00	4,326.00
D	Supply and Install manual call point/break glass	2	no.	1,757.00	3,514.00
E	Supply & Installation of new FACP without network card		no.	18,919.00	Rate only
F	Integration of new FACP to the existing FACP	1	Item	9,460.00	9,460.00
G	Supply, installation and connection of I/O module interface - 1 INPUT and 1 OUTPUT signal.	4	no.	1,419.00	5,676.00
H	Testing & Commisioning	1	no.	9,460.00	9,460.00
	FIRE FIGHTING SYSTEM				
	It is assumed that the landlord can provide isolation of the system, without cost, for any modications				
J	Fire extinguisher set, attached to wall on brackets.5 kilogram of dry powder and 5 kilograms of CO2 within electrical room	2	set	888.00	1,776.00
K	Co2 Extinguisher	2	no.	609.00	1,218.00
L	Install new pendnet fire sprinkler heads, valves and supplies,	55	no.	1,149.00	63,195.00
M	Relocation of existing sprinkler	30	no.	744.00	22,320.00
N	Opening and closing of the Zone Control Valve	2	Item	6,757.00	13,514.00
	Carried to the Summary (AED)				**173,542.00**

SL #	Item Description	Quantity	Unit	Rate	Amount (AED)
	EMERGENCY EXIT LIGHTING				
	(If KOJI are allowed to supply and install as per KOJI standards)				
A	Supply & Installation of new Emergency light,self contained	13	no.	1,217.00	15,821.00
B	Supply & Installation of new Exit light,self contained	6	no.	1,487.00	8,922.00
	COMMISSIONING				
C	Testing and commissioning of Electrical works	1	item	3,379.00	3,379.00
D	Testing and commissioning of air conditioning	1	item	10,811.00	10,811.00
E	Testing and commissioning of fire fighting	1	item	4,055.00	4,055.00
	Carried to the Summary (AED)				**42,988.00**

SL #	Item Description	Quantity	Unit	Rate	Amount (AED)
	Summary				
	Page 1				45,270.00
	Page 2				318,421.00
	Page 3				325,489.00
	Page 4				161,884.00
	Page 5				93,043.00
	Page 6				183,892.00
	Page 7				100,007.00
	Page 8				167,072.00
	Page 9				239,505.00
	Page 10				173,542.00
	Page 11				42,988.00
	Carried to the Main Summary (AED)				**1,851,113.00**

SL #	Item Description	Quantity	Unit	Rate	Amount (AED)
	Demolition Works				
A	Allow for removing, packing and shifting of existing loose furniture and Office furniture to the Client's storage area within the Dubai.	1	L/s	Excluded as per RFI Reply	
B	Allow for removal of existing Gypsum Partitions and cart away the debris to the Municipality dump yard.	1	L/s		
C	Allow for removal of the existing Fitted Furniture and cart away the debris to the Municipality dump yard.	1	L/s		
D	Allow for removal of Existing Floor Finishes and cart away the debris to the Municipality dump yard.	1	L/s		
E	Allow for removal existing Ceiling finishes and cart away the debris to the Municipality dump yard.	1	L/s	27,224.00	27,224.00
F	Allow for removal existing Roller Blinds and cart away the debris to the Municipality dump yard.	1	L/s		
G	Allow for removal existing Light fittings and cart away the debris to the Municipality dump yard.	1	L/s		
H	Allow for modification of existing Raised Floor to receive new floor finishes.	1	L/s		
	Carried to the Summary (AED)				**27,224.00**

SL #	Item Description	Quantity	Unit	Rate	Amount (AED)
	Floor Finishes				
	Supply and Installation of Carpet Flooring with glue on existing raised flooring.				
A	50 x 50cm Carpet tiles to Work station area, Experience Room and Pantry	251	sqm	179.00	44,929.00
B	50 x 50cm carpet tiles to Meeting Room 1 & 2.	10	sqm	179.00	1,790.00
	Supply and Installation of 18mm thick Engineered Wood Flooring on exsiting raised flooring.				
C	To GM room, Meeting, HR Marketing , Commercial, TR and Finance Rooms	104	sqm	218.00	22,672.00
	Supply and Installation of Loose Rug.				
D	to the Entrance	4	sqm	609.00	2,436.00
	Wall Finishes.				
E	Supply and Installation 100mm High using MDF with PU Painted finish including Aluminium U Channel.	120	Lam	101.00	12,120.00
F	Supply and Application of Fenomastic Paint to the existing and proposed Walls.	250	sqm	25.00	6,250.00
	Supply and Application of Special Paint to the existing columns and Meeting Room Including Gypsum Lining.				
G	To existing Columns, Finance Room	55	sqm	149.00	8,195.00
	Carried to the Summary (AED)				**98,392.00**

SL #	Item Description	Quantity	Unit	Rate	Amount (AED)
	Wall Finishes. (Cont'd…)				
	Supply and installation of veneered MDF Cladding Including all necessary supports and accessories.				
A	To meeting Rooms with Veneered MDF Cladding.	18	sqm	699.00	12,582.00
B	Curved Cladding To existing Column	6	sqm	936.00	5,616.00
C	Fluted MDF Cladding with PU Painted Finish, to Animation Wall Area, GM Office, Experience Room.	45	sqm	1,080.00	48,600.00
	Ceiling Finishes				
	Supply and installation of Gypsum ceiling using 12.5mm thick Gypsum on GI Metal suspension system including white Fenomastic paint.				
D	Gypsum Plain Ceiling to GM, HR, Marketing, Commercial, TR, Finance, meeting 1 & 2, Experience & Pantry.	125	sqm	163.00	20,375.00
E	Recessed Light Cove 75 x 100mm H	103	Lm	82.00	8,446.00
F	Gypsum Pelmet	34	Lm	95.00	3,230.00
	Supply and Installation of 40 x 100mm Wooden Slat Ceiling at 100mm c/c using PU White painted MDF including all suspensions.				
G	Wooden Slat Ceiling to Meeting Room and Workstation areas.	244	sqm	1,080.00	263,520.00
	Carried to the Summary (AED)				**362,369.00**

SL #	Item Description	Quantity	Unit	Rate	Amount (AED)
	Wall Partitions				
	Supply and installation of Glass Partitions with aluminium frame in Black paint including all supports. (All doors are measured separately)				
A	2600mm high.	45	sqm	541.00	24,345.00
B	to the meeting rooms with Smart glass ; 2600mm high	21	sqm	2,230.00	46,830.00
	Supply and Installation FR Gypsum Partition using 12.5mm thick Gypsum board in GI metal frame. (Finishes measured separately)				
C	100mm thick Gypsum Partitions.	192	sqm	203.00	38,976.00
	Supply and Installation of Movable Glasswall Series 5630 (without bottom mechanical seal) – with minimum possible glass configuration of 6mm thick clear tempered glass + 24mm air space + 8mm thick clear tempered glass i.e. total 38mm thick sealed unit to be inserted in our frame, Track to be in Powder Coated Finish.				
D	4 No's. of Panels per partition + 1 No. Flipper Panel; Size : 4770 x 2600mm H	1	No	46,170.00	46,170.00
	Doors and Windows				
	Supply and Installation of Glass Door with Aluminium frame in black paint finish including the hardware.				
E	Size : 900 x 2400mm H	7	no	3,784.00	26,488.00
F	with Smart Glass Size : 900 x 2400mm H	1	no	6,757.00	6,757.00
G	Sliding Door with Smart Glass Size : 900 x 2400mm H	2	no	7,433.00	14,866.00
	Supply And Installation of 60min FR Wooden Doors with PU Painted finish and Solid Wood Frame in PU Paint finish including all necessary accessories				
H	To Pantry; Size : 1000 x 2400mm H	1	no	4,836.00	4,836.00
	Carried to the Summary (AED)				**209,268.00**

SL #	Item Description	Quantity	Unit	Rate	Amount (AED)
	Joinery Works				
	Supply and Installation Storage Cabinet using Veneered MDF including all necessary accessories and Supports.				
A	To Meeting Room ; Size : 5150 x 600 x 2600mm H	1	no	18,308.00	18,308.00
B	to HR, Marketing, Commercial, TR & Finance Rooms; Size : 1600 x 400 x 2400mm H.	3	no	5,251.00	15,753.00
	Supply and Installation Storage Cabinet using Laminated MDF finish including all necessary accessories and Supports.				
C	to HR, Marketing, Commercial, TR & Finance Rooms; Size : 1600 x 400 x 2400mm H.	2	no	4,698.00	9,396.00
	Supply and Installation of Shelves using veneered MDF Including all necessary supports and accessories.				
D	Wall hung Shelves 300mm Wide to the columns.	14	Lam	504.00	7,056.00
E	Open Shelf With Metal frame 3600 x 450 x 2600mm H	1	no	13,473.00	13,473.00
	Supply and Installation of High Table using Laminated MDF Finish.				
F	To Experience Room; Size : 3630 x 410 x 1300mm H	1	No	4,894.00	4,894.00
	Supply and Installation Of Pantry Cabinet with Shutters in MDF in PU finish, Corian or Stone Counter Top, PU Painted Shelves, Carcass in Melamine White MDF Inclduing LED Strip Lights, all accessories and supports in accordance with the provided 3D render. **(All White Goods /Kitchen Appliances are excluded)**				
G	Size : 5520 x 600 x 2600mm H	1	No	21,560.00	21,560.00
	Roller Blinds				
H	Supply and Installation of Manually Operated Roller Blinds	110	m2	102.00	11,220.00
	Carried to the Summary (AED)				**101,660.00**

SL #	Item Description	Quantity	Unit	Rate	Amount (AED)
	Light Fittings **Supply of Lights. All cabling and fixing works are considered separately)**				
A	Track -3 Nos With Track Light (3200mm Length) - Magnetic type Power：12W;CCT：4000K;CRI：≥90;Beam angle：24°;Input Voltage：48V;IP Rate ：IP20;Dimension: L3200mm.	4	Sets	1,642.00	6,568.00
B	Downlight 300mm Long Power：8W;CCT：4000K;CRI：≥90;Beam angle：60°;IP Rate ： IP20;Input Voltage：24V;Dimension: L300mm; Material Quality : AL	85	No.	181.00	15,385.00
C	Hanging Pendant light Power：10W;CCT：4000K;CRI：≥90;Beam angle：36°;Input Voltage：185-265V;Dimension: Φ200mm;Dimmer:ON/OFF;Material Quality: Glass	11	No.	676.00	7,436.00
D	Linear continuos Light Power：30W/M;CCT：4000K;CRI：≥90;Beam angle：120°;Input Voltage：185-268V;Dimension: L2000mm;W70*H40mm;Dimmer:ON/OFF;Material Quality: Iron	50	No.	298.00	14,900.00
E	Allow for Dimmable drivers for the Meeting Room (Near GM Office)	1	item	2,433.00	2,433.00
	Carried to the Summary (AED)				**46,722.00**

SL #	Item Description	Quantity	Unit	Rate	Amount (AED)
	MEP WORKS				
	MECHANICAL, ELECTRICAL AND PLUMBING Misc				
A	Builders works in connection with MEP works, chasing, making good etc	1	item	6,258.00	6,258.00
	ELECTRICAL WORKS				
	SWITCH GEARS				
B	Modification of existing DB (power upgradation excluded)	1	no.	4,503.00	4,503.00
	CABLE TRAY & TRUNKING				
	Supply & Installation of HDGI cabletray & trunkig as per drawings including all the required accessaries				
C	100 X 50mm tray for data	25	m.	73.00	1,825.00
D	50 X 50mm trunking for lights & power	25	m.	95.00	2,375.00
	SMALL POWER OUTLET				
	Supply and installation of small power outlets as shown on the drawings and as specified including the necessary copper insullated wire and 25mm PVC conduits				
E	Floorbox (1 twin socket +2 data provision)	8	no.	822.00	6,576.00
F	Floorbox (2 twin socket +4 data provision)	18	no.	941.00	16,938.00
G	13A Single switch socket - PVC white finish	4	no.	318.00	1,272.00
H	13A twin switch socket - PVC white finish	3	no.	371.00	1,113.00
J	13A single switch socket with USB outlet-floor mounted	2	no.	729.00	1,458.00
K	13A spur outlet	2	no.	490.00	980.00
L	15A socket for Cofee machine & microwave	2	no.	596.00	1,192.00
	Carried to the Summary (AED)				**44,490.00**

SL #	Item Description	Quantity	Unit	Rate	Amount (AED)
	LIGHT FIXTURES				
	Install Light fixtures and associated items as per the drawings with plug in type ceilig rose and 2.5mm copper insulated wire and 20 mm pvc conduit				
A	Installation of ceiling lights	1	item	23,838.00	23,838.00
	LIGHTING SWITCHES				
B	1 Gang 1 way switches	8	no.	153.00	1,224.00
C	2 Gang 1 way switches	2	no.	179.00	358.00
D	Supply & installation of stand alone PIR sensors in the open space & offices	15	no.	808.00	12,120.00
E	Supply & Installation of touch panel in the meeting rooms	1	item	26,487.00	26,487.00
	ELV Containments				
	Supply & Installation of 25mm pvc conduits for the ELV system				
F	Data points	88	no.	133.00	11,704.00
G	AV points on meeting room & GM room	2	no.	133.00	266.00
	Carried to the Summary (AED)				**75,997.00**

SL #	Item Description	Quantity	Unit	Rate	Amount (AED)
	AIR CONDITIONING WORKS				
	HVAC UNITS				
	We assume that the existing FCU have enough capacity to cool the area and not cosnider any new FCU				
A	Relocation of existing FCU	2	nos	3,179.00	6,358.00
B	Perfomance testing for existing AC machines	6	nos	1,855.00	11,130.00
C	Thermostat for new VAV	10	no.	676.00	6,760.00
D	New VAV -bypass type for all closed rooms	10	no.	4,106.00	41,060.00
	DUCT WORKS Supply and install ductwork insulated angles,elbows,reducers,supports and all other items required .				
E	Modification of existimng supply & return air	1	Item	23,309.00	23,309.00 -
F	Flexible duct & plenum boxes	1	item	3,046.00	3,046.00 -
	DUCT CONTROL DEVICES				
	Supply & Installation of Volume control Dampers for supply,fresh &extract ducts				
G	Supply& Installation of VCD	1	item	4,874.00	4,874.00
	Carried to the Summary (AED)				**96,537.00**

SL #	Item Description	Quantity	Unit	Rate	Amount (AED)
	GRILLS & DIFFUSERS				
A	Supply & Installation of grills & diffusers	1	item	22,249.00	22,249.00
	FIRE ALARM DETECTION & ALARM SYSTEM				
B	Supply and install new smoke detector	7	no.	1,690.00	11,830.00
C	Relocation of smoke detector	8	no.	609.00	4,872.00
D	Supply and install new sounder with flasher	1	no.	2,163.00	2,163.00
E	Supply and Install manual call point/break glass	1	no.	1,757.00	1,757.00
F	Supply & Installation of new FACP without network card		no.	18,919.00	Rate only
G	Integration of new FACP to the existing FACP	1	Item	9,460.00	- 9,460.00
H	Supply, installation and connection of I/O module interface - 1 INPUT and 1 OUTPUT signal.	1	no.	1,419.00	- 1,419.00
J	Testing & Commisioning	1	no.	9,460.00	- 9,460.00
	FIRE FIGHTING SYSTEM				
K	It is assumed that the landlord can provide isolation of the system, without cost, for any modications				-
L	Fire extinguisher set, attached to wall on brackets.5 kilogram of dry powder and 5 kilograms of CO2 within electrical room	1	set	888.00	888.00
M	Co2 Extinguisher	1	no.	609.00	609.00
N	Install new pendnet fire sprinkler heads, valves and supplies,	28	no.	1,149.00	32,172.00
P	Relocation of existing sprinkler	26	no.	744.00	19,344.00
Q	Opening and closing of the Zone Control Valve	1	Item	6,082.00	6,082.00
	Carried to the Summary (AED)				**122,305.00**

SL #	Item Description	Quantity	Unit	Rate	Amount (AED)
	EMERGENCY EXIT LIGHTING				
	(If KOJI are allowed to supply and install as per KOJI standards)				
A	Supply & Installation of new Emergency light,self contained	8	no.	1,217.00	9,736.00
B	Supply & Installation of new Exit light,self contained	2	no.	1,487.00	2,974.00
	COMMISSIONING				
C	Testing and commissioning of Electrical works	1	item	20,271.00	20,271.00
D	Testing and commissioning of air conditioning	1	item	13,244.00	13,244.00
E	Testing and commissioning of fire fighting	1	item	4,055.00	4,055.00
	Carried to the Summary (AED)				**50,280.00**

SL #	Item Description	Quantity	Unit	Rate	Amount (AED)
	Summary				
	Page 1				27,224.00
	Page 2				98,392.00
	Page 3				362,369.00
	Page 4				209,268.00
	Page 5				101,660.00
	Page 6				46,722.00
	Page 7				44,490.00
	Page 8				75,997.00
	Page 9				96,537.00
	Page 10				122,305.00
	Page 11				50,280.00
	Carried to the Main Summary (AED)				**1,235,244.00**

QUALIFICATIONS & EXCLUSIONS

SUMMARY OF QUOTATION FOR BUILDING WORKS - REVISION NUMBER 1

Works:	Interior Fitout & MEP works at LVMH Beauty
Client:	M/s. LVMH BEAUTY
Site:	D3, Dubai, UAE.
Job No.	K2795
Date	Friday, October 6, 2023

QUALIFICATIONS

Q.01	All water and electricity for the works to be supplied free of charge by the Client.
Q.02	Site office and storage space shall be provided by client at free of cost.
Q.03	Access to the site is provided at all times including any necessary provision for building security.
Q.04	Our mark up for Prime Cost, Provisional Sums and Variations is subject to 20%.
Q.05	Existing wooden door at Main Entrance /Exit area at ADP area and Lift lobby Main Glass Sliding Door at BPC to be retained.
Q.06	we assume the enitre area is with existing Raised Floor and it will be retained.
Q.07	All Glass Partitions and Doors are considered as non Fire rated only.
Q.08	We have consider PVC white finish switches & sockets in our offer.
Q.09	We have cosnider PVC conduits for the Electrical works installation.
Q.10	All light fittings are cosnider non dimmabletype except in the meeting rooms ,in meeting rooms we have proposed dimming system with touch panel.
Q.11	VE Options are considered as per attached Annexure '3'-VE Schedule.

EXCLUSIONS

E.01	Any pre-existing defects within the building and/or its MEP services.
E.02	Attic Stocks and Spares.
E.03	PI Insurance.
E.04	All Artworks and Display Accessories.
E.05	FF&E including all Loose /Office Furniture including Low height storage cabinets.
E.06	Lux calculation for the Lights.
E.07	All LED TV and Screens.
E.08	All Planters, Planter Box and Green Walls.
E.09	Docking Station, PDU & Monitor Arms.
E.10	Table Lamps.
E.11	Power upgradation of existing SMDB and DB
E.12	Supply & installation of HVAC equipments
E.13	Coring works
E.14	Supply & installation of plumbing works
E.15	Supply & installation of ELV works
E.16	New cement sand screeding, as we retaining the existing Raised Access Floor.
E.17	Preparation and Submission of 3D renders.

PAYMENT TERMS

P.01	Advance payment, recovered pro-rata from valuations and fully from final account	40
P.02	Progress valuations of works at 14 day intervals and payment 14 days thereafter	55
P.03	Retention against snagging and defects for a period of 365 days thereafter	5

DURATION

D.01 As per the attached Program.

VE OPTIONS

K2795 LVMH BEAUTY

ANNEXURE '3" - VE SCHEDULE

Sl no	Location		Compliant	VE
			Description	Description
1	BPC	Oak Finish to SC1, SC2, F1, F3, F4, F8, Meeting Rooms, IT Store, IT1 & HR Rooms.	Engineered Wood Flooring	2mm thick LVT Flooring
2	BPC	to Break out, Lounge and Common Areas.	Engineered Wood Flooring	2mm thick LVT Flooring
3	GK	To GM room, Meeting, HR Marketing , Commercial, TR and Finance Rooms	Engineered Wood Flooring	2mm thick LVT Flooring
4	ADP	To ADP-LOEWE Area.	Roll Carpet	Carpet Tile flooring 50 x 50cm

INTERIORS

مجموعة كمال عثمان جمجوم ذ م م
Kamal Osman Jamjoom Group LLC