HTI CONTRACTING LLC
PO Box :390737
506 - Binary Tower , Business bay
Dubai , United Arab Emirates
www.hashtaginteriors.com

COMMERCIAL PROPOSAL - REV 02
FOR
(ARCHITECTURAL WORKS)

ALAAN PAY
9TH FLOOR, WASL 4 BUILDING, EXPO CITY
DUBAI - UNITED ARAB EMIRATES

To:
Mr. Mohamed Jaffer
Executive Operations Founder's Office
Office 1610, Concord Tower,
Al Sufouh, Dubai Media City,
.Dubai -United Arab Emirates

Date:
11th November 2025
Reference No.:
QTN-073/1225AH/0R2

HTI CONTRACTING LLC
PO Box :390737
506 - Binary Tower , Business bay
Dubai , United Arab Emirates
www.hashtaginteriors.com

General Terms & Conditions

Payment Terms: 25% Advance Upon Order confirmation against security chq and same to be returned along with release of next payment
25% upon completion of demolition
20% upon achieving 40% work at site
20% upon achieving 60% work at site
10% upon completion and handover (snag free)
Performa invoice must be approved by client within 7 days from submission.

Project Timeline: Documents and Drawings Preparation: 7-10 Days from the date of receipt of advance payment/LOI and as built drawings or kick off meeting with EXPO authority.

Initial Fitout Approval : 2-3 weeks from the receipt of NOC from respective authorities.
Site Works: 9 Weeks from the date of receipt of permit to work (PTW) or Clear access to site.

Validity: Our quote is valid for a period of 30 days from hereof.

Warranty: As per manufacturer and 365 days DLP from the date of occupancy handing over of the phases.
Note: Damages due to Misuse/Natural calamities/War etc. are excluded.

Insurance: Project insurance to be obtain as per HTI policy and additional charges may apply if specific covered required by any 3rd party.

We trust that you will find the attached quotation in line with your requirements, and shall look forward to your earliest response.

Yours faithfully
For HTI Contracting LLC

DUBAI - U.A.E.
H.T.I CONTRACTING L.L.C

Suraj M Roy
054 5850779
roy@hashtaginteriors.com

Special Note and Exclusion:

a. *Scope is limited to BOQ and Any additional works will be charged as variation.*
b. *Contract/ BOQ shall be treated as lump Sum contract.*
c. *Feel/Charges to approval authorities/mall management to be paid by client on actuals.*
d. *VAT excluded and to be charged as per UAE law.*
e. *Fire fighting, Fire Alarm works are priced as provisional sum and prices may vary based on DCD / EXPO comments.*
f. *GI AC Ducting, BTU meter, BMS, new thermostat, VAV control, etc. are excluded.*
h. *Upright sprinklers, void smoke detector, fire pump etc. are excluded.*
i. *Any specific requirements arise after project award by any statutory authority/client will be charged as variation.*
j. *Variation to be approved prior to start of works and 100% payment to be cleared by the client upon confirmation.*
k. *Incase of cancellation of project HTI has a right to charge a fee of 20% of project value from client.*
l. *Delay in work by any 3rd party appointed by consultant/building management/client. HTI will not be held responsible.*
m. *Any delay in payment, finishes approval, from approval authority or due to natural calamities HTI will not be held responsible.*
n. *PABX, active components, laptop, PC, white goods etc. are excluded.*
o. *Annual maintenance contract (AMC) and 24X7 excluded and cost to be paid by client directly to the buidling approved contractor.*
p. *IT works are excluded and to be priced only after discussion with IT team.*

HTI CONTRACTING LLC
PO Box :390737
506 - Binary Tower , Business bay
Dubai , United Arab Emirates
www.hashtaginteriors.com

	DESCRIPTION OF WORKS		AED
A.	ARCHITECTURAL WORKS:		
1	PREAMBLE/GENERAL WORKS:	AED	51,750.00
2	DEMOLITION WORKS:	AED	33,850.00
3	GLAZING WORKS:	AED	126,150.00
4	PARTITION WORKS:	AED	40,100.00
5	FINISHING WORKS:	AED	109,105.00
6	FLOORING WORKS:	AED	196,460.00
7	CEILING WORKS:	AED	94,144.00
8	INTERNAL SIGNAGE/BRANDING WORKS:	AED	9,900.00
9	JOINERY / WOOD WORKS:	AED	274,610.00
10	ELECTRICAL AND LIGHTING WORKS:	AED	276,720.00
11	PLUMBING AND DRAINAGE WORKS:	AED	8,900.00
12	FIRE FIGHTING AND FIRE ALARM WORKS (PROVISIONAL SUM) :	AED	116,214.00
13	HVAC WORKS (PROVISIONAL SUM) :	AED	56,120.00
14	IT STRUCTURE AND CABLING WORKS :	AED	15,100.00
15	CLOSE-OUT FORMALITIES	AED	8,000.00
	TOTAL AMOUNT FOR ARCHITECTURAL WORKS	AED	1,417,123.00
	LESS SPECIAL CLIENT DISCOUNT	AED	117,123.00
	NET PROJECT VALUE EXCLUDING TAX	AED	1,300,000.00

HTI CONTRACTING LLC
PO Box :390737
506 - Binary Tower , Business bay
Dubai , United Arab Emirates
www.hashtaginteriors.com

ARCHITECTURAL WORKS:		BRAND	QTY	UNIT	RATE	AMOUNT
ITEM	DESCRIPTION OF WORKS	SPECIFICATION			AED	AED
1.00	**PREAMBLE/GENERAL WORKS:**					
1.01	Mobilization and site setup- allow sum for contractor's site mobilization		1	Job	6,000.00	6,000.00
1.02	Provision for implementing and providing adequate health and safety measures on site		1	Job	1,500.00	1,500.00
	Note: Electricity connection will be taken from the existing DB at site. we have not considered temporary generator to supply the electricity.					
1.03	Allow sum for covering and protection of entrance area, lobby, corridor, service lifts and finished products to prevent any damages due to the on-going fit-out works as per the building management.		1	Job	4,000.00	4,000.00
1.04	Allow for charges of arranging permit/access for pick-ups and material delivery.		1	Job	3,000.00	3,000.00
	DOCUMENTS					
1.05	Preparation of construction/workshop drawings for approval of local authorities (EXPO, Civil defense department and DEWA) and joinery workshop drawings and as-build drawings.		1	Job	10,000.00	10,000.00
	PROJECT INSURANCES					
1.06	Insurance policies for the project as per HTI standard. Contractor/ Erection All Risks (CAR) and Third-		1	Job	5,250.00	5,250.00
	CLEANING					
1.07	Allow sum for removal of debris and daily general site cleaning for the entire project duration and professional cleaning upon handover.		1	Job	8,500.00	8,500.00
	SERVICES					
1.08	Allow consumption charges for electricity, water, existing washroom facilities and additional connection charges to be paid to DEWA.		1	Job		BY CLIENT
	APPROVAL PROCESS (AUTHORITIES AND BUILDING MANAGEMENT)					
	AUTHORITY APPROVAL (FOR 1 LEASE)					
1.09	Contractors coordination charges to liaise with local authorities such as, Civil defense and DM to obtain complete approval.		1	Job	3,500.00	3,500.00
1.10	Deposits and fees for local authority approvals to complete the approval process from DM, Civil defense.		1	Provisional Sum	10,000.00	10,000.00
1.11	Allow sum for building management approval - fees for drawing approvals.		1	Job	TBC	BY CLIENT
	TOTAL AMOUNT FOR PREAMBLE/GENERAL WORKS					**AED 51,750.00**

HTI CONTRACTING LLC
PO Box :390737
506 - Binary Tower , Business bay
Dubai , United Arab Emirates
www.hashtaginteriors.com

ARCHITECTURAL WORKS:		BRAND	QTY	UNIT	RATE	AMOUNT	
ITEM	DESCRIPTION OF WORKS	SPECIFICATION			AED	AED	
2.00	**DEMOLITION WORKS:**						
2.01	Removal of existing gypsum walls as per new proposed design layout.		1	Item	19,500.00	AED	19,500.00
2.02	Removal of existing doors, handrail and cart away the unnecessary panels.						
2.03	Removal of existing carpet tiles and grinding the floor to remove exiting glue.						
2.04	Removal of existing power sources, outlets, cables etc		1	Item	8,350.00	AED	8,350.00
2.05	Transportation and labor charges to dispose the same including authority fees.		1	Item	6,000.00	AED	6,000.00
					TOTAL AMOUNT FOR DEMOLITION WORKS	**AED**	**33,850.00**
3.00	**GLAZING WORKS:**						
3.01	**ACOUSTIC GLASS PARTITON GIBCA OR EQUIVALENT :** Supply and installation of 8+8mm laminated glass partition with powder coated heavy duty aluminium 42 series Aluminium framed, Framework: powder coated top, bottom and wall aluminium profiles in plain standard ral colors. Glass panel: single glazed 8+8 mm thick laminated clear tempered glass panels with polished edges. Glazing vertically connected by transparent tape joints. Overall height: 2700mm Acoustic rating: 36db (lab tested) **Glass Partition Height : 2700** **Location : Meeting and Conference Room**		158	Sqm	1,545.00	OPTIONAL ITEMS	
3.02	**<u>Framed Glass Door Cabins:</u>** Supply and installation of 12mm thick non- fire rated clear tempered glass single leaf door with heavy duty hinges with necessary frame all around with accessories with lock set and provision for access control. hardware finish: matt black finish door Size: 1800mm x 2800mm **Location : Closed Rooms**		9	Nos.	3,960.00	AED	35,640.00
3.03	Supply and installation of **12 mm thick** clear tempered glass partitions from floor to 2800 mm height. Glass partitions to be fixed on to 3cm BLACK aluminium channels at the top and bottom and glass to glass joint with clear silicon. **Glass Partition Height : 2600** **Location : As per design.**		158	Sqm	445.00	AED	70,310.00

HTI CONTRACTING LLC
PO Box :390737
506 - Binary Tower , Business bay
Dubai , United Arab Emirates
www.hashtaginteriors.com

ARCHITECTURAL WORKS:		BRAND	QTY	UNIT	RATE	AMOUNT	
ITEM	DESCRIPTION OF WORKS	SPECIFICATION			AED	AED	
3.04	**Framed Glass Door For Entrance:** Supply and installation of 12mm thick non- fire rated clear tempered glass double leaf door with heavy duty hinges with necessary frame all around with accessories with lock set and provision for access control. hardware finish: matt black finish door Size: 1800mm x 2800mm **Location : Office Entrance**		2	Nos.	6,980.00	AED	13,960.00
3.05	**SMART FILM:** Supply and Installation of (92% Data Sheet Provided) Ultra HD Film Cables/Wire Trunking Special PH Silicone Compounds **Location: Mr. Abdul Ghani/ Conference room and Mr. Ahmed Room.** Supply and Installation of Transformer & Ultra touch screen remote control.		158	Sqm	1,245.00	OPTIONAL ITEMS	
3.06	**REMOTE CONTROL:** Supply and Installation of Transformer & Ultra touch screen remote control. Location: Mr. Abdul Ghani/ Conference room and Mr. Ahmed Room.		8	Sqm	950.00	OPTIONAL ITEMS	
3.07	Re-installation of existing wooden door for the proposed store / IT room.		1	Nos.	2,240.00	AED	2,240.00
3.08	Removal of existing main entrance door, patching of the edges all around and handover to landlord/client within the expo city area.		2	Nos.	2,000.00	AED	4,000.00
					TOTAL AMOUNT FOR GLAZING WORKS	**AED**	**126,150.00**
4.00	**PARTITION WORKS:**						
4.01	**Gypsum Partitions.** Supply and installation of drywall partitions 100mm thick on comprising of 70 mm steel studs and 72mm track, 30Kg/m3 density of rockwool insulation covered by 12.5mm regular gypsum board on both sides with frame works of standard sections at a distance of 600mm c/c maximum and with necessary horizontal members at the required heights up to slab sofit height with Jointing, taping and sanding. **Make : Gypsum Boards / Joint Compound / Corner Tape / Fiber Tape : USG or equivalent**		186	Sqm	130.00	AED	24,180.00
4.02	**Gypsum Cladding.** Supply and installation of 40 mm thick wall cladding regular gypsum board cladding on blockwall for smooth finish. Location: DB wall/Fire hose reel. **Make : Gypsum Boards / Joint Compound / Corner Tape / Fiber Tape : USG or equivalent**		64	Nos.	95.00	AED	6,080.00

HTI CONTRACTING LLC
PO Box :390737
506 - Binary Tower , Business bay
Dubai , United Arab Emirates
www.hashtaginteriors.com

ARCHITECTURAL WORKS:		BRAND	QTY	UNIT	RATE	AMOUNT	
ITEM	DESCRIPTION OF WORKS	SPECIFICATION			AED	AED	
4.03	**Baffle Wall Partitions:.** Supply and installation of baffle drywall partitions 100mm thick on comprising of 70 mm steel studs and 72mm track, 30Kg/m3 density of rockwool insulation covered by 12.5mm regular gypsum board on both sides with frame works of standard sections at a distance of 600mm c/c maximum and with necessary horizontal members at the required heights up to slab height with Jointing, taping and sanding to receive the final finishes above glass panels. **Make : Gypsum Boards / Joint Compound / Corner Tape / Fiber Tape**	 	82	Sqm	120.00	AED	9,840.00
					TOTAL AMOUNT FOR PARTITION WORKS	**AED**	**40,100.00**
5.00	**FINISHING WORKS:**						
5.01	**New Gypsum Partitions and Baffle Walls.** Supply and Application of Paint on Partitions inclusive of Preparing the surface to receive the paint + stucco + 2 Coats of primer + 2 Coats of Painting. **Brand : Jotun or Berger**		504	Sqm	35.00	AED	17,640.00
5.02	**Existing Walls and Partitions.** Supply and Application of Paint on Partitions inclusive of Preparing the surface to receive the paint primer + 2 Coats of Painting. **Brand : Jotun or Berger**		820	Sqm	30.00	AED	24,600.00
5.03	Supply and installation of roller blinds from the external window per proposed design scheme.		362	Sqm	115.00	AED	41,630.00
5.04	Supply and installation 100 mm high black PU painted MDF skirting around the wall as per design in the proposed office areas.		397	LM	45.00	AED	17,865.00
5.05	**Wall Paper:** Supply and installation of premium quality wall paper for the proposed walls in **Conference room, Entrance Lobby walls and small meeting room.**		67	Sqm	110.00	AED	7,370.00
					TOTAL AMOUNT FOR FINISHING WORKS	**AED**	**109,105.00**
6.00	**FLOORING WORKS:**						
6.01	Supply and installation of bare finish raised floor with adjustable pedestal upto the height of 200 mm. **Location: Recpetion/4 nos. Meeting room near to reception/podcast lounge / store room/ compliance room**		243	Sqm	210.00	AED	51,030.00

HTI CONTRACTING LLC
PO Box :390737
506 - Binary Tower , Business bay
Dubai , United Arab Emirates
www.hashtaginteriors.com

ARCHITECTURAL WORKS:		BRAND	QTY	UNIT	RATE	AMOUNT	
ITEM	DESCRIPTION OF WORKS	SPECIFICATION			AED	AED	
6.02	Supply and installation of new 5-6 mm thick premium quality herringbone style flooring with underlay backing and glue. **Location: Coffee serving counter + Recption Area**		63	Sqm	170.00	AED	10,710.00
6.03	Supply and installation of 50x50 contract ID carpet tile flooring with felt backing, anti static, fire retardant as per approved sample. **Location : Entire Office/Working Space** Sample and Specification Sheet to be Submitted for approvals.		862	Sqm	135.00	AED	116,370.00
6.04	Supply and installation of termination strips for 2 different flooring treatment.		1	Item	2,250.00	AED	2,250.00
6.05	Supply and Installation of 50x50 carpet tiles in accent color for the collab area to suit proposed flooring design scheme.		40	Sqm	190.00	AED	7,600.00
6.06	Supply and apply self levelling compound to level the floor wherever required.		1	Item	8,500.00	AED	8,500.00
					TOTAL AMOUNT FOR FLOORING WORKS	**AED**	**196,460.00**
7.00	**CEILING WORKS:**						
7.01	Supply and installtion of INTERNAL PASSGAE AREA gypsum bulkhead with GI channel support, 12 mm thick moisture resistant gypsum board in the proposed internal corridor as per proposed design scheme.		237	Sqm	115.00	AED	27,255.00
7.02	Supply and installation of provision for cove/linear lights for internal corridor to enhance the look and feel.		117	RM	90.00	AED	10,530.00
7.03	**Ceiling Painting.** Supply and Application of Paint : RAL : 9010, on proposed gypsum bulkhead as per design. **Brand : Jotun or Berger**		237	Sqm	35.00	AED	8,295.00
7.04	**Open Ceiling Preparation.** Grinding/filling of holes/stucco of the existingslab wherever is accessible. **Brand : Jotun or Berger**		723	Sqm	8.00	AED	5,784.00
7.05	**Open Ceiling and Bulkhead Painting.** Supply and Application of Spray paint on proposed open ceiling as per design. **Brand : Jotun or Berger**		840	Sqm	42.00	AED	35,280.00
7.06	**MEP Services Painting.** Supply and Application of paint on existing MEP services in open ceiling area.		1	Job	7,000.00	AED	7,000.00
					TOTAL AMOUNT FOR CEILING WORKS	**AED**	**94,144.00**

HTI CONTRACTING LLC
PO Box :390737
506 - Binary Tower , Business bay
Dubai , United Arab Emirates
www.hashtaginteriors.com

ARCHITECTURAL WORKS:		BRAND	QTY	UNIT	RATE	AMOUNT	
ITEM	DESCRIPTION OF WORKS	SPECIFICATION			AED	AED	
8.00	**INTERNAL SIGNAGE/BRANDING WORKS:**						
8.01	Supply and installation of only grey color frosting as per client's guidelines upto 1500 mm coverage. **Location : Closed Cabin** **Brands : 3M or Equivalent**		158	Sqm	95.00	**OPTIONAL ITEMS**	
8.02	Supply and installation of company signage and logo, in acrylic cut-outs, fixed onto the reception backwall. Size: 1200L x 1000H mm **Location : Entrance Wall** EPS file to be provided by client.		2	Nos.	4,950.00	AED	9,900.00
		TOTAL AMOUNT FOR SIGANGE/BRANDING WORKS				**AED**	**9,900.00**
9.00	**JOINERY / WOOD WORKS:**						
9.01	**PANTRY COUNTER:** Low height unit: Supply and installation of locally customized coffee counter fabricated inside melamine outside painted MR mdf underneath storage with shutter, shelves & quartz top & backsplash including overhead unit. Low height unit Size: 4650L x 600D x 900H mm Overhead unit Size: 4650L x 400D x 600H mm Location: Pantry Manufacture : Joinery Item		1	Nos.	27,850.00	AED	27,850.00
9.02	Fabricate, Supply and installation of ISLAND COUNTER base cabinet with carcass is made up of 18 MM THK MR MDF with O/S White Laminate finish and Expose Edges with matching PVC lipping with necessary fittings and other supports to get fix, shutter is made up of 18 MM THK MR MDF with B/S Approved laminate finish and Expose Edges with matching PVC lipping with 5 x 5 MM THK Straight vertical groove with Black stain with necessary fittings and other supports to get fix. Size : 3600 x 800		1	Nos.	23,940.00	AED	23,940.00
9.03	**Hanging Acoustic Panel:** Supply and installation of customized ACOUSTIC panels with necessary fittings for the proposed collab area. Size: 1200L x 600D **Location: Collab Area** **Manufacture : Joinery Item**	 	1	Set	6,500.00	AED	6,500.00

ARCHITECTURAL WORKS:		BRAND	QTY	UNIT	RATE	AMOUNT	
ITEM	DESCRIPTION OF WORKS	SPECIFICATION			AED	AED	
9.04	**Hanging Acoustic Panel:** Supply and installation of customized ACOUSTIC panels with necessary fittings for the proposed collab area. Size: 1200L x 600D **Location: Collab Area** **Manufacture : Joinery Item**		1	LS	6,750.00	AED	6,750.00
9.05	Fabricate, Supply and installation of ISLAND COUNTER base cabinet with carcass is made up of 18 MM THK MR MDF with O/S White Laminate finish and Expose Edges with matching PVC lipping with necessary fittings and other supports to get fix, shutter is made up of 18 MM THK MR MDF with B/S Approved laminate finish and Expose Edges with matching PVC lipping with 5 x 5 MM THK Straight vertical groove with Black stain with necessary fittings and other supports to get fix. Size : 3600 x 800		1	Nos.	33,200.00	AED	33,200.00
9.06	**Hanging Wooden Panel:** Supply and installation of customized hanging wooden panel above the Island counter and visitor lounge area with necessary fittings and support. Size: 1200L x 600D **Location: Collab Area** **Manufacture : Joinery Item**		1	LS	32,300.00	AED	32,300.00
9.07	**Planter Box :** Supply and installation of customised melamine finish planter box as per design scheme with below sizes: 5500 x 800 3200 x 400 **Location: Collab Area** **Manufacture : Joinery Item**		1	Item	8,000.00	AED	8,000.00
9.08	**Metal frame for planters in meeting room:** Supply and installation of customized artificial planter wall in meeting rooms TV wall with necessary fittings and high quality artificial planters with MDF backing. Size: 1600L x 2600 **Location: Internal Meeting and Conference room.**		1	LS	51,430.00	AED	51,430.00

HTI CONTRACTING LLC
PO Box :390737
506 - Binary Tower , Business bay
Dubai , United Arab Emirates
www.hashtaginteriors.com

ARCHITECTURAL WORKS:		BRAND	QTY	UNIT	RATE	AMOUNT	
ITEM	DESCRIPTION OF WORKS	SPECIFICATION			AED	AED	
9.09	**Metal frame for plantersin Ceiling:** Supply and installation of customized artificial planter handing decoration in collab area with necessary fittings and high quality artificial planters with metal support. Size: 1200 mm dia with concelaed lights. **Location: Collab Area**		3	Nos.	2,250.00	AED	6,750.00
9.09	Supply and installation of locally customised metal powder coated frame or MDF painted includuing provision planter boxes as per proposed design scheme size 1200 x 2400 with necessary support into the floor and ceiling. **Location : Open Staff Area** **Note: Plants and accessories are excluded.**		2	Nos.	5,325.00	AED	10,650.00
9.10	Supply and installation of locally customised metal powder coated frame for acoustic panel and planter boxes as per proposed design scheme size 1500 x 2500 with necessary support into the floor and ceiling. **Location : Open Staff Area** **Note: Plants and accessories are excluded.**		3	Nos.	5,870.00	AED	17,610.00
9.11	Supply and installation of locally customised metal powder coated frame planter boxes as per proposed design scheme size 1200 x 2600 with necessary support into the floor and ceiling. **Location : Open Staff Area** **Note: Plants and accessories are excluded.**		4	Nos.	3,325.00	AED	13,300.00
9.12	Supply and installation of locally customised library wall with black painted finish wall unit with led lighting and necessary support and a hanging artificial palnter unit. **Location : Open Staff Area** **Note: Plants and accessories are excluded.**		1	Item	11,900.00	AED	11,900.00
9.13	Supply and installation of locally customised planter unit next to workstation without planter and underneth storage with shelves size 1200 x 400 x 1000 **Location : Open Staff Area** **Note: Plants and accessories are excluded.**		14	Item	1,745.00	AED	24,430.00
					TOTAL AMOUNT FOR JOINERY WORKS	**AED**	**274,610.00**
10.00	**ELECTRICAL AND LIGHTING WORKS:**						
10.01	Modification of the existing DB to suit the proposed electrical schedule as per new load & relocation of the same if needed. .		4	No	2,250.00	AED	9,000.00
10.02	Supply and installation of GI conduiting for the light/exposed power points		244	Nos.	125.00	AED	30,500.00

HTI CONTRACTING LLC
PO Box :390737
506 - Binary Tower , Business bay
Dubai , United Arab Emirates
www.hashtaginteriors.com

ARCHITECTURAL WORKS:		BRAND	QTY	UNIT	RATE	AMOUNT	
ITEM	DESCRIPTION OF WORKS	SPECIFICATION			AED	AED	
10.03	Supply and installation of wiring for the new light point inclduing.		244	Nos.	155.00	AED	37,820.00
10.04	Relocation of existing and Supply & fixing of new 1 way 1 gang/2/gang/3/gang/4gang white PVC switch (Make: MK or equivalent) with wiring and conduit.		1	LS	3,500.00	AED	3,500.00
10.05	Supply and installation of 13 Amp Double power socket with necessary conduiting, wiring as per the design (Conduit: PVC, Wire: Ducab, Switch & Socket: MK White Logic) . Workstattion - 144 Nos. Meeting Room - 12 Nos. Pantry Area - 8 Nos. Printer & Wi Fi - 16 Nos. Other/Spare - 20 Nos.		142	Nos.	320.00	AED	45,440.00
10.06	Supply and installation of 13 Amp single power socket with necessary conduiting, wiring as per the design(Conduit: PVC, Wire: Ducab, Switch & Socket: MK White Logic) .		22	Nos.	305.00	AED	6,710.00
10.07	Supply and installation of Electrical Floor outlet Make: Conduit- Decoduct PVC, Wire-Ducab PVC, Floor Box: MK (Normal Type) to be fixed at the external periphery.		47	Nos.	450.00	AED	21,150.00
10.08	Supply and installation of 16A Socket for the Server Rack.		1	Nos.	950.00	AED	950.00
10.09	Testing and commissioning of Electrical system.		1	Ls	5,000.00	AED	5,000.00
10.10	Allow sum for associated civil works (Floor opening and wall cutting, levelling & chipping for related pvc piping for Electrical works)		1	Ls	15,000.00	AED	15,000.00
	Note: 1) We consider that there is enough available load at site to suit the proposed design. 2) Existing electrical DEWA approved load schedule to be provided by client.						
	LIGHTING:						
10.11	Supply and Installation of recessed LED downlights Material : Aluminum | Finish : White I Light Source : Samsung, Wattage : 40W, CRI : 85 | Power Supply : Constant Current LED Driver, Dimmable : No | Protection : IP44, Size : W 595mm X L 595mm X H 8mm		88	Nos.	310.00	AED	27,280.00
10.12	Supply and installation of decorative pendant circular acoustic light 600 dia for round table meeting rooms with hanging kits, body in powder coated metal and driver with 3 years warranty.		6	Nos.	1,050.00	AED	6,300.00

ARCHITECTURAL WORKS:		BRAND	QTY	UNIT	RATE	AMOUNT	
ITEM	DESCRIPTION OF WORKS	SPECIFICATION			AED	AED	
10.13	Supply and installation of decorative pendant light above barista counter with hanging kits and fittings.		2	Nos.	1,650.00	AED	3,300.00
10.14	Supply and installation of pendant task lights for reception with hanging kits, and driver with 3 years warranty size 2000 x 70 / 1600x 70 as per proposed lighting layout.		62	Nos.	435.00	AED	26,970.00
10.15	Supply and installation of recessed led strip light with cover as per proposed design in passage area, meeting rooms.		89	Lm	210.00	AED	18,690.00
10.16	Supply and Installation of exposed LED track lights with frame in Aluminum | Light Source : Samsung or equivalent, Wattage : 36W, CRI : 85 | Power Supply : Constant Current LED Driver, Dimmable : No | Protection : IP44.		78	Nos.	245.00	AED	19,110.00
	TOTAL AMOUNT FOR ELECTRICAL AND LIGHTING WORKS					**AED**	**276,720.00**
11.00	**PLUMBING AND DRAINAGE WORKS:**						
11.01	Modification in existing plumbing and drainage pipeline with necessary PPR/PVC pipe in pantry area.		1	Item	5,250.00	AED	5,250.00
11.02	Supply and installation of 50ltr water heater including power.		1	Nos.	1,400.00	AED	1,400.00
11.03	Supply and installation of new sink and mixer.		1	Set	2,250.00	AED	2,250.00
	TOTAL AMOUNT FOR PLUMBING AND DRAINAGE WORKS					**AED**	**8,900.00**
12.00	**FIRE FIGHTING AND FIRE ALARM WORKS (PROVISIONAL SUM) :**						
12.01	Supply & Installation of Add. Single Loop Fire Alarm Control Panel.	SPECIAL NOTE: PRICES RECEIVED FROM BUILDING APPROVED CONTRACTOR AND IT MAY VARY BASED ON DCD APPROVED DRAWINGS AND COMMENTS.	1	Nos.	116,214.00	AED	116,214.00
12.02	Supply and installation of new Smoke Detector including base.		12	Nos.			
12.03	Supply and installation of Fire Alarm Sounder		1	Nos.			
12.04	Relocation of Fire Alarm Devices		6	Nos.			
12.05	Installation of Fire alarm Devices with Cable, PVC Conduits and Accessories		1	Nos.			
12.06	Programming of Unit and Building FACP		1	Nos.			
12.07	Self Contained Standalone Emergency Light Recessed Mounted		11	Nos.			
12.08	Self Contained Standalone Exit Light Ceiling Mounted Down A / Side Arrow		8	Nos.			
12.09	Relocation of Emergency lights.		4	Nos.			
12.10	Installation of Em/Ex Light with Cable, PVC Conduits and Accessories		3	Nos.			
12.11	Supply Install / Relocation of Existing Pendent Sprinkler with Necessary Pipe and Fittings.		42	Nos.			
12.12	5Kg CO2 / 6Kg DCP Fire Extinguisher		4	Nos.			
	TOTAL AMOUNT FOR FIRE FIGHTING AND FIRE ALARM WORKS					**AED**	**116,214.00**

HTI CONTRACTING LLC
PO Box :390737
506 - Binary Tower , Business bay
Dubai , United Arab Emirates
www.hashtaginteriors.com

ARCHITECTURAL WORKS:		BRAND	QTY	UNIT	RATE	AMOUNT	
ITEM	DESCRIPTION OF WORKS	SPECIFICATION			AED	AED	
13.00	**HVAC WORKS (PROVISIONAL SUM) :**						
13.01	Modification in existing PI ducting, Fabrication and installation of new branch PI ducting, complete with insulation to be connected to the existing ducts including plenum boxes.		1	Job	56,120.00	AED	56,120.00
13.02	Supply and installation of additional linear supply/return grills and relocation of the existing diffusers as per the layout.						
13.03	Supply and installation of VCDs Make: Danko						
13.04	Air balancing with Report (3rd party report excluded).						
	Note : New FCUs are excluded, Only existing air flow will be distributed. **BMS/BTU meter/Sound Attenuetors / VAVs are excluded.**						
	TOTAL AMOUNT FOR HVAC WORKS					**AED**	**56,120.00**
14.00	**IT STRUCTURE AND CABLING WORKS :**						
14.01	Supply and installation of 20 mm PVC conduit for network cable.		150	Nos.	90.00	AED	13,500.00
14.02	Supply and installation of 50 mm PVC conduit for HDMI cable.		4	Nos.	400.00	AED	1,600.00
14.03	Supply and installation of data and telephone cabling, including CAT 6 cables (UTP) and RJ 45 jacks and face plates at the user end.		150	Nos.	235.00	RATE ONLY AND BY CLIENT'S IT CONTRACTOR	
14.04	Termination of network cable with keystone jack, RJ45 at user end.		150	Nos.	70.00		
14.05	Supply and installation of 24 port patch panel to suit additional network point.		7	Set	625.00		
14.06	Supply and installation of 3 mtr patch cord to suit new requirements at user end.		150	Set	28.00		
14.07	Supply and installation of 1.5 mtr patch cord to suit new requirements at server end.		180	Set	22.00		
14.08	Supply and Installation of HDMI Cables from the Conference Table to Projectors/TV.		4	nos.	280.00		
14.09	Supply and Install Wi-Fi access points (Locations : to be confirmed by client's IT administrator.)		10	nos.	1,050.00		
14.10	Fluke Test Report		1	Set	6,000.00		
	TOTAL AMOUNT FOR IT WORKS					**AED**	**15,100.00**
15.00	**CLOSE-OUT FORMALITIES**						
15.01	Arranging inspection for completion certificate, warranties, supplier details.		1	Nos.	8,000.00	AED	8,000.00
15.02	Soft copy of approved draiwngs.		1	Nos.			
15.03	General Cleaning prior to handover.		1	Nos.			
	TOTAL AMOUNT FOR CLOSE-OUT FORMALITIES					**AED**	**8,000.00**
	FINAL SUMMARY						
	TOTAL AMOUNT FOR ARCHITECTURAL WORKS					**AED**	**1,417,123.00**
	LESS SPECIAL CLIENT DISCOUNT					**AED**	**117,123.00**
	NET PROJECT VALUE EXCLUDING TAX					**AED**	**1,300,000.00**

DUBAI - U.A.E.
HTI CONTRACTING L.L.C