Design Infinity

Commercial Proposal

LVMH / Beauty

INTERIOR FIT-OUT WORKS

(RFP # PCD-23-RFP-01)

..Beyond Imagination

Design Infinity

CONTENTS;

1. Cover Letter with Notes & Exclusions

2. Bill of Quantities for the following;
    1. ADP_LOEW_EMFK
    2. GIVENCHY AND KENZO
    3. BPC

3. Contact Person

LVMH / Beauty

DATE:06/10/2023

REF: DI/GN/414/2023/R1

M/S LVMH BEAUTY
BUILDING 11, LEVEL 2
DUBAI DESIGN DISTRICT
UNITED ARAB EMIRATES

PROJECT: INTERIOR FITOUT WORKS FOR LVMH BEAUTY (RFP # PCD-23-RFP-01) @ D3, DUBAI, UAE.

Dear Concern,

We thank you for giving us an opportunity to **offer** our proposal for **the Interior Fit-out works of the LVMH Beauty at D3, Dubai.** Please find herewith our competitive offer as per the attached bill of quantities amounting as below;

Total Tendered Price.

TOTAL AMOUNT FOR (ADP/LOEWE/MFK) AED:	782,336.00
TOTAL AMOUNT FOR (GIVENCHY AND KENZO) AED:	1,359,414.00
TOTAL AMOUNT FOR (BPC) AED:	1,954,444.00
GRAND TOTAL AMOUNT AED:	4,096,194.00
LESS (CORPORATE DISCOUNT) AED:	-102,344.00
NET TOTAL AMOUNT AED:	3,993,850.00

VAT 5%: AED: 199,692.50

Validity:

30 days from the above date.

Execution Timeline:

As per the Project Schedule.

Payment Terms:

To be discussed and agreed.

P.O. Box. 62522 | Dubai | UAE
Tel: +971 4 3795902
Fax: +971 4 3795903
Email: info@design-infinity.com

P. O. Box. 62560 | Abu Dhabi | UAE
Tel: +971 2 4482286
Fax: +971 2 4482287
Email: info@design-infinity.com

www.design-infinity.com

Notes:

- The above price is exclusive of Value Added Tax (VAT); 5% VAT shall be payable as an addition to the invoice value.

Exclusions: -

- Authority fees & deposits.
- Bank guarantee or Retention Requirements (If any)
- Lighting control system & Dimmable type lights.
- Plants, Artwork, Photo frames, and Display accessories.
- Plants & Planters.
- Internal/External Signages/LOGO.
- Supply and installation of Loose furniture.
- CCTV/Access control & IT Related works.
- Any other items not mentioned in the attached BOQ.

We look forward to establishing a constructive dialogue with you at all stages of your evaluation process. We always assure you of our best services.

We hope our offer is in line with your requirements and look forward to working with you.

Thank you and best regards,

Geetha Nayak
Managing Partner
Mob: +971 50 146 7608
E: geetha@design-infinity.com

P.O. Box. 62522 | Dubai | UAE
Tel: +971 4 3795902
Fax: +971 4 3795903
Email: info@design-infinity.com

P. O. Box. 62560 | Abu Dhabi | UAE
Tel: +971 2 4482286
Fax: +971 2 4482287
Email: info@design-infinity.com

www.design-infinity.com

Design Infinity

BILL OF QUANTITIES
(ADP_LOEW_EMFK)

..Beyond Imagination

LVMH
Beauty

Design Infinity *Beyond Imagination ...*

SUMMARY		
SL NO.	DESCRIPTION	AMOUNT (AED)
1	TOTAL AMOUNT FOR ADP_LOEWE_EMFK	782,336.00
2	TOTAL AMOUNT FOR GIVENCHY AND KENZO	1,359,414.00
3	TOTAL AMOUNT FOR BPC	1,954,444.00
	GRAND TOTAL AMOUNT AED:	4,096,194.00
	LESS (CORPORATE DISCOUNT) AED:	(102,344.00)
	NET TOTAL AMOUNT AED:	3,993,850.00

PROJECT: LVMH BEAUTY @ D3 BLDG-10 & 11					
(BILL OF QUANTITIES-FIT-OUT WORKS FOR ADP_LOEWE_EMFK)					
REF: DI/GN/414/2023/QTN-01/R1					October 6, 2023
SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)
1.00	**PRELIMINARIES**				
1.01	General- Contractor's preliminaries for mobilization, site preparation, Provision for all temporary barricades	1.00	Item	6,080.00	6,080.00
1.02	Charges for setting out transportations to/from site, material deliveries, small tools and equipment's, protection of finished products in on-going site, site attendance and call out attendance.	1.00	Item	2,700.00	2,700.00
1.03	Charges for Preparation of Technical drawings (Architectural & MEP)for Relevant authorities & to execute the works at site.	1.00	Item	6,080.00	6,080.00
1.04	Allow provision of Insurance for entire fit out period. Contractors all Risk Insurance (As per UAE Law)	1.00	Item	1,620.00	1,620.00
1.05	Charges for Project management, site supervision & coordination.	1.00	Item	6,430.00	6,430.00
1.06	Allow for coordination with government/authorities along with submission of proposed designs and obtaining completion certificate.	1.00	Item	6,760.00	6,760.00
1.07	Charges for scaffolding & hoarding.	1.00	Item	3,380.00	3,380.00
1.08	Health, Safety and Environmental Procedures.	1.00	Item	-	INCLUDED
1.09	Provision of general attendance on other Contractors appointed by the Employer.	1.00	Item	1,350.00	1,350.00
1.10	Regular cleaning of site during construction period and after completion professional deep cleaning and made ready to occupy. Including carting away the debris to Municipal dumping area.	1.00	Item	2,030.00	2,030.00
	Security deposit, Authority Fees, entry and exit pass for vehicles and labors, night work permit fee(If required) are excluded				
				SUBTOTAL AED:	**36,430.00**
	CIVIL WORKS				
2.00	**DEMOLITION WORKS**				
2.01	Charges for Removal of existing unwanted ID/MEP Finishes/fixtures and carting away the debris to the approved municipality dump yard. Including making openings at existing walls to provide access for doors as per the proposed design. **Demolition works are subject to Building management approval.*	1.00	Item	14,470.00	14,470.00
				SUBTOTAL AED:	**14,470.00**
3.00	**PARTITION WORKS**				
3.01	**GYPSUM BOARD LINING (Non-FR)** Supply and installation of Gypsum board Lining at the existing door openings as pe the proposed design.	1.00	Item	1,350.00	1,350.00
3.02	**GYPSUM PARTITION (NON-FR)** Supply and installation of 100mm thick Non FR Double Layer (knauf) gypsum partition with rock wool insulation (density 30 kg/m3) and 12.5mm thick gypsum boards on both sides, jointed and taped with 72 mm GI studs and 70 mm GI tracks and smoothened and made ready to receive finishes. *Height: 2700mm* *Location: As per the partition layout*	32.00	Sq.m	150.00	4,800.00
3.03	**SINGLE-GLAZED GLASS PARTITION.** Supply and fixing of 12 mm clear tempered fixed straight glass partition with top and bottom 20 x 30 mm black powder coated aluminum U channel with rubber beading including glass to glass clear silicone joints including wall sides powder coated U channel with rubber beading. *Height: 2500mm* *Location: As per the partition layout*	50.00	Sq.m	340.00	17,000.00
3.04	**SMART GLASS PARTITION (MEETING ROOM)** Supply and installation of smart glass fix partition inclusive of 12mm thick tempered glass with High Clarity Switchable smart film (To be pasted on glass) inclusive of Electronically adjustable control from transparent to opaque, aluminum black powder coated U channel. Accessories: * Over current and short circuit protected Power Drive with inbuilt Dry Contacts and supplied complete with remote control. * Neutral Cure Specialty Silicone sealant. *Height: 2500mm* *Location: As per the partition layout*	20.00	Sq.m	1,990.00	RATE ONLY

(BILL OF QUANTITIES-FIT-OUT WORKS FOR ADP_LOEWE_EMFK)					
REF: DI/GN/414/2023/QTN-01/R1					October 6, 2023
SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)
3.04	**FIXED GLASS WINDOW.** Supply & fixing fixed glass window 6mm external reflective + 12 mm Air Gap + 6mm internal clear glass double glazed window on powder coated aluminium frame with all fittings Profile : 105 mm Non Thermal break profile. As per design and approved sample. *Different sizes are as follows;*				
A	SIZE: L 1900mm X H 1200mm	2.00	Nos	2,620.00	5,240.00
B	SIZE: L 2100mm X H 1200mm	1.00	No	2,890.00	2,890.00
C	SIZE: L 3320mm X H 1200mm	3.00	Nos	4,580.00	13,740.00
3.05	**STACKABLE WALL B/W MEETING ROOM.** Supply and installation of Movable partition between meeting rooms as per the below; Omni Directional panels Acoustic Rating of 51 STC (Lab tested) Panel Finishes: Unfinished ready to accept finishes by others Panel Frames: Lamb's Wool / Gray / Brown (TBC) Track Finish: Clear Anodized Aluminum Track Type – 36 Partition P-1 : (MEETING ROOM) Opening : 5250mm (W) x 2700mm (H) 5 No's. of Panels per partition 1 No. Partition	1.00	Item	49,360.00	49,360.00
3.06	**I BEAM SUPPORT FOR OPERABLE PARTITION.** Scope :- Scope : Supply & Installation I beam : Mild steel I Beam 150x150x5mm Hanging support for I beam: 100x100x3mm Mild steel tube fixed with 200x200x10mm Mild steel plate & 4 Nos of M12 anchor bolts. MTL, Grade & Finish:- Mild steel - Single coat primer finish.	1.00	Item	6,860.00	6,860.00
3.07	**GYPSUM BAFFLE (NON FR)** Supply and ins tallation of FR (knauf)Gypsum baffle on the above-proposed Gypsum & Glass partition including necessary materials for installation. *Location: Above proposed Gypsum & Glass Partition*	32.00	LM	100.00	3,200.00
	Exclusion:- *Phone Booth partition*				
				SUBTOTAL AED:	**104,440.00**
4.00	**FLOOR FINISH**				
4.01	**EXISTING RAISED FLOOR RECTIFICATION.** Allow necessary Rectification works on existing Raised flooring. After the Proposed demolition, partition and FB Installation works. *Location: As necessary for the proposed design*	1.00	Item	19,380.00	19,380.00
4.02	**MDF FLOOR LINING.** Supply and installation of MDF Lining/Cladding above existing Raised floor. Including necessary materials of installation. As per design and approved *sample. Location: Proposed LVT Floor area*	1.00	Item	3,850.00	3,850.00
4.03	**CARPET FLOORING (FF-01)** Supply and Installation of Carpet flooring (FF-01) including adhesives for fixing. As per the design and approved sample. *Location: Meeting room, office cabins & workstation area*	201.00	Sq.m	160.00	32,160.00
4.04	**LVT FLOORING (FF-02)** Supply and installation of 3-4 mm Thk LVT flooring with necessary materials for fixing. As per the design and approved sample. *Location: Dining space*	38.00	Sq.m	160.00	6,080.00
4.05	**TRANSITION STRIP (SS FINISH)** Supply and Installation of SS transition strip. *Location: B/W floor finishes and door openings.*	10.00	LM	100.00	1,000.00
				SUBTOTAL AED:	**62,470.00**

(BILL OF QUANTITIES-FIT-OUT WORKS FOR ADP_LOEWE_EMFK)					
REF: DI/GN/414/2023/QTN-01/R1					October 6, 2023
SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)
5.00	**WALL FINISH**				
5.01	**WHITE PAINT.** Supply and application of Jotun Fenomastic White/Grey paint. As per the design and approved sample. (2 coats including leveling and sanding) *Location: General areas as per wall finishes plan*	135.00	Sq.m	34.00	4,590.00
5.02	**TEXTURE PAINT (CONCRETE EFFECT).** Supply and application of Texture paint. As per the design and approved sample. (2 coats including leveling and sanding) *Location: General areas as per wall finishes plan*	43.00	Sq.m	150.00	6,450.00
5.03	**WALL PAPER.** Supply and installation of Wallpaper. Including necessary materials for fixing. As per the design and approved sample. *Location: As per wall finishes plan*	67.00	Sq.m	160.00	10,720.00
5.04	**FROSTED STICKER.** Supply and Installation of Frosted Sticker on Proposed glass partition @ Level from 700mm to 1900mm for office cabins & full height at meeting rooms with necessary material for fixing as per design and approved sample. *Location: Proposed Glass Partition*	43.00	Sq.m	90.00	3,870.00
5.05	**MDF SKIRTING.** Supply and installation of 100mm high MDF Skirting finished with Black paint. Including necessary materials for fixing. As per the design and approved sample. *Location: As per Wall finishes layout*	92.00	LM	60.00	5,520.00
5.06	**ROLLER BLINDS (WHITE)** Supply and installation of Manual Roller Blinds on the existing glass window. As per the design and approved sample. Height: 2700mm *Location: General areas as per wall finishes plan*	79.00	Sq.m	100.00	7,900.00
				SUBTOTAL AED:	**39,050.00**
6.00	**CEILING FINISH**				
6.01	**GYPSUM PLAIN CEILING.** Supply and installation of non fire rated Gypsum Board Plain ceiling (Knauf or equivalent)with necessary hanging systems including GI wall angle "C "channel, furring channel with 12.5mm gypsum boards joined taped smoothened finish. *Location: As per proposed RCP*	239.00	Sq.m	110.00	26,290.00
6.02	**GYPSUM BULKHEAD.** Supply and installation of Plain Gypsum Bulkhead using 12.5mm thick gypsum boards (Knauf or equivalent) and GI suspension system. Gypsum board surface made ready to receive final finish. As per design and approved sample. *Location: As per proposed RCP*	115.00	LM	100.00	11,500.00
6.03	**GYPSUM PELMET.** Supply and installation of (knauf) Gypsum Pelmet with necessary fittings ready to receive final finishes. *Location: Periphery glass wall*	29.00	LM	90.00	2,610.00
6.04	**CEILING PAINT.** Supply and application of **Jotun Fenomastic paint** including all cleaning and levelling. As per design and approved sample. (2 coats including sanding). **Color/Type are as follows;**				
A	WHITE PAINT (ON GYPSUM CEILING)	239.00	Sqm	34.00	8,126.00
B	BLACK/WHITE PAINT (ON GYPSUM BULKHEAD/PELMET)	144.00	LM	30.00	4,320.00
6.05	**GYPSUM ACCESS PANEL.** Supply and installation of **Gypsum access panel** with frame and hinges. *Location: Proposed Gypsum ceiling area*	10.00	Nos	260.00	2,600.00
				SUBTOTAL AED:	**55,446.00**

(BILL OF QUANTITIES-FIT-OUT WORKS FOR ADP_LOEWE_EMFK)

REF: DI/GN/414/2023/QTN-01/R1 — **October 6, 2023**

SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)
7.00	**DOORS**				
7.01	**SINGLE GLAZED SINGLE LEAF GLASS DOOR.** Scope :- Supply & Installation; Glass panel : 12mm thick clear tempered glass cladded with 20x30mm black powder-coated aluminum U channel. Floor spring : Assa Abloy - DC410U. Handle: Ø30mm x 1200mm (Height) Top & Bottom Patch fittings : Royal Sahara brand; Size:- 900mm W x 2500 mm H. Finish:- Black powder coated *Location: As per GA Plan*	6	Nos	2,700.00	16,200.00
7.02	**SINGLE GLAZED SINGLE LEAF ARCH GLASS DOOR.** Scope :- Supply & Installation; Glass panel : 12mm thick clear tempered glass cladded with 20x30mm black powder-coated aluminum U channel. Floor spring : Assa Abloy - DC410U. Handle: Ø30mm x 1200mm (Height) Top & Bottom Patch fittings : Royal Sahara brand; Size:- 900mm W x 2500 mm H. Finish:- Black powder coated *Location: As per GA Plan*	1.00	No	3,720.00	3,720.00
7.03	**SINGLE GLAZED SINGLE LEAF SMART GLASS DOOR.** Scope :- Supply and installation of smart glass fix partition inclusive of 12mm thick tempered glass with High Clarity Switchable smart film (To be pasted on glass) inclusive of Electronically adjustable control from transparent to opaque, aluminum black powder coated U channel cladding all around the door leaf & standard door floor spring, patch fittings & handles. Accessories: * Over current and short circuit protected Power Drive with inbuilt Dry Contacts and supplied complete with remote control. * Neutral Cure Specialty Silicone sealant. *Size: L 900mm X H 2500mm* *Location: As per GA Plan*	2	Nos	8,870.00	RATE ONLY
	**** Main entrance and dining area door: Existing***				
				SUBTOTAL AED:	**19,920.00**
8.00	**JOINERY WORKS**				
8.01	**MEETING ROOM STORAGE CABINET.** Made of MDF Green PU Paint finish shutters and Laminated MDF finish open shelves with lights, carcass made out of white laminate finish. Including necessary materials for fixing. As per the design and approved sample.  Size-2400x450x2500 mm ht.	2.00	Nos	10,420.00	20,840.00
8.02	**ROUND COLUMN CLADDING & LEDGE UNIT** Made of MDF Laminate finish with fluted wall cladding design, ledge in white Corian top with necessary wooden support. Size-1635x450x50/1500 mm ht Location - Casual Meeting	1.00	No	8,010.00	8,010.00
8.03	**LOEWE MANAGER OPEN SHELF** Made of MDF texture paint finish(texture PC rate - 150AED/Sqm) Size-2100+1800x300x50 mm ht Location -LOEWE Manager	1.00	Item	5,220.00	5,220.00
8.04	**MFK MANAGER BACK WALL CLADDING.** Supply and installation of wall Laminate paneling including marble-looking glossy laminate finish as per the design. Including necessary materials for fixing. As per the design and approved sample. Size - 2700x3500 mm HT Location-MFK Manager	1.00	Item	5,680.00	5,680.00

(BILL OF QUANTITIES-FIT-OUT WORKS FOR ADP_LOEWE_EMFK)

REF: DI/GN/414/2023/QTN-01/R1 — **October 6, 2023**

SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)
8.05	**GENERAL MANAGER WALL METAL DISPLAY** Scope :- Scope: Supply & Installation Frame: 20x20mm Tube Glass shelves: Included 	1.00	Item	3,920.00	3,920.00
8.06	**FULL HEIGHT STORAGE CABINET.** Made of MDF Laminate finish with fluted shutter design, inside carcass will be white laminate finish. Size-1910+560x450x2400 mm ht.	1.00	No	13,250.00	13,250.00
8.07	**LOW HEIGHT STORAGE CABINET** Made out of Laminate MDF outer finish , the shutter in horizontal fluted design, inside carcass will be white laminate finish. Different Sizes are as follows;				
A	Size-1475x400x750mm ht. Location: Workstation area	5.00	Nos	3,970.00	RATE ONLY
B	Size-2350x400x750mm ht. Location: Workstation area	1.00	No	6,150.00	RATE ONLY
C	Size-3230x450x750mm ht. Location: Main entrance area	1.00	No	8,570.00	RATE ONLY
D	Size-2215x450x750mm ht. Location - LOEWE Manager	1.00	No	6,300.00	RATE ONLY
E	Size-1200x450x750mm ht. Location -HR/MFK Manager	2.00	No	4,030.00	RATE ONLY
8.08	**DINING LEDGE UNIT.** Made out of Laminated MDF outer finish, in metal cantilever support. Size-4846+6000+3000x450x50mm ht.	1.00	Item	8,110.00	8,110.00
				SUBTOTAL AED:	**65,030.00**
	MEP WORKS				
1.0	**LIGHT FIXTURES**				
	Supply of light fixture as pe the new layout Make-Creta Light Down light, Sport light, Strip light,				
1.1.1	TR 1: RECESSED TRACK	70.0	Mtrs	320.00	22,400.00
1.1.2	TR1A : RECESSED LINEAR TRACK LIGHT	40.0	Nos	260.00	10,400.00
1.1.3	TR 2: RECESSED TRACK	50.0	Mtrs	320.00	16,000.00
1.1.4	TR 2A: CYLINDRICAL TRACK LIGHT	42.0	Nos	220.00	9,240.00
1.1.5	CL1: LED STRIP LIGHTS	40.0	Mtrs	90.00	3,600.00
1.1.6	P1 : PENDANT LIGHTS AROUND COLUMN	6.0	Nos	410.00	2,460.00
1.1.7	P2 : PENDANT LIGHTS	6.0	Nos	1,280.00	7,680.00

(BILL OF QUANTITIES-FIT-OUT WORKS FOR ADP_LOEWE_EMFK)					
REF: DI/GN/414/2023/QTN-01/R1					October 6, 2023
SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)
1.1.8	P3: PENDANT LIGHTS	6.0	Nos	1,280.00	7,680.00
				SUB TOTAL FOR LIGHT FIXTURES AED:	79,460.00
2.0	ELECTRICAL WORKS				
2.1	Modification for the existing cable tray as per the new layout and requirements.				
2.1.1	Cable tray for the DB outgoing power cables above the ceiling	20.00	Mtr	120.00	2,400.00
2.1.2	Cable tray for the DB outgoing light cables	20.00	Mtr	120.00	2,400.00
2.1.3	Cable tray under the raised floor for power	20.00	Mtr	130.00	2,600.00
2.2	Modifications for the existing Distribution Boards				
2.2.1	DB-Light and Power- Existing	3.00	Nos	2,890.00	8,670.00
2.3	Lighting | Installation of Lighting system including conducting and wiring with all necessary accessories and ancillary works as specified and as indicating in the drawings. PVC Conduit and Wire				
2.3.1	Supply and installation of conduit and wiring for the light fixtures	100.00	Nos	190.00	19,000.00
2.3.2	Supply and installation of conduit and wiring for the linear lights	70.00	Mtr	190.00	13,300.00
2.3.3	Installation of light by using special supports	170.00	Nos	40.00	6,800.00
2.3.4	Installation of tracks	120.00	Mr	60.00	7,200.00
2.3.5	Supply and installation of lighting switches	10.00	Nos	180.00	1,800.00
2.4	Power | supply and installation of Power system including conducting and wiring with all necessary accessories and ancillary works as indicating in the drawings and as specified below .				
	Final circuit wiring; including necessary containment system, terminations other ancillary work, complete-Point wiring to socket outlets; PVC Finish				
2.4.1	Supply and installation of Single Socket including conducting & wiring 13A, 220V, 50Hz 2 pole and earth single switch socket outlet.	4.00	Nos	360.00	1,440.00
2.4.2	Supply and installation of Double Socket including conducting & wiring 13A, two gang, 220V, 50Hz, 2 pole and earth twin switch socket outlet.	14.00	Nos	390.00	5,460.00
2.4.3	Relocation for the existing Floor Box	7.00	Nos	450.00	3,150.00
2.4.4	Supply and Installation of Floor Box (FB-2) including wiring and pvc containment for 2no 13A Double power socket and 1no conduit for data/Voice outlet. Note: Data/Voice cabling and termination works are excluded. Floor box is considered for the workstations	15.00	Nos	900.00	13,500.00
2.4.5	Supply and installation of Power provisions for VAV's & Relocation of FCU's	8.00	Nos	540.00	4,320.00
2.4.6	Supply and installation 13 A Spur outlet with cabling and conducting.	4.00	Nos	410.00	1,640.00
2.4.7	Supply and installation of PVC conduit for the IT and data points	30.00	Nos	120.00	3,600.00
				SUB TOTAL AED:	97,280.00
2.5	SUNDRIES RELATED TO ELECTRICAL ENGINEERING INSTALLATIONS				
2.5.1	Allow for documents including shop drawings, as built drawings, operating instructions and maintenance manuals as specified.	1.00	Item	1,930.00	1,930.00

(BILL OF QUANTITIES-FIT-OUT WORKS FOR ADP_LOEWE_EMFK)					
REF: DI/GN/414/2023/QTN-01/R1					October 6, 2023
SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)
2.5.3	Allow for cutting or forming holes, mortices, chases or the like and making good finishing's. (Provisional sum)	1.00	Item	640.00	640.00
2.5.4	Allow for testing and commissioning of electrical services	1.00	Item	1,930.00	1,930.00
2.5.5	Allow for identification labels including plates, discs, labels, charts and color coding.	1.00	Item	640.00	640.00
				SUB TOTAL AED:	**5,140.00**
				GRAND TOTAL ELECTRICAL WORKS AED:	**102,420.00**
3.0	**MECHANICAL WORKS**				
	AIR CONDITIONING SYSTEM				
3.0.1	Supply and installation of VAV's for closed Rooms	6	Nos	2,890.00	17,340.00
3.0.2	Thermostats for VAV's	6	Nos	580.00	3,480.00
3.0.3	Relocation of FCU's	2	Nos	640.00	1,280.00
3.0.4	Valve package Kit	2	Nos	2,890.00	5,780.00
3.0.5	Stand alone Thermostats for Relocated FCU's	2	Nos	580.00	1,160.00
3.0.6	Modification of Chilled water Piping	2	Nos	1,230.00	2,460.00
3.1	**Air Distribution**				
	Supply, fabricate and install GI duct including volume splitter rod and dampers, access panels, supporting system, and connections complete in accordance with the specification and Drawing				
3.1.1	Modification of Duct works	80	Sqm	280.00	22,400.00
3.1.2	Flexible duct including RVCD	60	Nos	210.00	12,600.00
3.1.4	Supply and Installation of Plenum Box with 19mm Closed cell elastromeric insulation , Alu glass finish, 13mm Acoustic Lining , Necessary Supports & Connections	60	Nos	190.00	11,400.00
	SECTION - MECHANICAL INSTALLATION (Cont'd)				
3.1.5	Volume Control Damper	12	Nos	180.00	2,160.00
	Supply & Return Air Diffuser's				
3.1.6	Linear Grill for Gypsum ceiling				
3.1.7	SLSD	25	Mtr	230.00	5,750.00
3.1.8	RLSD	22	Mtr	210.00	4,620.00
3.1.9	Square Diffusers	32	Nos	230.00	7,360.00
				SUB TOTAL AED:	**97,790.00**
3.2	**SUNDRIES RELATED TO MECHANICAL WORKS**				
3.2.1	Testing and commissioning the HVAC Including Air Balancing & water Balancing	1	Item	5,780.00	5,780.00
					-

(BILL OF QUANTITIES-FIT-OUT WORKS FOR ADP_LOEWE_EMFK)					
REF: DI/GN/414/2023/QTN-01/R1					October 6, 2023
SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)
3.2.2	Allow for all necessary identification, including plates, discs,	1	Item	640.00	640.00
	labels, charts and color coding all complete as described				-
					-
	Allow for all necessary documents including	1	Item	5,780.00	5,780.00
3.2.3	as-built drawings, operating instructions and maintenance manuals				-
					-
3.2.4	**Performance Test for HVAC Equipment's**				-
	Performance testing for Existing FCU's	3	No	640.00	1,920.00
				SUB TOTAL AED:	**14,120.00**
				GRAND TOTAL (MECHANICAL WORKS) AED:	**111,910.00**
4	**CIVIL DEFENCE WORKS**				
4.1	**FIRE FIGHTING INSTALLATION**				
	All fire suppression services installations to be in accordance with relevant specification sections, and all other specifications and UAE building codes				
4.1.1	25 mm diameter.	1.00	Item	-	INCLUDED
4.1.2	32 mm diameter.	1.00	Item	-	INCLUDED
4.1.6	Sprinkler heads complete with all necessary accessories as specified and as shown on drawing				
4.1.7	Concealed pendant sprinkler new	24.00	Nos	880.00	21,120.00
4.1.8	Relocation for the existing pendent sprinkler with new head	7.00	Nos	670.00	4,690.00
4.1.9	Fire extinguishers and equipment complete as specified including supports, brackets, instruction signs and the like				
4.1.10	5 Kg CO2 Portable fire extinguisher.	2.00	Nos	320.00	640.00
4.1.11	4.5 Kg Dry chemical portable fire extinguisher	2.00	Nos	450.00	900.00
4.1.12	Supply and installation of zone control valve	1.00	Item	5,840.00	5,840.00
4.1.14	Draining, Refilling, Pressure Testing and Certification by third party	1.00	Item	5,780.00	5,780.00
				SUB TOTAL AED:	**38,970.00**
5.0	**EMERGENCY LIGHTING INSTALLATION**				
5.1	Emergency light fittings including battery pack, fixings, lamps and connections complete as described.				
5.1.1	Addressable emergency light, non maintained	6.00	Nos	1,350.00	8,100.00
5.1.2	Relocation for the existing Emergency/Exit light	4.00	Nos	480.00	1,920.00
5.1.3	PVC conduit and Fire rated cables for the emergency lights	1.00	Item	1,930.00	1,930.00
Notes	Existing CBS Emergency lights are keep above the ceiling				
				SUB TOTAL AED:	**11,950.00**
6.0	**FIRE ALARM INSTALLATION**				
	All the extra low voltage power installation works to be in accordance with relevant specification and all other specification and UAE building codes				
6.1	**Final sub-circuits**				
	Final circuit wiring; including necessary containment system, terminations other ancillary work, complete.				

(BILL OF QUANTITIES-FIT-OUT WORKS FOR ADP_LOEWE_EMFK)					
REF: DI/GN/414/2023/QTN-01/R1					October 6, 2023
SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)
6.1.1	Smoke detectors-New	7.00	Nos	1,600.00	11,200.00
6.1.2	Interface Module	2.00	Nos	2,120.00	4,240.00
6.1.3	Manual call point	1.00	Nos	1,670.00	1,670.00
6.1.4	Fire alarm sounder	1.00	Nos	1,670.00	1,670.00
6.1.5	Relocation for the existing Smoke detector	4.00	Nos	580.00	2,320.00
6.1.6	Termination of the new devices in the existing FACP panel	1.00	Item	2,890.00	2,890.00
6.1.7	Fire alarm Re-Programming, Testing and commissioning	1.00	Item	5,780.00	5,780.00
6.1.8	Installation of fire alarm devices including the PVC Conduit and FP200 fire red cables	1.00	Item	1,930.00	1,930.00
6.1.9	Graphic upgradation for the existing FACP panel	1.00	Item	2,890.00	2,890.00
6.1.10	Charge for DCD Civil defense till completion certificate	1.00	Item	5,780.00	5,780.00
				SUB TOTAL AED:	**40,370.00**
				GRAND TOTAL CIVIL DEFENCE WORKS AED:	**91,290.00**
	MEP NOTES & EXCLUSIONS;				
	Technical Notes : *-Considered Modification of Ducting, New Air outlets & Dampers* *-We have assumed that all the FCU's are in a Good condition.* *-We proposed New VAV's for the Closed Rooms* *-We have not considered Back up unit for Server Room. If its needs it will be as a variation.* *-We have considered Relocation of Pendent Sprinklers & Smoke detectors as per the site available & Additional Pendent Sprinklers & Smoke detectors will be added as per the site condition .* *-Required power provision to be provided by the Landlord and DEWA Approvals is not considered.* *-We proposed Standalone system for Proposed New VAV's & Relocated FCU's only* ***Exclusions*** *-CCU (or) Any Back up units for Server room* *-Main Duct Works & Accostic lagging* *-Supply of HVAC Equipment's* *-Supply (or) Any relocation of Upright sprinklers & Void detectors* *-Plumbing works* *-Any Upgradation Works* *-Chemical flushing* *-BMS* *-Cladding Works* *-Power upgradation.* *-lighting control system.* ***FIRE ALARM/FIRE FIGHTING WORKS.*** *1. Civil defense final price subject to final design.* *2. Assume existing Upright sprinkler and Void smoke detectors will be available at the site and can be reused.*				

(BILL OF QUANTITIES-FIT-OUT WORKS FOR ADP_LOEWE_EMFK)					
REF: DI/GN/414/2023/QTN-01/R1					October 6, 2023
SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)

SUMMARY (ADP_LOEW_EMFK)

SL NO.	DESCRIPTION	AMOUNT (AED)
1	PRELIMINARIES	36,430.00
2	DEMOLITION WORKS	14,470.00
3	PARTITION WORKS	104,440.00
4	FLOOR FINISH	62,470.00
5	WALL FINISH	39,050.00
6	CEILING FINISH	55,446.00
7	DOORS	19,920.00
8	JOINERY WORKS	65,030.00
9	LIGHT FIXTURES	79,460.00
10	ELECTRICAL WORKS	102,420.00
11	MECHANICAL WORKS	111,910.00
12	CIVIL DEFENCE WORKS	91,290.00
	GRAND TOTAL AMOUNT AED:	782,336.00

Design Infinity

BILL OF QUANTITIES
(GIVENCHY AND KENZO)

..Beyond Imagination

LVMH
Beauty

PROJECT: LVMH BEAUTY @ D3 BLDG-10 & 11					
(BILL OF QUANTITIES-FIT-OUT WORKS FOR GIVENCHY AND KENZO)					
REF: DI/GN/414/2023/QTN-02/R1					October 6, 2023
SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)
1.00	**PRELIMINARIES**				
1.01	General- Contractor's preliminaries for mobilization, site preparation, Provision for all temporary barricades	1.00	Item	6,080.00	6,080.00
1.02	Charges for setting out transportations to/from site, material deliveries, small tools and equipment's, protection of finished products in on-going site, site attendance and call out attendance.	1.00	Item	2,700.00	2,700.00
1.03	Charges for Preparation of Technical drawings (Architectural & MEP)for Relevant authorities & to execute the works at site.	1.00	Item	6,080.00	6,080.00
1.04	Allow provision of Insurance for entire fit out period. Contractors all Risk Insurance (As per UAE Law)	1.00	Item	1,620.00	1,620.00
1.05	Charges for Project management, site supervision & coordination.	1.00	Item	10,270.00	10,270.00
1.06	Allow for coordination with government/authorities along with submission of proposed designs and obtaining completion certificate.	1.00	Item	6,760.00	6,760.00
1.07	Charges for scaffolding & hoarding.	1.00	Item	3,380.00	3,380.00
1.08	Health, Safety and Environmental Procedures.	1.00	Item	-	INCLUDED
1.09	Provision of general attendance on other Contractors appointed by the Employer.	1.00	Item	1,350.00	1,350.00
1.10	Regular cleaning of site during construction period and after completion professional deep cleaning and made ready to occupy. Including carting away the debris to Municipal dumping area.	1.00	Item	2,030.00	2,030.00
	Security deposit, Authority Fees, entry and exit pass for vehicles and labors, night work permit fee(If required) are excluded				
				SUBTOTAL AED:	**40,270.00**
	CIVIL WORKS				
2.00	**DEMOLITION WORKS**				
2.01	Charges for Removal of existing unwanted ID/MEP Finishes/fixtures and carting away the debris to the approved municipality dump yard. Including making openings at existing walls to provide access for doors as per the proposed design. **Demolition works are subject to Building management approval.*	1.00	Item	23,110.00	23,110.00
				SUBTOTAL AED:	**23,110.00**
3.00	**PARTITION WORKS**				
3.01	**GYPSUM BOARD LINING (Non-FR)** Supply and installation of Gypsum board Lining at the existing door openings as pe the proposed design.	1.00	Item	1,520.00	1,520.00
3.02	**GYPSUM PARTITION (NON-FR)** Supply and installation of 100mm thick Non FR Double Layer (knauf) gypsum partition with rock wool insulation (density 30 kg/m3) and 12.5mm thick gypsum boards on both sides, jointed and taped with 72 mm GI studs and 70 mm GI tracks and smoothened and made ready to receive finishes. *Height: 2700mm* *Location: As per the partition layout*	117.00	Sq.m	150.00	17,550.00
3.03	**SINGLE-GLAZED GLASS PARTITION.** Supply and fixing of 12 mm clear tempered fixed straight glass partition with top and bottom 20 x 50 mm black powder coated aluminum U channel with rubber beading including glass to glass clear silicone joints including wall sides 20 x 50 mm powder coated U channel with rubber beading. *Height: 2500mm* *Location: As per the partition layout*	88.00	Sq.m	340.00	29,920.00
3.04	**SMART GLASS PARTITION (MEETING ROOMS)** Supply and installation of smart glass fix partition inclusive of 12mm thick tempered glass with High Clarity Switchable smart film (To be pasted on glass) inclusive of Electronically adjustable control from transparent to opaque, aluminum black powder coated U channel. Accessories: * Over current and short circuit protected Power Drive with inbuilt Dry Contacts and supplied complete with remote control. * Neutral Cure Specialty Silicone sealant. *Height: 2500mm* *Location: As per the partition layout*	27.00	Sq.m	1,990.00	RATE ONLY

(BILL OF QUANTITIES-FIT-OUT WORKS FOR GIVENCHY AND KENZO)					
REF: DI/GN/414/2023/QTN-02/R1					October 6, 2023
SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)
3.05	**STACKABLE WALL AT PANTRY** Supply and installation of Movable partition between Pantry/Experience room as per the below; Omni Directional Panels Panel Finishes: Sealed double glazed unit 6mm thick clear tempered glass 24mm air space 8mm thick clear tempered glass Panel Frames: Powder Coated in Standard RAL color Track Finish: Powder Coated in Standard RAL color Track Type – 36 Partition P-1 (PANTRY AREA) Opening – 4810mm W) x 2700mm (H) 4 No's. of Panels per partition + 1 No. Flipper Panel 1 No. Partition	1.00	Item	44,360.00	44,360.00
3.06	**I BEAM SUPPORT FOR OPERABLE PARTITION.** Scope :- Scope : Supply & Installation I beam : Mild steel I Beam 150x150x5mm Hanging support for I beam: 100x100x3mm Mild steel tube fixed with 200x200x10mm Mild steel plate & 4 Nos of M12 anchor bolts. MTL, Grade & Finish:- Mild steel - Single coat primer finish.	1.00	Item	5,720.00	5,720.00
3.07	**GYPSUM BAFFLE (NON FR)** Supply and ins tallation of FR (knauf)Gypsum baffle on the above-proposed Gypsum & Glass partition including necessary materials for installation. *Location: Above proposed Gypsum & Glass Partition*	82.00	LM	100.00	8,200.00
				SUBTOTAL AED:	**107,270.00**
4.00	**FLOOR FINISH**				
4.01	**EXISTING RAISED FLOOR RECTIFICATION.** Allow necessary Rectification works on existing Raised flooring. After the Proposed demolition, partition and FB Installation works. *Location: As necessary for the proposed design*	1.00	Item	30,810.00	30,810.00
4.02	**MDF FLOOR LINING.** Supply and installation of MDF Lining/Cladding above existing Raised floor. Including necessary materials of installation. As per design and approved *sample. Location: Proposed LVT Floor area*	118.00	Sq.m	90.00	10,620.00
4.03	**PORCELAIN FLOOR TILES (FF-01)** Supply and installation of 600X600mm Porcelain floor tiles (FF-01) with necessary materials for fixing. As per the design and approved sample. *Location: Open workstation, Pantry & Experience room*	262.00	Sq.m	170.00	44,540.00
4.04	**LVT FLOORING (FF-02)** Supply and installation of 3-4 mm Thk LVT flooring with necessary materials for fixing. As per the design and approved sample. *Location: GM Cabin, Meeting room, Office cabin & Meeting-01 & 02*	118.00	Sq.m	160.00	18,880.00
4.05	**TRANSITION STRIP (SS FINISH)** Supply and Installation of SS transition strip. *Location: B/W floor finishes and door openings.*	14.00	LM	100.00	1,400.00
	**** Exclusion;*** *- Loose Rugs*				
				SUBTOTAL AED:	**106,250.00**
5.00	**WALL FINISH**				
5.01	**WHITE PAINT.** Supply and application of Jotun Fenomastic White paint. As per the design and approved sample. (2 coats including leveling and sanding) *Location: General areas as per wall finishes plan*	218.00	Sq.m	34.00	7,412.00
5.02	**TEXTURE PAINT (CONCRETE EFFECT).** Supply and application of Texture paint. As per the design and approved sample. (2 coats including leveling and sanding) *Location: General areas as per wall finishes plan*	86.00	Sq.m	150.00	12,900.00

(BILL OF QUANTITIES-FIT-OUT WORKS FOR GIVENCHY AND KENZO)

REF: DI/GN/414/2023/QTN-02/R1 — **October 6, 2023**

SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)
5.03	**SLAT WALL CLADDING (TYPE-A)** Supply and installation of slat wall panel made of MDF Laminate finish. Including necessary materials for fixing. As per the design and approved sample. *Location: Entrance, GM Room, Pantry*	45.00	Sq.m	1,050.00	47,250.00
5.04	**SLAT WALL CLADDING (TYPE-B)** Supply and installation of black slat wall panel made of MDF Laminate finish as per the design. Size - 300 mm HT *Location: Pantry Bulkhead*	3.00	Sq.m	1,050.00	3,150.00
5.05	**MDF WALL PANELING.** Supply and installation of wall panel made of MDF in Laminate finish as per the design. Size - 2710x3000 mm HT Location: Meeting Rooms	38.00	Sq.m	570.00	21,660.00
5.06	**BACK-PAINTED GLASS CLADDING (WHITE)** Supply and installation of Writing board made of 6 mm thk back painted glass. including reinforcement support with necessary materials for fixing. As per design and approved sample. *Location: Meeting room*	13.00	Sq.m	540.00	7,020.00
5.07	**FROSTED STICKER.** Supply and Installation of Frosted Sticker on Proposed glass partition @ Level from 700mm to 1900mm for office cabins & full height at meeting rooms with necessary material for fixing as per design and approved sample. *Location: Proposed Glass Partition*	68.00	Sq.m	90.00	6,120.00
5.08	**MDF/TILE SKIRTING.** Supply and installation of 100mm high MDF Skirting finished with Black paint. Including necessary materials for fixing. As per the design and approved sample. *Location: As per Wall finishes layout*	115.00	LM	60.00	6,900.00
5.09	**ROLLER BLINDS (WHITE)** Supply and installation of Manual Roller Blinds on the existing glass window. As per the design and approved sample. Height: 2700mm *Location: General areas as per wall finishes plan*	92.00	Sq.m	100.00	9,200.00
				SUBTOTAL AED:	**121,612.00**
6.00	**CEILING FINISH**				
6.01	**GYPSUM PLAIN CEILING.** Supply and installation of non fire rated Gypsum Board Plain ceiling (Knauf or equivalent)with necessary hanging systems including GI wall angle "C "channel, furring channel with 12.5mm gypsum boards joined taped smoothened finish. *Location: As per proposed RCP*	133.00	Sq.m	110.00	14,630.00
6.02	**GYPSUM BULKHEAD.** Supply and installation of Plain Gypsum Bulkhead using 12.5mm thick gypsum boards (Knauf or equivalent) and GI suspension system. Gypsum board surface made ready to receive final finish. As per design and approved sample. *Location: As per proposed RCP*	85.00	LM	100.00	8,500.00
6.03	**MDF BAFFLE CEILING.** Supply and Installation of 50mm x 100mm thk Laminated MDF baffle ceiling including necessary material for fixing. As per design and approved *sample. Location: Workstation area*	247.00	Sq.m	1,080.00	266,760.00
6.04	**ALUMINIUM BAFFLE CEILING.** Scope :- Scope: Supply & Installation Baffle: 100x50mm Aluminum tube. (Joint lines will be visible at every 3000mm Length) C/C Distance: 100mm (50mm spacing between baffles) Fixing: Using metal hangers *Location: Workstation area*	247.00	Sq.m	1,320.00	OPTIONAL

(BILL OF QUANTITIES-FIT-OUT WORKS FOR GIVENCHY AND KENZO)					
REF: DI/GN/414/2023/QTN-02/R1					October 6, 2023
SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)
6.05	**GYPSUM PELMET.** Supply and installation of (knauf) Gypsum Pelmet with necessary fittings ready to receive final finishes. *Location: Periphery glass wall*	34.00	LM	90.00	3,060.00
6.06	**CEILING PAINT.** Supply and application of **Jotun Fenomastic paint** including all cleaning and levelling. As per design and approved sample. (2 coats including sanding). **Color/Type are as follows;**				
A	WHITE PAINT (ON GYPSUM CEILING)	133.00	Sqm	34.00	4,522.00
B	BLACK/WHITE PAINT (ON GYPSUM BULKHEAD/PELMET)	119.00	LM	30.00	3,570.00
C	BLACK/WHITE PAINT (@ SLAB ABOVE BAFFLE CEILING)	247.00	Sqm	40.00	9,880.00
6.07	**GYPSUM ACCESS PANEL.** Supply and installation of **Gypsum access panel** with frame and hinges. *Location: Proposed Gypsum ceiling area*	11.00	Nos	260.00	2,860.00
				SUBTOTAL AED:	**313,782.00**
7.00	**DOORS**				
7.01	**SINGLE GLAZED SINGLE LEAF GLAS SSWING DOOR.** Scope :- Supply & Installation; Glass panel : 12mm thick clear tempered glass cladded with 20x30mm black powder-coated aluminum U channel. Floor spring : Assa Abloy - DC410U. Handle: Ø30mm x 1200mm (Height) Top & Bottom Patch fittings : Royal Sahara brand; Size:- 900mm W x 2500 mm H. Finish:- Black powder coated *Location: As per GA Plan*	8.00	Nos	2,700.00	21,600.00
7.02	**SINGLE GLAZED SINGLE LEAF GLASS SLIDING DOOR.** Scope :- Supply & Installation; Glass panel : 12mm thick clear tempered glass cladded with 20x30mm black powder-coated aluminum U channel. Handle: Ø30mm x 1200mm (Height) Top & Bottom Patch fittings : Royal Sahara brand; Size:- 900mm W x 2500 mm H. Finish:- Black powder coated *Location: As per GA Plan*	2.00	Nos	3,720.00	7,440.00
7.03	**SINGLE GLAZED SINGLE LEAF SMART GLASS DOOR.** Scope :- Supply and installation of smart glass fix partition inclusive of 12mm thick tempered glass with High Clarity Switchable smart film (To be pasted on glass) inclusive of Electronically adjustable control from transparent to opaque, aluminum black powder coated U channel cladding all around the door leaf & standard door floor spring, patch fittings & handles. Accessories: * Over current and short circuit protected Power Drive with inbuilt Dry Contacts and supplied complete with remote control. * Neutral Cure Specialty Silicone sealant. *Size: L 900mm X H 2500mm* *Location: As per GA Plan*	1.00	No	8,870.00	RATE ONLY
7.04	**SINGLE GLAZED SINGLE LEAF SMART GLASS SLIDING DOOR.** Scope:- Supply and installation of smart glass fix partition inclusive of 12mm thick tempered glass with High Clarity Switchable smart film (To be pasted on glass) inclusive of Electronically adjustable control from transparent to opaque, aluminum black powder coated U channel cladding all around the door leaf & standard door sliding track & handles. Accessories: * Over current and short circuit protected Power Drive with inbuilt Dry Contacts and supplied complete with remote control. * Neutral Cure Specialty Silicone sealant *Location: As per GA Plan*	2.00	Nos	9,820.00	RATE ONLY

(BILL OF QUANTITIES-FIT-OUT WORKS FOR GIVENCHY AND KENZO)

REF: DI/GN/414/2023/QTN-02/R1 — **October 6, 2023**

SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)
7.05	**AUTOMATIC GLASS SLIDING DOOR.** Scope :- Scope : Supply & Installation Operator : Dormakaba ES 200 Easy S/L Operator Glass door: 10mm thick clear tempered glass. Inclusive of : Automatic Operator, Floor Guides, Program Switch, End Plates, Safety Sensor. Door Size: 1200mm W x 2500mm H	1.00	No	18,120.00	18,120.00
7.06	**WOODEN SINGLE LEAF DOOR (NON-FR)** Supply and installation of Non FR wooden door made in wood frame & architrave Shutter have 45 mm thk flush door shutter in both side in PU finish. Ironmongeries DEVON PC Rate 900AED/Set Size: 1000 x 2500 mm *Location: Main entrance & Pantry*	2.00	Nos	3,780.00	7,560.00
				SUBTOTAL AED:	**54,720.00**
8.00	**JOINERY WORKS**				
8.01	**LIBRARY CABINET:** Made of MDF Laminate finish shutters and veneer MDF finish open shelves with lights and metal support, carcass made out of white laminate finish. Size-3600x450x2400 mm ht. Location - GM Office	1.00	No	15,050.00	15,050.00
8.02	**COLUMN LEDGE (TYPE-A):** Made of MDF metallic Laminate finish ledges for item display Size-735 dia x 3000 mm ht. Location - GM Office, Workstation	2.00	Nos	6,760.00	13,520.00
8.03	**COLUMN LEDGE (TYPE-B):** Made of MDF metallic Laminate finish ledges for item display Size- 735 Dia x 3000 mm ht. Location - Open Workstation	1.00	Item	3,570.00	3,570.00
8.04	**COLUMN CLADDING (TYPE-C):** Made of MDF Laminate round column cladding Size- 735 Dia x 3000 mm ht. Location - Open Workstation	1.00	No	5,380.00	5,380.00
8.05	**EXPERIENCE ROOM LEDGE UNIT:** Made out of grey Laminate MDF finish with same back panel Size-4070x450x800 mm ht. Location - Open Workstation 	1.00	No	6,430.00	6,430.00
8.06	**DRY PANTRY CABINET:** Made out of grey metal Laminate top unit and bottom MDF unit with tile finish Size-5530x600/300x800/2400 mm ht. Location - Open Workstation	1.00	No	15,270.00	15,270.00
8.07	**MEETING ROOM LOW HEIGHT CABINET:** Made out of Laminate MDF finish drawers and inside carcass in white laminate finish Size-5155x450x800 mm ht. Location - Meeting Room	1.00	No	11,030.00	11,030.00
				SUBTOTAL AED:	**70,250.00**
	MEP WORKS				
1.0	**LIGHT FIXTURES**				

(BILL OF QUANTITIES-FIT-OUT WORKS FOR GIVENCHY AND KENZO)

REF: DI/GN/414/2023/QTN-02/R1 **October 6, 2023**

SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)
1.1	Supply of light fixture as pe the new layout Make-Creta Light Down light, Sport light, Strip light,				
1.1.1	TR5 : MAGNETIC TRACK	50.00	Mtrs	320.00	16,000.00
1.1.2	TR5A: MAGNETIC LINEAR TRACK LIGHT	45.00	Nos	260.00	11,700.00
1.1.3	LN1: LINEAR LED LIGHT	90.00	Mtrs	310.00	27,900.00
1.1.4	TR6 : SUSPENDED TRACK	45.00	Mtrs	110.00	4,950.00
1.1.5	TR6A : CYLINDRICAL TRACK LIGHT 	32.00	Nos	190.00	6,080.00
1.1.6	P1: LED PENDANT LIGHT	12.00	Nos	390.00	4,680.00
1.1.7	SL1: LED STRIP LIGHT AT JOINERY	100.00	Mtrs	90.00	9,000.00
1.1.8	TL1: TABLE LAMP	10.00	Nos	710.00	7,100.00
	SUB TOTAL FOR LIGHT FIXTURES AED:				**87,410.00**
2.0	**ELECTRICAL WORK**				
2.1	Modification for the existing cable tray as per the new layout and requirements.				
2.1.1	Cable tray for the DB outgoing power cables above the ceiling	30.00	Mtr	120.00	3,600.00
2.1.2	Cable tray for the DB outgoing light cables	30.00	Mtr	120.00	3,600.00
2.1.3	Cable tray under the raised floor for power	30.00	Mtr	130.00	3,900.00
2.2	Modifications for the existing Distribution Boards				
2.2.1	DB-Light and Power- Existing	3.00	Nos	2,890.00	8,670.00
2.3	Lighting | Installation of Lighting system including conducting and wiring with all necessary accessories and ancillary works as specified and as indicating in the drawings. PVC Conduit and Wire				
2.3.1	Supply and installation of conduit and wiring for the light fixtures	189.00	Nos	190.00	35,910.00
2.3.2	Supply and installation of conduit and wiring for the linear lights	100.00	Mtr	190.00	19,000.00
2.3.3	Installation of light by using special supports	289.00	Nos	40.00	11,560.00
2.3.4	Installation of tracks	82.00	Mr	60.00	4,920.00
2.3.5	Supply and installation of lighting switches	4.00	Nos	180.00	720.00
2.3.6	Supply and installation of Grid Switch	2.00	Nos	960.00	1,920.00

(BILL OF QUANTITIES-FIT-OUT WORKS FOR GIVENCHY AND KENZO)					
REF: DI/GN/414/2023/QTN-02/R1					October 6, 2023
SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)
2.3.4	Power | supply and installation of Power system including conducting and wiring with all necessary accessories and ancillary works as indicating in the drawings and as specified below .				
2.4	Final circuit wiring; including necessary containment system, terminations other ancillary work, complete-Point wiring to socket outlets; PVC Finish				
2.4.1	Supply and installation of Single Socket including conducting & wiring 13A, 220V, 50Hz 2 pole and earth single switch socket outlet.	4.00	Nos	360.00	1,440.00
2.4.2	Supply and installation of Double Socket including conducting & wiring 13A, two gang, 220V, 50Hz, 2 pole and earth twin switch socket outlet.	8.00	Nos	390.00	3,120.00
2.4.3	Relocation for the existing Floor Box	6.00	Nos	450.00	2,700.00
2.4.4	Supply and Installation of Floor Box (FB-2) including wiring and pvc containment for 2no 13A Double power socket and 1no conduit for data/Voice outlet. Note: Data/Voice cabling and termination works are excluded. Floor box is considered for the workstations	18.00	Nos	900.00	16,200.00
2.4.5	Supply and installation of Power provisons for VAV's & Relocation of FCU's	14.00	Nos	540.00	7,560.00
2.4.6	Supply and installation 13 A Spur outlet with cabling and conducting.	4.00	Nos	410.00	1,640.00
2.4.7	Supply and installation of PVC conduit for the IT and data points	47.00	Nos	120.00	5,640.00
2.4.8	Supply and installation of cable tray for the data cables above the ceiling.	20.00	Mtr	120.00	2,400.00
2.4.9	Supply and installation of cable tray for the data cables below the raised floor.	20.00	Item	120.00	2,400.00
				SUB TOTAL AED:	**136,900.00**
3.0	**SUNDRIES RELATED TO ELECTRICAL ENGINEERING INSTALLATIONS**				
3.0.1	Allow for documents including shop drawings, as built drawings, operating instructions and maintenance manuals as specified.	1.00	Item	1,930.00	1,930.00
3.0.2	Allow for cutting or forming holes, mortices, chases or the like and making good finishing's. (Provisional sum)	1.00	Item	640.00	640.00
3.0.3	Allow for testing and commissioning of electrical services	1.00	Item	1,930.00	1,930.00
3.0.4	Allow for identification labels including plates, discs, labels, charts and color coding.	1.00	Item	640.00	640.00
				SUB TOTAL AED:	**5,140.00**
				GRAND TOTAL ELECTRICAL WORKS AED:	**142,040.00**
4.0	**MECHANICAL WORKS**				
	AIR CONDITIONING SYSTEM				
4.0.1	Supply and installation of VAV's for closed Rooms	10.00	Nos	2,890.00	28,900.00
4.0.2	Thermostats for VAV's	10.00	Nos	580.00	5,800.00
4.0.3	Relocation of FCU's	4.00	Nos	640.00	2,560.00
4.0.4	Valve package Kit	4.00	Nos	2,890.00	11,560.00
4.0.5	Stand alone Thermostats for Relocated FCU's	4.00	Nos	580.00	2,320.00
4.0.6	Modification of Chilled water Piping	4.00	Nos	1,230.00	4,920.00

(BILL OF QUANTITIES-FIT-OUT WORKS FOR GIVENCHY AND KENZO)					
REF: DI/GN/414/2023/QTN-02/R1					October 6, 2023
SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)
4.1	**Air Distribution**				
	Supply, fabricate and install GI duct including volume splitter rod and dampers, access panels, supporting system, and connections complete in accordance with the specification and Drawing				
4.1.1	Modification of Duct works	118.00	Sqm	280.00	33,040.00
					-
4.1.2	Flexible duct including RVCD	84.00	Nos	210.00	17,640.00
4.1.3	Supply and Installation of Plenum Box with 19mm Closed cell elastomeric insulation , Aluglass finish, 13mm Acoustic Lining , Necessary Supports & Connections	84.00	Nos	190.00	15,960.00
	SECTION - MECHANICAL INSTALLATION (Cont'd)				
4.1.4	Volume Control Damper	20.00	Nos	150.00	3,000.00
4.1.5	Provisional sum for connection of all the existing items to the existing BMS system.				
	Supply & Return Air Diffuser's				
4.1.7	Linear Grill for Gypsum ceiling				
4.1.8	SLSD	37.00	Mtr	230.00	8,510.00
4.1.9	RLSD	35.00	Mtr	210.00	7,350.00
4.1.10	Square Diffusers	47.00	Nos	230.00	10,810.00
	SUB TOTAL AED:				**152,370.00**
4.2	**SUNDRIES RELATED TO MECHANICAL ENGINEERING INSTALLATIONS**				
4.2.1	Testing and commissioning the HVAC Including Air Balancing & water Balancing	1.00	Item	4,490.00	4,490.00
					-
4.2.2	Allow for all necessary identification, including plates, discs,	1.00	Item	1,280.00	1,280.00
	labels, charts and color coding all complete as described				-
4.2.3	Allow for all necessary documents including	1.00	Item		INCLUDED
	as-built drawings, operating instructions and maintenance manuals				-
4.2.4	**Performance Test for HVAC Equipment's**				-
	Performance testing for Existing FCU's	7.00	Nos	640.00	4,480.00
	SUB TOTAL AED:				**10,250.00**
	GRAND TOTAL MECHANICAL WORKS AED:				**162,620.00**
5	**CIVIL DEFENCE WORKS**				
5.1	**FIRE FIGHTING INSTALLATION**				
	All fire suppression services installations to be in accordance with relevant specification sections, and all other specifications and UAE building codes				
5.1.1	25 mm diameter.	1.00	Item		INCLUDED
5.1.2	32 mm diameter.	1.00	Item		INCLUDED
5.1.3	Sprinkler heads complete with all necessary accessories as specified and as shown on drawing				

(BILL OF QUANTITIES-FIT-OUT WORKS FOR GIVENCHY AND KENZO)					
REF: DI/GN/414/2023/QTN-02/R1					October 6, 2023
SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)
5.1.4	New Upright Sprinkler	22.00	Nos	880.00	19,360.00
5.1.5	Relocation for the existing pendent sprinkler with new head	12.00	Nos	670.00	8,040.00
5.1.6	Fire extinguishers and equipment complete as specified including supports, brackets, instruction signs and the like				
5.1.7	5 Kg CO2 Portable fire extinguisher.	2.00	Nos	320.00	640.00
5.1.8	4.5 Kg Dry chemical portable fire extinguisher	2.00	Nos	450.00	900.00
5.1.9	Supply and installation of zone control valve	2.00	Nos	5,840.00	11,680.00
5.1.11	Draining, Refilling, Pressure Testing and Certification by third party	1.00	Item	5,780.00	5,780.00
				SUB TOTAL AED:	**46,400.00**
6.0	**EMERGENCY LIGHTING INSTALLATION**				
	Emergency light fittings including battery pack, fixings, lamps and connections complete as described.				
6.0.1	Addressable emergency light, non maintained	14.00	Nos	1,350.00	18,900.00
6.0.2	Relocation for the existing Emergency/Exit light	4.00	Nos	480.00	1,920.00
6.0.3	PVC conduit and Fire rated cables for the emergency lights	1.00	Item	4,490.00	4,490.00
Notes	Existing CBS Emergency lights are keep above the ceiling				
				SUB TOTAL AED:	**25,310.00**
7.0	**FIRE ALARM INSTALLATION**				
	All the extra low voltage power installation works to be in accordance with relevant specification and all other specification and UAE building codes				
	Final sub-circuits				
	Final circuit wiring; including necessary containment system, terminations other ancillary work, complete.				
7.0.1	Smoke detectors-New	4.00	Nos	1,600.00	6,400.00
7.0.2	Interface Module	2.00	Nos	2,120.00	4,240.00
7.0.3	Manual call point	4.00	Nos	1,670.00	6,680.00
7.0.4	Fire alarm sounder	4.00	Nos	1,670.00	6,680.00
7.0.5	Relocation for the existing Smoke detector	10.00	Nos	580.00	5,800.00
7.0.6	Termination of the new devices in the existing FACP panel	1.00	Item	2,890.00	2,890.00
7.0.7	Fire alarm Re-Programming, Testing and commissioning	1.00	Item	5,780.00	5,780.00
7.0.8	Installation of fire alarm devices including the PVC Conduit and FP200 fire red cables	1.00	Item	5,780.00	5,780.00

(BILL OF QUANTITIES-FIT-OUT WORKS FOR GIVENCHY AND KENZO)					
REF: DI/GN/414/2023/QTN-02/R1					October 6, 2023
SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)
7.0.9	Graphic upgradation for the existing FACP panel	1.00	Item	5,780.00	5,780.00
7.0.10	Charge for DCD Civil defense till completion certificate	1.00	Item	8,340.00	8,340.00
				SUB TOTAL AED:	58,370.00
				GRAND TOTAL CIVIL DEFENCE WORKS AED:	130,080.00
	MEP NOTES & EXCLUSIONS;				
	Technical Notes : *-Considered Modification of Ducting, New Air outlets & Dampers* *-We have assumed that all the FCU's are in a Good condition.* *-We proposed New VAV's for the Closed Rooms* *-We have not considered Back up unit for Server Room. If its needs it will be as a variation.* *-We have considered Relocation of Pendent Sprinklers & Smoke detectors as per the site available & Additional Pendent Sprinklers & Smoke detectors will be added as per the site condition .* *-Required power provision to be provided by the Landlord and DEWA Approvals is not considered.* *-We proposed Standalone system for Proposed New VAV's & Relocated FCU's only* ***Exclusions*** *-CCU (or) Any Back up units for Server room* *-Main Duct Works & Accostic lagging* *-Supply of HVAC Equipment's* *-Supply (or) Any relocation of Upright sprinklers & Void detectors* *-Plumbing works* *-Any Upgradation Works* *-Chemical flushing* *-BMS* *-Cladding Works* *-Power upgradation.* *-lighting control system.* ***FIRE ALARM/FIRE FIGHTING WORKS.*** *- Civil defense final price subject to final design.* *- Assume existing Upright sprinkler and Void smoke detectors will be available at the site and can be reused.*				

(BILL OF QUANTITIES-FIT-OUT WORKS FOR GIVENCHY AND KENZO)					
REF: DI/GN/414/2023/QTN-02/R1					October 6, 2023
SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)

SUMMARY (GIVENCHY AND KENZO)

SL NO.	DESCRIPTION	AMOUNT (AED)
1	PRELIMINARIES	40,270.00
2	DEMOLITION WORKS	23,110.00
3	PARTITION WORKS	107,270.00
4	FLOOR FINISH	106,250.00
5	WALL FINISH	121,612.00
6	CEILING FINISH	313,782.00
7	DOORS	54,720.00
8	JOINERY WORKS	70,250.00
9	LIGHT FIXTURES	87,410.00
10	ELECTRICAL WORKS	142,040.00
11	MECHANICAL WORKS	162,620.00
12	CIVIL DEFENCE WORKS	130,080.00
	GRAND TOTAL AMOUNT AED:	1,359,414.00

Design Infinity

BILL OF QUANTITIES
(BPC)

..Beyond Imagination

LVMH
Beauty

PROJECT: LVMH BEAUTY @ D3 BLDG-10 & 11					
(BILL OF QUANTITIES-FIT-OUT WORKS FOR BPC OFFICE)					
REF: DI/GN/414/2023/QTN-03/R1					October 6, 2023
SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)
1.00	**PRELIMINARIES**				
1.01	General- Contractor's preliminaries for mobilization, site preparation, Provision for all temporary barricades	1.00	Item	6,080.00	6,080.00
1.02	Charges for setting out transportations to/from site, material deliveries, small tools and equipment's, protection of finished products in on-going site, site attendance and call out attendance.	1.00	Item	2,700.00	2,700.00
1.03	Charges for Preparation of Technical drawings (Architectural & MEP)for Relevant authorities & to execute the works at site.	1.00	Item	6,080.00	6,080.00
1.04	Allow provision of Insurance for entire fit out period. Contractors all Risk Insurance (As per UAE Law)	1.00	Item	1,620.00	1,620.00
1.05	Charges for Project management, site supervision & coordination.	1.00	Item	15,470.00	15,470.00
1.06	Allow for coordination with government/authorities along with submission of proposed designs and obtaining completion certificate.	1.00	Item	6,760.00	6,760.00
1.07	Charges for scaffolding & hoarding.	1.00	Item	3,380.00	3,380.00
1.08	Health, Safety and Environmental Procedures.	1.00	Item	-	INCLUDED
1.09	Provision of general attendance on other Contractors appointed by the Employer.	1.00	Item	1,350.00	1,350.00
1.10	Regular cleaning of site during construction period and after completion professional deep cleaning and made ready to occupy. Including carting away the debris to Municipal dumping area.	1.00	Item	2,030.00	2,030.00
	Security deposit, Authority Fees, entry and exit pass for vehicles and labors, night work permit fee(If required) are excluded				
				SUBTOTAL AED:	**45,470.00**
	CIVIL WORKS				
2.00	**DEMOLITION WORKS**				
2.01	Charges for Removal of existing unwanted ID/MEP Finishes/fixtures and carting away the debris to the approved municipality dump yard. Including making openings at existing walls to provide access for doors as per the proposed design. **Demolition works are subject to Building management approval.*	1.00	Item	41,240.00	41,240.00
				SUBTOTAL AED:	**41,240.00**
3.00	**PARTITION WORKS**				
3.01	**GYPSUM BOARD LINING (Non-FR)** Supply and installation of Gypsum board Lining at the existing door openings as pe the proposed design.	1.00	Item	300.00	300.00
3.02	**GYPSUM PARTITION (FR)** Supply and installation of 100mm thick FR Double Layer (knauf) gypsum partition with rock wool insulation (density 30 kg/m3) and 12.5mm thick gypsum boards on both sides, jointed and taped with 72 mm GI studs and 70 mm GI tracks and smoothened and made ready to receive finishes. *Height: 2700mm* *Location: IT/Store area*	11.00	Sq.m	190.00	2,090.00
3.03	**GYPSUM PARTITION (NON-FR)** Supply and installation of 100mm thick Non FR Double Layer (knauf) gypsum partition with rock wool insulation (density 30 kg/m3) and 12.5mm thick gypsum boards on both sides, jointed and taped with 72 mm GI studs and 70 mm GI tracks and smoothened and made ready to receive finishes. *Height: 2700mm* *Location: As per the partition layout*	120.00	Sq.m	150.00	18,000.00
3.04	**SINGLE-GLAZED GLASS PARTITION.** Supply and fixing of 12 mm clear tempered fixed straight glass partition with top and bottom 20 x 50 mm black powder coated aluminum U channel with rubber beading including glass to glass clear silicone joints including wall sides 20 x 50 mm powder coated U channel with rubber beading. *Height: 2500mm* *Location: As per the partition layout*	175.00	Sq.m	340.00	59,500.00
3.05	**FIXED GLASS WINDOW.** Supply & fixing fixed glass window 6mm external reflective + 12 mm Air Gap + 6mm internal clear glass double glazed window on powder coated aluminium frame with all fittings Profile : 105 mm Non Thermal break profile. As per design and approved sample. Size: *L 4400mm X H 1700mm*	1.00	Item	1,990.00	1,990.00

(BILL OF QUANTITIES-FIT-OUT WORKS FOR BPC OFFICE)

REF: DI/GN/414/2023/QTN-03/R1 — **October 6, 2023**

SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)
3.06	**SMART GLASS PARTITION (MEETING ROOMS)** Supply and installation of smart glass fix partition inclusive of 12mm thick tempered glass with High Clarity Switchable smart film (To be pasted on glass) inclusive of Electronically adjustable control from transparent to opaque, aluminum black powder coated U channel. Accessories: * Over current and short circuit protected Power Drive with inbuilt Dry Contacts and supplied complete with remote control. * Neutral Cure Specialty Silicone sealant. *Height: 2500mm* *Location: As per the partition layout*	7.00	Sq.m	1,990.00	RATE ONLY
3.05	**GYPSUM BAFFLE (NON FR)** Supply and ins tallation of FR (knauf)Gypsum baffle on the above-proposed Gypsum & Glass partition including necessary materials for installation. *Location: Above proposed Gypsum & Glass Partition*	120.00	LM	100.00	12,000.00
				SUBTOTAL AED:	**93,880.00**
4.00	**FLOOR FINISH**				
4.01	**EXISTING RAISED FLOOR RECTIFICATION.** Allow necessary Rectification works on existing Raised flooring. After the Proposed demolition, partition and FB Installation works. *Location: As necessary for the proposed design*	1.00	Item	61,860.00	61,860.00
4.02	**MDF FLOOR LINING.** Supply and installation of MDF Lining/Cladding above existing Raised floor. Including necessary materials of installation. As per design and approved *sample. Location: Proposed LVT Floor area*	763.00	Sq.m	90.00	68,670.00
4.03	**LVT FLOORING CONCRETE EFFECT (FF-01)** Supply and installation of 3-4 mm Thk LVT flooring with necessary materials for fixing. As per the design and approved sample. *Location: As per floor finishes plan* 	535.00	Sq.m	160.00	85,600.00
4.04	**LVT FLOORING WOODEN EFFECT (FF-02)** Supply and installation of 3-4 mm Thk LVT flooring with necessary materials for fixing. As per the design and approved sample. *Location: Closed offices/cabins*	228.00	Sq.m	160.00	36,480.00
4.05	**TRANSITION STRIP (SS FINISH)** Supply and Installation of SS transition strip. *Location: B/W floor finishes and door openings.*	25.00	LM	100.00	2,500.00
	**** Exclusion;*** *- Loose Rugs*				
				SUBTOTAL AED:	**255,110.00**
5.00	**WALL FINISH**				
5.01	**WHITE PAINT.** Supply and application of Jotun Fenomastic White paint. As per the design and approved sample. (2 coats including leveling and sanding) *Location: General areas as per wall finishes plan*	448.00	Sq.m	34.00	15,232.00
5.02	**BLUE/BLACK PAINT.** Supply and application of Jotun Fenomastic Color (Blue & Black) paint. As per the design and approved sample. (2 coats including leveling and sanding) *Location: As per wall finishes plan*	59.00	Sq.m	50.00	2,950.00

(BILL OF QUANTITIES-FIT-OUT WORKS FOR BPC OFFICE)

REF: DI/GN/414/2023/QTN-03/R1 — **October 6, 2023**

SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)
5.03	**TEXTURE PAINT.** Supply and application of Texture paint. As per the design and approved sample. (2 coats including leveling and sanding) *Location: As per wall finishes plan*	115.00	Sq.m	150.00	17,250.00
5.04	**WALL PAPER.** Supply and installation of digital printed vinyl sticker/wall paper. As per the design and approved sample. *Location: Breakout area*	1.00	Item	810.00	810.00
5.05	**MDF WALL PANELING.** Supply and installation of wall panel made of MDF in Laminate finish as per the design. *Location: As per wall finishes plan*	44.00	Sq.m	570.00	25,080.00
5.06	**SLAT WALL CLADDING (TYPE-A)** Supply and installation of slat wall panel made of MDF PU Paint finish. Including necessary materials for fixing. As per the design and approved sample. *Location: As per wall finishes plan*	10.00	Sq.m	1,050.00	10,500.00
5.07	**MOSS WALL.** Supply and installation of Artificial Moss wall As per proposed design. Including necessary materials for installation. As per the design and approved sample. *Location: As per wall finishes plan*	8.00	Sq.m	3,120.00	24,960.00
5.08	**BACK-PAINTED GLASS CLADDING (WHITE/GREY)** Supply and installation of Writing board made of 6 mm thk back painted glass. including reinforcement support with necessary materials for fixing. As per design and approved sample. *Location: As per wall finishes layout*	88.00	Sq.m	540.00	47,520.00
5.09	**FROSTED STICKER.** Supply and Installation of Frosted Sticker on Proposed glass partition @ Level from 700mm to 1900mm for office cabins & full height at meeting rooms with necessary material for fixing as per design and approved sample. *Location: Proposed Glass Partition*	91.00	Sq.m	90.00	8,190.00
5.10	**MDF/TILE SKIRTING.** Supply and installation of 100mm high MDF Skirting finished with Black paint. Including necessary materials for fixing. As per the design and approved sample. *Location: As per Wall finishes layout*	220.00	LM	60.00	13,200.00
5.11	**ROLLER BLINDS (WHITE)** Supply and installation of Manual Roller Blinds on the existing glass window. As per the design and approved sample. Height: 2700mm *Location: General areas as per wall finishes plan*	265.00	Sq.m	100.00	26,500.00
				SUBTOTAL AED:	**192,192.00**
6.00	**CEILING FINISH**				
6.01	**GYPSUM PLAIN CEILING.** Supply and installation of non fire rated Gypsum Board Plain ceiling (Knauf or equivalent)with necessary hanging systems including GI wall angle "C "channel, furring channel with 12.5mm gypsum boards joined taped smoothened finish. *Location: As per proposed RCP*	272.00	Sq.m	110.00	29,920.00
6.02	**GYPSUM BULKHEAD.** Supply and installation of Plain Gypsum Bulkhead using 12.5mm thick gypsum boards (Knauf or equivalent) and GI suspension system. Gypsum board surface made ready to receive final finish. As per design and approved sample. *Location: As per proposed RCP*	185.00	LM	100.00	18,500.00

(BILL OF QUANTITIES-FIT-OUT WORKS FOR BPC OFFICE)					
REF: DI/GN/414/2023/QTN-03/R1					October 6, 2023
SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)
6.03	**EXISTING MDF BAFFLE CEILING.** Allow necessary modification works on the existing baffle ceiling at the Breakout area. As per design Make it ready to match with the proposed design. Including supply and installation of wooden access panel for MEP services.	1.00	P.S	20,474.00	20,474.00
6.04	**GYPSUM PELMET.** Supply and installation of (knauf) Gypsum Pelmet with necessary fittings ready to receive final finishes. *Location: Periphery glass wall*	100.00	LM	90.00	9,000.00
6.05	**CEILING PAINT.** Supply and application of **Jotun Fenomastic paint** including all cleaning and levelling. As per design and approved sample. (2 coats including sanding). **Color/Type are as follows;**				
A	WHITE PAINT (ON GYPSUM CEILING)	272.00	Sqm	34.00	9,248.00
B	BLACK/WHITE PAINT (ON GYPSUM BULKHEAD/PELMET)	285.00	LM	30.00	8,550.00
C	BLACK/WHITE PAINT @ OPEN CEILING AREA	389.00	Sqm	40.00	15,560.00
6.06	**GYPSUM ACCESS PANEL.** Supply and installation of **Gypsum access panel** with frame and hinges. *Location: Proposed Gypsum ceiling area*	18.00	Nos	260.00	4,680.00
				SUBTOTAL AED:	**115,932.00**
7.00	**DOORS**				
7.01	**SINGLE GLAZED SINGLE LEAF GLASS DOOR.** Scope :- Supply & Installation; Glass panel : 12mm thick clear tempered glass cladded with 20x30mm black powder-coated aluminum U channel. Floor spring : Assa Abloy - DC410U. Handle: Ø30mm x 1200mm (Height) Top & Bottom Patch fittings : Royal Sahara brand; Size:- 900mm W x 2500 mm H. Finish:- Black powder coated *Location: As per GA Plan*	13.00	Nos	2,700.00	35,100.00
7.02	**SINGLE GLAZED SINGLE LEAF SMART GLASS DOOR.** Scope :- Supply and installation of smart glass fix partition inclusive of 12mm thick tempered glass with High Clarity Switchable smart film (To be pasted on glass) inclusive of Electronically adjustable control from transparent to opaque, aluminum black powder coated U channel cladding all around the door leaf & standard door floor spring, patch fittings & handles. Accessories: * Over current and short circuit protected Power Drive with inbuilt Dry Contacts and supplied complete with remote control. * Neutral Cure Specialty Silicone sealant. *Size: L 900mm X H 2500mm* *Location: As per GA Plan*	1.00	No	8,870.00	RATE ONLY
7.03	**WOODEN SINGLE LEAF DOOR (FR)** Supply and installation of FR wooden door made in wood frame & architrave Shutter have 45 mm thk flush door shutter in both side in PU finish. Ironmongeries DEVON PC Rate 900AED/Set Size: 1000 x 2400 mm	1.00	No	9,820.00	9,820.00
7.04	**EXISTING DOOR REFURBISHMENT WORKS.** Allow necessary refurbishment works for existing wooden doors, making the finish white to match the proposed concept. (Ironmongeries: Existing) Size: 900 x 2200 mm *Location : Pantry Safe room*	1.00	No	1,630.00	1,630.00
	* *Big meeting room, 6PAX meeting room, Main entrance doors are existing.*				
				SUBTOTAL AED:	**46,550.00**

(BILL OF QUANTITIES-FIT-OUT WORKS FOR BPC OFFICE)

REF: DI/GN/414/2023/QTN-03/R1 — **October 6, 2023**

SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)
8.00	**JOINERY WORKS**				
8.01	**FULL HEIGHT STORAGE CABINET:** Made of MDF Green PU Paint finish shutters and Laminated MDF finish open shelves with lights, carcass made out of white laminate finish. Size-2400x450x2400 mm ht. Location - HR7	1	No	10,420.00	10,420.00
8.02	**TV WALL WITH LEDGE:** Made out of wood/metal TV backing with ledge in Laminated MDF fnish with metal support Size-1200x450x50mm ht. Location - F1, IT-1, Meeting room, Open workstation,F3, & SC1 	6	Nos	940.00	5,640.00
8.03	**TV WALL WITH LEDGE:** Made out of wood/metal TV backing with ledge in Laminated MDF finish with metal support Size-1200+1800x450x50mm ht. Location - SC1	1	No	1,780.00	1,780.00
8.04	**FULL HEIGHT STORAGE CABINET:** Made of MDF in Laminate finish carcass made out of white laminate finish. Size-4414x500x2400 mm ht. Location - Lounge area	1	No	18,510.00	18,510.00
8.05	**FULL HEIGHT STORAGE CABINET:** Made of MDF in Laminate finish carcass made out of white laminate finish. Size-2800x500x2400 mm ht. Location -Breakout	1	No	11,700.00	11,700.00
8.06	**ISLAND COUNTER:** In Laminate MDF bottom unit and grey Armani marble counter top and both side Size - 2995x1000x900 mm Ht Location -Breakout	1	No	20,610.00	20,610.00
8.07	**ROUND TABLE:** Made out of Laminate MDF base and top in 20mm thk Laminated MDF finish Size-700x900 mm ht. Location - Breakout Area	2	Nos	5,300.00	10,600.00
8.08	**LOW HEIGHT STORAGE CABINET:** Made out of Laminated MDF outer finish, inside carcass will be white laminate finish. Size-6070+4170+2600x450x750mm ht. Location - IT Service Room	1	No	29,030.00	29,030.00
8.09	**FULL HEIGHT STORAGE CABINET:** Made out of Laminated MDF outer finish, inside carcass will be laminate finish. Size-5000x450x2600mm ht. Location - IT Service Room	1	No	20,270.00	20,270.00
	** Pantry Counter: Existing*				
				SUBTOTAL AED:	**128,560.00**
	MEP WORKS				
1.0	**LIGHT FIXTURES**				
1.1	Supply of light fixture as pe the new layout Make-Creta Light Down light, Sport light, Strip light,				
1.1.1	LN1 : LINEAR LED LIGHT	80.0	Mtrs	310.00	24,800.00

(BILL OF QUANTITIES-FIT-OUT WORKS FOR BPC OFFICE)

REF: DI/GN/414/2023/QTN-03/R1 **October 6, 2023**

SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)
1.1.2	TR3 : SUSPENDED TRACK AT WORKSTATIONS	135.0	Mtrs	110.00	14,850.00
1.1.3	TR3A: TRACK MOUNTED CYLINDRICAL TRACK LIGHT	120.0	Nos	190.00	22,800.00
1.1.4	TR4 : RECESSED MAGNETIC TRACK	135.0	Mtrs	320.00	43,200.00
1.1.5	TR4A : RECESSED MAGNETIC LINEAR TRACK LIGHT	95.0	Nos	260.00	24,700.00
1.1.6	L1: DECORATIVE PENDANT LIGHT	15.0	Nos	3,210.00	48,150.00
1.1.7	L1: DECORATIVE PENDANT LIGHT	10.0	Nos	320.00	3,200.00
1.1.8	W1 : LED WEATHER PROOF LIGHT AT SERVER ROOM, STORE IP54	4.0	Nos	210.00	840.00
1.1.9	TL1 : TABLE LAMP	10.0	Nos	710.00	7,100.00
	SUB TOTAL FOR LIGHT FIXTURES AED:				**189,640.00**
2.0	**ELECTRICAL WORK**				
2.1	Modification for the existing cable tray as per the new layout and requirements.				
2.1.1	Cable tray for the DB outgoing power cables above the ceiling	60.00	Mtr	120.00	7,200.00
2.1.2	Cable tray for the DB outgoing light cables	60.00	Mtr	120.00	7,200.00
2.1.3	Cable tray under the raised floor for power	60.00	Mtr	130.00	7,800.00
2.2	Modifications for the existing Distribution Boards				
2.2.1	DB-Light and Power- Existing	4.00	Nos	2,890.00	11,560.00
2.2.2	Lighting |Installation of Lighting system including conducting and wiring with all necessary accessories and ancillary works as specified and as indicating in the drawings. PVC Conduit and Wire				
2.2.3	Supply and installation of conduit and wiring for the light fixtures	524.00	Nos	190.00	99,560.00
2.2.4	Supply and installation of conduit and wiring for the linear lights	80.00	Mtr	190.00	15,200.00
2.2.5	Installation of light by using special supports	604.00	Nos	40.00	24,160.00
2.2.6	Installation of tracks	270.00	Mtr	60.00	16,200.00
2.2.7	Supply and installation of lighting switches	20.00	Nos	180.00	3,600.00
2.2.8	Supply and installation of Grid Switch	2.00	Nos	960.00	1,920.00
2.2.9	Power | supply and installation of Power system including conducting and wiring with all necessary accessories and ancillary works as indicating in the drawings and as specified below .				

(BILL OF QUANTITIES-FIT-OUT WORKS FOR BPC OFFICE)					
REF: DI/GN/414/2023/QTN-03/R1					October 6, 2023
SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)
2.3	Final circuit wiring; including necessary containment system, terminations other ancillary work, complete-Point wiring to socket outlets; PVC Finish				
2.3.1	Supply and installation of Single Socket including conducting & wiring 13A, 220V, 50Hz 2 pole and earth single switch socket outlet.	12.00	Nos	360.00	4,320.00
2.3.2	Supply and installation of Double Socket including conducting & wiring 13A, two gang, 220V, 50Hz, 2 pole and earth twin switch socket outlet.	40.00	Nos	390.00	15,600.00
2.3.3	Relocation for the existing Floor Box	22.00	Nos	450.00	9,900.00
2.3.4	Supply and Installation of Floor Box (FB-2) including wiring and pvc containment for 2no 13A Double power socket and 1no conduit for data/Voice outlet. Note: Data/Voice cabling and termination works are excluded. Floor box is considered for the workstations	40.00	Nos	900.00	36,000.00
2.3.5	Supply and installation of Power provisions for VAV's & Relocation of FCU's	23.00	Nos	540.00	12,420.00
2.3.6	Supply and installation 13 A Spur outlet with cabling and conducting.	20.00	Nos	410.00	8,200.00
2.3.7	Supply and installation power supply for the relocated fcu with cabling and conducting.	12.00	Nos	410.00	4,920.00
2.3.8	Supply and installation of PVC conduit for the IT and data points	107.00	Nos	120.00	12,840.00
				SUB TOTAL AED:	**298,600.00**
2.4	**SUNDRIES RELATED TO ELECTRICAL ENGINEERING INSTALLATIONS**				
2.4.1	Allow for documents including shop drawings, as built drawings, operating instructions and maintenance manuals as specified.	1.00	Item	1,930.00	1,930.00
2.4.2	Allow for co-ordination with other engineering installations.	1.00	Item	-	INCLUDED
2.4.3	Allow for cutting or forming holes, mortices, chases or the like and making good finishing's. (Provisional sum)	1.00	Item	640.00	640.00
2.4.4	Allow for testing and commissioning of electrical services	1.00	Item	1,930.00	1,930.00
2.4.5	Allow for identification labels including plates, discs, labels, charts and color coding.	1.00	Item	640.00	640.00
				SUB TOTAL AED:	**5,140.00**
				GRAND TOTAL ELECTRICAL WORKS AED:	**303,740.00**
3.0	**MECHANICAL WORKS**				
	AIR CONDITIONING SYSTEM				
	Air Distribution				
3.0.1	Supply and installation of VAV's for closed Rooms	14	Nos	2,890.00	40,460.00
3.0.2	Thermostats for VAV's	14	Nos	580.00	8,120.00
3.0.3	Relocation of FCU's	9	Nos	640.00	5,760.00
3.0.4	Valve package Kit	9	Nos	2,890.00	26,010.00
3.0.5	Stand alone Thermostats for Relocated FCU's	9	Nos	580.00	5,220.00
3.0.6	Modification of Chilled water Piping	9	Nos	1,230.00	11,070.00
3.1	Supply, fabricate and install GI duct including volume splitter rod and dampers, access panels, supporting system, and connections complete in accordance with the specification and Drawing				

(BILL OF QUANTITIES-FIT-OUT WORKS FOR BPC OFFICE)					
REF: DI/GN/414/2023/QTN-03/R1					October 6, 2023
SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)
3.1.1	Modification of Duct works	240	Sqm	280.00	67,200.00
					-
3.1.2	Flexible duct including RVCD	162	Nos	210.00	34,020.00
3.1.3	Supply and Installation of Plenum Box with 19mm Closed cell elastomeric insulation , Aluglass finish, 13mm Acoustic Lining , Necessary Supports & Connections	162	Nos	190.00	30,780.00
	SECTION - MECHANICAL INSTALLATION (Cont'd)				
3.1.4	Volume Control Damper	30	Nos	150.00	4,500.00
3.1.5	Provisional sum for connection of all the existing items to the existing BMS system.	1	PS		EXCLUDED
	Supply & Return Air Diffuser's				
3.1.6	Linear Grill for Gypsum ceiling				
3.1.7	SLSD	65	Mtr	230.00	14,950.00
3.1.8	RLSD	55	Mtr	210.00	11,550.00
3.1.9	Square Diffusers	97	Nos	230.00	22,310.00
				SUB TOTAL AED:	**281,950.00**
3.2	**SUNDRIES RELATED TO MECHANICAL ENGINEERING INSTALLATIONS**				
3.2.1	Testing and commissioning the HVAC Including Air Balancing & water Balancing	1	Item	5,780.00	5,780.00
					-
3.2.2	Allow for all necessary identification, including plates, discs,	1	Item	1,280.00	1,280.00
	labels, charts and color coding all complete as described				-
3.2.3					-
	Allow for all necessary documents including	1	Item		INCLUDED
3.2.4	as-built drawings, operating instructions and maintenance manuals				-
					-
3.2.5	**Performance Test for HVAC Equipment's**				-
	Performance testing for Existing FCU's	17	Nos	640.00	10,880.00
				SUB TOTAL AED:	**17,940.00**
				GRAND TOTAL MECHANICAL WORKS AED:	**299,890.00**
4	**CIVIL DEFENCE WORKS**				
4.1	**FIRE FIGHTING INSTALLATION**				
	All fire suppression services installations to be in accordance with relevant specification sections, and all other specifications and UAE building codes				
4.1.1	25 mm diameter.	1.00	Item	-	INCLUDED
4.1.2	32 mm diameter.	1.00	Item	-	INCLUDED
4.1.3	Sprinkler heads complete with all necessary accessories as specified and as shown on drawing				
4.1.4	New Upright Sprinkler	80.00	Nos	880.00	70,400.00
4.1.5	Relocation for the existing pendent sprinkler with new head	30.00	Nos	670.00	20,100.00
4.1.6	Fire extinguishers and equipment complete as specified including supports, brackets, instruction signs and the like				

(BILL OF QUANTITIES-FIT-OUT WORKS FOR BPC OFFICE)					
REF: DI/GN/414/2023/QTN-03/R1					October 6, 2023
SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)
4.1.7	5 Kg CO2 Portable fire extinguisher.	6.00	Nos	320.00	1,920.00
4.1.8	4.5 Kg Dry chemical portable fire extinguisher	6.00	Nos	450.00	2,700.00
4.1.9	Supply and installation of zone control valve	4.00	Nos	5,840.00	23,360.00
4.2	Connection to the existing sprinkler pipe network using applicable fittings and other necessary works	1.00	Item	-	INCLUDED
4.2.1	Draining, Refilling, Pressure Testing and Certification by third party	1.00	Item	5,780.00	5,780.00
				SUB TOTAL AED:	**124,260.00**
5.0	**EMERGENCY LIGHTING INSTALLATION**				
	Emergency light fittings including battery pack, fixings, lamps and connections complete as described.				
5.0.1	Addressable emergency light, non maintained	20.00	Nos	1,350.00	27,000.00
5.0.2	Relocation for the existing Emergency/Exit light	12.00	Nos	480.00	5,760.00
5.0.3	PVC conduit and Fire rated cables for the emergency lights	1.00	Item	4,490.00	4,490.00
Notes	Existing CBS Emergency lights are keep above the ceiling				
				SUB TOTAL AED:	**37,250.00**
6.0	**FIRE ALARM INSTALLATION**				
	All the extra low voltage power installation works to be in accordance with relevant specification and all other specification and UAE building codes				
	Final sub-circuits				
	Final circuit wiring; including necessary containment system, terminations other ancillary work, complete.				
6.0.1	Smoke detectors-New	10.00	Nos	1,600.00	16,000.00
6.0.2	Interface Module	2.00	Nos	2,120.00	4,240.00
6.0.3	Manual call point	4.00	Nos	1,670.00	6,680.00
6.0.4	Fire alarm sounder	4.00	Nos	1,670.00	6,680.00
6.0.5	Relocation for the existing Smoke detector	32.00	Nos	580.00	18,560.00
6.0.6	Termination of the new devices in the existing FACP panel	1.00	Item	2,890.00	2,890.00
6.0.7	Fire alarm Re-Programming, Testing and commissioning	1.00	Item	5,780.00	5,780.00

(BILL OF QUANTITIES-FIT-OUT WORKS FOR BPC OFFICE)					
REF: DI/GN/414/2023/QTN-03/R1					October 6, 2023
SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)
6.0.8	Installation of fire alarm devices including the PVC Conduit and FP200 fire red cables	1.00	Item	5,780.00	5,780.00
6.0.9	Graphic upgradation for the existing FACP panel	1.00	Item	5,780.00	5,780.00
6.1	Charge for DCD Civil defense till completion certificate	1.00	Item	8,340.00	8,340.00
				SUB TOTAL AED:	80,730.00
				GRAND TOTAL CIVIL DEFENCE WORKS AED:	242,240.00
	MEP NOTES & EXCLUSIONS;				
	Technical Notes : *-Considered Modification of Ducting, New Air outlets & Dampers* *-We have assumed that all the FCU's are in a Good condition.* *-We proposed New VAV's for the Closed Rooms* *-We have not considered Back up unit for Server Room. If its needs it will be as a variation.* *-We have considered Relocation of Pendent Sprinklers & Smoke detectors as per the site available & Additional Pendent Sprinklers & Smoke detectors will be added as per the site condition .* *-Required power provision to be provided by the Landlord and DEWA Approvals is not considered.* *-We proposed Standalone system for Proposed New VAV's & Relocated FCU's only* ***Exclusions*** *-CCU (or) Any Back up units for Server room* *-Main Duct Works & Accostic lagging* *-Supply of HVAC Equipment's* *-Supply (or) Any relocation of Upright sprinklers & Void detectors* *-Plumbing works* *-Any Upgradation Works* *-Chemical flushing* *-BMS* *-Cladding Works* *-Power upgradation.* *-lighting control system.* ***FIRE ALARM/FIRE FIGHTING WORKS.*** *- Civil defense final price subject to final design.* *- Assume existing Upright sprinkler and Void smoke detectors will be available at the site and can be reused.*				

(BILL OF QUANTITIES-FIT-OUT WORKS FOR BPC OFFICE)					
REF: DI/GN/414/2023/QTN-03/R1					October 6, 2023
SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)

SUMMARY (BPC OFFICE)

SL NO.	DESCRIPTION	AMOUNT (AED)
1	PRELIMINARIES	45,470.00
2	DEMOLITION WORKS	41,240.00
3	PARTITION WORKS	93,880.00
4	FLOOR FINISH	255,110.00
5	WALL FINISH	192,192.00
6	CEILING FINISH	115,932.00
7	DOORS	46,550.00
8	JOINERY WORKS	128,560.00
9	LIGHT FIXTURES	189,640.00
10	ELECTRICAL WORKS	303,740.00
11	MECHANICAL WORKS	299,890.00
12	CIVIL DEFENCE WORKS	242,240.00
	GRAND TOTAL AMOUNT AED:	1,954,444.00

Design Infinity

CONTACT PERSON

..Beyond Imagination

Geetha Nayak
Managing Partner

Contact Details:
M: 971 50 146 7608
T: 971 43795902
F: 971 4 379 5903
E: geetha@design-infinity.com

Dubai (Head Office) Address
Unit 212-213 & 301-303, O-Block,
Hamsah Complex, Al Karama
Same Building as Ansar Gallery Karama
PO Box 62522, Dubai, UAE
Tel: 971 4 379 5902
Fax: 971 4 379 5903

Dubai Branch Office & Warehouse
JOINERY, GLASS & METAL DIVISION
Dubai Investment Park 2
Plot Number: 597-813
Dubai UAE
Tel: 971 4 321 6946

Abu Dhabi Office
Office No. M1, Building No. P/181
PO Box 62560, Al Muroor
Abu Dhabi, UAE
Tel: 971 2 448 2286