Design Infinity

WWW.DESIGN-INFINITY.COM

COMMERCIAL PROPOSAL

AURIGA CAPITAL

INTERIOR FIT-OUT WORKS FOR AURIGA CAPITAL RHQ
LOCATION: LEVEL 2 (204) BURJ DAMAN, DIFC, UAE

Design Infinity

Table of CONTENTS

1. Cover Letter with Notes & Exclusions
2. Bill of Quantities (ID & MEP works)
3. Annexure-01 (Bill of Quantities (Loose Furniture)
4. Contact Person

AURIGA CAPITAL

Design Infinity

COVER LETTER

AURIGA CAPITAL

DATE: 16/12/2024

REF: DI/GN/506/2024/R1

To,
M/s AURIGA CAPITAL RHQ
LEVEL 2 (204)
BURJ DAMAN, DIFC
DUBAI, UAE

RFP No. (AURI-2024-RFP-01)

SUB: INTERIOR FIT-OUT WORKS FOR AURIGA CAPITAL RHQ, LEVEL 2 (204) BURJ DAMAN, DIFC

Dear Concern,

We thank you for allowing us to **offer** our **proposal** for the **Fit-out works** for the **Auriga Capital RHQ @ Level 2 (204) Burj Daman, DIFC.** Please find herewith our **competitive offer** as per the attached bill of quantities amounting to below.

Total Tendered Price.

TOTAL AMOUNT (ID & MEP WORKS) AED:	**2,072,700.00**
TOTAL RATE PER SQFT AED:	**459.61**
TOTAL AMOUNT IT/AV WORKS AED:	**331,280.00**
TOTAL AMOUNT LOOSE FURNITURE (OP-01) AED:	**269,130.00**
GRAND TOTAL AMOUNT AED:	**2,673,110.00**

Validity: 30 days from the above date.

Payment Terms: To be discussed.

Execution Timeline: As per Project Schedule.

ديزاين انفنيتي ش.ذ.م.م
P.O. Box: 62522
DUBAI - U.A.E.
DESIGN INFINITY L.L.C

Notes:

- The above price is exclusive of Value Added Tax (VAT); 5% VAT shall be payable as an addition to the invoice value.
- All Government/ Municipal/civil defence Fees, Deposits are to be paid by the Client on Actuals.
- As it is a single-owner, only one DEWA meter is permitted. Therefore, we have considered a separate PMU meters for the other units that will be leased in the future.
- The pricing for the lighting control system have priced as rate only as instructed in the RFI response.

Exclusions: -

- All fees and deposits for statutory authorities.
- Bank guarantee or Retention Requirements (If any)
- Company branding/graphics & Art Works.
- Fire rating treatment for the entrance walls/doors.
- Any work related to BMS system.
- Air condition for phone booth.
- Any other items not mentioned in the attached BOQ.

We look forward to establishing a constructive dialogue with you at all stages of your evaluation process. Always assure you of our best services.

We hope our offer is in line with your requirements and look forward to working with you.

Thank you and best regards,

Geetha Nayak
Managing Partner
Mob: +971 50 146 7608
E: geetha@design-infinity.com

ديزاين انفنيتي ش.ذ.م.م
P.O. Box: 62522
DUBAI - U.A.E.
DESIGN INFINITY L.L.C

Design Infinity

BILL OF QUANTITIES

(ID & MEP WORKS)

AURIGA CAPITAL

Design Infinity *Beyond Imagination ...*

PROJECT: FIT-OUT WORKS FOR AURIGA CAPITAL RHQ, LEVEL 2 (204) BURJ DAMAN, DIFC, UAE		
REF: DI/GN/506/2024/R1		December 16, 2024
	SUMMARY	
SL NO.	**DESCRIPTION**	**AMOUNT (AED)**
1	PRELIMINARIES	89,086.00
2	DEMOLITION WORKS	11,490.00
3	CIVIL WORKS	87,695.00
4	PARTITION WORKS	201,250.00
5	FLOOR FINISH	58,430.00
6	WALL FINISH	161,980.00
7	CEILING FINISH	87,371.00
8	DOORS	69,210.00
9	JOINERY WORKS	357,270.00
10	OTHERS (SIGNAGE/PLANTS & WHITE GOODS)	57,518.00
11	LIGHT FIXTURES	75,950.00
12	ELECTRICAL ENGINEERING INSTALLATION	180,780.00
13	MECHANICAL ENGINEERING INSTALLATION	451,370.00
14	CIVIL DEFENCE WORKS INSTALLATION	169,950.00
15	PANTRY ACCESSORIES	13,350.00
	TOTAL AMOUNT (ID & MEP WORKS) AED:	**2,072,700.00**
	TOTAL RATE PER SQFT AED:	**459.61**
16	**TOTAL AMOUNT IT/AV WORKS AED:**	**331,280.00**
17	**TOTAL AMOUNT LOOSE FURNITURE (OPTION-01) AED:**	**269,130.00**
	GRAND TOTAL (INCLUDING IT/AV & LOOSE FURNITURE) AED:	**2,673,110.00**

ديزاين انفنيتي ش.ذ.م.م
P.O. Box: 62522
DUBAI - U.A.E.
DESIGN INFINITY L.L.C

PROJECT: FIT-OUT WORKS FOR AURIGA CAPITAL RHQ, LEVEL 2 (204) BURJ DAMAN, DIFC, UAE

(BILL OF QUANTITIES-FIT-OUT WORKS)

REF: DI/GN/506/2024/R1 — **December 16, 2024**

SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)
1.00	**PRELIMINARIES**				
1.01	General- Contractor's preliminaries for mobilization, site preparation, Provision for all temporary barricades	1.00	Item	20,610.00	20,610.00
1.02	Charges for setting out transportations to/from site, material deliveries, small tools and equipment's, protection of finished products in on-going site, site attendance and call out attendance.	1.00	Item	10,620.00	10,620.00
1.03	Allow for coordination with government/authorities along with submission of proposed designs and obtaining completion certificate.	1.00	Item	11,870.00	11,870.00
1.04	Allow provision of Insurance for entire fit out period. Contractors all Risk Insurance (As per UAE Law)	1.00	Item	3,750.00	3,750.00
1.05	Charges for Project management, site supervision & coordination.	1.00	Item	19,740.00	19,740.00
1.06	Charges for scaffolding & Hoarding. *Graphis on hoarding: By client.*	1.00	P.S	6,250.00	6,250.00
1.07	Health, Safety and Environmental Procedures.	1.00	Item	-	INCLUDED
1.08	Allow for covering and protection of existing common area to prevent any damage to the on-going works as per building regulations	1.00	Item	6,876.00	6,876.00
1.09	Provision of general attendance on other Contractors appointed by the Employer.	1.00	Item	2,500.00	2,500.00
1.10	Regular cleaning of site during construction period and after completion professional deep cleaning and made ready to occupy. Including carting away the debris to Municipal dumping area.	1.00	Item	6,870.00	6,870.00
	Security deposit, Authority Fees, entry and exit pass for vehicles and labors, night work permit fee(If required) Electricity and Water charges are excluded.				
				SUBTOTAL AED:	**89,086.00**
2.00	**DEMOLITION WORKS**				
2.01	Charges for Removal of existing unwanted solid walls and carting away the debris to the approved municipality dump yard.	1.00	Item	11,490.00	11,490.00
2.02	Demolishing, take out and remove all existing unwanted doors and carting away the debris to the approved municipality dump yard.				
2.03	Providing special covering and protection for the existing glazing during demolition works.				
	***Demolition works are subject to Building management approval.**				
				SUBTOTAL AED:	**11,490.00**
3.00	**CIVIL WORKS**				
3.01	**EXISTING RAISED FLOOR MODIFICATION WORKS.** Allow necessary Rectification works on existing Raised flooring. After Proposed Partition/ FB Installation works. *Location: As necessary for the proposed design*	1.00	Item	39,160.00	39,160.00
3.02	**MDF BACKING.** Allow necessary MDF backing above the raised flooring for proposed LVT flooring. *Location: Proposed LVT floor area*	155.00	Sq.m	95.00	14,725.00
3.03	**SCREEDING (150MM)** Supply and installation of 150 mm thick PCC screeding (ratio 1:2:6) to obtain perfect line of surface level ready to receive the desired floor finish. *Location: Proposed Wet areas*	1.00	Item	3,255.00	3,255.00
3.04	**BITUMEN SHEET WATERPROOFING.** Supply and installation of Waterproofing (Single layer) with bitumen Sheet in the floor and 600mm high on walls. Including necessary materials for installation. *Location: Proposed wet areas*	1.00	Item	4,805.00	4,805.00
3.05	**PLASTERING.** Supply and apply Cement Plastering (Double Side)as necessary for smooth finishing and ready for final finishes. Location: Proposed block walls Up to 2.8 LVL	300.00	Sq.m	65.00	19,500.00
3.06	**MEP RELATED BUILDERS WORK.** Chasing, chiseling & chipping with other civil works related to passing and laying conduits for wiring of additional electrical points etc. then filling up the cavity and ready to receive the new fittings and finishes all in accordance with drawings.	1.00	Item	6,250.00	6,250.00
				SUBTOTAL AED:	**87,695.00**

P.O. Box: 62522 DUBAI - U.A.E. DESIGN INFINITY L.L.C.

(BILL OF QUANTITIES-FIT-OUT WORKS)					
REF: DI/GN/506/2024/R1				December 16, 2024	
SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)
4.00	PARTITION WORKS				
4.01	**BLOCK WALL 100MM THK.** Supply and installation of 100mm thick block wall. Including necessary materials for fixing. *Location: As per partition plan*	242.00	Sqm	120.00	29,040.00
4.02	**STIFFENER COLUMN & BEAM.** Providing stiffener column& beam for the proposed block wall with necessary materials for fixing. *Location: For proposed Block wall*	150.00	LM	200.00	30,000.00
4.03	**GYPSUM WALL (FIRE RATED)** Supply and installation of 100mm thick FR Single Layer (knauf) gypsum partition with rock wool insulation (density 30 kg/m3) and 12.5mm thick gypsum boards on both sides, jointed and taped with 72 mm GI studs and 70 mm GI tracks and smoothened and made ready to receive finishes. *Location: DB Area LVL Up to 2.8Mtr*	30.00	Sq.m	120.00	3,600.00
4.04	**GYPSUM PARTITION (ACOUSTIC)** Supply and installation of Acoustic gypsum partition with rock wool insulation (density 60 kg/m3) and 12.5mm thick double layer gypsum boards on both sides, jointed and taped with 72 mm GI studs and 70 mm GI tracks and smoothened and made ready to receive finishes.	161.00	Sq.m	210.00	33,810.00
4.05	**GYPSUM WALL (NON ACOUSTIC)** Supply and installation of 100mm thick Non-FR Single Layer (knauf) gypsum partition with rock wool insulation (density 30 kg/m3) and 12.5mm thick gypsum boards on both sides, jointed and taped with 72 mm GI studs and 70 mm GI tracks and smoothened and made ready to receive finishes. *Location: As per GA Plan*	161.00	Sq.m	100.00	OPTIONAL
4.06	**CEMENT BOARD PARTITION.** Supply and installation of Calcium Silicate Partitions with frameworks made by steel stud and channel with joint tapes with Rockwool insulation and ready to receive for the final finish. As per the design and approved sample. *Location: Proposed wet areas*	94.00	Sq.m	170.00	15,980.00
4.07	**ACOUSTIC GLASS PARTITION.** Supply and installation of single glazed partition using 13.52mm acoustic laminated glass, with 25x25mm QIC Internal glazing system (Powder coated finish) and cleat slots for seamless joining. (Acoustic Rating-Rw-38dB). *Height: 2800mm*	89.00	Sq.m	690.00	61,410.00
4.08	**SINGLE-GLAZED GLASS PARTITION -(NON ACOUSTIC)** Supply and fixing of 12 mm clear tempered fixed straight glass partition with top and bottom 20 x 30 mm black powder coated aluminum U channel with rubber beading glass to glass clear silicone joints including wall sides 20 x 30 mm powder coated U channel with rubber beading. *Height: 2800mm* *Location: Internal area*	89.00	Sq.m	370.00	RATE ONLY
4.09	**SMART GLASS PARTITION** Supply and installation of smart glass fix partition inclusive of Glass Panel: 13.52mm Thick Clear Laminated Glass (6mm Clear Glass + 1.52 mm Clear PVB + 6mm Clear Glass) Fixing: 30x20mm aluminum with powder coated finish. Cut-to-size Switchable Smart Film with electronically adjustable control from opaque to transparent, related accessories to be pasted on existing glass panels and swing door. Over current and short circuit protected Power Drive with inbuilt Dry Contacts and supplied complete with remote control. Neutral Cure Specialty Silicone Sealant *Height: 2800mm* *Location: As per the partition layout*	89.00	Sq.m	1,940.00	OPTIONAL
4.10	**PERIPHERAL GLASS PARTITION (NON-FR)** Supply and fixing of 12 mm clear tempered fixed straight glass partition with top and bottom 20 x 30 mm black powder coated aluminum U channel with rubber beading glass to glass clear silicone joints including wall sides 20 x 30 mm powder coated U channel with rubber beading. *Height: 2800mm* *Location: Peripheral area - Subject to BM Approval.*	50.00	Sq.m	370.00	18,500.00

دي زاين انفنيتي ش.ذ.م.م
P.O. Box: 62522
DUBAI - U.A.E.
DESIGN INFINITY L.L.C

(BILL OF QUANTITIES-FIT-OUT WORKS)					
REF: DI/GN/506/2024/R1					December 16, 2024
SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)
4.11	**FIRE RATED GLASS PARTITION.** Supply and installation of 60 minutes FR Glass partition (Using GP-1 GI Powder Coated Partitions fully glazed with 8mm Fire Rated Glass and frames. With necessary fitting and fixtures for the installation. All in accordance with the manufactures specifications. *Location: Peripheral area - Subject to BM Approval.*	50.00	Sq.m	5,120.00	RATE ONLY
4.12	**GYPSUM BAFFLE (NON-FR)** Supply and ins tallation of NON-FR (knauf) Gypsum baffle on above & below proposed glass partition including necessary materials for installation. *Location: Above/Below Glass Partition*	99.00	LM	90.00	8,910.00
				SUBTOTAL AED:	**201,250.00**
5.00	**FLOOR FINISH**				
5.01	**LVT FLOORING.** Supply and installation of LVT flooring with necessary materials for fixing. As per the design and approved sample. *Location: As per floor finishes plan.*	155.00	Sq.m	150.00	23,250.00
5.02	**CARPET FLOORING.** Supply and Installation of Carpet flooring including adhesives for fixing. As per the design and approved sample. *Location: As per floor finishes plan.*	264.00	Sq.m	120.00	31,680.00
5.03	**TRANSITION STRIP (SS FINISH)** Supply and Installation of SS transition strip. *Location: B/W floor finishes & Door openings.*	35.00	LM	100.00	3,500.00
	Exclusions; - *Supply and installation of New raised flooring.* - *Granite Threshold.*				
				SUBTOTAL AED:	**58,430.00**
6.00	**WALL FINISH**				
6.01	**GYPSUM BOARD LINING (SINGLE LAYER) (Non-FR)** Supply and installation of Non-FR Gypsum board cladding (Single layer) on top of existing block wall (without rock wool) including necessary vertical/Horizontal grooves/trims. As per the design. *Location: On top of Existing walls & Proposed manager TV walls*	195.00	Sq.m	125.00	24,375.00
6.02	**WHITE PAINT.** Supply and application of Jotun Fenomastic White paint. As per the design and approved sample. (2 coats including levelling and sanding) *Location: General areas as per wall finishes plan*	650.00	Sq.m	34.00	22,100.00
6.03	**TEXTURE PAINT.** Supply and application of texture paint. As per design and approved sample. *Location: As per Wall finishes layout*	95.00	Sq.m	170.00	16,150.00
6.04	**MARBLE WALL CLADDING.** Supply and Installation of Travertine marble cladding with necessary wooden backing. *Location: Reception Back wall*	39.00	Sqm	1,740.00	67,860.00
6.05	**ROLLER BLINDS (MANUAL)** Supply and installation of Manual Roller Blinds (Straight) on existing glass window. As per design and approved sample. *Location: Existing windows*	46.00	Sq.m	100.00	4,600.00
6.06	**FROSTED STICKER.** Supply and Installation of Frosted Sticker on Proposed glass partition with necessary material for fixing as per design and approved sample. *Location: Proposed Glass Partition*	105.00	Sq.m	110.00	11,550.00
6.07	**MDF SKIRTING.** Supply and installation of 100mm MDF Skirting finished with paint. Including necessary materials for fixing. As per design and approved sample. *Location: As per Wall finishes layout*	279.00	LM	55.00	15,345.00
				SUBTOTAL AED:	**161,980.00**

P.O. Box: 62522 DUBAI - U.A.E. DESIGN INFINITY L.L.C

(BILL OF QUANTITIES-FIT-OUT WORKS)					
REF: DI/GN/506/2024/R1				December 16, 2024	
SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)
7.00	CEILING FINISH				
7.01	**GYPSUM PLAIN CEILING.** Supply and installation of non fire rated Gypsum Board Plain ceiling (Knauf or equivalent)with necessary hanging systems including GI wall angle "C "channel, furring channel with 12.5mm gypsum boards joined taped smoothened finish. *Location: As per proposed RCP*	364.00	Sq.m	90.00	32,760.00
7.02	**SOLOPANEL CEILING.** Supply and installation of(Knauf Solo panel or equivalent) with necessary hanging systems including GI wall angle "C "channel, furring channel, boards joined taped smoothened finish. Including painting. *Location: As per proposed RCP*	55.00	Sqm	195.00	10,725.00
7.03	**GYPSUM BULKHEAD.** Supply and installation of Plain Gypsum Bulkhead using 12.5mm thick gypsum boards (Knauf or equivalent) and GI suspension system. Gypsum board surface made ready to receive the final finish. As per the design and approved sample. *Location: As per proposed RCP*	216.00	LM	95.00	20,520.00
7.04	**GYPSUM PELMET.** Supply and installation of (knauf) Gypsum Pelmet with necessary fittings ready to receive final finishes. *Location: Periphery glass wall*	17.00	LM	90.00	1,530.00
7.05	**CEILING PAINT.** Supply and application of Jotun Fenomastic paint including all cleaning and levelling. As per design and approved sample. (2 coats including sanding). Color/Type are as follows;				
A	**WHITE PAINT (ON GYPSUM CEILING)**	364.00	Sqm	34.00	12,376.00
B	**WHITE PAINT (ON GYPSUM BULKHEAD & PELMET)**	233.00	LM	20.00	4,660.00
7.06	**GYPSUM ACCESS PANEL.** Supply and installation of Gypsum access panel with frame and hinges. *Location: Proposed Gypsum ceiling area*	20.00	Nos	240.00	4,800.00
				SUBTOTAL AED:	**87,371.00**
8.00	DOORS				
8.01	**MAIN ENTRANCE DOUBLE LEAF GLASS DOOR. (Non-FR)** Supply and installation of Non- FR Double leaf Glass door. With necessary fitting and fixtures for the installation. All in accordance with the manufactures specifications. Size: L 2000mm X H 2800mm	1.00	No	6,870.00	6,870.00
8.02	**MAIN ENTRANCE /INTERNAL SINGLE LEAF GLASS DOOR. (Non-FR)** Supply and installation of Non- FR Single leaf Glass door. With necessary fitting and fixtures for the installation. All in accordance with the manufactures specifications. Size: L 1000mm X H 2800mm	2.00	Nos	3,690.00	7,380.00
8.03	**FIRE RATED MAIN ENTRANCE DOUBLE LEAF GLASS DOOR.** Supply and installation of 60 minutes FR Double leaf Glass door. With necessary fitting and fixtures for the installation. All in accordance with the manufactures specifications. Size: L 2000mm X H 2800mm	1.00	No	30,610.00	RATE ONLY
8.04	**FIRE RATED MAIN ENTRANCE SINGLE LEAF GLASS DOOR.** Supply and installation of 60 minutes FR Single leaf Glass door. With necessary fitting and fixtures for the installation. All in accordance with the manufactures specifications. Size: L 1000mm X H 2800mm	2.00	Nos	19,360.00	RATE ONLY
8.05	**ACOUSTIC SINGLE LEAF GLASS DOOR.** Supply and installation of framed single leaf swing door using 13.52mm thick acoustic laminated glass with QIC Evolution outer frame (Size-44x68mm) and QAS Integra Shutter frame (56x30mm) ,fitted with GEZE Floor spring, Offset Straps, bottom lock and 1200mm long custom fabricated handle. All fittings are in powder coated finish. (Acoustic Rating-Rw 38dB) *Size-1000x2800mm*	8.00	Nos	6,870.00	54,960.00

ديزاين انفينيتي ش.ذ.م.م P.O. Box: 62522 DUBAI - U.A.E. DESIGN INFINITY L.L.C

(BILL OF QUANTITIES-FIT-OUT WORKS)					
REF: DI/GN/506/2024/R1				December 16, 2024	
SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)
8.06	**SMART GLASS DOOR.** Supply and installation of smart glass door inclusive of 12mm thick tempered glass with High Clarity Switchable smart film (To be pasted on glass) inclusive of Electronically adjustable control from transparent to opaque, aluminum black powder coated U channel cladding all around the door leaf & standard door floor spring, patch fittings & handles. Accessories: * Over current and short circuit protected Power Drive with inbuilt Dry Contacts and supplied complete with remote control. * Neutral Cure Specialty Silicone sealant. Size:- 1000mm W x 2800mm H	8.00	Nos	8,790.00	OPTIONAL
				SUBTOTAL AED:	**69,210.00**
9.00	**JOINERY WORKS**				
	CUSTOM MADE JOINERY (OFFICE-1)				
9.01	**J1: COUNTER @ EXE LOUNGE.** Made of MDF laminated carcass and MDF veneer finish shutter top and bottom unit with both side tall unit, bottom counter top in black marble finish (PC rate- 350AED/Sqm) and back splash in black painted glass. Size-3470x650x2800 mm ht.	1	No	16,030.00	16,030.00
9.02	**J2: PANTRY COUNTER-1** Made of MDF laminated carcass and shutter finished with MDF Veneer and counter top in black marble finish (PC rate- 450 AED/Sqm). and back splash in black painted glass. Size-3520x600/400x800/750 + 900x600x2400 mm ht.	1	No	20,620.00	20,620.00
9.03	**J5: PRINTER CABINET+COUNTER-1** Made of MDF laminated carcass and MDF veneer shutter in top and bottom unit. Cabinet top same veneer MDF finish. Size-2750x500/300x900/750 mm HT	1	No	8,390.00	8,390.00
9.04	**J3: SERVER RACK/FULL HEIGHT CABINET-1** Made of closed server cabinet in MDF laminated carcass and MDF PU paint finish Size - 1000x600x1200 mm HT	1	No	1,730.00	1,730.00
9.05	**J4: OPEN + CLOSED CABINET-1** Made of MDF laminated carcass with MDF veneer shutter closed unit and open unit in black PU painted MDF finish. @Cabin area Size -4540x700x2800 mm ht. + 5500x400x2800 mm Ht.	1	No	19,250.00	19,250.00
9.06	**J5: OPEN +CLOSED STORAGE-2,** Made of MDF laminated carcass and MDF veneer shutter in top and bottom unit. Cabinet top same veneer MDF finish. Open shelves in MDF black laminate finish with fluted PU Paint MDF wall panel Size- 3180x500/300x900/750 mm HT	1	No	15,770.00	15,770.00
9.07	**FULL HEIGHT CABINET @ PANTRY,** Made of MDF laminated carcass and MDF veneer shutter . Cabinet top same veneer MDF finish. Size- 1450x400x2800 mm HT	1	No	5,170.00	5,170.00
9.08	**RECEPTION COUNTER,** made of MDF Veneer unit with laminated MDF carcass, counter top and facia in white solid surface finish. Size - 1750x800x750/1100 mm ht.	1	No	13,990.00	13,990.00
9.09	**MEETING ROOM STORAGE,** made of both side MDF Veneer push to open shutters with center writable wall Size -1700+1700x300x2400 mm ht. +1280x100x2800 mm ht Location - 8 Pax Meeting.	1	No	15,570.00	15,570.00
9.10	**MEETING ROOM TV PANEL,** made of MDF PU Paint wall panel with necessary wood/metal backing. Size -4100x150x2800 mm ht. Location - 8 Pax Meeting.	1	No	6,510.00	6,510.00
9.11	**PLANTER BOX,** made of MDF Laminated bottom storage unit with top planter box in same finish for artificial plants. Size -1400x400x900 mm ht. Location - Workstation.	1	No	3,190.00	3,190.00
9.12	**PLANTER BOX,** made of MDF Laminated bottom storage unit with top planter box in same finish for artificial plants. Size -700x400x900 mm ht. Location - Workstation.	2	Nos	2,270.00	4,540.00

ديزاين انفينيتي ش.ذ.م.م
P.O.Box: 64622
DUBAI - U.A.E.
DESIGN INFINITY L.L.C

(BILL OF QUANTITIES-FIT-OUT WORKS)					
REF: DI/GN/506/2024/R1				December 16, 2024	
SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)
9.13	**J7: DB CABINET-1**, Made of MDF veneer wooden paneling with push to open shutter for DB Size - 1200x400x1200 mm HT	1	No	1,790.00	1,790.00
	CUSTOM MADE JOINERY (OFFICE-2)				
9.14	**J2: PANTRY COUNTER-2** Made of MDF laminated carcass and shutter finished with MDF Veneer and counter top in black marble finish (PC rate- 450 AED/Sqm). and back splash in black painted glass. Size-3120x600/400x800/750 + 900x600x2800 mm ht.	1	No	20,470.00	20,470.00
9.15	**J4: OPEN + CLOSED CABINET-2** Made of MDF laminated carcass with MDF veneer shutter closed unit and open unit in black PU painted MDF finish. Size -3000x400x2800 mm ht. Location - Cabin.	2	Nos	16,200.00	32,400.00
9.16	**J4: CLOSED CABINET-3** ,Made of MDF laminated carcass with MDF veneer shutter closed unit . Size -3540x400x2800 mm ht. Location - Corridor	1	No	12,630.00	12,630.00
9.17	**J3: SERVER RACK CABINET-2** Made of closed server cabinet in MDF laminated carcass and MDF veneer finish shutters. Size - 1700x400x2800 mm HT	1	No	5,710.00	5,710.00
9.18	**J5: PRINTER CABINET+COUNTER-3,** Made of MDF laminated carcass and MDF veneer shutter in top and bottom unit. Cabinet top same veneer MDF finish. Size- 1450x400x2800 mm HT	1	No	5,170.00	5,170.00
9.19	**RECEPTION TABLE,** made of MDF Veneer unit with laminated MDF carcass, counter top and facia in white solid surface finish. Size - 1750x800x750/1100 mm ht.	1	No	13,990.00	13,990.00
9.20	**J7: DB CABINET-1**, Made of MDF veneer wooden paneling with push to open shutter for DB Size - 1200x400x1200 mm HT	1	No	1,790.00	1,790.00
9.21	**MEETING ROOM STORAGE,** made of both side MDF Veneer push to open shutters with center writable wall Size -2950x300x2800 mm ht. Location - 8 Pax Meeting.	1	No	9,870.00	9,870.00
9.22	**MEETING ROOM TV PANEL,** made of MDF PU Paint wall panel with necessary wood/metal backing. Size -3870x150x2800 mm ht. Location - 8 Pax Meeting.	1	No	6,200.00	6,200.00
9.23	**MEETING ROOM TV PANEL,** made of MDF PU Paint wall panel with necessary wood/metal backing. Size -2960x150x2800 mm ht. Location - Cabin.	2	Nos	4,970.00	9,940.00
9.24	**PLANTER BOX,** made of MDF Laminated bottom storage unit with top planter box in same finish for artificial plants. Size -1400x400x900 mm ht. Location - Workstation.	1	No	3,190.00	3,190.00
9.25	**PLANTER BOX,** made of MDF Laminated bottom storage unit with top planter box in same finish for artificial plants. Size -700x400x900 mm ht. Location - Workstation.	1	No	2,270.00	2,270.00
	CUSTOM MADE JOINERY (OFFICE-3)				
9.26	**J2: PANTRY COUNTER-3** Made of MDF laminated carcass and shutter finished with MDF Veneer and counter top in black marble finish (PC rate- 450 AED/Sqm). and back splash in black painted glass. Size-4120x600/400x800/750 + 900x600x2800 mm ht.	1	No	22,480.00	22,480.00
9.27	**J5: PRINTER CABINET:** Made of MDF laminated carcass and MDF veneer shutter in top and bottom unit. Cabinet top same veneer MDF finish. Size- 2800x400x800/700 mm HT	1	No	7,330.00	7,330.00
9.28	**J3: SERVER RACK CABINET-2** Made of closed server cabinet in MDF laminated carcass and MDF veneer finish shutters. Size - 1000x400x2800 mm HT	1	No	4,380.00	4,380.00

ديزاين انفنيتي ش.ذ.م.م
P.O. Box: 62522
DUBAI - UAE
DESIGN INFINITY L.L.C

(BILL OF QUANTITIES-FIT-OUT WORKS)					
REF: DI/GN/506/2024/R1					December 16, 2024
SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)
9.29	**J4: OPEN + CLOSED CABINET-2** Made of MDF laminated carcass with MDF veneer shutter closed unit and open unit in black PU painted MDF finish. Size -2950x400x2800 mm ht. Location - Cabin.	1	No	11,140.00	11,140.00
9.30	**J4: CLOSED CABINET-3** ,Made of MDF laminated carcass with MDF veneer shutter closed unit . Size -2730+2340x600x2800 mm ht. Location - Corridor	1	No	18,090.00	18,090.00
9.31	**MEETING ROOM STORAGE,** made of both side MDF Veneer push to open shutters with center writable wall Size -2800x300x2800 mm ht. Location - 7 Pax Meeting.	1	No	9,070.00	9,070.00
9.32	**MEETING ROOM TV PANEL,** made of MDF PU Paint wall panel with necessary wood/metal backing. Size -2800x150x2800 mm ht. Location - 8 Pax Meeting.	1	No	6,030.00	6,030.00
9.33	**RECEPTION TABLE,** made of MDF Veneer unit with laminated MDF carcass, counter top and facia in white solid surface finish. Size - 1550x800x750/1100 mm ht.	1	No	12,870.00	12,870.00
9.34	**J7: DB CABINET-**1, Made of MDF veneer wooden paneling with push to open shutter for DB Size - 1200x400x1200 mm HT	1	No	1,790.00	1,790.00
9.35	**PLANTER BOX,** made of MDF Laminated bottom storage unit with top planter box in same finish for artificial plants. Size -1400x400x900 mm ht. Location - Workstation.	2	Nos	3,190.00	6,380.00
9.36	**SLAT WALL,** Made of MDF laminated slat wall with necessary wooden support. Size - 50x150x2800 mm HT	3	Nos	510.00	1,530.00
				SUBTOTAL AED:	**357,270.00**
10.00	**OTHERS (SIGNAGE/PLANTS & WHITE GOODS)**				
10.01	**SIGNAGE @ UNIT-01** Allow provisional sum to provide signage as per the design-requirement. @ Unit-01 Type-1 : MDF CNC cut	1.00	P.S	3,690.00	3,690.00
10.02	**SIGNAGE @ UNIT-02 &03** Allow provisional sum to provide signage as per the design-requirement. @ Unit-01 Type-1 : MDF CNC cut	1.00	P.S	7,370.00	**OPTIONAL**
10.03	**ARTIFICIAL PLANTS @ UNIT-01** Allow a provisional sum to provide Artificial plants/Planters as per the proposed design. Including necessary materials for fixing as per the design and approved sample.	1.00	P.S	9,120.00	9,120.00
10.04	**ARTIFICIAL PLANTS @ UNIT-02 &03** Allow a provisional sum to provide Artificial plants/Planters as per the proposed design. Including necessary materials for fixing as per the design and approved sample.	2.00	P.S	9,120.00	**OPTIONAL**
10.05	**SHEER CURTAIN @ UNIT-01** Allow a provisional sum to provide Sheer curtain (manually operated) as per the proposed design. Including necessary materials for fixing as per the design and approved sample.	1.00	P.S	8,430.00	8,430.00
10.06	**WHITE GOODS.** Supply and installation of the following;				
A	Siemens Built In Upright Refrigerator 321 Liters	3.00	P.S	5,470.00	16,410.00
B	Siemens Built In Under Counter Refrigerator 123 Liters @ Executive Lounge	1.00	P.S	3,020.00	3,020.00
C	Samsung Microwave Oven 32 Liters	3.00	P.S	630.00	1,890.00
D	Panasonic Top Loading Water Dispenser	3.00	P.S	730.00	2,190.00
E	Nespresso coffee maker	3.00	P.S	2,600.00	7,800.00

P.O. Box: 62532 DUBAI - U.A.E. DESIGN INFINITY L.L.C

(BILL OF QUANTITIES-FIT-OUT WORKS)					
REF: DI/GN/506/2024/R1				December 16, 2024	
SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)
F	Coffee maker @ Executive Lounge	1.00	P.S	1,670.00	1,670.00
G	Installation and Coordination Charges **(@10%)**	1.00	Item	3,298.00	3,298.00
				SUBTOTAL AED:	**57,518.00**
	MEP WORKS				
	ELECTRICAL ENGINEERING INSTALLATION				
11.00	**LIGHT FIXTURES**				
	Supply of light fixture as pe the new layout Make- Creta Lighting Type-Non-Dimmable				
11.01	ACOUSTIC LINEAR LIGHT @ WORKSTATION	25	Mtrs	470.00	11,750.00
11.02	TRIMLESS SPOTLIGHT	70	Nos.	150.00	10,500.00
11.03	DECORATIVE LIGHT	3	Nos.	560.00	1,680.00
11.04	LINEAR PENDANT LIGHT @CABINS	4	Nos.	940.00	3,760.00
11.05	LINEAR PENDANT LIGHT @ MEETING ROOMS	3	Nos.	940.00	2,820.00
11.06	WALL MOUNTED LIGHT	4	Nos.	810.00	3,240.00
11.07	MAGNETIC LINEAR LIGHTINCLUDING MAGNETIC TRACK RAIL	30	Nos.	820.00	24,600.00
11.08	COVE LIGHT 	200	Mtrs	80.00	16,000.00
11.09	JOINERY STRIP LIGHT	20	Mtrs	80.00	1,600.00
				SUB TOTAL FOR LIGHT FIXTURES AED:	**75,950.00**
12.00	**ELECTRICAL ENGINEERING INSTALLATION**				
	Supply and installation of new cable Tray/ Trunking with necessary accessories as per the new layout				
12.01	Cable trunking for the DB outgoing cables Light and power	1.00	Item	4,750.00	4,750.00
12.02	Supply and installation of cable tray for LV cables	1.00	Item	3,370.00	3,370.00
	Supply & Installation of Distribution board including breakers, spare, spaces, etc. Make: ABB, Encloser- Al Fanar				
12.03	New SMDB Incomer 63A , Available Load: 16 KW Note: Necessary electrical load will be provided by Landlord	1.00	No	6,250.00	6,250.00
12.04	DB-Light & power Incomer 40A , Approx.. Load: 5 KW	3.00	Nos	3,750.00	11,250.00
12.05	Supply and installation of PMU meter for each unit. Note: We have considered separate PMU meter for each offices	3.00	Nos	4,750.00	14,250.00

ديزاين انفينيتي ش.ذ.م.م
P.O. Box: 62522
DUBAI - U.A.E.
DESIGN INFINITY L.L.C

(BILL OF QUANTITIES-FIT-OUT WORKS)					
REF: DI/GN/506/2024/R1					December 16, 2024
SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)
	LV Cables Supply and lying of LV Cable including necessary glanding and termination				
12.06	4C x 16 sqmm XLPE/SWA/PVC + 1C x 16 sqmm ECC/PVC from the existing SMDB 3/1 to new SMDB	40.00	Mtrs	90.00	3,600.00
12.07	4C x 10 sqmm XLPE/SWA/PVC + 1C x 10 sqmm ECC/PVC from the new SMDB to DB in each units	60.00	Mtrs	80.00	4,800.00
	Lighting |Installation of Lighting system including conducting and wiring with all necessary accessories and ancillary works as specified and as indicating in the drawings. PVC Conduit and Wire				
12.08	Supply and installation of conduit and wiring for the light fixtures	114.00	Nos.	175.00	19,950.00
12.09	Installation of LED strip light including conduit and wiring	220.00	Mtr.	55.00	12,100.00
12.10	Installation of Linear light including conduit and wiring	25.00	Mtr.	95.00	2,375.00
12.11	Installation of light fixtures	114.00	Nos.	35.00	3,990.00
12.12	Installation of Decorative Light with required fittings	1.00	Nos.	75.00	75.00
12.13	Supply and installation of lighting switches (BSS Finish)				
12.14	Supply and Installation of 1Gang 1 way switch switches	3.00	Nos	210.00	630.00
12.15	Supply and Installation of 2Gang 1 way switch switches	4.00	Nos	230.00	920.00
12.16	Supply and Installation of 3Gang 1 way switch switches	4.00	Nos	250.00	1,000.00
12.17	Supply and installation of grid switch for lights	3.00	Nos	970.00	2,910.00
	Lighting Control system				
12.18	Supply and installation of Dali dimmable lighting control system with LCP for each 3 offices, keypad, sensors etc. with necessary Dali wiring and containment	1.00	Item	56,350.00	RATE ONLY
12.19	Supply of dimmable drivers for light fixtures	1.00	Item	26,060.00	RATE ONLY
	Supply and install power outlets connect, test and commission the following power socket outlets including plates and boxes, etc. Including PVC containment and wiring Brand : MK, Finish : BSS				
12.20	Supply and installation of Single Socket including conducting & wiring 13A, 220V, 50Hz 2 pole and earth single switch socket outlet.	10.00	Nos	450.00	4,500.00
12.21	Supply and installation of Double Socket including conducting & wiring 13A, two gang, 220V, 50Hz, 2 pole and earth twin switch socket outlet.	23.00	Nos	470.00	10,810.00
12.22	Supply and Installation of Floor Box (FB-1) including wiring and pvc containment for 1no 13A Single power socket and 1 No.of data Note: Data/Voice cabling and termination works are excluded.	5.00	Nos	720.00	3,600.00
12.23	Supply and Installation of Floor Box (FB-2) including wiring and pvc containment for 1no 13A Double power socket and 2 No.of data Note: Data/Voice cabling and termination works are excluded.	17.00	Nos	750.00	12,750.00
12.24	Supply and installation of 15A Single socket for Fridge, Microwave and Coffee machine including conduiting & wiring	11.00	Nos	470.00	5,170.00
12.25	Supply and installation of power provision for the server racks including conduiting & wiring	3.00	Nos	940.00	2,820.00
12.26	Supply and installation of power provision for the Signage Logo including conduiting & wiring	3.00	Nos	690.00	2,070.00
12.27	Supply and installation power supply for Access control system including conduiting & wiring	3.00	Nos	440.00	1,320.00

P.O. Box: 62522 DUBAI - U.A.E. DESIGN INFINITY L.L.C

(BILL OF QUANTITIES-FIT-OUT WORKS)					
REF: DI/GN/506/2024/R1				December 16, 2024	
SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)
12.28	Supply and installation of power provision for the Wi-Fi points including conduiting & wiring	6.00	Nos	440.00	2,640.00
12.29	Supply and installation power provision for FTU including conduiting & wiring	40.00	Nos	440.00	17,600.00
12.30	Supply and installation of 20A DP switch with neon indicator for water heater including conduiting & wiring	1.00	Nos	560.00	560.00
12.31	Supply and installation power provision for FACP including conduiting & wiring	1.00	No	440.00	440.00
12.32	Supply and installation of DP switch for the TV points as per the DEWA standard.	8.00	Nos	370.00	2,960.00
12.33	Supply and installation of Floor box and double socket for future expansion	1.00	Item	3,750.00	RATE ONLY
				SUB TOTAL AED:	**159,460.00**
	CONTAINMENT SYSTEM				
	Data Installation				
12.33	Supply and installation of conduit for the IT and data points	40.00	Nos	110.00	4,400.00
12.34	Supply and installation of cable tray for the data cables above the ceiling.	1.00	Item	5,620.00	5,620.00
	Access control system, cctv & Wi-Fi				
12.35	Allow for containment of access control system as per the new design proposal	18.00	Nos	110.00	1,980.00
	AV system				
12.36	Allow for containment of AV system as per the new design proposal	8.00	Nos	150.00	1,200.00
				SUB TOTAL AED:	**13,200.00**
	SUNDRIES RELATED TO ELECTRICAL ENGINEERING INSTALLATIONS				
12.37	Allow for documents including shop drawings, as built drawings, operating instructions and maintenance manuals as specified.	1.00	Item	-	INCLUDED
12.38	Allow for co-ordination with other engineering installations.	1.00	Item	-	INCLUDED
12.39	Allow for cutting or forming holes, mortices, chases or the like and making good finishing's.	1.00	Item	-	INCLUDED
12.40	Allow for testing and commissioning electrical services(3rd party excluded)	1.00	Item	3,120.00	3,120.00
12.41	Allow for identification labels including plates, discs, labels, charts and color coding.	1.00	Item	-	INCLUDED
12.42	Shop drawing preparation and DEWA approval	1.00	Item	5,000.00	5,000.00
12.43	Allow for building in or cutting and pinning brackets or the like and making good finishing's.	1.00	Item	-	INCLUDED
				SUB TOTAL AED:	**8,120.00**
				ELECTRICAL TOTAL AED:	**180,780.00**
13.00	**MECHANICAL ENGINEERING INSTALLATION**				
	AIR CONDITIONING SYSTEM				
13.01	Supply and installation of Floor Terminal Unit (TU4) inclusive of two centrifugal fans, motorized damper, multifunctional electronic controller with "bus" communication card, air discharge and intake floor grills, 5m power connection cable with British Standard fused plug. This unit has an LCD Screen for reading all necessary data and easily changing them if required. supply & installation of all necessary data (bus communication) cabling & RJ45. (Manufacturer: AET, UK, Delivery Time : 10-14 Weeks) . (BMS Works other than Mentioned above is not considered)	40.00	Nos	10,120.00	404,800.00
13.02	Supply & installation of floor grill FGC by AET/Hiross. Grille face area: 150x599mm Grille Hight Adjustable: 22 mm	3.00	Nos	810.00	2,430.00
13.03	Supply & installation of Return Linear Diffuser on the ceiling	42.00	Mtr	150.00	6,300.00

ديزاين انفينيتي ش.ذ.م.م P.O. Box: 62522 DUBAI - U.A.E. DESIGN INFINITY L.L.C.

(BILL OF QUANTITIES-FIT-OUT WORKS)					
REF: DI/GN/506/2024/R1					December 16, 2024
SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)
13.04	Supply & installation of Extract Diffuser for pantry	3.00	Nos	110.00	330.00
13.05	Supply & installation of GI Duct work with insulation necessary fittings and accessories for the Extract air system.	1.00	Item	4,500.00	4,500.00
13.06	Supply & installation of Exhaust Fan for pantry	1.00	Nos	1,190.00	1,190.00
13.07	Air Balancing , Testing & commissioning	1.00	Item	3,120.00	3,120.00
				SUB TOTAL AED:	**422,670.00**
	PLUMBING SYSTEM				
13.08	Supply and installation of the Waste pipe works with necessary fittings and accessories	1.00	Item	3,990.00	3,990.00
13.09	Supply and installation of floor trap	3.00	Nos	310.00	930.00
13.10	Supply and installation of Floor cleanout	3.00	Nos	310.00	930.00
13.11	Supply and installation of Sani pump for drainage line	3.00	Nos	4,680.00	14,040.00
13.12	Supply and install of Cold Water Supply (PPR) Pipes & Fittings with necessary accessories	1.00	Item	3,000.00	3,000.00
13.13	Supply and install of Hot Water Supply Pipes & Fittings with necessary accessories	1.00	Item	1,750.00	1,750.00
13.14	Supply and install of Pax Pipes For Water Supply			-	INCLUDED
13.15	Supply and installation of Water Heater	3.00	Nos	940.00	2,820.00
13.16	Pressure testing for water supply line	1.00	Item	620.00	620.00
13.17	Gravity test for drain lines & Commissioning	1.00	Item	620.00	620.00
				SUB TOTAL AED:	**28,700.00**
	GRAND TOTAL (MECHANICAL ENGINEERING INSTALLATION) AED:				**451,370.00**
14.00	**CIVIL DEFENCE WORKS**				
A	**FIRE FIGHTING INSTALLATION**				
14.01	Sprinkler heads complete with all necessary accessories as specified and as shown on drawing				
14.02	Supply and installation of Pendent Sprinkler	9.00	Nos	620.00	5,580.00
14.03	New Upright sprinklers with necessary piping	48.00	Nos	620.00	29,760.00
14.04	Relocation of pendent sprinklers	39.00	Nos	440.00	17,160.00
14.05	Fire extinguisher set	3.00	Nos	560.00	1,680.00
14.06	Shop drawing preparation and coordination for DCD approval	1.00	LS	2,500.00	2,500.00
14.07	Charges for Zone control valve closing and pressure test	1.00	Nos	3,120.00	3,120.00
B	**EMERGENCY LIGHTING INSTALLATION**				
14.08	Emergency light Self contained, non maintained	14.00	Nos	750.00	10,500.00
14.09	Emergency Exit light Surface mounted self contained type	6.00	Nos	850.00	5,100.00
14.10	Removal and refixing of Existing Emergency/Exit Light with necessary wiring and accessories CBS	10.00	Nos	500.00	5,000.00
14.11	Reprogramming for the existing CBS Panel	1.00	Item	4,370.00	4,370.00
C	**FIRE ALARM INSTALLATION**				
	Fire alarm devices with necessary containment system, terminations other ancillary work, complete.				
14.12	Supply and Installation of Addressable Fire Alarm Control Panel	1.00	No	14,370.00	14,370.00
14.13	Supply and Installation of Addressable Fire Alarm Control Panel -unit 1 & 2	2.00	Nos	15,620.00	RATE ONLY
14.14	Supply and Installation of Addressable Smoke Detector with containment and wiring	12.00	Nos	1,000.00	12,000.00
14.15	Relocation of existing Addressable Smoke Detector with required containment and wiring	6.00	Nos	500.00	3,000.00
14.16	Relocation of existing speaker with required containment and wiring	6.00	Nos	500.00	3,000.00
14.17	Supply and Installation of Addressable Smoke Detector with LED indicator including containment and wiring	18.00	Nos	1,280.00	23,040.00
14.18	Supply and Installation of Sounder with containment and wiring	3.00	Nos	970.00	2,910.00
14.19	Supply and Installation of Manual call point with containment and wiring	3.00	Nos	970.00	2,910.00

DESIGN INFINITY L.L.C. P.O. Box: 23049 DUBAI - U.A.E.

(BILL OF QUANTITIES-FIT-OUT WORKS)					
REF: DI/GN/506/2024/R1					December 16, 2024
SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)
14.20	Supply and Installation of New interfacing unit with necessary containment and wiring	9.00	Nos	1,620.00	14,580.00
14.21	Fire alarm Programming, Testing and commissioning.	1.00	Lot	9,370.00	9,370.00
				CIVIL DEFENCE TOTAL AED:	169,950.00
15.00	PANTRY ACCESSORIES (PROVISIONAL SUM)				
	Supply & Installation of following items; Make: RAK/EQUIV.				
15.01	PANTRY SINK.	3.00	Nos	940.00	2,820.00
15.02	SINK MIXER.	3.00	Nos	690.00	2,070.00
15.03	PULLABLE BIN @ PANTRY.	3.00	Nos	620.00	1,860.00
15.04	WASTE BIN - GENERAL AREAS (5 Nos for each unit)	15.00	Nos	440.00	6,600.00
				SUBTOTAL PANTRY ACCESSORIES AED:	13,350.00
16.00	IT /AV WORKS				
A	STRUCTURED CABLING SYSTEM				
	Horizontal CAT6A Cabling - Norden				
16.01	UK Face Plate Plain 02 Port White	80.00	Nos	15.00	1,200.00
16.02	Keystone 45 Angled Bracket with Icon White	160.00	Nos	10.00	1,600.00
16.03	Category 6A UTP Keystone Jack 90D White	160.00	Nos	15.00	2,400.00
16.04	Cat6A UTP Patch Panel Blank Tool Less 24 port	7.00	Nos	95.00	665.00
16.05	Category 6A UTP Keystone Jack Tool Less 180D White	160.00	Nos	15.00	2,400.00
16.06	1U Metal Cable Management with cover	7.00	Nos	60.00	420.00
16.07	Category 6A U/UTP 23 AWG 4 pair cable E-series PVC	37.00	Nos	850.00	31,450.00
16.08	Network rack	3.00	Nos	2,250.00	6,750.00
16.09	06WAY PDU UNIVERSAL SOCKET WITH SWITCH, 13AMP, 1.8MTR CABLE LENGTH, UK PLUG, 19" INSTALLATION	3.00	Nos	110.00	330.00
16.10	Category 6A U/UTP Patch Cord E Series PVC 01 MTR	160.00	Nos	20.00	3,200.00
16.11	Category 6A U/UTP Patch Cord E Series PVC 03 MTR	160.00	Nos	25.00	4,000.00
16.12	Installation Testing and Commissioning (Including Calibrated Fluke Testing and documentation)	160.00	Nos	105.00	16,800.00
16.13	Supply and installation of 6 core single mode cable from server room to floor telephone room to hire ISP services	1.00	LS	3,750.00	3,750.00
	IT Notes & exclusions: Stand alone access control system considered at entrances. CCTV system considered in common areas only. Considered 2 no's WAP , 3 no's CCTV at each units Any network switch, BGM are excluded. Any CCTV Rack, surveillance monitor are not considered				
				SUBTOTAL STRUCTURED CABLING SYSTEM AED:	74,965.00
B	CCTV WORKS				
16.14	CCTV- Hikvision				
16.15	Supply and installation of Hikvision 4MP fixed IP dome camera -Hikvision	9.00	Nos	350.00	3,150.00
16.16	Supply and installation of 8 channel NVR Make- Hikvision	3.00	Nos	810.00	2,430.00
16.17	Supply and installation of 6TB hard disc for 31 days	3.00	Nos	810.00	2,430.00
16.18	supply and installation of CAT6A data cabling with termination	9.00	Nos	250.00	2,250.00
16.19	Installation Testing and Commissioning (Including Calibrated Fluke Testing and documentation)	9.00	Nos	150.00	1,350.00
				TOTAL FOR CCTV SYSTEM AED:	11,610.00

P.O. Box: 62522 DUBAI - U.A.E. DESIGN INFINITY L.L.C

(BILL OF QUANTITIES-FIT-OUT WORKS)					
REF: DI/GN/506/2024/R1					December 16, 2024
SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)
C	**ACS SYSTEM- SUPREMA STAND ALONE SYSTEM,ENTRANCES ONLY**				
16.20	BiostationL2- FINGERPRINT, RFID(13.56MHZMIFARE/DESFIRE), OPTICAL SENSOR(OP5),LIVE FINGER DETECTION(FINGER+CARD+PIN),INDOOR UNIT	3.00	Nos	2,870.00	8,610.00
16.21	POWER ADAPTOR (24V)	3.00	Nos	90.00	270.00
16.22	SMART CARDS - MIFARE 1K COMPATIBLE (10/PKT)	3.00	Nos	50.00	150.00
16.23	EM Lock (600LBS) + Door Contact	3.00	Nos	440.00	1,320.00
16.24	Cabling & Accessories	3.00	Nos	440.00	1,320.00
16.25	Installation and testing commissioning	3.00	Nos	500.00	1,500.00
				TOTAL FOR ACS SYSTEM AED:	**13,170.00**
D	**WI-FI**				
16.26	Ubiquiti Access Point Wi-Fi 6 Pro, Dual-band Wi-Fi 6 (802.11ax), 5 GHz (4x4 MU-MIMO and OFDMA) Up to 4.8 Gbps throughput rate, 2.4 GHz (2x2 MU-MIMO and OFDMA) band with up to 573.5 Mbps throughput rate, PoE , 13W	6.00	No	770.00	4,620.00
16.27	AP mount bracket kit (10-pack)	1.00	No	940.00	940.00
16.28	Unifi Controller Gen2, 1 TB 2.5" SATA HDD, 1 x Gigabit Ethernet, Manage up to 50 Unifi devices	1.00	No	2,620.00	2,620.00
16.29	Ubiquiti Networks UniFi 16-Port Gigabit PoE+ Compliant Managed Switch	1.00	No	2,750.00	2,750.00
16.30	AC power cord	3.00	No	110.00	330.00
16.31	Ubiquiti SFP-1/10GLR-31 Compatible SFP+ 1000BASE-LX and 10GBASE-LR Dual-Rate 1310nm 10km DOM Duplex LC/UPC SMF Optical Transceiver Module	1.00	No	150.00	150.00
16.32	Cabling & Accessories	1.00	Ls	4,005.00	4,005.00
16.33	Professional Charges including Configuration & Commissioning of Access Points	1.00	Ls	5,620.00	5,620.00
				TOTAL FOR WI-FI AED:	**21,035.00**
E	**AV WORKS**				
	8-9 PAX-BOARD ROOM- 3NOS				
16.34	Qm85 -Supply and installation of Samsung 85inch commercial grade display QM85C Direct-Lit 4K Crystal UHD LED Display for Business Dynamic Crystal Color with Quantum Processor 4K for incredible picture quality. Slim and symmetrical design allowing for seamless environment Powerful All-in-one Digital Signage Solution. Cisco Certified Display. Professional display supporting video call and wireless screen sharing	4.00	Nos	9,370.00	37,480.00
16.35	Push Pull Wall bracket for above	4.00	Nos	1,620.00	6,480.00
16.36	BARCO R9861613EUB CX-30 set GEN2, certified in line with EU wireless requirements includes 2 USB-C Button	4.00	Nos	9,740.00	38,960.00
16.37	POLY STUDIO X52 & TC10; 4K Video Conf/Collab/Wireless Pres Sys:Touch Cntrl,4K 5x EPTZ auto-track Cam,Codec,Stereo Spkrphone,Display Clamp;Cables:1 HDMI 1.83m,1 CAT5E LAN 4.57m;NTSC/PAL;Pwr:UK-Type G, BS 1363	4.00	Nos	15,990.00	63,960.00
16.38	Poly Expansion Mic	4.00	Nos	1,120.00	4,480.00
16.39	Poly+, One Year, Poly Studio X52 &TC10	4.00	Nos	1,690.00	6,760.00
16.40	3y Partner Poly+ Studio X52. (Optional)	4.00	Nos	3,500.00	14,000.00
16.41	Audio Video, Control Cables and Connectors	4.00	Nos	940.00	3,760.00
16.42	Cable cubby with 1x Wireless Charging Spot, 1x HDMI, 1x USB Type A, 2x Cat6, 2x Universal Power	6.00	Nos	3,690.00	22,140.00
16.43	Installation, Programming and Testing Commissioning Charges	4.00	Nos	3,120.00	12,480.00
				SUBTOTAL 8-9 PAX-BOARD ROOM- 3NOS	**210,500.00**

P.O. Box: 62522 DUBAI - U.A.E. DESIGN INFINITY L.L.C

(BILL OF QUANTITIES-FIT-OUT WORKS)					
REF: DI/GN/506/2024/R1					December 16, 2024
SI NO.	DESCRIPTION	QTY	UNIT	UNI RATE	TOTAL (AED)
F	DISPLAY SCREEN				
	FOR EXECUTIVE LOUNGE, MANAGER'S CABIN-4NOS				
16.44	Samsung-Qm65 -Supply and installation of Samsung 65inch commercial grade display QM65C Direct-Lit 4K Crystal UHD LED Display for Business Dynamic Crystal Color with Quantum Processor 4K for incredible picture quality. Slim and symmetrical design allowing for seamless environment Powerful All-in-one Digital Signage Solution. Cisco Certified Display. Professional display supporting video call and wireless screen sharing	5.00	Nos	4,370.00	RATE ONLY
16.45	Push Pull Wall bracket for above	5.00	Nos	620.00	
16.46	Audio Video, Control Cables and Connectors	5.00	Nos	440.00	
16.47	Installation, Programming and Testing Commissioning Charges	5.00	Nos	440.00	
				SUBTOTAL DISPLAY SCREEN AED:	OPTIONAL
				GRAND TOTAL IT/AV WORKS AED:	331,280.00

ديزاين انفنيتي ش.ذ.م.م
P.O. Box: 62522
DUBAI - U.A.E.
DESIGN INFINITY L.L.C

Design Infinity

ANX-01
BILL OF QUANTITIES
LOOSE FURNITURE (OPTION-01)

AURIGA CAPITAL

Design Infinity *Beyond Imagination ...*

QUOTATION

DATE: **16 December 2024**
Quotation #: DC-131224-001-ID-R1

PROJECT : Auriga Capital

SCOPE OF WORK : SUPPLY AND INSTALLATION OF FURNITURE

(OPTION - 1)

SI NO.	DESCRIPTION	VISUAL PRESENTATION	QTY	UNIT	UNI RATE	Total PRICE
	Executive Lounge					
1	Sofa - customized Fabric/PU upholstered, powder coated steel leg including 2 Nos throw pillow Dim: 2200*820*680 (as per final shop drawings) Origin: FarEast Delivery: 11-12 Weeks Warranty: 5 Years (Against Manufacturing Defects)	 Concept image	1	EA	4,552.00	4,552.00
2	Coffee table Wood veneer top with wood veneer base Dim: 1200*600*380 (as per final shop drawings) Origin: FarEast Delivery: 11-12 Weeks Warranty: 5 Years (Against Manufacturing Defects)	 Concept image	1	EA	1,878.00	1,878.00
3	Coffee table Veneer top and base Dim: D520*500 Origin: FarEast Delivery: 11-12 Weeks Warranty: 5 Years (Against Manufacturing Defects)		2	EA	1,441.00	2,882.00
4	Pouf Fabric/PU upholstered Dim: 500*500*420 Origin: FarEast Delivery: 11-12 Weeks Warranty: 5 Years (Against Manufacturing Defects)		2	EA	697.00	1,394.00
5	Arm chair - customized Fabric upholstered, solid wood leg Dim: 790*760*840 (as per final shop drawings) Origin: FarEast Delivery: 11-12 Weeks Warranty: 5 Years (Against Manufacturing Defects)	 Concept image	2	EA	2,189.00	4,378.00

ديزاين انفنيتي ش.ذ.م.م
P.O. Box: 62522
DUBAI - U.A.E.
DESIGN INFINITY L.L.C

Design Infinity *Beyond Imagination ...*

QUOTATION

DATE: **16 December 2024**
Quotation #: DC-131224-001-ID-R1

PROJECT : Auriga Capital

SCOPE OF WORK : SUPPLY AND INSTALLATION OF FURNITURE

(OPTION - 1)

SI NO.	DESCRIPTION	VISUAL PRESENTATION	QTY	UNIT	UNI RATE	Total PRICE
	Reeption / Waiting area					
	Desk	Joinery Scope				
6	Task Chair 1.Material: mesh back&fabric seat 2.*Synchronized-tilting system with lock, lockable at 4 different positions *Sliding seat *Lumber support *Armrest with 4 D.O.F. (Degree Of Freedom) Adjustment 3.Height adjustable 4.Nylon base 5.White frame FInish: Back mesh : grey ,or black Seat mesh : dark grey ,or light grey Dim: 670*590*980-1075 Origin: FarEast Delivery: 11-12 Weeks Warranty: 5 Years (Against Manufacturing Defects)	 	3	EA	1,073.00	3,219.00
7	Sofa Fabric/PU upholstered, powder coated steel leg Dim: 1800*820*680 Origin: FarEast Delivery: 11-12 Weeks Warranty: 5 Years (Against Manufacturing Defects)		1	EA	2,960.00	2,960.00
8	Coffee table MDF painted or wood veneer top with knife edge, powder coated steel leg Dim: D600*310 Origin: FarEast Delivery: 11-12 Weeks Warranty: 5 Years (Against Manufacturing Defects)		3	EA	1,223.00	3,669.00
9	Arm chair Fabric/PU leather upholstered, solid wooden leg Dim: 830*690*700 Origin: FarEast Delivery: 11-12 Weeks Warranty: 5 Years (Against Manufacturing Defects)		6	EA	2,209.00	13,254.00

ديزاين انفنيتي ش.ذ.م.م
P.O. Box: 62522
DUBAI - U.A.E.
DESIGN INFINITY L.L.C

Design Infinity *Beyond Imagination ...*

QUOTATION

DATE: **16 December 2024**
Quotation #: DC-131224-001-ID-R1

PROJECT : Auriga Capital

SCOPE OF WORK : SUPPLY AND INSTALLATION OF FURNITURE

(OPTION - 1)

SI NO.	DESCRIPTION	VISUAL PRESENTATION	QTY	UNIT	UNI RATE	Total PRICE
	Cabins					
10	1.Table top material: thickness:25mm core material:E1 particle board from FSC certified factory decor paper:Schattdecor from Germany PVC edge 2.Steel leg 3.Sideboard with open shelf in front+open shelf at side+swing door+3drawers （1600mm side cabinet is with 1 swing door) 4.Flip aluminium cover and steel wire box under for wiring 5.Melamine privacy panel INCLUDED **-Without frontal screen** **-Without mobile pedestal** **-Electric PDU not included** Dim: 1800*1800*750 Main desk: 1800*800*750 Side return: 1800*500*625 Origin: FarEast Delivery: 11-12 Weeks Warranty: 5 Years (Against Manufacturing Defects)		4	EA	3,665.00	14,660.00
11	Chair 1.Material:mesh back&fabric seat, with adjustable headrest 2.*Synchronized-tilting system with lock, lockable at 4 different positions *Sliding seat *Lumber support *Armrest with 4 D.O.F. (Degree Of Freedom) Adjustment 3.Height adjustable 4.Nylon base 5.White frame Finish: Back mesh : grey ,or black Seat mesh : dark grey, or light grey Dim: 670*590*1155-1250 Origin: FarEast Delivery: 11-12 Weeks Warranty: 5 Years (Against Manufacturing Defects)	 	4	EA	1,145.00	4,580.00
12	Visitor Chair fabric / PU leather upholstered chair body , aluminum alloy base with castors Dim: 610*580*890 Origin: FarEast Delivery: 11-12 Weeks Warranty: 5 Years (Against Manufacturing Defects)		8	EA	1,210.00	9,680.00

ديزاين انفنيتي ش.ذ.م.م
P.O. Box: 62522
DUBAI - U.A.E.
DESIGN INFINITY L.L.C

Design Infinity *Beyond Imagination ...*

QUOTATION

DATE: **16 December 2024**
Quotation #: DC-131224-001-ID-R1

PROJECT : Auriga Capital

SCOPE OF WORK : SUPPLY AND INSTALLATION OF FURNITURE

(OPTION - 1)

SI NO.	DESCRIPTION	VISUAL PRESENTATION	QTY	UNIT	UNI RATE	Total PRICE
13	PDU with Flipbox Single (Black) Black Aluminum Faceplate, Alloy Aluminum inside plate Black Iron housing profile; Finish: Black / Brush: Black Manual Frame Opening - Single 2 x Universal Type Power Socket 2 x Data Cat6 RJ45 with 3m cable 3 meter power cable with UK plug Delivery: 10 weeks Warranty : Five (5) years (Against Manufacturing Defects		4	EA	900.00	RATE ONLY
	Open Workstation					
14	6 Pax Face to Face Cluster 1.Table top material: thickness:25mm core material:E1 particle board from FSC certified factory decor paper:Schattdecor from Germany PVC edge 2.Leg:steel leg 3.Flip aluminium cover and steel wire box under for wiring 4.Fabric screen panel Screen size is 200mm shorter than desk size, height 300mm -Metal board attached on middle leg for cable management -Without Modesty panel -Without mobile pedestal -Electric PDU not included Dim: 3600*1400*750 (each user: 1200 x 700) Origin: FarEast Delivery: 11-12 Weeks Warranty: 5 Years (Against Manufacturing Defects)		1	EA	4,987.00	4,987.00

ديزاين انفنيتي ش.ذ.م.م
P.O. Box: 62522
DUBAI - U.A.E.
DESIGN INFINITY L.L.C

Design Infinity *Beyond Imagination ...*

QUOTATION

DATE: **16 December 2024**
Quotation #: DC-131224-001-ID-R1

PROJECT : Auriga Capital

SCOPE OF WORK : SUPPLY AND INSTALLATION OF FURNITURE

(OPTION - 1)

SI NO.	DESCRIPTION	VISUAL PRESENTATION	QTY	UNIT	UNI RATE	Total PRICE
15	4 Pax Face to Face Cluster 1.Table top material: thickness:25mm core material:E1 particle board from FSC certified factory decor paper:Schattdecor from Germany PVC edge 2.Leg:steel leg 3.Flip aluminium cover and steel wire box under for wiring 4.Fabric screen panel Screen size is 200mm shorter than desk size, height 300mm -Metal board attached on middle leg for cable management -Without Modesty panel -Without mobile pedestal -Electric PDU not included Dim: 2400*1400*750 ((each user: 1200 x 700) Origin: FarEast Delivery: 11-12 Weeks Warranty: 5 Years (Against Manufacturing Defects)		4	EA	3,432.00	13,728.00
16	2 pax side by side Cluster 1.Table top material: thickness:25mm core material:E1 particle board from FSC certified factory decor paper:Schattdecor from Germany PVC edge 2.Leg:steel leg 3.Flip aluminium cover and steel wire box under for wiring 4.Fabric screen panel Screen size is 200mm shorter than desk size, height 300mm -Metal board attached on middle leg for cable management -Without Modesty panel -Without mobile pedestal -Electric PDU not included Dim: 2400*700*750 (each user: 1200 x 700) Origin: FarEast Delivery: 11-12 Weeks Warranty: 5 Years (Against Manufacturing Defects)	 	2	EA	2,694.00	5,388.00

ديزاين انفنيتي ش.ذ.م.م
P.O. Box: 62522
DUBAI - U.A.E.
DESIGN INFINITY L.L.C

QUOTATION

DATE: **16 December 2024**
Quotation #: DC-131224-001-ID-R1

PROJECT : Auriga Capital

SCOPE OF WORK : SUPPLY AND INSTALLATION OF FURNITURE

(OPTION - 1)

SI NO.	DESCRIPTION	VISUAL PRESENTATION	QTY	UNIT	UNI RATE	Total PRICE
17	3 pax side by side Cluster 1.Table top material: thickness:25mm core material:E1 particle board from FSC certified factory decor paper:Schattdecor from Germany PVC edge 2.Leg:steel leg 3.Flip aluminium cover and steel wire box under for wiring 4.Fabric screen panel Screen size is 200mm shorter than desk size, height 300mm -Metal board attached on middle leg for cable management -Without Modesty panel -Without mobile pedestal -Electric PDU not included Dim: 3600*700*750 (each user: 1200 x 700) Origin: FarEast Delivery: 11-12 Weeks Warranty: 5 Years (Against Manufacturing Defects)	 	2	EA	3,791.00	7,582.00
18	Mobile pedestal Super fine cold rolled steel plate, 0.8mm thickness, 10 times anti-rust treatment, automatic powder coating, three full-extension drawers, with lock 30cm wide with seat cushion on top Dim: 300×500×640 cushion : 300*500*40 Origin: FarEast Delivery: 11-12 Weeks Warranty: 5 Years (Against Manufacturing Defects)	 	32	EA	579.00	18,528.00
	Cabinet with planter box	PART OF JOINERY				-
19	PDU for workstation Silver Aluminum Profile 1.5U with holding angles 2 x UK Power Sockets - 3 Pin BS, 230V 1 x Data Cat6A RJ 45 with 3 meter data cable 1 x USB 2.0 with cable (Type A)- for Data transferring 1 x Twin USB (Type A+C) fast charging (30W) On/Off Power Switch 1 x 3 meter starter lead, female GST18i to UK Plug BS1363,13A fused (Wieland type connector) Delivery: 10 weeks Warranty : Five (5) years (Against Manufacturing Defects			EA	429.00	RATE ONLY

ديزاين انفنيتي ش.ذ.م.م
P.O. Box: 62522
DUBAI - U.A.E.
DESIGN INFINITY L.L.C

QUOTATION

DATE: **16 December 2024**
Quotation #: DC-131224-001-ID-R1

PROJECT : Auriga Capital

SCOPE OF WORK : SUPPLY AND INSTALLATION OF FURNITURE

(OPTION - 1)

SI NO.	DESCRIPTION	VISUAL PRESENTATION	QTY	UNIT	UNI RATE	Total PRICE
20	Task Chair 1.Material: mesh back&fabric seat 2.*Synchronized-tilting system with lock, lockable at 4 different positions *Sliding seat *Lumber support *Armrest with 4 D.O.F. (Degree Of Freedom) Adjustment 3.Height adjustable 4.Nylon base 5.White frame FInish: Back mesh : grey ,or black Dim: 670*590*980-1075 Origin: FarEast Delivery: 11-12 Weeks Warranty: 5 Years (Against Manufacturing Defects)	 	32	EA	1,073.00	34,336.00
	Phone booth					
21	Phone booth (1pax) - Frame:6063 aviation aluminnum alloy Glass: 10mm ultra white tempered glass , 4+4 laminated door glass Wall: 6063 aviation aluminnum alloy +1.0mm steel surface/Gabriel upholstery + acoustic package + 13mm polyester panel + G350 noise-reducing fabric Roof: 6063 aviation aluminnum alloy + 1.0mm steel surface + acoustic package + polyester panel + G350 ; noise-reducingfabric Bottom plate: E0 level 25+9mm solid wood plywood + black PVC edge banding + steel frame +25mm adjusting feet + polyester carpet Metal frame in powder coating finish Including 1pcs of melamine tabletop Power Configuration: 1 power track（1 AC;1 wireless charging ;AC 220V Ventilation: 1.68m³/min, 59.3CFM, air chang rate 50/h ; Noise reduction: DS,A 28.5 dB Bar chair included Dim: Overall W1070*D1070*H2280 Inner: W900*D900 (1030 is glass to glass)*H2130 Origin: FarEast Delivery: 10 weeks; Warranty : Five (5) years (Against Manufacturing Defects	 	3	EA	22,043.00	66,129.00
	Meeting Room					

ديزاين انفنيتي ش.ذ.م.م
P.O. Box: 62522
DUBAI - U.A.E.
DESIGN INFINITY L.L.C

QUOTATION

DATE: **16 December 2024**
Quotation #: DC-131224-001-ID-R1

PROJECT : Auriga Capital

SCOPE OF WORK : SUPPLY AND INSTALLATION OF FURNITURE

(OPTION - 1)

SI NO.	DESCRIPTION	VISUAL PRESENTATION	QTY	UNIT	UNI RATE	Total PRICE
22	Meeting table - 8 pax (2 nos) + 9 pax Melamine tabletop with 4 sides knife edge Powder coated steel leg Flip-up and cable tray included **Note: PDU/Electrification not included; quoted separetly** Dim: 3200*1200*750 Origin: FarEast Delivery: 11-12 Weeks Warranty: 5 Years (Against Manufacturing Defects)		2	EA	4,833.00	9,666.00
23	Meeting table - 8 pax (2 nos) + 9 pax Melamine tabletop with 4 sides knife edge Powder coated steel leg Flip-up and cable tray included **Note: PDU/Electrification not included; quoted separetly** Dim: 2400*1200*750 Origin: FarEast Delivery: 11-12 Weeks Warranty: 5 Years (Against Manufacturing Defects)		1	EA	3,540.00	3,540.00
24	PDU for Meeting tables Rotary (black) Black Aluminum Profile **Manual Rotation Opening and Closing (not motorised)** 4 x UK power sockets , 230V 2 x Data Cat6A RJ 45 with 3 meter data cable 2 x HDMI module with cable 1 x USB 3.0 with cable (Type A) - for Data transferring 1 x Twin USB (Type A+C) charging 3 meter power cable with UK plug Delivery: 10 weeks Warranty : Five (5) years (Against Manufacturing Defects	 	5	EA	1,372.00	6,860.00
25	Meeting chair 1.High quality PU leather back& seat 2.Fixed aluminium armrest 3.Tilting system with lock 4.Aluminium leg 5.Height adjustable Dim: 580*620*860-970 Origin: FarEast Delivery: 10 weeks Warranty : Five (5) years (Against Manufacturing Defects		23	EA	1,360.00	31,280.00

ديزاين انفنيتي ش.ذ.م.م
P.O. Box: 62522
DUBAI - U.A.E.
DESIGN INFINITY L.L.C

Design Infinity *Beyond Imagination ...*

QUOTATION

DATE: **16 December 2024**
Quotation #: DC-131224-001-ID-R1

PROJECT : Auriga Capital

SCOPE OF WORK : SUPPLY AND INSTALLATION OF FURNITURE

(OPTION - 1)

SI NO.	DESCRIPTION	VISUAL PRESENTATION	QTY	UNIT	UNI RATE	Total PRICE
25A Optional	Meeting chair 1.High quality PU leather back& seat 2.Soft PU leather armrest 3.Synchronized-tilting system with lock lockable at 4 different positions 4. Aluminium leg Dim: 560*580*800 Origin: FarEast Delivery: 10 weeks Warranty : Five (5) years (Against Manufacturing Defects			EA	1,360.00	Rate Only
25B Optional	Meeting chair 1.High quality PU leather back& seat 2.Fixed aluminium armrest with soft PU pad 3.Synchronized-tilting mechanism, lockable at 4 different positions 4.Height adjustable 5. Aluminium leg Dim: 630*640*950 Origin: FarEast Delivery: 10 weeks Warranty : Five (5) years (Against Manufacturing Defects			EA	1,334.00	Rate Only
					TOTAL AMOUNT AED:	**269,130.00**

VAT @ 5% (AED) 13,456.50

TERMS AND CONDITIONS

VAT: VAT @ 5% applicable as per FTA UAE.

Payment : 50% advance along with order confirmation, 40% on material delivery to site and 10% on installation.
Delivery and completion payments to be released within 15 days from the date of invoice submission.

Delivery: As mentioned against each line items weeks from the date of order, finishes approval, and receipt of advance payment (excluding seasonal holidays at the origin.),Subject to availability at the time of order.

Validity : 30 Days

General Note : All prices are net based on the total quantity as per above quotation. If the quantity is reduced the price is liable to vary and need to reconfirm by Design Infinity LLC, prior to finalizing the order. Item/s not mention and item/s quantity not included in the above quotation will be additional.
Material and Upholstery finishes as per Manufacturer's standard selection/ range.
Desk (Desk, Meeting Table and workstation) level electric sockets/ modules are not included in the quotation.
Force Majeure: Our agreed delivery terms are valid under normal circumstances. Design Infinity LLC will not be held responsible for any delays caused by situations beyond our control or any Acts of God, that would prevent us or our manufacturing and shipping partners to deliver and install any or all the products being the subject of the agreement between us. Should such circumstances arise we will inform you at the earliest opportunity to agree alternative arrangements.

ديزاين انفنيتي ش.ذ.م.م
P.O. Box: 62522
DUBAI - U.A.E.
DESIGN INFINITY L.L.C

Design Infinity

ANX-01
BILL OF QUANTITIES
LOOSE FURNITURE (OPTION-02)

AURIGA CAPITAL

QUOTATION

DATE: **16 December 2024**
Quotation #: DC-131224-001-ID-R1

PROJECT : Auriga Capital

SCOPE OF WORK : SUPPLY AND INSTALLATION OF FURNITURE

OPTION - 2 (WITH SIT-STAND DESKING)

SI NO.	DESCRIPTION	VISUAL PRESENTATION	QTY	UNIT	UNI RATE	Total PRICE
	Executive Lounge					
1	Sofa - customized Fabric/PU upholstered, powder coated steel leg including 2 Nos throw pillow Dim: 2200*820*680 (as per final shop drawings) Origin: FarEast Delivery: 11-12 Weeks Warranty: 5 Years (Against Manufacturing Defects)	 Concept image	1	EA	4,552.00	4,552.00
2	Coffee table Wood veneer top with wood veneer base Dim: 1200*600*380 (as per final shop drawings) Origin: FarEast Delivery: 11-12 Weeks Warranty: 5 Years (Against Manufacturing Defects)	 Concept image	1	EA	1,878.00	1,878.00
3	Coffee table Veneer top and base Dim: D520*500 Origin: FarEast Delivery: 11-12 Weeks Warranty: 5 Years (Against Manufacturing Defects)		2	EA	1,441.00	2,882.00
4	Pouf Fabric/PU upholstered Dim: 500*500*420 Origin: FarEast Delivery: 11-12 Weeks Warranty: 5 Years (Against Manufacturing Defects)		2	EA	697.00	1,394.00
5	Arm chair - customized Fabric upholstered, solid wood leg Dim: 790*760*840 (as per final shop drawings) Origin: FarEast Delivery: 11-12 Weeks Warranty: 5 Years (Against Manufacturing Defects)		2	EA	2,189.00	4,378.00

دي زاين انفنيتي ش.ذ.م.م
P.O. Box: 62522
DUBAI - U.A.E.
DESIGN INFINITY L.L.C

QUOTATION

DATE: **16 December 2024**
Quotation #: DC-131224-001-ID-R1

PROJECT : Auriga Capital

SCOPE OF WORK : SUPPLY AND INSTALLATION OF FURNITURE

OPTION - 2 (WITH SIT-STAND DESKING)

SI NO.	DESCRIPTION	VISUAL PRESENTATION	QTY	UNIT	UNI RATE	Total PRICE
	Reception / Waiting area					
	Desk	PART OF JOINERY				
6	Task Chair 1.Material: mesh back&fabric seat 2.*Synchronized-tilting system with lock, lockable at 4 different positions *Sliding seat *Lumber support *Armrest with 4 D.O.F. (Degree Of Freedom) Adjustment 3.Height adjustable 4.Nylon base 5.White frame FInish: Back mesh : grey ,or black Seat mesh : dark grey ,or light grey Dim: 670*590*980-1075 Origin: FarEast Delivery: 11-12 Weeks Warranty: 5 Years (Against Manufacturing Defects)		3	EA	1,073.00	3,219.00
7	Sofa Fabric/PU upholstered, powder coated steel leg Dim: 1800*820*680 Origin: FarEast Delivery: 11-12 Weeks Warranty: 5 Years (Against Manufacturing Defects)		1	EA	2,960.00	2,960.00
8	Coffee table MDF painted or wood veneer top with knife edge, powder coated steel leg Dim: D600*310 Origin: FarEast Delivery: 11-12 Weeks Warranty: 5 Years (Against Manufacturing Defects)		3	EA	1,223.00	3,669.00

ديزاين انفنيتي ش.ذ.م.م
P.O. Box: 62522
DUBAI - U.A.E.
DESIGN INFINITY L.L.C

QUOTATION

DATE: **16 December 2024**
Quotation #: DC-131224-001-ID-R1

PROJECT : Auriga Capital

SCOPE OF WORK : SUPPLY AND INSTALLATION OF FURNITURE

OPTION - 2 (WITH SIT-STAND DESKING)

SI NO.	DESCRIPTION	VISUAL PRESENTATION	QTY	UNIT	UNI RATE	Total PRICE
9	Arm chair Fabric/PU leather upholstered, solid wooden leg Dim: 830*690*700 Origin: FarEast Delivery: 11-12 Weeks Warranty: 5 Years (Against Manufacturing Defects)		6	EA	2,209.00	13,254.00
	Cabin's					
10	Desk ht adjustable with side storage 1.Table top material: thickness:18mm core material:E1 particle board from FSC certified factory decor paper:Schattdecor from Germany PVC edge 2.Electrical height adjustable frame 3.Timotion Dual motor, Weight capacity:120KG Electrical control, 2 tubes height range 710-1170mm 4.Flip-up in table top and cable tray under table top for wire management 5.side cabinet with 2drawers +1 swing door+open front malemine Modesty panel Included **No Mobile pedestal** **Note : No PDU / electrification included.** Dim: 160*70*660-1310mm+ W100*D450 side privacy panel :700*600H Origin : FarEast Delivery : 11-12 weeks Warranty : 5 Years (Against Manufacturing Defects)		4	EA	3,847.00	15,388.00

ديزاين انفنيتي ش.ذ.م.م
P.O. Box: 62522
DUBAI - U.A.E.
DESIGN INFINITY L.L.C

QUOTATION

DATE: **16 December 2024**
Quotation #: DC-131224-001-ID-R1

PROJECT : Auriga Capital

SCOPE OF WORK : SUPPLY AND INSTALLATION OF FURNITURE

OPTION - 2 (WITH SIT-STAND DESKING)

SI NO.	DESCRIPTION	VISUAL PRESENTATION	QTY	UNIT	UNI RATE	Total PRICE
11	Chair 1.Material:mesh back&fabric seat, with adjustable headrest 2.*Synchronized-tilting system with lock, lockable at 4 different positions *Sliding seat *Lumber support *Armrest with 4 D.O.F. (Degree Of Freedom) Adjustment 3.Height adjustable 4.Nylon base 5.White frame Finish: Back mesh : grey ,or black Seat mesh : dark grey ,or light grey Dim: 670*590*1155-1250 Origin: FarEast Delivery: 11-12 Weeks Warranty: 5 Years (Against Manufacturing Defects)	 	4	EA	1,145.00	4,580.00
12	Visitor Chair fabric / PU leather upholstered chair body , aluminum alloy base with castors Dim: 610*580*890 Origin: FarEast Delivery: 11-12 Weeks Warranty: 5 Years (Against Manufacturing Defects)		8	EA	1,210.00	9,680.00
13	PDU with Flipbox Single (Black) Black Aluminum Faceplate, Alloy Aluminum inside plate Black Iron housing profile; Finish: Black / Brush: Black Manual Frame Opening - Single 2 x Universal Type Power Socket 2 x Data Cat6 RJ45 with 3m cable 3 meter power cable with UK plug Delivery: 10 weeks Warranty : Five (5) years (Against Manufacturing Defects	 	4	EA	900.00	RATE ONLY

ديزاين انفنيتي ش.ذ.م.م
P.O. Box: 62522
DUBAI - U.A.E.
DESIGN INFINITY L.L.C

QUOTATION

DATE: **16 December 2024**
Quotation #: DC-131224-001-ID-R1

PROJECT : Auriga Capital

SCOPE OF WORK : SUPPLY AND INSTALLATION OF FURNITURE

OPTION - 2 (WITH SIT-STAND DESKING)

SI NO.	DESCRIPTION	VISUAL PRESENTATION	QTY	UNIT	UNI RATE	Total PRICE
	Open Workstation					
14	HEIGHT ADJUSTABLE TABLE - FACE TO FACE 2 PAX 1.Table top material: thickness:25mm core material:E1 particle board from FSC certified factory decor paper:Schattdecor from Germany PVC edge 2.Electrical height adjustable frame 3.Timotion Dual motor, Weight capacity:120KG Electrical control, 2 tubes height range 710-1170mm 4.Flip-up and cable tray included 5.Fabric screen includes Screen height is 680MM,length is same as desk including metal board in side leg for wire through -Without Modesty panel -Without mobile pedestal -Electric PDU not included Dim: 1200*1400*750 Origin: FarEast Delivery: 11-12 Weeks Warranty: 5 Years (Against Manufacturing Defects)		11	EA	5,003.00	55,033.00
15	Single height adjustable desk 1.Table top material: thickness:25mm core material:E1 particle board from FSC certified factory decor paper:Schattdecor from Germany PVC edge 2.Electrical height adjustable frame 3.Timotion Dual motor, Weight capacity:120KG Electrical control, 2 tubes height range 710-1170mm 4.Flip-up and cable tray included including snake spine -Fabric screen with acoustic panel inside Including steel screen holder -Without Modesty panel -Without mobile pedestal -Electric PDU not included Dim: 1200*700*750H Origin: FarEast Delivery: 11-12 Weeks Warranty: 5 Years (Against Manufacturing Defects)	 	10	EA	2,648.00	26,480.00

ديزاين انفنيتي ش.ذ.م.م
P.O. Box: 62522
DUBAI - U.A.E.
DESIGN INFINITY L.L.C

QUOTATION

DATE: **16 December 2024**
Quotation #: DC-131224-001-ID-R1

PROJECT : Auriga Capital

SCOPE OF WORK : SUPPLY AND INSTALLATION OF FURNITURE

OPTION - 2 (WITH SIT-STAND DESKING)

SI NO.	DESCRIPTION	VISUAL PRESENTATION	QTY	UNIT	UNI RATE	Total PRICE
16	Mobile pedestal Super fine cold rolled steel plate, 0.8mm thickness, 10 times anti-rust treatment, automatic powder coating, three full-extension drawers, with lock 30cm wide with seat cushion on top Dim: 300×500×640 cushion : 300*500*40 Origin: FarEast Delivery: 11-12 Weeks Warranty: 5 Years (Against Manufacturing Defects)	 	32	EA	579.00	18,528.00
	Cabinet with planter box	PART OF JOINERY				-
17	PDU for workstation Silver Aluminum Profile 1.5U with holding angles 2 x UK Power Sockets - 3 Pin BS, 230V 1 x Data Cat6A RJ 45 with 3 meter data cable 1 x USB 2.0 with cable (Type A)- for Data transferring 1 x Twin USB (Type A+C) fast charging (30W) On/Off Power Switch 1 x 3 meter starter lead, female GST18i to UK Plug BS1363,13A fused (Wieland type connector) Delivery: 10 weeks Warranty : Five (5) years (Against Manufacturing Defects			EA	429.00	RATE ONLY
18	Task Chair 1.Material: mesh back&fabric seat 2.*Synchronized-tilting system with lock, lockable at 4 different positions *Sliding seat *Lumber support *Armrest with 4 D.O.F. (Degree Of Freedom) Adjustment 3.Height adjustable 4.Nylon base 5.White frame FInish: Back mesh : grey ,or black Seat mesh : dark grey ,or light grey Dim: 670*590*980-1075 Origin: FarEast Delivery: 11-12 Weeks Warranty: 5 Years (Against Manufacturing Defects)	 	32	EA	1,073.00	34,336.00

ديزاين انفنيتي ش.ذ.م.م
P.O. Box: 62522
DUBAI - U.A.E.
DESIGN INFINITY L.L.C

QUOTATION

DATE: **16 December 2024**
Quotation #: DC-131224-001-ID-R1

PROJECT : Auriga Capital

SCOPE OF WORK : SUPPLY AND INSTALLATION OF FURNITURE

OPTION - 2 (WITH SIT-STAND DESKING)

SI NO.	DESCRIPTION	VISUAL PRESENTATION	QTY	UNIT	UNI RATE	Total PRICE
	Phone booth					
19	Phone booth (1pax) - Frame:6063 aviation aluminnum alloy Glass: 10mm ultra white tempered glass , 4+4 laminated door glass Wall: 6063 aviation aluminnum alloy +1.0mm steel surface/Gabriel upholstery + acoustic package + 13mm polyester panel + G350 noise-reducing fabric Roof: 6063 aviation aluminnum alloy + 1.0mm steel surface + acoustic package + polyester panel + G350 ; noise-reducingfabric Bottom plate: E0 level 25+9mm solid wood plywood + black PVC edge banding + steel frame +25mm adjusting feet + polyester carpet Metal frame in powder coating finish Including 1pcs of melamine tabletop Power Configuration: 1 power track（1 AC;1 wireless charging ;AC 220V Ventilation: 1.68m³/min, 59.3CFM, air chang rate 50/h ; Noise reduction: DS,A 28.5 dB Bar chair included Dim: Overall W1070*D1070*H2280 Inner: W900*D900 (1030 is glass to glass)*H2130 Origin: FarEast Delivery: 10 weeks; Warranty : Five (5) years (Against Manufacturing Defects	 	3	EA	22,043.00	66,129.00
	Meeting Room					
20	Meeting table - 8 pax (2 nos) + 9 pax Melamine tabletop with 4 sides knife edge Powder coated steel leg Flip-up and cable tray included **Note: PDU/Electrification not included; quoted separetly** Dim: 3200*1200*750 Origin: FarEast Delivery: 11-12 Weeks Warranty: 5 Years (Against Manufacturing Defects)		2	EA	4,833.00	9,666.00
21	Meeting table - 8 pax (2 nos) + 9 pax Melamine tabletop with 4 sides knife edge Powder coated steel leg Flip-up and cable tray included **Note: PDU/Electrification not included; quoted separetly** Dim: 2400*1200*750 Origin: FarEast Delivery: 11-12 Weeks Warranty: 5 Years (Against Manufacturing Defects)		1	EA	3,540.00	3,540.00

ديزاين انفينيتي ش.ذ.م.م
P.O. Box: 62522
DUBAI - U.A.E.
DESIGN INFINITY L.L.C

QUOTATION

DATE: **16 December 2024**
Quotation #: DC-131224-001-ID-R1

PROJECT : Auriga Capital

SCOPE OF WORK : SUPPLY AND INSTALLATION OF FURNITURE

OPTION - 2 (WITH SIT-STAND DESKING)

SI NO.	DESCRIPTION	VISUAL PRESENTATION	QTY	UNIT	UNI RATE	Total PRICE
22	PDU for Meeting tables Rotary (black) Black Aluminum Profile **Manual Rotation Opening and Closing** 4 x UK power sockets , 230V 2 x Data Cat6A RJ 45 with 3 meter data cable 2 x HDMI module with cable 1 x USB 3.0 with cable (Type A) - for Data transferring 1 x Twin USB (Type A+C) charging 3 meter power cable with UK plug Delivery: 10 weeks Warranty : Five (5) years (Against Manufacturing Defects	 	5	EA	1,372.00	6,860.00
23	Meeting chair 1.High quality PU leather back& seat 2.Fixed aluminium armrest 3.Tilting system with lock 4.Aluminium leg 5.Height adjustable Dim: 580*620*860-970 Origin: FarEast Delivery: 10 weeks Warranty : Five (5) years (Against Manufacturing Defects		23	EA	1,360.00	31,280.00
24A Optional	Meeting chair 1.High quality PU leather back& seat 2.Soft PU leather armrest 3.Synchronized-tilting system with lock lockable at 4 different positions 4. Aluminium leg Dim: 560*580*800 Origin: FarEast Delivery: 10 weeks Warranty : Five (5) years (Against Manufacturing Defects			EA	1,360.00	Rate Only

ديزاين انفنيتي ش.ذ.م.م
P.O. Box: 62522
DUBAI - U.A.E.
DESIGN INFINITY L.L.C

Design Infinity *Beyond Imagination ...*

QUOTATION

DATE: **16 December 2024**
Quotation #: DC-131224-001-ID-R1

PROJECT : Auriga Capital

SCOPE OF WORK : SUPPLY AND INSTALLATION OF FURNITURE

OPTION - 2 (WITH SIT-STAND DESKING)

SI NO.	DESCRIPTION	VISUAL PRESENTATION	QTY	UNIT	UNI RATE	Total PRICE
24B Optional	Meeting chair 1.High quality PU leather back& seat 2.Fixed aluminium armrest with soft PU pad 3.Synchronized-tilting mechanism, lockable at 4 different positions 4.Height adjustable 5. Aluminium leg Dim: 630*640*950 Origin: FarEast Delivery: 10 weeks Warranty : Five (5) years (Against Manufacturing Defects			EA	1,334.00	Rate Only
					TOTAL AMOUNT AED:	**319,686.00**

VAT @ 5% (AED) 15,984.30

TERMS AND CONDITIONS

VAT: VAT @ 5% applicable as per FTA UAE.

Payment : 50% advance along with order confirmation, 40% on material delivery to site and 10% on installation.
Delivery and completion payments to be released within 15 days from the date of invoice submission.

Delivery: As mentioned against each line items weeks from the date of order, finishes approval, and receipt of advance payment (excluding seasonal holidays at the origin.),Subject to availability at the time of order.

Validity : 30 Days

General Note : All prices are net based on the total quantity as per above quotation. If the quantity is reduced the price is liable to vary and need to reconfirm by Design Infinity LLC, prior to finalizing the order. Item/s not mention and item/s quantity not included in the above quotation will be additional.
Material and Upholstery finishes as per Manufacturer's standard selection/ range.
Desk (Desk, Meeting Table and workstation) level electric sockets/ modules are not included in the quotation.
Force Majeure: Our agreed delivery terms are valid under normal circumstances. Design Infinity LLC will not be held responsible for any delays caused by situations beyond our control or any Acts of God, that would prevent us or our manufacturing and shipping partners to deliver and install any or all the products being the subject of the agreement between us. Should such circumstances arise we will inform you at the earliest opportunity to agree alternative arrangements.

ديزاين انفنيتي ش.ذ.م.م
P.O. Box: 62522
DUBAI - U.A.E.
DESIGN INFINITY L.L.C

CONTACT PERSON

Design Infinity

GEETHA NAYAK
MANAGING PARTNER

CONTACT DETAILS:

T: 971 43795902

M: 971 50 146 7608

E: geetha@design-infinity.com

DUBAI (HEAD OFFICE) ADDRESS:
UNIT 201-203, 212-213 & 301-303
HAMSAH BUILDING, O-BLOCK
PO BOX 62522, AL KARAMA
DUBAI, UNITED ARAB EMIRATES
T: 04 379 5902

DUBAI BRANCH – OFFICE & WAREHOUSE
JOINERY, GLASS & METAL DIVISION
DUBAI INVESTMENT PARK 2
PLOT NUMBER: 597-813
TEL: 971 4 321 6946

ABU DHABI OFFICE
OFFICE NO. M1, P/181 BUILDING
PO BOX 62560, AL MUROOR
ABU DHABI, UNITED ARAB EMIRATES
T: 02 448 2286

WWW.DESIGN-INFINITY.COM