verve

space + design

Hamptons

INTERNATIONAL

PROPOSAL FOR INTERIOR FITOUT WORKS

INTERIOR FIT-OUT WORKS

FOR

AT

PARK HEIGHTS SQUARE 1 , LEVEL 1, DUBAI HILLS

For
HAMPTONS INTERNATIONAL

Prepared by:
Gayathri Gopi
Verve Interior Decoration LLC
PO Box 128279, Dubai, UAE
Email: gayathri@vervedesign.ae

Prepared on:

February 6, 2025

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

CONTRACT AGREEMENT: General terms and conditions

Project Timeline: As per approved Project schedule

Payment Terms:

Advance Payment : 30% Advance payment against order confirmation.
Progress Payment : 20% upon approval of all the material samples and mobilization of materials to the site
Progress Payment : 45% as per site progress
Final Payment : 5% upon work completion at site and hand over.

Payment to be honored within 7 days from the date of receipt of Invoice

All products offered by us on this project carry a warranty against defective materials and/or workmanship as follows:
Fit Out Works : 12 Months from the date of Handover.

Insurances:
All our personnel working on the project will be covered under our Workmen Compensation
All works carried out at site will be covered by our Contractor's All Risk Policy

Validity.
Our offer is valid for a period of 30 days from hereof
Note: Bank guarantee / Retention / Liquidated damages excluded

Please sign below for acceptance of the offer. The BOQ will be treated as the final scope of work and contract will form the integral part of the project.

Signature: _____
on behalf of: HAMPTONS

Name:
Date:

Signature:_____
on behalf of : Verve Interior Decoration LLC

Name: Syed Mehdi
Date: February 6, 2025

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR HAMPTONS INTERNATIONAL CORPORATE OFFICE @ PARK HEIGHTS SQUARE 1 , DUBAI - UAE		
Quote Ref No: VID/1002/25/CP/QTN_01/R1		06-Feb-25
SR. NO	SUMMARY	TOTAL (AED)
1	PRELIMINARIES	55,600.00
2	DEMOLITION AND CIVIL WORKS	6,900.00
3	PARTITION WORKS	118,300.00
4	FLOOR FINISH	405,340.00
5	WALL FINISH	127,419.00
6	CEILING FINISH	302,092.00
7	DOORS	122,920.00
8	SIGNAGE WORKS - Provisional Sum	14,300.00
9	JOINERY WORKS	398,602.00
10	LIGHTING WORKS	199,007.00
11	SANITARY FITTINGS	1,935.00
12	HVAC WORKS	197,194.00
13	ELECTRICAL WORKS	253,001.00
14	CIVIL DEFENCE WORKS	196,100.00
15	PLUMBING WORKS	8,036.00
	TOTAL AMOUNT (AED):	2,406,746.00
16	LOOSE FURNITURE	379,923.00
	GRAND TOTAL AMOUNT (AED):	2,786,669.00

Note: **Any variation in terms of quantity that comes up during the course of work has to be paid by the client and hence client is liable for payment of Variation. Retention is not considered.**

Exclusions:

1) All fees and deposit for statutory authorities.
2) Any other items not mentioned in the attached BOQ.

For Verve Interior Decoration LLC
Syed Mehdi
Sales Director
+971 50 513 9878
syed@vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR HAMPTONS INTERNATIONAL CORPORATE OFFICE @ PARK HEIGHTS SQUARE 1 , DUBAI - UAE

Quote Ref No: VID/1002/25/CP/QTN_01/R1 **06-Feb-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
1.00	**PRELIMINARIES**				
1.01	General- Contractor's preliminaries for mobilization, site preparation, Provision for all temporary barricades, setting out transportations to/from site, material deliveries, small tools and equipment's, protection of finished products in on-going site, site attendance and call out attendance, electricity & water charges including charges for scaffolding. PPE and other site requirements to be followed	1	Item	5,000.00	5,000.00
1.02	Co ordination Charges for obtaining approvals from the Landlord & the related authorities.	1	Item	2,100.00	2,100.00
1.03	Preparation of Technical drawings as required for submission to Relevant authorities. Detail drawings includes Architectural and MEP drawings. Subject to receipt of current approved as built drawings	1	Item	19,100.00	19,100.00
1.04	CAR Insurance for fit out work during the execution of works. (includes third party liability) *Note: Insurance coverage is limited to CAR of Contract Value. If higher coverage limit is required by building management and any other authorities, the additional premium amount will be charged separately* .	1	Item	3,100.00	3,100.00
1.05	Professional indemnity insurance	1	Item	11,500.00	11,500.00
1.06	Regular cleaning of site during construction period and after completion professional deep cleaning and made ready to occupy. Including carting away the debris to Municipal dumping area.	1	Item	8,300.00	8,300.00
1.07	Charges for site protection (protection of common area finishes and the area near to the work space)	1	Item	3,500.00	3,500.00
1.08	Fit-out consultants fees for full fit out - AED 3.00 per Sqft	1	Item	26,600.00	By client
1.09	Draining/Recharging of Fire Fighting system	1	Item	1,500.00	1,500.00
1.10	Disabling/Enabling of Fire Fighting system	1	Item	1,500.00	1,500.00
1.11	Design review fee - AED 3.5 per Sqft	1	Item	31,070.00	On actual
	Note: Security deposit, Authority Fees, entry and exit pass for vehicles and labors, night work permit fee, Mall management fees(If required) has to be paid by the client on actuals				
	Note : Provision for mock up and samples submissions at site as per requirement included, however special items are chargeable and shall be billed to the client on actual.				
				SUB TOTAL PRELIMINARIES :	**55,600.00**
2.00	**DEMOLITION AND CIVIL WORKS**				
2.01	Demolition of the existing walls to make the door opening, closing of the existing door opening, removal of existing door as per site condition including carting away to DM approved yard.	1	Item	6,900.00	6,900.00
2.02	Builders works to accommodate MEP works - Wall chasing				
				SUB TOTAL DEMOLITION AND CIVIL WORKS :	**6,900.00**
3.00	**PARTITION WORKS**				
3.01	**GYPSUM PARTITION SINGLE LAYER (NON FR)** Supply and installation of **Non-FR gypsum board partition** with 12.5mm Thk Non-FR gypsum board (Knauf or equivalent) single layer on both sides with studs, 50 mm thick rockwool insulation and necessary frames and accessories. Height up to 3.9 m **Location : As per layout**				

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR HAMPTONS INTERNATIONAL CORPORATE OFFICE @ PARK HEIGHTS SQUARE 1 , DUBAI - UAE

Quote Ref No: VID/1002/25/CP/QTN_01/R1 **06-Feb-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
a	100 mm thick	170	Sq.m	120.00	20,400.00
b	200 mm thick	95	Sq.m	135.00	12,825.00
3.02	**GYPSUM PARTITION SINGLE LAYER (FR 60 min)** Supply and installation of **100 mm Thk FR gypsum board partition** with 12.5mm Thk FR gypsum board (Knauf or equivalent) single layer on both sides with studs, 50 mm thick rockwool insulation and necessary frames and accessories. Height up to 3.9 m **Location : Server room**	45	Sq.m	250.00	11,250.00
3.03	**CEMENT BOARD PARTITION** Supply and installation of **100 mm Thk Cement board partition** with cement board (Ecopro or equivalent) single layer on both sides with studs, necessary frames and accessories. Height up to 3.9 m **Location : Coffee bar**	18	Sq.m	200.00	3,600.00
3.04	**GYPSUM CLADDING - FR 60 min** Supply and installation of **FR 12.5 mm thick Gypsum board (Knauf or equivalent) wall cladding** with necessary material for fixing, smoothened and made ready to receive final finishes. Height up to 2.8 m **Location : To existing walls and columns**	240	Sq.m	110.00	26,400.00
3.05	Supply and installation GRC cladding at curved edges	1	Item	6,000.00	6,000.00
3.06	**CEMENT BOARD CLADDING** Supply and installation of **Cement board wall cladding** with necessary material for fixing, smoothened and made ready to receive final finishes. Height up to 2.8 m **Location : To existing walls at coffee bar area**	22	Sq.m	160.00	3,520.00
3.07	**GLASS PARTITION - NON FR** Supply and installation of **single glazed 50 x 50 mm powder coated aluminum framed single layered partition (around the partitions)** utilizing 12 mm thick glass with all around straight polished edges including glass to glass clear joints. Height up to 2.5 m **Location : All glass partitions inside the unit**				
a	Height up to 2.6 m **Location : Phone booths**	4	Sq.m	555.00	2,220.00
b	Height up to 2.6 m **Location : Meeting rooms, corridor**	42	Sq.m	555.00	23,310.00
c	Height up to 2.8 m **Location : Meeting at the main entrance**	2	Sq.m	555.00	1,110.00
3.08	**GYPSUM BAFFLE (NON-FR)** Supply and installation of **Non-FR gypsum baffle wall** with 12.5mm Thk Non-FR gypsum board (Knauf or equivalent) single layer on both sides with 50mm thick rockwool insulation, necessary frames and accessories . Height up to 1.1 m **Location : Above proposed glass partitions**	30	Sq.m	125.00	3,750.00
3.09	**Provision for MDF support below proposed glass partitions / raised floor**	27	LM	145.00	3,915.00
	Note : We have considered 60 min Fire Rated Gypsum cladding to existing walls and columns within the tenant space.				
				SUB TOTAL PARTITION WORKS :	**118,300.00**
4.00	**FLOOR FINISH**				

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai.UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR HAMPTONS INTERNATIONAL CORPORATE OFFICE @ PARK HEIGHTS SQUARE 1 , DUBAI - UAE

Quote Ref No: VID/1002/25/CP/QTN_01/R1 **06-Feb-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
4.01	**RAISED FLOOR** Supply and installation of **Raised access floor FS-800 cementitious** 600 x 600 x 33 mm steel top, steel bottom fully encapsulated bare finish panel with up to 15cm ffh flat pedestal & stringer **Make : AFT**	816	Sq.m	168.00	137,088.00
4.02	**ANTI STATIC RAISED FLOOR** Supply and installation of **Anti static raised floor (HPL) finish**, up to height of 200mm **Location : Server room**	8	Sq.m	449.00	3,592.00
4.03	**SELF LEVELLING ON RAISED FLOOR** Supply and installation of 2 to 3 mm self levelling compound to make the floor ready to receive the new flooring. **Location : Proposed LVT/ Tile flooring**	494	Sq.m	100.00	49,400.00
4.04	**CARPET FLOORING TYPE 1** Supply and installation of Carpet tile flooring including adhesives and all necessary material for fixing. Make : Solar **Location : Phone booth, seating lounge, storage room, server room, workstation** Note : To be installed directly on the raised floor	235	Sq.m	105.00	24,675.00
4.05	**CARPET FLOORING TYPE 2** Supply and installation of Carpet tile flooring including adhesives and all necessary material for fixing. Make : Tegola/ Belgotex **Location : Meeting rooms** Note : To be installed directly on the raised floor	82	Sq.m	120.00	9,840.00
4.06	**LVT FLOORING** Supply and installation of **Luxury Vinyl Tile - cement look flooring** with necessary material for installation. Make : Taiga **Location : Corridor, waiting area**	70	Sq.m	130.00	9,100.00
4.07	**LVT FLOORING** Supply and installation of **Luxury Vinyl Tile - wood look flooring (Chevron pattern)** with necessary material for installation. **Location : Coffee bar**	73	Sq.m	210.00	15,330.00
4.08	**CERAMIC TILE FLOORING - TYPE 2** Supply and installation of **Ceramic Tile flooring** with grouting including cutting and alignment. As per design and approved sample. Size : 100 x 100 cm PC Rate : 190 AED per Sq.m **Location : Display area**	355	Sq.m	367.00	130,285.00
4.09	**TRANSITION STRIP** Supply and installation of Transition Strip in SS finish (ready available). **Location : Between different floor finishes, Door entrances.**	129	LM	120.00	15,480.00
4.10	**STONE THRESHOLD** Supply and installation of Stone Threshold Size : L3000 x W495 mm **Location : Main Entrance**	1	Item	1,920.00	1,920.00

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR HAMPTONS INTERNATIONAL CORPORATE OFFICE @ PARK HEIGHTS SQUARE 1 , DUBAI - UAE					
Quote Ref No: VID/1002/25/CP/QTN_01/R1					06-Feb-25
SR.NO	**DESCRIPTION**	**QTY**	**UNIT**	**UNIT RATE**	**TOTAL (AED)**
4.11	**STONE THRESHOLD** Supply and installation of Stone Threshold Size : L900 x W275 mm **Location : Entrances**	3	Item	1,510.00	4,530.00
4.12	**WATER PROOFING** Supply and installation of **Cementitious water proofing** 2 coats including protection screed. Area considered : 40 Sqm **Location : Floor area and wall up to 1.2 m behind wash basin**	1	LS	4,100.00	4,100.00
	Note: All finishes are subject to final sample approval.				
				SUB TOTAL FLOOR FINISH :	**405,340.00**
5.00	**WALL FINISH**				
5.01	**WALL PAINT** Supply and application of **Jotun Fenomastic Paint Finish (white)** with all cleaning and levelling. Height up to 2.8 m	560	Sq.m	32.00	17,920.00
5.02	**TEXTURE PAINT** Supply and application of **Texture paint** Height up to 2.8 m **Location : Display area**	110	Sq.m	137.00	15,070.00
5.03	**FABRIC/ PET PANEL WALL CLADDING** Supply and installation of **fabric/ pet wall cladding** including necessary materials for installation. Height up to 2 m **Location : Phone booth** Note : considered for 2 walls in each booth	18	Sq.m	504.00	9,072.00
5.04	**MDF WALL CLADDING - TYPE 1** Supply and installation of **plain MDF wall cladding in wood veneer finish** including necessary fittings and accessories for installation. Height up to 2.8 mm	24	Sq.m	744.00	17,856.00
5.05	**MDF WALL CLADDING - TYPE 2** Supply and installation of **slatted MDF wall cladding in wood veneer finish** including necessary fittings and accessories for installation. Height up to 2.8 mm	15	Sq.m	1,075.00	16,125.00
5.06	**WALLPAPER** Supply and application of **wallpaper** including necessary surface preparation and materials for application. PC Rate : 55 AED per Sq.m Height up to 2.8 m **Location : Meeting room - 6 pax - near server room**	26	Sq.m	129.00	Rate only
5.07	**MIRROR CLADDING** Supply and installation of 6 mm thick plain silver mirror with straight polished edges fixing by silicone including MDF backing, without cut outs and holes. Height up to : 2.5 m Make : Guardian **Location : Display area**	15	Sq.m	504.00	7,560.00
5.08	**SKIRTING** Supply and installation of (up to 50 mm high) **MDF skirting in PU paint finish** with necessary fittings and accessories. **Note : Non concealed**	235	LM	58.00	13,630.00

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR HAMPTONS INTERNATIONAL CORPORATE OFFICE @ PARK HEIGHTS SQUARE 1 , DUBAI - UAE					
Quote Ref No: VID/1002/25/CP/QTN_01/R1					06-Feb-25
SR.NO	**DESCRIPTION**	**QTY**	**UNIT**	**UNIT RATE**	**TOTAL (AED)**
5.09	**ROLLER BLINDS - MANUAL** Supply and installation of **sunscreen blinds** Height up to 3.9 m **Location : External glazing**	351	Sq.m	86.00	30,186.00
	Note : 1. All finishes are subject to final sample approval. 2. Frosted sticker for glass partition and doors not considered.				
				SUB TOTAL WALL FINISH :	**127,419.00**
6.00	**CEILING FINISH**				
6.01	**PLAIN GYPSUM CEILING - FR** Supply and installation of **FR Gypsum Board Plain ceiling** (Knauf or equivalent) with necessary hanging systems including wall angle "C "channel, furring channel with 12.5mm gypsum boards joined taped smoothened finish.				
a	**Location : Display area**	438	Sq.m	129.00	56,502.00
b	**Location : Meeting room + corridor**	104	Sq.m	129.00	13,416.00
c	**Location : Workstation**	232	Sq.m	129.00	29,928.00
d	**Location : Seating lounge + Phone booths**	40	Sq.m	129.00	5,160.00
6.02	**PLAIN GYPSUM CEILING - FR** Supply and installation of **FR Gypsum Board Plain ceiling** (Knauf or equivalent) with necessary hanging systems including wall angle "C "channel, furring channel with 12.5mm gypsum boards joined taped smoothened finish. **Location : Server room**	8	Sq.m	129.00	1,032.00
6.03	**GYPSUM CEILING PAINT** Supply and application of **Jotun Fenomastic WHITE paint** including all cleaning and levelling. As per design and approved sample. (2 coats including sanding). **Location : Proposed Gypsum ceiling areas**	738	Sq.m	32.00	23,616.00
6.04	**TILE CEILING** Supply and installation of **60 X 60 cm Metal Tile ceiling** (Exposed system) including necessary fittings and accessories for installation. **Location : Storage room**	20	Sq.m	94.00	1,880.00
6.05	**STRETCH CEILING** Supply and installation of **stretch ceiling** including necessary materials for installation. Area considered : 54 Sq.m Make : Barrisol PVC translucent sheet Capella UMBIOT2 Note : Price includes Dimmable white LED lights	1	Item	87,400.00	Rate only
Option	**STRETCH CEILING** Supply and installation of **stretch ceiling** including necessary materials for installation. Area considered : 54 Sq.m Make : Euroceil Note : Price includes Dimmable white LED lights	1	Item	74,800.00	74,800.00

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR HAMPTONS INTERNATIONAL CORPORATE OFFICE @ PARK HEIGHTS SQUARE 1 , DUBAI - UAE					
Quote Ref No: VID/1002/25/CP/QTN_01/R1					06-Feb-25
SR.NO	**DESCRIPTION**	**QTY**	**UNIT**	**UNIT RATE**	**TOTAL (AED)**
6.06	**MIRROR CLADDING** Supply and installation of 6 mm thick plain silver mirror with straight polished edges fixing by silicone including MDF backing, without cut outs and holes. Height up to : 2.5 m Make : Guardian **Location : Seating lounge**	3	Sq.m	504.00	Rate only
6.07	**GYPSUM BULKHEAD - COVE LIGHT** Supply and installation of Gypsum Bulkhead up to 150 mm high for cove with 12.5 mm gypsum boards with paint finish.	136	LM	138.00	18,768.00
6.08	**GYPSUM BULKHEAD** Supply and installation of Gypsum Bulkhead 770 mm high with 12.5 mm gypsum boards with wood veneer finish. **Location : Around the bulkhead**	60	LM	826.00	49,560.00
6.09	**GYPSUM PELMET** Supply and installation of **Gypsum Pelmet** with necessary fittings with paint finish. Height up to 150 mm **Location : For blinds**	82	LM	145.00	11,890.00
6.10	**SHADOW GAP** Supply and installation of shadow gap as per the design.	260	LM	36.00	9,360.00
6.11	**GYPSUM ACCESS PANEL** Supply and installation of **Gypsum access panel (Max 60 x 60 cm)** with frame and hinges. **Location : Proposed Gypsum ceiling area** Note : Subject to final MEP drawings	20	Nos.	309.00	6,180.00
	Note : All finishes are subject to final sample approval.				
				SUB TOTAL CEILING FINISH :	**302,092.00**
7.00	**DOORS**				
7.01	**ACOUSTIC GLASS DOOR - NON FR** Supply and installation of 12 mm thick glass single leaf frameless glass doors with all around straight polished edges fixing by OFFSET pivot hinges , bottom lock and 1000 mm long H type straight round handle including all around 50 mm wide overlapped UNICA door frame. Note: All fittings are in powder coating or SS finish.				
a	Size: L 800 mm X H 2800 mm **Location : Meeting rooms 6 pax at entrance**	1	No.	5,360.00	5,360.00
b	Size: L 900 mm X H 2600 mm **Location : Meeting rooms, corridor**	5	Nos	5,360.00	26,800.00
c	Size: L 750 mm X H 2600 mm **Location : Meeting rooms, corridor**	4	Nos	4,560.00	18,240.00
7.02	**AUTOMATIC SLIDING GLASS DOOR** Supply and installation of 10 mm super-lite clear tempered fire rated (1 hour) Double leaf powder coated aluminium framed automatic glass sliding door with all around straight polish edges fixing by DT Prime drive 239 Automatic sliding door operator mechanism and bottom lock. Size : L3000 x H2800 mm **Location : Main Entrance - Display area**	1	No.	38,700.00	38,700.00

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai.UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR HAMPTONS INTERNATIONAL CORPORATE OFFICE @ PARK HEIGHTS SQUARE 1 , DUBAI - UAE

Quote Ref No: VID/1002/25/CP/QTN_01/R1 — **06-Feb-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
7.03	**DECORATIVE AUTOMATIC SLIDING GLASS DOOR** Supply and installation of 10 mm ribbed glass Double leaf powder coated aluminium framed automatic glass sliding door with all around straight polish edges fixing by DT Prime drive 239 Automatic sliding door operator mechanism and bottom lock. Size : L1400 x H2800 mm **Location : Entrance to office area from display area**	1	No.	45,410.00	Rate only
Option	**DECORATIVE MANUAL SLIDING GLASS DOOR** Supply and installation of 10 mm ribbed glass Double leaf powder coated aluminium framed manual glass sliding door with all around straight polish edges and bottom lock. Size : L1400 x H2800 mm **Location : Entrance to office area from display area**	1	No.	16,550.00	16,550.00
7.04	Provision to repaint the existing single leaf wooden entrance door (Only on the internal side), including the frames . Note : Subject to building management approval	3	Nos	1,240.00	3,720.00
7.05	**SINGLE LEAF WOODEN DOOR - FR 60 min** Supply and installation of Semi solid Timber swing door in veneer finish, with Frame, architrave, in PU paint finish with all necessary ironmongery and material for fixing. Size: 900 x 2600 mm Ht **Location : Server room**	1	No.	5,900.00	5,900.00
7.06	**DOUBLE LEAF WOODEN DOOR - Non FR** Supply and installation of Semi solid Timber swing door in veneer finish, with Frame, architrave, in PU paint finish with all necessary ironmongery and material for fixing. Size: 1700 x 2600 mm Ht **Location : Storage room**	1	No.	7,650.00	7,650.00
				SUB TOTAL DOORS :	**122,920.00**
8.00	**SIGNAGE WORKS - Provisional Sum**				
8.01	Supply and installation of aluminum 3D painted back lit signage as per the design. Size: L 2200 x H 600 mm **Location : Reception** Note : Subject to final design and sample approval.	1	Item	7,900.00	7,900.00
8.02	Supply and installation of aluminum 3D painted back lit signage as per the design. Size: L 1500 x H 400 mm **Location : Corridor** Note : Subject to final design and sample approval.	1	Item	6,400.00	6,400.00
	Note : 1. Any other signage excluded. 2. Size variation of +/- 10% considered.				
				SUB TOTAL SIGNAGE WORKS :	**14,300.00**
9.00	**JOINERY WORKS**				

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR HAMPTONS INTERNATIONAL CORPORATE OFFICE @ PARK HEIGHTS SQUARE 1 , DUBAI - UAE

Quote Ref No: VID/1002/25/CP/QTN_01/R1 — **06-Feb-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
9.01	**RECEPTION DESK** Fabrication, Supply and installation of Reception **counter with MDF in veneer/ PU paint finish** as per design with stone fascia (flutted) and white corian countertop. Fascia Stone PC Rate : 1385 AED per Sq.m Size : L5000 x D1000 x H1100 mm **Location : Reception** 	1	Item	64,780.00	Rate only
Option	**RECEPTION DESK** Fabrication, Supply and installation of Reception **counter with MDF in veneer/ PU paint finish** as per design with stone fascia (plain) and white corian countertop. Fascia Stone PC Rate : 185 AED per Sq.m Size : L5000 x D1000 x H1100 mm **Location : Reception** 	1	Item	36,235.00	36,235.00
9.02	**COFFEE BAR** Fabrication, supply and installation of Coffee bar counter with **bottom cabinets, wall shelves in veneer finish MR MDF, corian counter top, overhead shelves** in PU paint MDF & metal powder coated finish with provision for lights as per design with all necessary for fixing as per below **Location : Coffee bar** Note : Backsplash included 	1	Item	192,250.00	192,250.00
a	Bottom cabinets 1 - Size : L14000 x D1000 x H1200 mm	1	Item		
b	Bottom cabinets 2 - Size : L7500 x D700 x H900 mm	1	Item		
c	Corian countertop, fascia, backsplash	1	Item		
d	Ledge above counter - 14 LM	1	Item		
e	Wall shelves - Size : L7000 x D500 mm	3	Nos		
f	MDF slatted wall cladding in PU paint finish behind shelves - Ht up to 1.3 m	3	Sqm		
g	Overhead shelves 1 - Size : L14400 x D400 x H300 mm	1	Item		
h	Overhead shelves 1 - Size : L13400 x D300 x H500/1000 mm	1	Item		
i	Foot rest - Size : L14400 mm	1	Item		
9.03	**RECEPTION BACKWALL** Fabrication, supply and installation of Reception Backwall with MDF cladding with grooves, Decorative glass partition on both sides as per design including necessary materials for installation as per below 	1	Item	18,709.00	18,709.00
a	MDF wall cladding in veneer finish with grooves, slats	17	Sqm		
b	Decorative glass partition with powder coated frame Size L850 x H2800 mm	2	Item		

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR HAMPTONS INTERNATIONAL CORPORATE OFFICE @ PARK HEIGHTS SQUARE 1 , DUBAI - UAE

Quote Ref No: VID/1002/25/CP/QTN_01/R1 **06-Feb-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
9.04	**SEATER WITH PLANTER BOX** Fabrication, supply and installation of Seating unit made with MDF in veneer finish, fabric upholstered cushion seat and backrest, planter box in MDF veneer finish including necessary materials for installation. Planter size : L4800 x D570 x H1100 mm Seat size : L4400 x D700 x H900 mm **Location : Behind Reception** Note : Planter box considered for artificial plants	1	Item	22,569.00	22,569.00
9.05	**PLANTER BOX WITH COLUMN CLADDING** Fabrication, supply and installation of Planter box, wall cladding around the column made with MDF in veneer finish including necessary materials for installation. Size : L800 mm; cladding Dia 900 mm ; up to 3 m ht **Location : Display area around the columns** Note : Planter box considered for artificial plants	2	Item	9,595.00	19,190.00
9.06	**BENCH SEATS** Fabrication, supply and installation of Seating unit made with MDF in veneer finish, fabric upholstered cushion seat and backrest including necessary materials for installation. Seat size : L4300 x D600 x H900 mm **Location : Corridor** Note : MDF wall cladding above seating excluded.	1	Item	14,892.00	14,892.00
9.07	**TV WALL CLADDING** Fabrication, supply and installation of TV wall with wooden cladding and cabinet made with MDF in wood veneer/PU paint finish mirror cladding, internal melamine shelves including necessary materials for installation. Overall size : L3700 x D400 x H2800 mm Wall cladding : L2100 x H2800 mm Cabinet Size : L1600 x H2800 mm **Location : Meeting room - 12 pax**	1	Item	15,529.00	15,529.00
9.08	**FILING CABINETS** Fabrication, supply and installation of Full height cabinets made with MDF in wood veneer/PU paint finish including necessary materials for installation. Overall size : L3700 x D600 x H2800 mm **Location : Workstation**	1	Item	20,571.00	20,571.00
9.09	**DISPLAY SHELVES** Fabrication, supply and installation of Display shelves made with MDF in wood veneer/PU paint finish including necessary materials for installation. Planter with storage size : L2900 x D400 x H1200 mm Ledge : L2900 mm - 3 nos **Location : Seating lounge** Note : Planter box considered for artificial plants MDF wall cladding excluded.	1	Item	15,836.00	15,836.00

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR HAMPTONS INTERNATIONAL CORPORATE OFFICE @ PARK HEIGHTS SQUARE 1 , DUBAI - UAE

Quote Ref No: VID/1002/25/CP/QTN_01/R1 **06-Feb-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
9.10	**NICHE SEATS** Fabrication, supply and installation of Seating unit made with MDF in veneer finish, fabric upholstered cushion seat and backrest including necessary materials for installation. Seat size : L3850 x D600 x H900 mm **Location : Seating lounge** Note : MDF wall cladding above seating excluded. 	1	Item	13,334.00	13,334.00
9.11	**PRINTER CABINET** Fabrication, supply and installation of Printer cabinet with MDF in veneer finish (over head cabinet and storage counter top) and cabinets (in PU painted shutters) as below with all necessary materials for fixing. Lower cabinet size : 1950 x 600 x 1100 mm Upper cabinet size : 1950 x 500 x 600 mm	1	Item	6,322.00	6,322.00
9.12	**WALL MOUNT LEDGE** Fabrication, supply and installation of wall mounted Ledge with MDF in wood veneer finish including necessary materials for installation. Size : L 1100 x D 400 x H 40 mm **Location : Phone booth** Note : Considered for 3 Nos phone booths only	3	Item	1,365.00	4,095.00
9.13	**DISPLAY SHELVES** Fabrication, supply and installation of Display shelves made with MDF in wood veneer/PU paint finish including necessary materials for installation. Overall size : L1700 x D600 x H2800 mm **Location : Meeting room - 4 pax near entrance**	1	Item	9,452.00	9,452.00
9.14	**DISPLAY SHELVES** Fabrication, supply and installation of Display shelves made with MDF in wood veneer/PU paint finish including necessary materials for installation. Overall size : L1000 x D600 x H2800 mm **Location : Corridor - show suite back entrance**	1	Item	5,318.00	5,318.00
9.15	Plants including soil, gravel, pebbles, etc. - **Provisional sum**	1	Item	4,300.00	4,300.00
9.16	**MODEL DISPLAY UNITS - PS SUM** Fabrication, supply and installation of Model display units made with MDF in veneer/ PU paint finish including necessary materials for installation.				
a	**TYPE A** Size : L3500 x D2400 x H750 mm	4	Item	17,405.00	Rate only
b	**TYPE B** Size : L2400 x D1350 x H750 mm	4	Item	6,713.00	Rate only
c	**TYPE C** Size : L1600 x D1600 x H750 mm	3	Item	5,304.00	Rate only
	Note : 1. All finishes are subject to final sample approval. 2. Cabinets considered with internal finish and shelves in white melamine. 3. All models, artworks, accessories - excluded.				
				SUB TOTAL JOINERY WORKS :	**398,602.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai.UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR HAMPTONS INTERNATIONAL CORPORATE OFFICE @ PARK HEIGHTS SQUARE 1 , DUBAI - UAE

Quote Ref No: VID/1002/25/CP/QTN_01/R1 **06-Feb-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
10.00	**LIGHTING WORKS**				
	Supply of the following lights				
	DIMMABLE LIGHTS				
10.01	**DECORATIVE LIGHT** 40W; Finish: Black Size : L3600 mm **Location : Reception** 	1	Nos	9,434.00	9,434.00
10.02	**TWIN SPOT LIGHT** Watts: 2x28W; Finish: Black Size: 240x126mm	72	Nos	440.00	31,680.00
10.03	**DOWNLIGHT** Watts 20W; **Location : Meeting rooms**	12	Nos	157.00	1,884.00
10.04	**DECORATIVE WALL LIGHT** Watts: 5+2W; Finish: Black Size: L480 x 65mm **Location : Display area - columns**	2	Nos	1,384.00	2,768.00
10.05	**DECORATIVE PENDANT LIGHT** Watts: 5W; Finish: Black Size: Ø40x230mm **Location : Display area**	12	Nos	742.00	8,904.00
10.06	**TRACK LIGHT** Watts: 10W; Finish: Black Size: Ø55x155mm **Location : Display area**	18	Nos	321.00	5,778.00
a	**TRACK - L1000 mm**	12	LM	226.00	2,712.00
10.07	**MAGNETIC TRACK LIGHT** Wattage : 12W **Location : Display area**	16	Nos	233.00	3,728.00
a	**MAGNETIC TRACK - L1000 mm** **Location : Display area**	25	LM	277.00	6,925.00
10.08	**MAGNETIC TRACK LIGHT** Wattage : 8W **Location : Display area**	8	Nos	189.00	1,512.00

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR HAMPTONS INTERNATIONAL CORPORATE OFFICE @ PARK HEIGHTS SQUARE 1 , DUBAI - UAE

Quote Ref No: VID/1002/25/CP/QTN_01/R1 **06-Feb-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
a	**MAGNETIC TRACK - L1000 mm** Wall mount **Location : Display area**	12	LM	277.00	3,324.00
10.09	**LED COVE LIGHT - Straight**	195	LM	73.00	14,235.00
10.10	**LED COVE LIGHT - Curved**	10	LM	111.00	1,110.00
a	Driver	41	Nos	302.00	12,382.00
10.11	**PROFILE LIGHT FOR COFFEE BAR OVERHEAD SHELVES**	45	LM	566.00	25,470.00
10.12	**Lighting control panel - PS SUM**	1	Item	39,000.00	39,000.00
	NON DIMMABLE LIGHTS				
10.13	**DOWNLIGHT** Watts : 20 W **Location : Workstation, meeting rooms**	38	Nos	69.00	2,622.00
10.14	**SUSPENDED LINEAR LIGHT** Watts: 40W/m **Location : Workstation**				
a	Size : L4400 x 50 x 75 mm	3	Nos	1,220.00	3,660.00
b	Size : L3200 x 50 x 75 mm	8	Nos	893.00	7,144.00
c	Size : L2000 x 50 x 75 mm	1	Nos	553.00	553.00
10.15	**TRACK LIGHT** Watts: 10W; Finish: Black Size: Ø53x130mm **Location : Seating lounge**	7	Nos	201.00	1,407.00
a	**TRACK - L1000 mm**	5	LM	392.00	1,960.00
10.16	**MAGNETIC TRACK** Size : 1000 mm **Location : Meeting rooms**	14	LM	253.00	3,542.00
a	**MAGNETIC TRACK LIGHT** Wattage : 3 x 2 W Size : 106 x 35 x 59 mm **Location : Meeting rooms**	12	Nos	164.00	1,968.00
10.17	**DECORATIVE LIGHT** Watts: 5x5W Size: L1000 x H1000mm **Location : Meeting rooms**	2	Set	1,950.00	Rate only

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR HAMPTONS INTERNATIONAL CORPORATE OFFICE @ PARK HEIGHTS SQUARE 1 , DUBAI - UAE

Quote Ref No: VID/1002/25/CP/QTN_01/R1 — **06-Feb-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
Option	**SUSPENDED LINEAR LIGHT** Watts: 40W/m **Location : Meeting rooms**				
a	Size : L3400 x 50 x 75 mm	1	Nos	984.00	984.00
b	Size : L2000 x 50 x 75 mm	1	Nos	893.00	893.00
10.18	**DECORATIVE LIGHT** Dia : 450 mm Wattage : 40W **Location : Workstation**	1	No	692.00	692.00
10.19	**DECORATIVE LIGHT** Size: Ø150xH360mm Wattage : 6W **Location : Phone booth, seating lounge**	6	Nos	289.00	1,734.00
10.20	**LED PANEL LIGHT** Size : 60 x 60 cm; 40W **Location : Storage room**	9	Nos	82.00	738.00
10.21	**DECORATIVE LIGHT** Watts: 2x3W Size: 118x80mm; **Location : Corridor wall**	1	Nos	264.00	264.00
	Note : 1. Quantity subject to final RCP design and LUX calculations				
				SUB TOTAL LIGHTS :	**199,007.00**
11.00	**SANITARY FITTINGS**				
11.01	**PANTRY SINK + Bottle trap + Waste** Undermounted Single Bowl Sink Size : 380 x 440 x 190 mm **Supply and installation**	1	Nos	1,224.00	1,224.00
11.02	**PANTRY SINK MIXER + Angle valve** Single Hole Kitchen Sink Mixer **Supply and installation**	1	Nos	711.00	711.00
				SUB TOTAL SANITARY FITTINGS :	**1,935.00**
	MEP WORKS				
12.00	**HVAC WORKS**				
	<u>AC MACHINES AND ACCESSORIES</u>				

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR HAMPTONS INTERNATIONAL CORPORATE OFFICE @ PARK HEIGHTS SQUARE 1 , DUBAI - UAE

Quote Ref No: VID/1002/25/CP/QTN_01/R1 **06-Feb-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
12.01	Supply and installation of **FCU** with all necessary supports and fittings with necessary vibration isolators. Make : Clima Uno				
a	4 TR	4	Nos	5,716.00	22,864.00
12.02	Supply and installation of VAV as per the requirement Location : All meeting rooms - Display area	3	Nos	3,597.00	10,791.00
12.03	Supply and installation of thermostat including wiring	7	Nos	660.00	4,620.00
12.04	Supply and installation of Valve package for FCU	1	Ls.	7,547.00	7,547.00
12.05	Supply and installation of chilled water piping	1	Ls.	15,723.00	15,723.00
12.06	Performance test on existing FCUs Note : Not included, as the existing AC machines are relatively new.	7	Nos.	755.00	Rate only
12.07	Relocation of the existing thermostat	7	Nos.	252.00	1,764.00
	DUCTING AND ACCESSORIES				
12.08	Supply and installation of new PI ducting including all the accessories VCD , etc.	1	Item	31,655.00	31,655.00
12.09	Supply and installation of inline ducted fan including the ducting and related accessories . **Location : Coffee area**	1	Item	3,597.00	3,597.00
12.10	Extension of duct for the fresh and extract air using PI ducting Note : Stub out present at site	1	Item	19,424.00	19,424.00
12.11	Chemical flushing - Culligan considered Note : Considered only for the new FCU	1	Item	15,827.00	15,827.00
12.12	Supply and installation of cross talk attenuators in the meeting rooms (2 nos)	2	Set	935.00	1,870.00
	GRILLS AND DIFFUSER				
12.12	Linear Slot grills (3-Slot)	1	Item	45,900.00	45,900.00
12.13	Linear Slot grills single slot - display area				
	DRAIN PIPE				
12.14	Supply and Installation of **PVC Pipe** with insulation. - connecting to the existing line	1	Item	5,540.00	5,540.00
12.15	Testing and commissioning with air balancing (Verve)	1	Item	2,158.00	2,158.00
12.16	Third party testing with air balancing works	1	Item	7,914.00	7,914.00
	Notes : 1. BTU Meter works and BMS Connection / cabling/ wiring excluded 2. Considered to install the outdoor machine in the balcony , subject to building management approval				
				SUB TOTAL HVAC WORKS :	**197,194.00**
13.00	**ELECTRICAL WORKS**				
13.01	PVC conduiting and wiring for light points including installation. Note: Light points are subject to revise upon final RCP Layout.	270	Nos	209.00	56,430.00
13.02	PVC conduiting and wiring for dimmer switch	182	Nos	122.00	22,204.00
13.03	Supply and installation of **Single switches for lighting.** Including cabling works. (MK-Normal White)	20	Nos	259.00	5,180.00
13.04	Supply and installation of **Grid switch for lighting.** Including **PVC conduiting**. (Black Matt PVC finish Legrand / schneider) for Open workstation & corridor.	5	Nos	260.00	1,300.00

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai.UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR HAMPTONS INTERNATIONAL CORPORATE OFFICE @ PARK HEIGHTS SQUARE 1 , DUBAI - UAE					
Quote Ref No: VID/1002/25/CP/QTN_01/R1					06-Feb-25
SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
13.05	Supply and installation of **13A Single wall Power Socket,** in PVC finish including conduiting and wiring. (Schneider / Legrand)	7	Nos	317.00	2,219.00
13.06	Supply and installation of **13A Twin wall Power Socket,** in black PVC finish including conduiting and wiring. (Schneider / Legrand)	13	Nos	338.00	4,394.00
13.07	Supply and installation of **15A Single wall Power Socket,** in Black PVC finish including conduiting and wiring. (Schneider / Legrand)	3	Nos	468.00	1,404.00
13.08	Supply and installation of **Floor Box -Twin 13A+ Twin Data.** with cabling and conduiting and data and telephone plates provision only. Make : Obo or equivalent	55	Nos	647.00	35,585.00
13.09	Supply and installation of **20A SP isolator power for the new FCU units**	4	Nos	791.00	3,164.00
13.10	Power for LED screens	6	Nos	791.00	4,746.00
13.11	Power for Stretch ceiling	14	Nos	223.00	3,122.00
13.12	Supply and installation of DP switch for the new VAV	3	Nos	504.00	1,512.00
13.13	**50mm conduit** and cabling provision for **HDMI/VGI including the connections for the conferencing systems**	11	Nos.	647.00	7,117.00
13.14	Supply and installation of **PVC** containment for **WI-FI Points**. (Provisional qty)	8	Nos.	180.00	1,440.00
13.15	Supply and installation of **PVC** containment for **Access control** (Provisional qty)	6	Nos	180.00	1,080.00
13.16	Supply and installation of **PVC** containment for **CCTV Points**. (Provisional qty)	6	Nos.	180.00	1,080.00
13.17	Supply and installation of **PVC** containment for **speakers system .** (Provisional qty)	9	Nos.	180.00	1,620.00
13.18	Supply and installation of **PVC** containment for **printers.**	1	Nos.	180.00	180.00
13.19	Supply and installation of **PVC** containment for **AV Rack**	2	Nos.	180.00	360.00
13.20	Supply and installation of **PVC** containment for thermostat (new AC machine + new VAV + replacement of existing thermostat)	14	Nos.	180.00	2,520.00
13.21	Power provision for **Signage** with timer switch	2	Nos.	935.00	1,870.00
13.22	Supply and installation of CT meter cabinet in the electrical room	1	Nos.	5,036.00	5,036.00
13.23	Modification of existing SMDB	1	Nos.	6,475.00	6,475.00
13.24	Supply and installation of new SMDB including the armored cabling works	1	Nos.	17,986.00	17,986.00
13.25	Relocation and Modification of existing **DB** with all other accessories as per DEWA standards Note : Subject to load availability	3	Nos.	2,158.00	6,474.00
13.26	Supply and installation of the cable tray / trunking to carry out the above works .	1	Lot	6,835.00	6,835.00
13.27	Supply & Installation of 150mm GI Cable Tray with necessary fittings & supports -For IT, AV, Light, Power	1	Lot	27,194.00	27,194.00
13.28	DEWA submission, inspection and approval. - 1 submission considered	1	No	5,036.00	5,036.00
13.29	Testing commissioning.	1	Item	2,158.00	2,158.00
13.30	Providing **PVC conduit for data** - one data per person considered	96	Nos	180.00	17,280.00

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR HAMPTONS INTERNATIONAL CORPORATE OFFICE @ PARK HEIGHTS SQUARE 1 , DUBAI - UAE

Quote Ref No: VID/1002/25/CP/QTN_01/R1 — 06-Feb-25

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
	Note: 1. We have assumed that the existing infrastructure's power has sufficient capacity to cater to the requirement of the project. 2. We have not allowed for upgrade of the capacity of any base building system. 3. All electrical conduits considered are of PVC type. 4. Subject to final MEP drawings **Exclusions:** 1. Any BMS integration or related works. 2. DEWA Consultancy for power upgrade.				
				SUB TOTAL ELECTRICAL WORKS :	**253,001.00**
14.00	**CIVIL DEFENCE WORKS**				
14.01	**FIRE ALARM WORKS**				
a	Supply & Installation of Fire Alarm Addressable Control Panel 1 Loop With Battery	1	Nos.		
b	Supply and installation of smoke detector with base	34	Nos.		
c	Supply and installation of LED indicator for the Void smoke detector	23	Nos.		
d	Relocation of existing smoke detector with sounder base	11	Nos.		
e	Supply and installation of heat detector with base	1	Nos.		
f	Supply of break glass unit with back box	4	Nos.		
g	Supply of sounder unit	5	Nos.		
h	Supply of interface modules	9	Nos.		
i	Programming , Testing & Commissioning	1	Item		
j	Supply Certificate, Installation Certificate, Warranty Certificate	1	Item		
14.02	**FIRE FIGHTING WORKS**				
a	Supply & installation of new pendant sprinkler with pipes & accessories including upright	35	Nos	LS	196,100.00
b	Relocation of existing upright sprinklers with pipes & accessories	65	Nos		
c	Supply & installation of fire extinguisher set (4KG CO2 + 5 KG DCP)	6	Set		
d	Pressure test	1	Item		
e	Draining & recharging of FFS	1	Item		
f	Certification charges	1	Item		
g	Supply and installation of automatic fire extinguisher **(FM 200 excluded as the area is less than 9 sq.m.)**	1	Item		
14.03	**EMERGENCY WORKS**				
a	Supply and installation of Emergency Light (Self contained)	26	Nos.		
b	Supply and installation of existing exit light	9	Nos.		
c	DCD Certificates Fire Proof Cable 1.5 Sqmm Accessories Device Installation	1	Item		
	Notes / Exclusions: 1. Any additional charges/ fees for any third party shall be paid by the client. 2. Assumed existing sprinkler heads are as per the DCD standards 3. FM 200 , central battery system works excluded **4. Rates subject to base build contractor , Verve to charge 15% coordination charge on actual quote submitted by Base build contractor. Verve provided provisional sum**				
				SUB TOTAL CIVIL DEFENCE WORKS :	**196,100.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR HAMPTONS INTERNATIONAL CORPORATE OFFICE @ PARK HEIGHTS SQUARE 1 , DUBAI - UAE					
Quote Ref No: VID/1002/25/CP/QTN_01/R1					06-Feb-25
SR.NO	**DESCRIPTION**	**QTY**	**UNIT**	**UNIT RATE**	**TOTAL (AED)**
15.00	**PLUMBING WORKS**				
15.01	Supply and installation of **Water Supply PPR pipe** for Hot and Cold with socket, Elbow ,Threaded Road and other accessories as per standard	1	LS	3,000.00	3,000.00
15.02	Supply and installation of **UPVC drainage Pipe** for waste and Soil Pipe and connecting to existing line with ,fittings ,socket ,and other accessories as per Standard				
15.03	Pressure Test and Gravity Test				
15.04	Supply and installation of Sani pump	1	No.	5,036.00	5,036.00
				SUB TOTAL PLUMBING WORKS :	**8,036.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR HAMPTONS INTERNATIONAL CORPORATE OFFICE @ PARK HEIGHTS SQUARE 1 , DUBAI - UAE

Quote Ref No: VID/1002/25/CP/QTN_01/R1						February 6, 2025
SR.NO	**SAMPLE IMAGE**	**DESCRIPTION**	**QTY**	**UNIT**	**RATE**	**TOTAL (AED)**
16.00	**LOOSE FURNITURE**					
		WORKSTATION AREA				
16.01		**WORKSTATION - FACE TO FACE** 18mm thick MDF melamine finish table top; Metal powder-coated O Series Leg with powder-coated beams to support the tabletop; Flipup on the tabletop side for wire management. Screen - 18(9+9)mm Fabric hardboard (1150mm(W) x 350mm(D)) Worktop: Melamine. [Light Oak / Dark Oak / Walnut / White] Legs: Metal. [White / Grey] DIM :- 1200mm(W) * 700mm(D) * 750mm(H) Note : Price includes cable management - 1 No each per desk				
a		Cluster of 8 pax	3	Nos.	6,200.00	18,600.00
b		Cluster of 6 pax	7	Nos.	4,710.00	32,970.00
c		Cluster of 4 pax	1	No.	3,205.00	3,205.00
16.02		**WORKSTATION - LINEAR** 18mm thick MDF melamine finish table top; Metal powder-coated O Series Leg with powder-coated beams to support the tabletop; Flipup on the tabletop side for wire management. Screen - 18(9+9)mm Fabric hardboard (1150mm(W) x 350mm(D)) Worktop: Melamine. [Light Oak / Dark Oak / Walnut / White] Legs: Metal. [White / Grey] DIM :- 1200mm(W) * 700mm(D) * 750mm(H) Note : Price includes cable management - 1 No each per desk				
a		Cluster of 3 pax	1	Nos.	3,042.00	3,042.00
16.03		**MOBILE PEDESTAL** DIM :- 400mm(W) x 450mm (D) x 520mm(H) Melamine - [Light Oak / Dark Oak / Walnut / White]	73	Nos.	426.00	31,098.00
16.04		PDU: Includes: 2 USB CHARGER (A+C) + 2 UK Power+ 2 CAT 6 Data and with Cable Starter: 2.2 meter UK	73	Nos.	296.00	Rate only
16.05		**TASK CHAIR**	73	Nos.	1,515.00	Rate only

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR HAMPTONS INTERNATIONAL CORPORATE OFFICE @ PARK HEIGHTS SQUARE 1 , DUBAI - UAE

Quote Ref No: VID/1002/25/CP/QTN_01/R1 — **February 6, 2025**

SR.NO	SAMPLE IMAGE	DESCRIPTION	QTY	UNIT	RATE	TOTAL (AED)
Option		**TASK CHAIR**	73	Nos.	485.00	35,405.00
16.06		**PLANTER BOX WITH STORAGE** Custom made - MDF veneer finish Size : L1400 x D400 x H1200 mm	6	Nos.	2,900.00	Rate only
Option		**PLANTER BOX WITH STORAGE** 18mm thick top & sides and door with edge band with aluminum type handles and center lock, with soft closure. Finish : Melamine. [Light Oak / Dark Oak / Walnut / White] Note: planter box only for artificial plants Size : L1400 x D400 x H1200 mm	6	Nos.	2,173.00	Rate only
16.07		**MEETING PODS** Booth:- Upholstered with high density foam over steel frame structure with fabric finish. Coffee Table:- High density board table with SS base. DIM : Booth : 2120*1855*1340mm Coffee table : 1200*690*700mm FINISH Booth: Acoustic Fabric Table: Melamine	1	No.	15,231.00	15,231.00
16.08		**POUF** Size : Dia 600 x 450 mm Fabric	2	Nos.	757.00	1,514.00
16.09		**COFFEE TABLE** Size : Dia 600 x 450 mm	1	No.	521.00	521.00
16.10		**POUFF 2** Fabric Size : 600 x 500 x 450 mm	2	Nos.	592.00	1,184.00

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR HAMPTONS INTERNATIONAL CORPORATE OFFICE @ PARK HEIGHTS SQUARE 1 , DUBAI - UAE

Quote Ref No: VID/1002/25/CP/QTN_01/R1 — **February 6, 2025**

SR.NO	SAMPLE IMAGE	DESCRIPTION	QTY	UNIT	RATE	TOTAL (AED)
16.11		**PHONE BOOTH CHAIRS**	3	Nos.	734.00	2,202.00
		SEATING LOUNGE				
16.12		**3 SEATER SOFA** Material : Fabric/ Faux leather	1	No.	2,970.00	2,970.00
16.13		**LOUNGE CHAIR** Material : Fabric/ Faux leather	2	Nos.	1,609.00	3,218.00
16.14		**CENTER TABLE** Size : 900 x 600 x H450 mm	1	No.	1,491.00	1,491.00
16.15		**POUF** Size : Dia 600 x 450 mm Fabric	2	Nos.	757.00	1,514.00
16.16		**POUFF 2** Fabric Size : 600 x 500 x 450 mm	2	Nos.	592.00	1,184.00
		NICHE SEATS				
16.17		**POUF** Size : Dia 600 x 450 mm Fabric	2	Nos.	763.00	1,526.00
16.18		**COFFEE TABLE** Size : Dia 700 x H750 mm	2	Nos.	710.00	1,420.00
		MEETING ROOM				

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR HAMPTONS INTERNATIONAL CORPORATE OFFICE @ PARK HEIGHTS SQUARE 1 , DUBAI - UAE

Quote Ref No: VID/1002/25/CP/QTN_01/R1 — **February 6, 2025**

SR.NO	SAMPLE IMAGE	DESCRIPTION	QTY	UNIT	RATE	TOTAL (AED)
16.19		**MEETING TABLE** Ready made Finish : Melamine Size : L3500 x D1200 x H750 mm	1	No.	5,107.00	5,107.00
16.20		**MEETING TABLE** Ready made Finish : Melamine Size : L2100 x D1200 x H750 mm	1	No.	3,468.00	3,468.00
16.21		**MEETING CHAIRS** Fabric	18	Nos.	1,018.00	Rate only
Option		**MEETING CHAIRS**	18	Nos.	651.00	11,718.00
16.22		**COFFEE TABLE** Size : Dia 600 x 450 mm	2	Nos.	521.00	1,042.00
16.23		**3 SEATER SOFA** Material : Fabric Size : L1620 x D800 x H480 mm	3	Nos.	4,899.00	Rate only
Option		**3 SEATER SOFA** Material : Vegan leather	3	Nos.	4,314.00	12,942.00
16.24		**SINGLE SEATER SOFA - Custom made** Material : Legs in MS PC. Back and seat upholstered in fabric.	8	Nos.	3,719.00	Rate only
Option		**LOUNGE CHAIR** Material : Faux Leather	8	Nos.	1,562.00	12,496.00

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR HAMPTONS INTERNATIONAL CORPORATE OFFICE @ PARK HEIGHTS SQUARE 1 , DUBAI - UAE

Quote Ref No: VID/1002/25/CP/QTN_01/R1 — **February 6, 2025**

SR.NO	SAMPLE IMAGE	DESCRIPTION	QTY	UNIT	RATE	TOTAL (AED)
16.25		**CENTER TABLE** Base in beech wood. Top in quartz. Size : Dia 1000 mm	3	Nos.	3,486.00	Rate only
Option		**CENTER TABLE** White eco-marble top, Titanium electroplated steel legs Size : Dia 1000 mm	3	Nos.	3,278.00	9,834.00
16.26		**POUF** Size : Dia 600 x 450 mm Fabric	2	Nos.	757.00	1,514.00
		DISPLAY AREA				
16.27		**COFFEE TABLE** Base in MS PC. Top in quartz. Dia 600 x H 350 mm	10	Nos.	2,610.00	26,100.00
16.28		**COFFEE TABLE 2** Base in MS PC. Top in quartz. Size : L1500 x D500 x H350 mm	2	Nos.	3,269.00	6,538.00
16.29		**LOUNGE CHAIRS - Custom made** Material : Fabric/Faux Leather	36	Nos.	2,154.00	77,544.00
16.30		**MEETING PODS** Booth:- Upholstered with high density foam over steel frame structure with fabric finish. Coffee Table:- High density board table with SS base. DIM : Booth : 2120*1855*1340mm Coffee table : 1200*690*700mm FINISH Booth: Acoustic Fabric Table: Melamine	2	Nos.	15,231.00	30,462.00
		RECEPTION				
16.31		**TASK CHAIR**	3	Nos.	1,515.00	Rate only

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR HAMPTONS INTERNATIONAL CORPORATE OFFICE @ PARK HEIGHTS SQUARE 1 , DUBAI - UAE						
Quote Ref No: VID/1002/25/CP/QTN_01/R1						February 6, 2025
SR.NO	SAMPLE IMAGE	DESCRIPTION	QTY	UNIT	RATE	TOTAL (AED)
Option		**TASK CHAIR**	3	Nos.	485.00	1,455.00
		COFFEE BAR				
16.32		**BAR STOOL** FINISH : Frame:- Wood Seat & Backrest : fabric/ Faux Leather Base : Solid Wood	8	Nos.	2,676.00	21,408.00
	Lead time	**12 - 14 weeks**				
	Note : Images are for indicative purposes , actual product may vary slightly , subject to material specifications					
					TOTAL LOOSE FURNITURE :	**379,923.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

Thank you,

© **Verve Design, 2024**

Verve Interior Decoration llc

Unit M04,
Al Reemas Building,
Sheikh Zayed Road, Al Quoz,
PO Box - 128279,
Dubai, UAE.

t : +971 4 240 0119
f : +971 4 240 8403
info@vervedesign.ae
www.vervedesign.ae