verve

space + design

Huspy™

PROPOSAL FOR INTERIOR FITOUT WORKS

INTERIOR FIT-OUT WORKS

FOR

AT

15th FLOOR, MARINA PLAZA ,DUBAI -U.A.E

For
HUSPY

Prepared by:
Shahabas Kareem
Verve Interior Decoration LLC
PO Box 128279, Dubai, UAE
Email: shahabas@vervedesign.ae

Prepared on:

April 15, 2025

verve
space + design

CONTRACT AGREEMENT: General terms and conditions

Project Timeline: As per approved Project schedule

Payment Terms:

Advance Payment : 30% Advance payment against order confirmation.
Progress Payment : 20% upon approval of all the material samples and mobilization of materials to the site
Progress Payment : 35% as per site progress
Completion Layout : 10% on practical Completion (Office fit to occupy)
Final Payment : 5% upon completion of snagging as per the client approval

Payment to be honored within 7 days from the date of receipt of Invoice

All products offered by us on this project carry a warranty against defective materials and/or workmanship as follows:
Fit Out Works : 12 Months from the date of Handover.

Insurances:
All our personnel working on the project will be covered under our Workmen Compensation
All works carried out at site will be covered by our Contractor's All Risk Policy

Validity.
Our offer is valid for a period of 30 days from hereof
Note: Bank guarantee or Retention Requirements TBC

Please sign below for acceptance of the offer. The BOQ will be treated as the final scope of work and contract will form the integral part of the project.

Signature: _____
on behalf of: HUSPY

Name: Sawan Nalinchandra Karia
Date: 15 April 2025

Signature:_____
on behalf of : Verve Interior Decoration LLC

Name: Syed Mehdi
Date: April 15, 2025
Quote Ref No: VID/1019/25/CP/QTN_01/R04

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR HUSPY @ MARINA PLAZA , DUBAI-UAE		
Quote Ref No: VID/1019/25/CP/QTN_01/R04		15-Apr-25
SR. NO	SUMMARY - OPTION 1	TOTAL (AED)
1	PRELIMINARIES	41,597.00
2	DEMOLITION AND CIVIL WORKS	48,932.00
3	PARTITION WORKS	74,656.00
4	FLOOR FINISH	165,653.00
5	WALL FINISH	111,397.00
6	CEILING FINISH	125,175.00
7	DOORS	36,228.00
8	SIGNAGE WORKS - Provisional Sum	6,505.00
9	JOINERY WORKS	167,766.00
10	LIGHTING WORKS - NON DIMMABLE	99,635.00
11	HVAC WORKS	110,145.00
12	ELECTRICAL WORKS	183,753.00
13	CIVIL DEFENCE WORKS - PROVISIONAL SUM	128,558.00
	GRAND TOTAL AMOUNT (AED):	1,300,000.00

Note: **Any variation in terms of quantity that comes up during the course of work has to be paid by the client and hence client is liable for payment of Variation. Retention is not considered.**

Notes/Exclusions:

1) All fees and deposit for statutory authorities.
2) Any other items not mentioned in the attached BOQ.
3) Loose Furniture not included in Summary.

For Verve Interior Decoration LLC

Syed Mehdi
Sales Director
+971 50 513 9878
syed@vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR HUSPY @ MARINA PLAZA , DUBAI-UAE

Quote Ref No: VID/1019/25/CP/QTN_01/R04 **15-Apr-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
1.00	**PRELIMINARIES**				
1.01	General- Contractor's preliminaries for mobilization, site preparation, Provision for all temporary barricades, setting out transportations to/from site, material deliveries, small tools and equipment's, protection of finished products in on-going site, site attendance and call out attendance, electricity & water charges including charges for scaffolding. PPE and other site requirements to be followed	1	Item	5,689.00	5,689.00
1.02	Co ordination Charges for obtaining approvals from the Landlord & the related authorities.	1	Item	2,146.00	2,146.00
1.03	Preparation of Technical drawings as required for submission to Relevant authorities. Detail drawings includes Architectural and MEP drawings. Subject to receipt of current approved as built drawings	1	Item	15,990.00	15,990.00
1.04	CAR Insurance for fit out work during the execution of works. (includes third party liability) *Note: Insurance coverage is limited to CAR of Contract Value. If higher coverage limit is required by building management and any other authorities, the additional premium amount will be charged separately* .	1	Item	3,544.00	3,544.00
1.05	Professional indemnity insurance	1	Item	11,438.00	Rate Only
1.06	Regular cleaning of site during construction period and after completion professional deep cleaning and made ready to occupy. Including carting away the debris to Municipal dumping area.	1	Item	9,936.00	9,936.00
1.07	Charges for site protection (protection of common area finishes and the area near to the work space)	1	Item	4,292.00	4,292.00
	Note: Security deposit, Authority Fees, entry and exit pass for vehicles and labors, night work permit fee, Mall management fees(If required) has to be paid by the client on actuals				
	Note : Provision for mock up and samples submissions at site as per requirement included, however special items are chargeable and shall be billed to the client on actual.				
	SUB TOTAL PRELIMINARIES :				**41,597.00**
2.00	**DEMOLITION AND CIVIL WORKS**				
2.01	Demolition of the existing walls, doors, floor & ceiling finishes as per site condition including carting away to DM approved yard .	1	Ls.	44,640.00	44,640.00
2.02	Builders works to accommodate MEP works	1	Ls.	4,292.00	4,292.00
	SUB TOTAL DEMOLITION AND CIVIL WORKS :				**48,932.00**
3.00	**PARTITION WORKS**				
3.01	**GYPSUM PARTITION SINGLE LAYER (NON FR)** Supply and installation of 100 mm Thk Non-FR gypsum partition with 12.5 mm Thk Non-FR gypsum board (Knauf or equivalent) single layer on both sides with studs, 50mm thick rockwool insulation and necessary frames and accessories. Height up to 3.6 m **Location : As per layout**	48	Sq.m	122.00	5,856.00

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai.UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR HUSPY @ MARINA PLAZA , DUBAI-UAE

Quote Ref No: VID/1019/25/CP/QTN_01/R04 **15-Apr-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
3.02	**CURVED GYPSUM PARTITION SINGLE LAYER (NON FR)** Supply and installation of 100 mm Thk Non-FR gypsum partition with 12.5 mm Thk Non-FR gypsum board (Knauf or equivalent) single layer on both sides with studs, 50mm thick rockwool insulation and necessary frames and accessories. Height up to 2.7 m **Location : As per layout**	18	Sq.m	129.00	2,322.00
3.03	**GYPSUM PARTITION SINGLE LAYER (FR)** Supply and installation of **100mm Thk FR gypsum partition** with 12.5mm Thk FR gypsum board (Knauf or equivalent) Single layer on both sides with studs, 50mm thick rockwool insulation and necessary frames and accessories. Height up to 3.6 m **Location : Server room**	25	Sq.m	157.00	3,925.00
3.04	**GYPSUM PARTITION DOUBLE LAYER (NON FR)** Supply and installation of 125 mm Thk Non-FR gypsum partition with 2 x 12.5 mm Thk Non-FR gypsum board (Knauf or equivalent) double layer on both sides with studs, 50mm thick rockwool insulation and necessary frames and accessories. Height up to 3.6 m **Location : Conference Room 12 PAX, Meeting Room 4 Pax - 2 Nos**	120	Sq.m	179.00	21,480.00
3.05	**GYPSUM PARTITION DOUBLE LAYER (FR)** Supply and installation of 125 mm Thk FR gypsum partition with 2 x 12.5 mm Thk FR gypsum board (Knauf or equivalent) double layer on both sides with studs, 50mm thick rockwool insulation and necessary frames and accessories. Height up to 3.6 m **Location : Server Room**	6	Sq.m	250.00	4/9/2025
3.06	**GYPSUM PARTITION DOUBLE LAYER (FR)** Supply and installation of 150 mm Thk FR gypsum partition with 2 x 12.5 mm Thk FR gypsum board (Knauf or equivalent) double layer on both sides with studs, 50mm thick rockwool insulation and necessary frames and accessories. Height up to 3.6 m **Location : Demise Wall**	41	Sq.m	279.00	11,439.00
3.06	**GLASS PARTITION - NON FR** Supply and installation of **single glazed 40 x 40 mm powder coated aluminum framed single layered partition (around the partitions)** utilizing 12 mm thick glass with all around straight polished edges including glass to glass clear joints. Height up to 2.7 m **Location : Workstation Entrance**	9	Sq.m	501.00	4,509.00
3.07	**ACOUSTIC GLASS PARTITION - NON FR** Supply and fixing of 25 x 25 mm aluminium framed QIC partition utilizing 13.52mm clear acoustic laminated (6 mm clear tempered glass + 1.52 mm acoustic PVB + 6mm clear tempered glass) with all around straight polished edges fixing by clip profiles with rubber gasket , including glass to glass beading joints . Height up to 2.7 m **Location : Conference Room 12 PAX, Meeting Room 4 Pax - 2 Nos**	19	Sq.m	787.00	14,953.00
3.08	**GYPSUM BAFFLE (NON-FR)** Supply and installation of **Non-FR gypsum baffle wall** with 12.5mm Thk Non-FR gypsum board (Knauf or equivalent) single layer on both sides with 50mm thick rockwool insulation, necessary frames and accessories . Height up to 0.9 m **Location : Above proposed Framed glass partition**	5	LM	136.00	680.00

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR HUSPY @ MARINA PLAZA , DUBAI-UAE

Quote Ref No: VID/1019/25/CP/QTN_01/R04 **15-Apr-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
3.09	**DOUBLE LAYER GYPSUM BAFFLE (NON-FR)** Supply and installation of **Non-FR gypsum baffle wall** with 12.5mm Thk Non-FR gypsum board (Knauf or equivalent) single layer on both sides with 50mm thick rockwool insulation, necessary frames and accessories . Height up to 0.9 m **Location : Above proposed acoustic glass partition**	10	LM	179.00	1,790.00
3.10	**Provision for MDF support below proposed glass partitions / raised floor**	14	LM	143.00	2,002.00
3.11	**GYPSUM CLADDING - NFR** Supply and installation of **NFR 12.5 mm thick Gypsum board (Knauf or equivalent) wall cladding** with necessary material for fixing, smoothened and made ready to receive final finishes. Height up to 2.7 m **Location : Meeting Room 4 Pax TV niche**	20	Sq.m	100.00	2,000.00
3.12	**GYPSUM CLADDING - NFR** Supply and installation of **NFR 12.5 mm thick Gypsum board (Knauf or equivalent) wall cladding** with necessary material for fixing, smoothened and made ready to receive final finishes. Height up to 2.7 m **Location : To existing demise walls**	132	Sq.m	107.00	Rate Only
3.13	Supply and installation of MDF support to install the TV	22	Sq.m	100.00	2,200.00
	SUB TOTAL PARTITION WORKS :				**74,656.00**
4.00	**FLOOR FINISH**				
4.01	Allow Necessary charges for modification of existing raised to make the partitions. Note: We have assumed existing raised floors are in good condition; only modification considered.	1	Ls	18,577.00	18,577.00
4.02	Supply and installation of anti static raised floor (HPL) finish. Max Height - 200mm Area - 5 m2 **Location : Server room**	1	Ls	3,574.00	3,574.00
4.03	**SELF LEVELLING ON RAISED FLOOR** Supply and installation of 2 to 3 mm self levelling compound to make the floor ready to receive the new flooring. **Location : Proposed LVT flooring, Tile**	270	Sq.m	100.00	27,000.00
4.04	**CERAMIC TILE FLOORING - TYPE 1** Supply and installation of Ceramic Tile flooring with grouting including cutting and alignment. As per design and approved sample. Size : 60 x 120 cm PC Rate : 125 AED per Sq.m Location : As per design Note : Subject to sample approval.	66	Sq.m	274.00	18,084.00

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR HUSPY @ MARINA PLAZA , DUBAI-UAE

Quote Ref No: VID/1019/25/CP/QTN_01/R04 **15-Apr-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
4.05	**CERAMIC TILE FLOORING - TYPE 2** Supply and installation of Ceramic Tile flooring with grouting including cutting and alignment. As per design and approved sample. Size : 60 x 120 cm PC Rate : 125 AED per Sq.m Location : As per design Note : Subject to sample approval.	58	Sq.m	274.00	15,892.00
4.06	**CP 01 CARPET FLOORING** Supply and Installation of Carpet tile flooring including adhesives and all necessary material for fixing. Make : Clouds Location : As per Design Note : To be installed directly on the raised floor	404	Sq.m	103.00	41,612.00
4.07	**CP 02 CARPET FLOORING** Supply and Installation of Carpet tile flooring including adhesives and all necessary material for fixing. Make : Tegola Location : As per Design Note : To be installed directly on the raised floor	11	Sq.m	111.00	1,221.00
4.08	**LVT FLOORING** Supply and installation of **Luxury Vinyl Tile flooring** with necessary material for installation. Make : Amtico **Location : Workstation Corridor area**	147	Sq.m	151.00	22,197.00
4.09	**TRANSITION STRIP** Supply and installation of Transition Strip in SS finish (ready available). **Location : Between different floor finishes, Door entrances.**	162	LM	108.00	17,496.00
	Note: All finishes are subject to final sample approval.				
	SUB TOTAL FLOOR FINISH :				**165,653.00**
5.00	**WALL FINISH**				
5.01	**WALL PAINT** Supply and application of **Jotun Fenomastic Paint Finish (white)** with all cleaning and levelling. Closed Ceiling Height up to 2.7 m Open Ceiling Height up to 3.6 m	340	Sq.m	34.00	11,560.00
5.02	**WALL PAINT COLOR** Supply and application of **Jotun Fenomastic Paint Finish (Color)** with all cleaning and levelling. Closed Ceiling Height up to 2.7 m	27	Sq.m	39.00	1,053.00
5.03	**TEXTURE PAINT** Supply and application of Texture paint as per the design Height up to 2.7 m	50	Sq.m	129.00	6,450.00
5.04	**PET PANEL WALL CLADDING** Supply and installation of **pet wall cladding** including necessary materials for installation. Height up to 1.2 m **Location : 4 PAX - Meeting room** Note: To be selected from verve standard collection.	16	Sq.m	501.00	8,016.00

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR HUSPY @ MARINA PLAZA , DUBAI-UAE

Quote Ref No: VID/1019/25/CP/QTN_01/R04 **15-Apr-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
5.05	**MDF WALL CLADDING - type 1** Supply and installation of **plain/slatted MDF wall cladding in wood veneer finish** including necessary fittings and accessories for installation. Height up to 2.7 mm **Location: Reception back wall**	19	Sq.m	787.00	14,953.00
5.06	**MDF WALL CLADDING - type 2** Supply and installation of plain **MDF wall cladding in PU paint finish** including necessary fittings and accessories for installation. Height up to 2.7 mm **Location: Workstation Entrance Near Screen**	8	Sq.m	644.00	5,152.00
5.07	**MDF WALL CLADDING - type 3** Supply and installation of **plain MDF wall cladding in wood veneer finish** including necessary fittings and accessories for installation. Height up to 2.7 mm **Location: Open Stage**	7	Sq.m	930.00	6,510.00
5.08	Supply and installation of Wallpaper based on 3D design Height upto 2700 mm PC Rate: 50AED/sq.m **Location : As per design**	37	Sq.m	127.00	4,699.00
5.09	**GREEN PAINT** Supply and application of **Jotun Fenomastic Green Paint Finish.** with all cleaning and levelling. Closed Ceiling Height up to 2.7 m **Location: Podcast Room**	34	Sq.m	39.00	1,326.00
5.10	**BACKPAINTED GLASS - (WRITABLE WALL)** Supply and installation of Back painted crystal clear glass with necessary material for fixing including MDF backing. Maxi Height - 1.2m	13	Sq.m	644.00	8,372.00
5.11	Supply and installation of plain Frosted sticker . Height upto 1200 mm Location : New glass partition and doors	19	Sq.m	100.00	1,900.00
5.12	**BACKSPLASH WALL TILE** Supply and installation of wall tiles including necessary materials for fixing. PC Rate : 80AED/Sq.m Brand: RAK / Equivalent Size : 260x26x8.5 mm Location: Island Coffee Bar	22	Sq.m	284.00	6,248.00
5.13	**SKIRTING** Supply and installation of (up to 50 mm high) **MDF skirting in PU paint finish** with necessary fittings and accessories. **Note : Non concealed**	247	LM	64.00	15,808.00
5.14	Supply and installation of switchable smart film as per the design. **Location : Meeting Room 4 Pax 2 NOS, Conference Room.** **Height : 2700 mm**	30	Sq.m	1,216.00	Rate only
5.15	**ROLLER BLINDS - MANUAL** Supply and installation of **sunscreen blinds** **Height: Upto 3600mm** **Location : External glazing**	225	Sq.m	86.00	19,350.00

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai.UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR HUSPY @ MARINA PLAZA , DUBAI-UAE

Quote Ref No: VID/1019/25/CP/QTN_01/R04 — **15-Apr-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
	Note: 1. All finishes are subject to final sample approval.				
	SUB TOTAL WALL FINISH :				**111,397.00**
6.00	**CEILING FINISH**				
6.01	**PLAIN GYPSUM CEILING** Supply and installation of **Gypsum Board Plain ceiling** (Knauf or equivalent) with necessary hanging systems including wall angle "C "channel, furring channel with 12.5mm gypsum boards joined taped smoothened finish. **Location : As per design**	292	Sq.m	107.00	4/9/2025
6.02	**60 X 60 CM VINYL FACED GYPSUM CEILING.** Supply and installation of 60x60cm vinyl faced ceiling tile. **Location : Server room**	4	Sq.m	114.00	456.00
6.03	**GYPSUM CEILING PAINT** Supply and application of **Jotun Fenomastic WHITE paint** including all cleaning and levelling. As per design and approved sample. (2 coats including sanding). **Location : Proposed Gypsum ceiling areas**	164	Sq.m	34.00	5,576.00
6.04	**GYPSUM CEILING PAINT COLOR** Supply and application of **Jotun Fenomastic Color paint** including all cleaning and levelling. As per design and approved sample. (2 coats including sanding). **Location : Proposed Gypsum ceiling areas**	128	Sq.m	39.00	4,992.00
6.05	Supply and Installation of Acoustic Cloud Ceiling Thickness: 12 mm Cloud size: 1800 mm dia - 3 Nos **Location: Open stage Seating**	1	Ls	7,082.00	7,082.00
6.06	Allow Necessary charges for relocation of existing acoustic baffle ceiling panel Location: Conference Room Note: 1) We have assumed existing panels are in good condition to relocate. 2) New panel and Any modification work excluded	1	Ls	2,266.00	2,266.00
6.07	**GYPSUM BULKHEAD** Supply and installation of 100/200 mm high Gypsum Bulkhead with 12.5 mm gypsum boards with paint finish.	55	Lm	132.00	7,260.00
6.08	**GYPSUM BULKHEAD - COVE LIGHT** Supply and installation of 100 mm high Gypsum Bulkhead for cove with 12.5 mm gypsum boards with paint finish.	31	Lm	139.00	4,309.00
6.09	**GYPSUM BULKHEAD - U BULKHEAD** Supply and installation of 100 mm high Gypsum Bulkhead with 12.5 mm gypsum boards with black paint finish. **Location: Conference Room**	15	Lm	146.00	2,190.00
6.10	**GYPSUM BULKHEAD** Supply and installation of 900 mm high Gypsum Bulkhead with 12.5 mm gypsum boards with white paint finish. **Location: Baffle ceiling area**	12	Lm	132.00	1,584.00

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR HUSPY @ MARINA PLAZA , DUBAI-UAE

Quote Ref No: VID/1019/25/CP/QTN_01/R04 **15-Apr-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
6.11	**GYPSUM BULKHEAD** Supply and installation of 900 mm high Gypsum Bulkhead with 12.5 mm gypsum boards with color paint finish. **Location: Workstation passage**	88	Lm	137.00	12,056.00
6.12	**GYPSUM BULKHEAD** Supply and installation of 400 mm high Gypsum Bulkhead with 12.5 mm gypsum boards with color paint finish. **Location: Manager desk Area, Printer Area**	10	Lm	137.00	1,370.00
6.13	**GYPSUM PELMET** Supply and installation of **Gypsum Pelmet** with necessary fittings with paint finish. **Location : For blinds**	82	LM	132.00	10,824.00
6.14	**SHADOW GAP** Supply and installation of shadow gap as per the design.	154	LM	36.00	5,544.00
6.15	**GYPSUM ACCESS PANEL** Supply and installation of **Gypsum access panel (Max 60 x 60 cm)** with frame and hinges. **Location: Proposed Gypsum ceiling area** Note : Subject to final MEP drawings	9	Nos.	308.00	2,772.00
6.16	**OPEN CEILING PAINT** Supply and application of **Jotun Fenomastic paint at Open ceiling** with MEP Services.	450	Sq.m	57.00	25,650.00
	Note : All finishes are subject to final sample approval.				
	SUB TOTAL CEILING FINISH :				**125,175.00**
7.00	**DOORS**				
7.01	**ACOUSTIC GLASS DOOR** Supply and fixing of 13.52mm clear acoustic laminated (6 mm clear tempered glass + 1.52 mm acoustic PVB + 6mm clear tempered glass) glass single leaf frameless glass doors with all around straight polished edges fixing by DORMA BTS 65 floor machine, OFFSET pivot hinges , bottom lock and 800*600 mm long H type handle including all around 50 mm wide overlapped UNICA door frame. Size: 1000x2700mm **Location : Meeting rooms 2 Nos, Conference Room**	3	Nos	4,983.00	14,949.00
7.02	Supply and fixing of 12 mm clear tempered glass single leaf 76 * 42 mm powder coated beading type aluminium framed pivot door with all around straight polish edges fixing with DORMA BTS 65 floor machine, top and bottom pivot, bottom lock and 800 * 600 mm long H type round straight handle. Size:- 1000x2700mm **Location : Workstation Entrance**	2	Nos	3,232.00	6,464.00
7.03	**SINGLE LEAF WOODEN DOOR - NON FR** Supply and installation of Semi solid wooden swing door NON FR in PU paint finish, with Frame, architrave, in PU paint finish with all necessary ironmongery and material for fixing. Size: 900 x 2200mm Ht **Location : Podcast Room** Note : Concealed door	1	No.	4,512.00	4,512.00

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR HUSPY @ MARINA PLAZA , DUBAI-UAE

Quote Ref No: VID/1019/25/CP/QTN_01/R04 **15-Apr-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
7.04	**WOODEN SWING DOOR - FR 60 min** Supply and installation of single leaf 60 mins-fire rated MDF flush single swing door with solid Meranti or Beech wood frame and architraves in approved matte or semi-gloss PU paint finish including all necessary standard ironmongeries. Size : 900 mm x H 2200 mm **Location : Server room**	1	Nos	5,724.00	5,724.00
7.05	Allow Necessary charge for removal and refixing of existing glass entrance door and supply and installation of MDF framing in PU paint finish. Note: price is including the powder coating of existing ironmongery	1	Ls	4,579.00	4,579.00
	SUB TOTAL DOORS :				**36,228.00**
8.00	**SIGNAGE WORKS - Provisional Sum**				
8.01	Supply and installation of aluminum 3D painted back lit signage as per the design. Size: L 1800 x H 600 mm **Location : Reception** Note : Subject to final design and sample approval.	1	Item	6,505.00	6,505.00
8.02	Fabrication installation of 40mm embossed aluminum powders coated sides with 4mm thick acrylic fascia signage with frontlit led. Size: L 2000 mm **Location : Coffee Bar column** 	1	Item	6,581.00	Rate Only
	Note : 1. Any other signage excluded.				
	SUB TOTAL SIGNAGE WORKS :				**6,505.00**
9.00	**JOINERY WORKS**				
9.01	**RECEPTION DESK** Fabrication, Supply and installation of **Reception counter with MDF in veneer/ PU paint finish** as per design. **Overall Size : 2500 mm x 900 mm x 1100 mm** **Location : Reception** 	1	Item	10,819.00	10,819.00
9.02	**LEDGE** Fabrication, supply and installation of Ledge made MDF with marble top finish and fluted cladding on column as per design. Size: (900+4000+900) mm x 350mm **Location : Entrance Area** **Marble PC Rate : 350 / -per sq.m.** 	1	Item	16,927.00	16,927.00

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR HUSPY @ MARINA PLAZA , DUBAI-UAE

Quote Ref No: VID/1019/25/CP/QTN_01/R04 **15-Apr-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
9.03	**COFFEE COUNTER** Fabrication, supply and installation of Dry Coffee counter with **MDF Unit in veneer finish** with **2cm Marble counter top** and shelves made MDF in veneer finish as per design with all necessary for fixing. **Location : Entrance Coffee bar Area** Lower cabinet size : 6000 x 600 x 900 mm Shelves size : 6000 x 300 mm Note : Tile Backsplash Considered Separately **Marble PC Rate : 350 / -per sq.m.** 	1	Item	31,116.00	31,116.00
9.04	Supply and installation of Curved edge for reception back wall made MDF in PU paint finish with provision for cove as per design.	1	Item	2,146.00	2,146.00
9.05	**TV WALL UNIT** Fabrication, Supply and installation of plain MDF wall cladding in wood veneer/PU paint finish with groove as per the design including necessary fittings and accessories for installation . Overall Wall size: 5000 x 2700 mm **Location Conference Room** 	1	Item	9,657.00	9,657.00
9.06	**SEATING WITH PLANTER BOX** Fabrication, supply and installation of seating unit with MDF in veneer finish and fabric upholstered cushion, planter box made MDF in veneer finish as per the design. Seating Size: 3200mm x 600 x 500mm Planter Box: 3200 x 600 x 1100mm **Location Conference Room** Note: Planter box considered for artificial plants Plants Excluded	1	Item	19,456.00	19,456.00
9.07	Fabrication, Supply and installation of 25mm High Linear strip made MDF in PU paint finish.	1	Item	2,575.00	2,575.00
9.08	**HOT DESK** Fabrication, supply and installation of Hot desk with round leg made MDF in veneer finish with provision for plant as per design including necessary materials for installation. Size : : 4250 x 700 mm **Location : Workstation** 	2	Item	7,486.00	14,972.00
9.09	**PLANTER BOX FOR ARTIFICIAL PLANT** Fabrication, supply and installation of planter box made with MDF in veneer finish, necessary materials for installation. Size: (3150) x 300 x 1100mm **Location : Workstation**	2	Item	6,760.00	13,520.00

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR HUSPY @ MARINA PLAZA , DUBAI-UAE

Quote Ref No: VID/1019/25/CP/QTN_01/R04 — **15-Apr-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
9.10	**PRINTER CABINET** Fabrication, supply and installation of Printer cabinet with MDF in veneer finish as below with all necessary for fixing. **Lower cabinet size : 3550 x 600 x 1100 mm** **Upper cabinet size : 3550 x 500 x 600 mm** 	1	Item	8,959.00	8,959.00
9.11	**FULL HEIGHT CABINET** Fabrication, supply and installation of Full height cabinets made with MDF in PU paint finish including necessary materials for installation. Overall size : L6250 x D650 x H2700 mm **Location : UTILITY CABINET**	1	Item	24,142.00	24,142.00
9.12	Allow necessary charges for removal and refixing of existing booth seating without any modification and seating. Fabrication, supply and installation of seating unit with MDF in veneer finish and fabric upholstered cushion. Seating Size: 1200x600x500mm - 2 Nos	1	Item	10,215.00	10,215.00
9.13	Supply and installation of platform Edge made MDF finished by veneer finish.	1	Item	3,262.00	3,262.00
9.14	**CUSTOM MADE WORKSTATION** Custom made - made with top & base in MDF with laminate finish, planter box made MDF in laminate finish. Includes PDU (2 USB CHARGER (A+C) + 2 UK Power+ 2 CAT 6 Data and with Cable Starter: 2.2 meter UK), cable tray, cable spine 				
a	**CLUSTER OF 6 PAX - FACE TO FACE** Size : L3600 x D1200 x H750 mm	10	No.	15,193.00	Rate Only
b	**CLUSTER OF 4 PAX - FACE TO FACE** Size : L2400 x D1200 x H750 mm	14	No.	10,044.00	Rate Only
c	**CLUSTER OF 4 PAX - LINEAR** Size : L4800 x D700 x H750 mm	2	No.	10,548.00	Rate Only
d	**RECTANGULAR DESKS** Size : L1600 x D800 x H750 mm	4	No.	4,025.00	Rate Only
	SUB TOTAL JOINERY WORKS :				**167,766.00**
10.00	**LIGHTING WORKS - NON DIMMABLE**				
	Supply of the following lights				
10.01	**DECORATIVE LIGHT** **Location : Reception** **Size : 1000 mm** **Wattage : 5x5W** 	1	Nos	1,956.00	1,956.00

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR HUSPY @ MARINA PLAZA , DUBAI-UAE

Quote Ref No: VID/1019/25/CP/QTN_01/R04 — **15-Apr-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
10.02	**DECORATIVE LIGHT** **Location : Meeting rooms + MD cabin** **Dia : 380 mm** **Wattage : 10W**	2	Nos	265.00	530.00
10.03.a	**MAGNETIC TRACK** **Size : 1000 mm** **Location : As per design**	100	LM	254.00	25,400.00
10.03.b	**MAGNETIC TRACK LIGHT** **Wattage : 3 x 2 W** **Size : 106 x 35 x 59 mm** **Location : Meeting rooms + workstation area + MD cabin**	65	Nos	164.00	10,660.00
10.05	**DOUBLE SPOT LIGHT** **Finish : Black** **Location : Pantry** **Size: 196x104mm , 2x11W**	8	Nos	227.00	1,816.00
10.06	**PENDANT LIGHT - (20 W)** **Overall Size : 95 mm dia x 150 mm**	81	Nos	145.00	11,745.00
10.07	**SPOT LIGHT - 11 W**	29	Nos	82.00	2,378.00
10.08	**WALL MOUNTED LIGHT - 8W**	2	Nos	442.00	884.00
10.09	**WALL MOUNTED LIGHT - 3x3W**	4	Nos	215.00	860.00
10.10	**SUSPENDED LINEAR LIGHT** **Oblong Size: L4000xW800mm**	1	Nos	3,659.00	3,659.00
10.11	**SUSPENDED LINEAR LIGHT** **Size: L5000** Note: We have not consider curved edges	1	Nos	1,514.00	1,514.00
10.12	**LINEAR LIGHT - (40 W/m)** **Profile Size : 50 x 75 x 3600 mm**	19	Nos	1,090.00	20,710.00
10.13	**LINEAR LIGHT - (40 W/m)** **Profile Size : 50 x 75 x 6000 mm**	2	Nos	1,817.00	3,634.00

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR HUSPY @ MARINA PLAZA , DUBAI-UAE

Quote Ref No: VID/1019/25/CP/QTN_01/R04 **15-Apr-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
10.14	**ROUND DOWN LIGHT**	11	Nos	82.00	902.00
10.15	**LED STRIP LIGHT including driver**	85	LM	109.00	9,265.00
10.16	**SUSPENDED CIRCULAR LIGHT** **Size: 900mm Dia**	2	Nos	946.00	1,892.00
10.17	**SUSPENDED CIRCULAR LIGHT** **Size: 1800mm Dia**	1	Nos	1,830.00	1,830.00
	Note : 1. Quantity subject to final RCP design and LUX calculations 2. Non dimmable lights				
	SUB TOTAL LIGHTS :				**99,635.00**
	MEP WORKS				
11.00	**HVAC WORKS**				
	AC MACHINES AND ACCESSORIES				
11.01	Relocation of existing FCU from existing office based on new design Note : Considering existing AC machines are in good working condition.	2	Nos.	1,431.00	2,862.00
11.02	Relocation of existing thermostat	9	Nos	358.00	3,222.00
11.03	Performance test of existing FCU	9	Nos	715.00	Rate Only
	CHW PIPING AND ACCESSORIES				
11.04	Modification and extension of the existing chilled water piping as required	1	Ls	7,153.00	7,153.00
11.05	Chemical flushing - Culligan	1	Ls	12,876.00	12,876.00
	DUCTING AND ACCESSORIES				
11.06	Supply and installation of new Phenolic ducting including all the accessories	1	Ls.	34,069.00	34,069.00
11.07	Supply and installation of **12 mm rubber type Acoustic liner**				
11.08	Supply and installation of **Volume Control Damper.**				
11.09	Supply and Installation of flexible duct, plenum box and ring.				
11.10	Supply and installation of cross talk attenuator , Location: Meeting Room, Conference	1	Ls	3,407.00	3,407.00
11.11	Extension of duct for the fresh and extract air using phenolic ducting Note : Stub out present at site	1	Item	19,307.00	19,307.00
	GRILLS AND DIFFUSER				
11.12	Linear Slot grills/Diffuser	1	Item	12,875.00	12,875.00
	DRAIN PIPE				
11.13	Supply and Installation of **PVC Pipe** with insulation. - connecting to the existing line	1	Item	5,793.00	5,793.00
11.14	Testing and commissioning with air balancing (Verve)	1	Item	2,143.00	2,143.00
11.15	Third party testing with air balancing works	1	Item	6,438.00	6,438.00

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR HUSPY @ MARINA PLAZA , DUBAI-UAE

Quote Ref No: VID/1019/25/CP/QTN_01/R04 **15-Apr-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
	Notes : 1. BTU Meter works and BMS Connection / cabling/ wiring excluded 2. We have assumed existing FCU are in good condition; only relocation of 2 Nos considered. . Due top non availability of As-built drawings relocation of FCU to be confirmed as per site condition upon commencement of work				
	SUB TOTAL HVAC WORKS :				**110,145.00**
12.00	**ELECTRICAL WORKS**				
12.01	PVC conduiting and wiring for light points including installation. Note: Light points are subject to revise upon final RCP Layout.	217	Nos	207.00	44,815.50
12.02	Supply and installation of **Single switches for lighting.** Including cabling works.(MK-Normal White)	14	Nos	258.00	3,612.00
12.03	Supply and installation of **Grid switch for lighting.** Including **PVC conduiting**. (Black Matt PVC finish Legrand / schneider) for Open workstation & corridor.	2	Nos	259.00	518.00
12.04	Supply and installation of **13A Single wall Power Socket,** in PVC finish including conduiting and wiring. (Schneider / Legrand)	15	Nos	315.00	4,725.00
12.05	Supply and installation of **13A Twin wall Power Socket,** in black PVC finish including conduiting and wiring. (Schneider / Legrand)	14	Nos	336.00	4,704.00
12.06	Supply and installation of **15A Single wall Power Socket,** in Black PVC finish including conduiting and wiring. (Schneider / Legrand)	3	Nos	465.00	1,395.00
12.07	Supply and installation of **Floor Box -Twin 13A+ Twin Data.** with cabling and conduiting and data and telephone plates provision only. Make : Obo or equivalent Note: 1 Nos Floor Box for 4 Person considered	46	Nos	644.00	29,624.00
12.08	50mm conduit and cabling provision for HDMI/VGI.	5	Nos.	644.00	3,220.00
12.09	Supply and installation of **PVC** containment for **WI-FI Points**. (Provisional qty)	6	Nos.	179.00	1,074.00
12.10	Supply and installation of PVC containment for **Access control** (Provisional qty)	4	Nos	179.00	716.00
12.11	Supply and installation of **PVC** containment for **CCTV Points**. (Provisional qty)	6	Nos.	179.00	1,074.00
12.12	Supply and installation of **PVC** containment for speakers system . (Provisional qty)	6	Nos.	179.00	1,074.00
12.13	Supply and installation of **PVC** containment for printers.	2	Nos.	179.00	358.00
12.14	Supply and installation of **PVC** containment for **AV Rack**	1	Nos.	179.00	179.00
12.15	Supply and installation of **PVC** containment for thermostat (Replacement of existing thermostat)	9	Nos.	179.00	1,611.00
12.16	Power provision for **Signage** with timer switch	1	Nos.	930.00	930.00
12.17	Supply and installation of **New SMDB** assembling, dressing, fixing as per DEWA standard.	1	Nos	7,010.00	7,010.00
12.18	Supply and installation of **MCC**	1	Nos	2,861.00	2,861.00
12.19	Supply and installation of Armoured cable . (For SMDB)	1	LS	10,730.00	10,730.00
12.20	Relocation of existing **DB** with all other accessories as per DEWA standards Note : Subject to load availability	1	Item	5,722.00	5,722.00
12.21	Supply & Installation of 100mm GI Cable Tray with necessary fittings & supports -For armoured cable	1	LS	4,292.00	4,292.00

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai.UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR HUSPY @ MARINA PLAZA , DUBAI-UAE

Quote Ref No: VID/1019/25/CP/QTN_01/R04 **15-Apr-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
12.22	Supply & Installation of 150mm GI Cable Tray with necessary fittings & supports -For IT, AV, Light, Power	1	Lot	16,595.00	16,595.00
12.23	DEWA submission, inspection and approval. - 1 submission considered	1	No	5,007.00	5,007.00
12.24	Testing commissioning.	1	Item	2,146.00	2,146.00
12.25	Providing **PVC conduit for Data for workstations and cabins** Note : Not considered for workstations	144	Nos	157.00	22,608.00
12.26	Allow Necessary charges for demerging and merging of existing DB	1	Ls	7,152.50	7,152.50
	Note: 1. We have assumed that the existing infrastructure's power has sufficient capacity to cater to the requirement of the project. 2. We have not allowed for upgrade of the capacity of any base building system. 3. All electrical conduits considered are of PVC type. 4. We have not allowed for any specific lighting control system in this offer. 5. Subject to final MEP drawings **Exclusions:** 1. Any BMS integration or related works. 2. DEWA Consultancy for power upgrade.				
	SUB TOTAL ELECTRICAL WORKS :				**183,753.00**
13.00	**CIVIL DEFENCE WORKS - PROVISIONAL SUM**				
13.01	**FIRE ALARM WORKS**				
a	Supply and installation of Fire Alarm Control Panel (GENT)	1	Nos		
b	Re-Installation of existing Smoke detector with New Piping & Cabling	25	Nos		
c	Supply and installation of MCP WITH BACK BOX	2	Nos		
d	Supply and installation of Void smoke detector with LED indicator	1	item		
e	Supply and installation of Sounder with Flasher	3	Nos		
f	Building Interfacing	1	Item		
g	24x7/Access Control Interfacing	1	Item		
h	Fire Alarm Control Panel Programming (SD:31,HD:1,MCP:2,Sounder:3)	1	Item		
j	Dismantling of Existing Fire Alarm System	1	Item		
13.02	**FIRE FIGHTING WORKS**				
a	Supply and installation of Pendent Sprinkler(Q.R 68°C)	6	Nos		
b	Relocation of Existing Fire Extinguisher	15	Nos		
d	Supply and installation of Fire Blanket (FIREGUARD)	1	Item		
d	Relocation of Existing Concealed Sprinkler with New Pendent Sprinkler Head(Q.R 68°C)	1	Item		
e	Supply and installation of automatic extinguisher.	1	Item	LS	128,558.00
f	Sprinkler line Draining & Refilling	1	Item		
g	Supply, Warranty and installation Certificates				
13.03	**EMERGENCY WORKS**				
b	Supply and installation of Self Contained Emergency Light Surface Mounted Type (FRONTIER)	8	Nos.		
c	Supply and installation of Self Contained Exit Light Hanging (FRONTIER)	1	Item		

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR HUSPY @ MARINA PLAZA , DUBAI-UAE					
Quote Ref No: VID/1019/25/CP/QTN_01/R04					15-Apr-25
SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
	Notes / Exclusions: 1. Any additional charges/ fees for any third party shall be paid by the client. 3. Assumed existing sprinkler heads are as per the DCD standards 4. FM 200, central battery system works excluded 5. Existing Sprinkler main line Modification for other services excluded. 6. Any existing device found damaged/faulty on re-installation time will be charged accordingly. **7. Rates subject to base build contractor , Verve to charge 15% coordination charge on actual quote submitted by Base build contractor. Verve provided provisional sum**				
	SUB TOTAL CIVIL DEFENCE WORKS :				**128,558.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR HUSPY @ MARINA PLAZA , DUBAI-UAE

Quote Ref No: VID/1019/25/CP/QTN_01/R0 — April 15, 2025

SR.NO	As per 3D	SAMPLE IMAGE	DESCRIPTION	QTY	UNIT	RATE	TOTAL (AED)
17.00	LOOSE FURNITURE						
			RECEPTION AND COFFEE BAR AREA				
17.01			**TASK CHAIR**	1	No.		By Client
17.02			**SOFA SEATER** Size : L3200 x D900 x H430/850 mm Material : Fabric	2	No.	5,868.00	11,736.00
17.03			**LOUNGE CHAIRS** Material : Fabric	4	No.	3,495.00	Rate only
Option			**LOUNGE CHAIRS** Material : Fabric	4	No.	1,868.00	7,472.00
17.04			**CENTER TABLE** Size Dia 800 x H400 mm Finish : Marble	2	No.	3,609.00	7,218.00
17.05			**LOUNGE CHAIRS** Material : Fabric/ PU leather	2	No.	1,451.00	2,902.00
17.06			**CENTER TABLE** Size Dia 650 x H400 mm Finish : Stone table top, wooden PU paint legs	2	No.	2,461.00	4,922.00
			CONFERENCE ROOM				
17.07			**CONFERENCE TABLE** Custom made - Table top made with 40 mm thick MDF with wood veneer finish, base in MDF PU paint finish Size : L4800 x D1200 x H750 mm	1	No.	20,726.00	20,726.00
Option			**CONFERENCE TABLE** Material : Melamine top with painted legs Size : L4800 x D1200 x H750 mm	1	No.	9,022.00	Rate only

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR HUSPY @ MARINA PLAZA , DUBAI-UAE

Quote Ref No: VID/1019/25/CP/QTN_01/R0 — **April 15, 2025**

SR.NO	As per 3D	SAMPLE IMAGE	DESCRIPTION	QTY	UNIT	RATE	TOTAL (AED)
17.08			**CONFERENCE CHAIRS** Material : PU leather	12	No.	1,224.00	14,688.00
			WORKSTATION				
17.09			**TASK CHAIR**	128	No.		By Client
17.10			**VISITOR CHAIRS**	8	No.	416.00	3,328.00
17.11			**PLANTER BOX** Planter box made with 18mm thick MR MDF in laminate finish. Size : L1200 x D350 x H1100 mm Note : Plants excluded	4	No.	2,145.00	8,580.00
17.12			**LOUNGE CHAIRS** Material : Fabric/ PU leather	2	No.	1,451.00	2,902.00
17.13			**CENTER TABLE** Size Dia 600 x H550 mm Finish : Solid Plywood with ash wood pattern Tabletop with steel base in white color.	1	No.	921.00	921.00
17.14			**POUF**	7	No.	814.00	5,698.00
17.15			**HIGH CHAIRS** Material : Fabric/ Metal powder coated legs	17	No.	959.00	16,303.00

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR HUSPY @ MARINA PLAZA , DUBAI-UAE

Quote Ref No: VID/1019/25/CP/QTN_01/R0 — **April 15, 2025**

SR.NO	As per 3D	SAMPLE IMAGE	DESCRIPTION	QTY	UNIT	RATE	TOTAL (AED)
17.16			**ROUND HIGH TABLE** melamine finish table top/ Metal powder coated legs. **Size : Dia 700 x H1100 mm**	6	Nos	997.00	5,982.00
17.17			**HIGH CHAIRS** Material : Fabric/ Metal powder coated legs	12	Nos	366.00	4,392.00
			MEETING ROOMS		####		
17.18			**ROUND MEETING TABLE** Melamine top with metal powdercoated legs Size : Dia 1200 x H750 mm	2	No.	997.00	1,994.00
17.19			**MEETING CHAIRS** Material : Fabric	8	No.	883.00	7,064.00
Option			**MEETING CHAIRS**	8	No.	1,830.00	Rate only
			PODCAST ROOM				
17.20			**SOFA SEATER** Size : L2000 x D760 x H440 mm Material : Fabric	1	No.	3,584.00	3,584.00
17.21			**LOUNGE CHAIRS** Material : Fabric/ PU leather	2	No.	1,451.00	2,902.00
17.22			**CENTER TABLE** 18 mm thick Melamine table top, with Metal pole leg with round flat base in chrome finish. Size : L1000 x D600 x H450 mm	1	No.	833.00	833.00

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR HUSPY @ MARINA PLAZA , DUBAI-UAE

Quote Ref No: VID/1019/25/CP/QTN_01/R0 — **April 3, 2025**

SR.NO	As per 3D	SAMPLE IMAGE	DESCRIPTION	QTY	UNIT	RATE	TOTAL (AED)
Option			**PEDESTAL** Pedestal made MDF outside in veneer finish. Dim:600*500*700 Ht mm.	1	Nos	1,073.00	Rate only
			ACOUSTIC PODS				
Option			**ACOUSTIC PODS** Dimension: W1080 X D1000 X H2326 mm	4	No.	24,932.00	Rate only
						TOTAL LOOSE FURNITURE :	**134,147.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

PROJECT NAME: INTERIOR FIT OUT WORKS FOR HUSPY @ MARINA PLAZA, DUBAI-UAE

PROJECT CODE: 1019_25

Quote Ref No: VID/1019/25/CP/QTN 01/R01

General Notes

1. The price is exclusive of Value Added Tax (VAT); 5% VAT shall be payable as an addition to the invoice value.
2. Any variation in terms of quantity that comes up during the course of work has to be paid by the client and hence client is liable for payment of Variation.
3. Insurance coverage is limited to CAR of Contract Value. If higher coverage limit is required by building management and any other authorities, the additional premium amount will be charged separately
4. LEED building consultancy and certification is excluded.
5. Hoarding, Branding and posters is excluded.
6. Professional indemnity insurance is excluded.
7. Performance & retention bank Bonds not considered.
8. Security deposit, Authority Fees, entry and exit pass for vehicles and labors, night work permit fee, Building/ Mall management fees (If required) has to be paid by the client on actuals
9. Provision for mock up and samples submissions at site as per requirement included, however special items are chargeable and shall be billed to the client on actual.
10. Customized workstation considered as rate only; if required there will be a variation.

NOTES & EXCLUSIONS

Internal finishes:

1. All finishes are subject final sample approval.

MEP Works:

1. All MEP works are subject final MEP design and authority approval.
2. Assuming existing cooling capacity is sufficient.
3. Ducting PI; Square or rectangular ducting.
4. We have assumed that the existing infrastructure's power has sufficient capacity to cater to the requirement of the project.
5. We have not allowed for upgrading the capacity of any base building system.
6. All electrical conduits considered are of PVC type.
7. We have not allowed for any specific lighting control system in this offer.
8. All terminations considered to the stub out present at site, connected to building system.

Civil Defense works

1. To be claimed on actual based on invoice submitted by AMC contractor (Verve to charge 15% of the value as coordination charges) Verve provided provisional sum.
2. Any additional charges/ fees for any third party shall be paid by the client.
3. FM 200, central battery system works excluded.
4. We have assumed existing Emergency control panel to have sufficient capacity to accommodate the new exit and emergency light. New Emergency control panel excluded from scope.

MEP works – Exclusions

1. BTU Meter, any BMS integration or related works.
2. DEWA Consultancy for power upgrade
3. New DB
4. IT cabling, CCTV camera, Access control, Speakers, Wi-Fi AP, BMS works, Occupancy sensor.

Exclusions

1. Any other items not mentioned in the attached BOQ.
2. White Goods, Music System
3. TV, LED Screen, Projector, Kitchen/ Pantry Equipment, Electronic devices.
4. All Artworks, Rugs, Accessories and marketing works.
5. Etisalat/Du works.
6. Task Chair.
7. Planters.

Thank you,

© **Verve Design, 2023**

Verve Interior Decoration llc

Unit M04,
Al Reemas Building,
Sheikh Zayed Road, Al Quoz,
PO Box - 128279,
Dubai, UAE.

t : +971 4 240 0119
f : +971 4 240 8403
info@vervedesign.ae
www.vervedesign.ae