verve

space + design

LEAN

PROPOSAL FOR INTERIOR FITOUT WORKS

INTERIOR FIT-OUT WORKS

FOR

AT

NASSIMA TOWER ,DUBAI -U.A.E

For
LEAN TECHNOLOGIES

Prepared by:

Verve Interior Decoration LLC
PO Box 128279, Dubai, UAE

Prepared on:

May 2, 2025

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

CONTRACT AGREEMENT: General terms and conditions

Project Timeline: As per approved Project schedule

Payment Terms:

Advance Payment : 30% Advance payment against order confirmation.
Progress Payment : 20% upon approval of all the material samples and mobilization of materials to the site
Progress Payment : 45% as per site progress
Final Payment : 5% upon work completion at site and hand over.

Payment to be honored within 7 days from the date of receipt of Invoice

All products offered by us on this project carry a warranty against defective materials and/or workmanship as follows:
Fit Out Works : 12 Months from the date of Handover.

Insurances:
All our personnel working on the project will be covered under our Workmen Compensation
All works carried out at site will be covered by our Contractor's All Risk Policy

Validity.
Our offer is valid for a period of 30 days from hereof
Note: Bank guarantee or Retention Requirements excluded

Please sign below for acceptance of the offer. The BOQ will be treated as the final scope of work and contract will form the integral part of the project.

Signature: _____
on behalf of: LEAN TECHNOLOGIES

Name:
Date:

Signature:_____
on behalf of : Verve Interior Decoration LLC

Name: Syed Mehdi
Date: May 2, 2025

Quote Ref No: VID/1057/25/CP/QTN_01/R1

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR LEAN TECHNOLOGIES @ NASSIMA TOWER , DUBAI-UAE		
Quote Ref No: VID/1057/25/CP/QTN_01/R1		02-May-25
SR. NO	SUMMARY	TOTAL (AED)
1	PRELIMINARIES	63,884.00
2	DEMOLITION AND CIVIL WORKS	83,237.00
3	PARTITION WORKS	153,683.00
4	FLOOR FINISH	243,222.00
5	WALL FINISH	274,727.00
6	CEILING FINISH	281,928.00
7	DOORS	117,485.00
8	SIGNAGE WORKS - Provisional Sum	9,393.00
9	JOINERY WORKS	205,533.00
10	LIGHTING WORKS - NON DIMMABLE	69,896.00
11	HVAC WORKS	123,716.00
12	ELECTRICAL WORKS	221,442.00
13	CIVIL DEFENCE WORKS - PROVISIONAL SUM	145,000.00
14	PLUMBING WORKS AND SANITARY WARES	41,285.00
	TOTAL AMOUNT (AED):	2,034,431.00
15	WHITE GOODS	3,261.00
16	LOOSE FURNITURE	355,790.00
17	ACOUSTIC PODS	89,010.00
	GRAND TOTAL AMOUNT (AED):	2,482,492.00

Note: **Any variation in terms of quantity that comes up during the course of work has to be paid by the client and hence client is liable for payment of Variation. Retention is not considered.**

Exclusions/Notes:

1) All fees and deposit for statutory authorities are excluded.
2) Any other items not mentioned in the attached BOQ.
3) 3D is provided for the reference purposes , we have followed the GA plan for the quotation provided.
4) Any work related to general common area are excluded.
5) Only deep cleaning and minor ceiling modifications in the male and female toilets are included; existing tiles and sanitary wares will be retained

For Verve Interior Decoration LLC

Syed Mehdi
Sales Director
+971 50 513 9878
syed@vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR LEAN TECHNOLOGIES @ NASSIMA TOWER , DUBAI-UAE

Quote Ref No: VID/1057/25/CP/QTN_01/R1 **02-May-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
1.00	**PRELIMINARIES**				
1.01	General- Contractor's preliminaries for mobilization, site preparation, Provision for all temporary barricades, setting out transportations to/from site, material deliveries, small tools and equipment's, protection of finished products in on-going site, site attendance and call out attendance, electricity & water charges . PPE and other site requirements to be followed	1	Item	18,064.00	18,064.00
1.02	Co ordination Charges for obtaining approvals from the Landlord & the related authorities.	1	Item	5,058.00	5,058.00
1.03	Preparation of Technical drawings as required for submission to Relevant authorities. Detail drawings includes Architectural and MEP drawings. Subject to receipt of current approved as built drawings	1	Item	14,461.00	14,461.00
1.04	CAR Insurance for fit out work during the execution of works. (includes third party liability) *Note: Insurance coverage is limited to CAR of Contract Value. If higher coverage limit is required by building management and any other authorities, the additional premium amount will be charged separately* .	1	Item	3,613.00	3,613.00
1.05	Professional indemnity insurance	1	Item	11,561.00	Rate Only
1.06	Regular cleaning of site during construction period and after completion professional deep cleaning and made ready to occupy. Including carting away the debris to Municipal dumping area. Note : Price includes the deep cleaning of the existing toilets .	1	Item	8,960.00	8,960.00
1.07	Charges for site protection (protection of common area finishes and the area near to the work space)	1	Item	4,335.00	4,335.00
1.08	Charges for scaffolding	1	Item	9,393.00	9,393.00
	Note: Security deposit, Authority Fees, entry and exit pass for vehicles and labors, night work permit fee, Mall management fees(If required) has to be paid by the client on actuals				
	Note : Provision for mock up and samples submissions at site as per requirement included, however special items are chargeable and shall be billed to the client on actual.				
				SUB TOTAL PRELIMINARIES :	**63,884.00**
2.00	**DEMOLITION AND CIVIL WORKS**				
2.01	Demolition of the existing walls, doors, floor & ceiling finishes as per site condition including carting away to DM approved yard . Note : Price includes removal of the existing raised floor , complete demolition of the 2 nos. washrooms	1	Ls.	78,902.00	78,902.00
2.02	Builders works to accommodate MEP works	1	Ls.	4,335.00	4,335.00
2.03	Provisional Sum for the lift lobby upgrade as per approved design . Note : Subject to final design approval and materials selection by client	1	Ls.	92,517.00	Rate only
				SUB TOTAL DEMOLITION AND CIVIL WORKS :	**83,237.00**
3.00	**PARTITION WORKS**				
3.01	**GYPSUM PARTITION SINGLE LAYER (NON FR)** Supply and installation of 100 mm Thk Non-FR gypsum partition with 12.5 mm Thk Non-FR gypsum board (Knauf or equivalent) single layer on both sides with studs, 50mm thick rockwool insulation and necessary frames and accessories. Height up to 4 m **Location : As per layout**	38	Sq.m	137.00	5,206.00

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR LEAN TECHNOLOGIES @ NASSIMA TOWER , DUBAI-UAE

Quote Ref No: VID/1057/25/CP/QTN_01/R1 **02-May-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
3.02	**GYPSUM PARTITION SINGLE LAYER (NON FR)** Supply and installation of 200 mm Thk Non-FR gypsum partition with 12.5 mm Thk Non-FR gypsum board (Knauf or equivalent) single layer on both sides with studs, 50mm thick rockwool insulation and necessary frames and accessories. Height up to 4 m **Location : As per layout**	24	Sq.m	173.00	4,152.00
3.03	**CURVED GYPSUM PARTITION SINGLE LAYER (NON FR)** Supply and installation of 200 mm Thk Non-FR gypsum partition with 12.5 mm Thk Non-FR gypsum board (Knauf or equivalent) single layer on both sides with studs, 50mm thick rockwool insulation and necessary frames and accessories. Height up to 4 m **Location : As per layout**	4	Sq.m	145.00	580.00
3.04	**GYPSUM PARTITION DOUBLE LAYER (NON FR)** Supply and installation of 125 mm Thk Non-FR gypsum partition with 2 x 12.5 mm Thk Non-FR gypsum board (Knauf or equivalent) double layer on both sides with studs, 50mm thick rockwool insulation and necessary frames and accessories. Height up to 4 m **Location : Conference Room 12 to 14 PAX, All Meeting Rooms , Custom phone booths**	207	Sq.m	195.00	Rate Only
3.04a	**GYPSUM PARTITION SINGLE LAYER (NON FR)** Supply and installation of 100 mm Thk Non-FR gypsum partition with 12.5 mm Thk Non-FR gypsum board (Knauf or equivalent) single layer on both sides with studs, 50mm thick rockwool insulation and necessary frames and accessories. Height up to 4 m **Location : As per layout**	207	Sq.m	137.00	28,359.00
3.05	**CURVED GYPSUM PARTITION DOUBLE LAYER (NON FR)** Supply and installation of 125 mm Thk Non-FR gypsum partition with 2 x 12.5 mm Thk Non-FR gypsum board (Knauf or equivalent) double layer on both sides with studs, 50mm thick rockwool insulation and necessary frames and accessories. Height up to 4 m **Location : Meeting Room near Reception Area**	4	Sq.m	181.00	724.00
3.06	**ACOUSTIC GLASS PARTITION - NON FR** Supply and fixing of 25 x 25 mm aluminum framed QIC partition utilizing 13.52mm clear acoustic laminated (6 mm clear tempered glass + 1.52 mm acoustic PVB + 6mm clear tempered glass) with all around straight polished edges fixing by clip profiles with rubber gasket , including glass to glass beading joints . Height up to 2.7 m **Location : Conference Room , All meeting rooms , Custom phone booths , Entrance to collaboration area**	57	Sq.m	795.00	45,315.00
3.07	**GYPSUM BAFFLE (NON-FR)** Supply and installation of **Non-FR gypsum baffle wall** with 12.5mm Thk Non-FR gypsum board (Knauf or equivalent) single layer on both sides with 50mm thick rockwool insulation, necessary frames and accessories . Height up to 1 m **Location : Above proposed Foldable partition**	10	LM	137.00	1,370.00
3.08	**GYPSUM BAFFLE (NON-FR)** Supply and installation of **Non-FR gypsum baffle wall** with 12.5mm Thk Non-FR gypsum board (Knauf or equivalent) single layer on both sides with 50mm thick rockwool insulation, necessary frames and accessories . Height up to 1.3 m **Location : Above proposed acoustic glass partition**	43	sq.m.	123.00	5,289.00
3.09	Provision for MDF support below proposed glass partitions / raised floor	35	LM	181.00	6,335.00

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai.UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR LEAN TECHNOLOGIES @ NASSIMA TOWER , DUBAI-UAE

Quote Ref No: VID/1057/25/CP/QTN_01/R1 **02-May-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
3.10	**GYPSUM CLADDING - NFR** Supply and installation of **NFR 12.5 mm thick Gypsum board (Knauf or equivalent) wall cladding** with necessary material for fixing, smoothened and made ready to receive final finishes. Height up to 3 m **Location : one wall in the Engineer's offices, one wall 2 Nos 4 PAX Meeting Room** Note: Gypsum cladding to the existing columns excluded.	27	Sq.m	108.00	2,916.00
3.11	Supply and installation of MDF support to install the TV and LED Screens	11	Nos.	361.00	3,971.00
3.12	Supply and installation of sliding / folding door with frame and 38 mm thick sealed double glazed unit with 2 layers of 11.52 mm clear tempered laminated glass with 14 mm thick spacer Size : 3050 x 3000 mm Acoustic Rating upto 46 DB .	1	Nos.	39,624.00	39,624.00
3.13	Supply and installation of MS - metal structure to support the above operable partition. Height : 1000 mm	1	Ls.	5,600.00	5,600.00
	WASHROOMS REFURBISHMENT				
3.14	**CEMENT BOARD CLADDING - NFR** Supply and installation of **NFR 12.5 mm thick CEMENT board (Geminite or equivalent) wall cladding** with necessary material for fixing, smoothened and made ready to receive final finishes. Height up to 3 m **Location : Behind WC to receive wall mounted WC + Urinal**	21	Sq.m	202.00	4,242.00
	Note : Any wall cladding to any other existing walls is excluded from scope .				
				SUB TOTAL PARTITION WORKS :	**153,683.00**
4.00	**FLOOR FINISH**				
4.01	Supply and installation of new FS 800 raised floor including all the fixing materials . Height : 150 to 170 mm Make : ZT floor or equivalent	618	sq.m.	170.00	105,060.00
4.02	Supply and installation of raised platform with carpet and wooden veneer finish as per the design. Location : Collaboration area	1	Ls.	2,818.00	2,818.00
4.03	**SELF LEVELLING ON RAISED FLOOR** Supply and installation of 2 to 3 mm self levelling compound to make the floor ready to receive the new flooring. **Location : Proposed LVT flooring , Tile Flooring**	211	Sq.m	101.00	21,311.00
4.04	**CARPET FLOORING - TYPE 1** Supply and Installation of Carpet tile flooring including adhesives and all necessary material for fixing. Make : Tegola or equivalent **Location : Workstation areas** Note : To be installed directly on the raised floor	269	Sq.m	136.00	36,584.00
4.05	**CARPET FLOORING - TYPE 2** Supply and Installation of Carpet tile flooring including adhesives and all necessary material for fixing. Make : Modulyss-Alpha / First Forward or equivalent **Location : Phone booth + Meeting rooms** Note : To be installed directly on the raised floor	108	Sq.m	169.00	18,252.00

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR LEAN TECHNOLOGIES @ NASSIMA TOWER , DUBAI-UAE

Quote Ref No: VID/1057/25/CP/QTN_01/R1 **02-May-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
4.06	**CARPET FLOORING - TYPE 3** Supply and Installation of Carpet tile flooring including adhesives and all necessary material for fixing. Make : Canvas or equivalent **Location : Conference room + Platform in collaboration area** Note : To be installed directly on the raised floor	34	Sq.m	136.00	4,624.00
4.07	**LVT FLOORING - TYPE 1** Supply and installation of **Luxury Vinyl Tile flooring** with necessary material for installation. Make : Amtico Spacia or equivalent **Location : Reception**	10	Sq.m	201.00	2,010.00
4.08	**LVT FLOORING - TYPE 2** Supply and installation of **Luxury Vinyl Tile flooring** with necessary material for installation. Make : Nox or equivalent **Location : Passages + Reception + Dining room and Pantry area**	122	Sq.m	161.00	19,642.00
4.09	**LVT FLOORING - TYPE 2** Supply and installation of **Luxury Vinyl Tile flooring** with necessary material for installation. Make : Nox or equivalent **Location : Collaboration area + Open Hot desk area**	69	Sq.m	181.00	12,489.00
4.09 opt	**LVT FLOORING - TYPE 1** Supply and installation of **Luxury Vinyl Tile flooring** with necessary material for installation. Make : Amtico Spacia or equivalent **Location : Collaboration area**	46	Sq.m	201.00	Rate only
4.10	**TILE FLOORING** Supply and installation of 200 x 200 mm Decorative **Tile flooring** with necessary material for installation. **PC Rate : 60/- per sq.m.** **Location : Collaboration area**	12	Sq.m	207.00	2,484.00
4.11	**TRANSITION STRIP** Supply and installation of Transition Strip in SS finish (ready available). **Location : Between different floor finishes, Door entrances.**	89	LM	108.00	9,612.00
	WASHROOMS REFURBISHMENT				
4.12	**TILE FLOORING** Supply and installation of 600 x 600 mm **Tile flooring** with necessary material for installation , considered normal grout . **Note : Epoxy grout excluded** **PC Rate : 55/- per sq.m.** **Location : Toilets and near corridor**	40	Sq.m	161.00	6,440.00
4.13	Supply and installation of threshold , 1000 mm long and 200 mm wide. PC Rate : 250/ sq.m.	6	Nos.	316.00	1,896.00
	Note: All finishes are subject to final sample approval.				
				SUB TOTAL FLOOR FINISH :	**243,222.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR LEAN TECHNOLOGIES @ NASSIMA TOWER , DUBAI-UAE

Quote Ref No: VID/1057/25/CP/QTN_01/R1 **02-May-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
5.00	**WALL FINISH**				
5.01	**MARBLE LOOK WALL CLADDING** **Location : Reception**				
a	**WALL TILE** Supply and installation of wall tiles including necessary materials for fixing. Height upto 2.5 m PC Rate : 350 AED per Sq.m Size : 120 x 280/270 cm - cut to size 100 x 240 / 250 cm due to the capacity of the service lift **Note : Max 3 tiles considered**	7	Sq.m	659.00	4,613.00
5.02	**MDF WALL CLADDING** Supply and installation of plain **MDF wall cladding in Veneer finish** including necessary fittings and accessories for installation. Includes the grooves as per the requirement . Height up to 3 m **Location: Workstation (LED screen wall) + Conference room TV wall + Reception + Dining area**	50	Sq.m	874.00	43,700.00
5.03	**WALL PAINT** Supply and application of **Jotun Fenomastic Paint Finish (white)** with all cleaning and levelling. Location : As per the design False Ceiling areas height - 3 m Open ceiling areas height - 3.9 m	972	Sq.m	35.00	34,020.00
5.04	**WALL PAINT COLOR** Supply and application of **Jotun Fenomastic Paint Finish (Color)** with all cleaning and levelling. False Ceiling areas height - 3 m	19	Sq.m	39.00	741.00
5.05	**TEXTURED WALL PAINT** Supply and application of textured paint including all the base coats and wall preparation with all cleaning and levelling. **Location : Dining area + Conference room + TV wall in the workstation areas** Height : upto 3000 mm Make : Mas paint or equivalent	51	Sq.m	137.00	6,987.00
5.06	**PET PANEL WALL CLADDING** Supply and installation of **P.E,T wall cladding** including necessary materials for installation including grooves c/c 100 mm. Height up to 3 m **Location : Workstation area , next to the LED screens wall.** Note: To be selected from verve standard collection. Note : Each panel size is 1.2 x 2.4 m , so there will be a joint every 2.4 m	7	Sq.m	614.00	4,298.00
5.07	**PET PANEL WALL CLADDING** Supply and installation of **P.E,T wall cladding** including necessary materials for installation including grooves as per the design. Wall Dimension: 3.9 x 2 m **Location : Workstation area , next to the LED screens wall.** Note: To be selected from verve standard collection.	1	Ls	7,514.00	7,514.00

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR LEAN TECHNOLOGIES @ NASSIMA TOWER , DUBAI-UAE

Quote Ref No: VID/1057/25/CP/QTN_01/R1 **02-May-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
5.08	**PET PANEL WALL CLADDING** Supply and installation of plain **P.E,T wall cladding** including necessary materials for installation with no grooves . Height up to 1.2 m **Location : TV wall in all the meeting rooms + All gypsum walls Phone booths** Note: To be selected from verve standard collection.	43	Sq.m	506.00	21,758.00
5.09	**BACKPAINTED GLASS - (WRITABLE WALL)** Supply and installation of Back painted crystal clear glass with necessary material for fixing including MDF backing. **Height : 1.2 m** **Location : As per the design**	58	Sq.m	629.00	36,482.00
5.10	**BACKPAINTED GLASS - BACKSPLASH** Supply and installation of Back painted crystal clear glass with necessary material for fixing including MDF backing. **Height : 1 m** **Location : Pantry (behind t he counter on the existing wall + existing column around the seating)**	7	Sq.m	629.00	4,403.00
5.11	Supply and installation of marker holder (non concealed) below the entire length of the back painted glass as per the requirement in PU painted finish.	48	r.m.	253.00	12,144.00
5.12	Supply and installation of plain Frosted sticker . Height upto 1500 mm Location : All glass partition and doors excluding the below areas	39	Sq.m	108.00	4,212.00
5.13	Supply and installation of Frosted sticker with the logo design. . Height upto 1500 mm Location : Phone booths glass partition and doors	8	Sq.m	181.00	1,448.00
5.14	Supply and installation of gradient design frosted sticker . Height upto 3000 mm Location : Conference room glass partition and doors .	8	Sq.m	217.00	1,736.00
5.15	Supply and installation of room identification manifestation as per the design. Height : 1500 mm Location : Meeting rooms only	10	Nos.	181.00	1,810.00
5.16	**SUSPENDED PET PANEL** Supply and installation of suspended **P.E,T , CNC cut panels as per the design** including necessary materials for installation with wire clips as per the design as per the design. W800mm x Height up to 2.4 m **Location : Workstation area** Note: To be selected from verve standard collection.	5	Nos.	1,951.00	9,755.00
5.17	**SKIRTING** Supply and installation of (up to 50 mm high) **MDF skirting in PU paint finish** with necessary fittings and accessories. **Note : Non concealed**	378	LM	58.00	21,924.00
5.18	**ROLLER BLINDS - MANUAL** Supply and installation of **sunscreen blinds** **Height: Upto 3100mm** **Location : External glazing**	307	Sq.m	87.00	26,709.00

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai.UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR LEAN TECHNOLOGIES @ NASSIMA TOWER , DUBAI-UAE

Quote Ref No: VID/1057/25/CP/QTN_01/R1 **02-May-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
5.19	**SHEER CURTAIN - MANUAL** Supply and installation of sheer curtain with concealed track as per the design . **Height: Upto 3000mm** **Location : Collaboration area** **Fabric PC Rate : 100 / - m**	15	Sq.m	267.00	4,005.00
	WASHROOMS REFURBISHMENT				
5.20	**WALL PAINT** Supply and application of **Jotun Fenomastic Paint Finish (white)** with all cleaning and levelling. Location : Male and female toilet corridors False Ceiling areas height - 2.7 m (assumed)	78	Sq.m	35.00	2,730.00
5.21	**WALL TILE** Supply and installation of 600 x 600 mm wall tiles including necessary materials for fixing. Make : RAK or equivalent Height upto 2.7 m PC Rate : 55 AED per Sq.m Location : Cubicles and toilet area	143	Sq.m	166.00	23,738.00
	Note: 1. All finishes are subject to final sample approval.				
				SUB TOTAL WALL FINISH :	**274,727.00**
6.00	**CEILING FINISH**				
6.01	**PLAIN GYPSUM CEILING** Supply and installation of **Gypsum Board Plain ceiling** (Knauf or equivalent) with necessary hanging systems including wall angle "C "channel, furring channel with 12.5mm gypsum boards joined taped smoothened finish. **Location : As per design**	216	Sq.m	116.00	25,056.00
6.02	**GYPSUM CEILING PAINT** Supply and application of **Jotun Fenomastic WHITE paint** including all cleaning and levelling. As per design and approved sample. (2 coats including sanding). **Location : Proposed Gypsum ceiling areas**	216	Sq.m	35.00	7,560.00
6.03	**60 X 60 PERFORATED CEILING TILES** Supply and installation of 60x60cm acoustic mineral fiber ceiling tile. Make : AMF / Knauff or equivalent **Location : Meeting rooms + Conference room**	82	Sq.m	177.00	14,514.00
6.04	**OPEN CEILING PAINT** Supply and installation of black open ceiling slab painting including all the necessary coats . **Location : Reception + Open hot desk area + Dining area + Collab + Workstation areas**	280	Sq.m	55.00	15,400.00
6.05	**GYPSUM BULKHEAD** Supply and installation of up to 800 mm wide Gypsum Bulkhead with 12.5 mm gypsum boards with paint finish around the 60 x 60 ceiling and open ceiling .	358	Lm	153.00	54,774.00
6.06	**GYPSUM BULKHEAD** Supply and installation of upto 800 mm high Gypsum Bulkhead with 12.5 mm gypsum boards with paint finish around the 60 x 60 ceiling , open ceiling and around gypsum ceiling in the passage .	465	Lm	153.00	71,145.00

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR LEAN TECHNOLOGIES @ NASSIMA TOWER , DUBAI-UAE

Quote Ref No: VID/1057/25/CP/QTN_01/R1 **02-May-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
6.07	**PET HANGING CEILING UNIT** Fabrication, Supply and installation of PET hanging ceiling as per the design. Location : Reception Size : 4000 x 1500 mm Thickness: 24 mm Height: 200 mm Location : Reception + Dual acoustic pod area 	2	Nos	7,587.00	15,174.00
6.08	**DECORATIVE CEILING** Supply and installation of suspended acoustic panels (1000 x 1000 x 50 mm x 9 nos.) detail as per the design with provision for the light including the metal strips around the opening . Location : Collaboration Area Size of opening : 4000 x 4000 mm No.of light provision - 9 Nos Note : Lights provided separate 3D for reference purpose only 	1	Nos.	21,676.00	21,676.00
6.09	**SUSPENDED CEILING UNIT** Fabrication, Supply and installation of PET hanging ceiling as per the design. Thickness: 24 mm Height: 200 mm . Location : Open Hot desk area Size : 3600 x 2100 mm 	1	Nos.	4,335.00	4,335.00
6.10	**GYPSUM BULKHEAD - U BULKHEAD** Supply and installation of 100 mm high Gypsum Bulkhead with 12.5 mm gypsum boards with paint finish. **Location: Along the magnetic and normal track light and around Collaboration decorative ceiling**	35	Lm	139.00	4,865.00
6.11	**GYPSUM BULKHEAD - COVELIGHT** Supply and installation of 100 mm high Gypsum Bulkhead with 12.5 mm gypsum boards with paint finish. **Location: Along the magnetic and normal track light and around Collaboration decorative ceiling**	52	Lm	168.00	8,736.00
6.12	**GYPSUM PELMET** Supply and installation of **Gypsum Pelmet** with necessary fittings with paint finish. **Location : For blinds and sheer curtain**	99	LM	160.00	15,840.00
6.13	**SHADOW GAP** Supply and installation of shadow gap as per the design wall and ceiling junction areas	324	LM	36.00	11,664.00
6.14	**GYPSUM ACCESS PANEL** Supply and installation of **Gypsum access panel (Max 60 x 60 cm)** with frame and hinges. **Location: Proposed Gypsum ceiling area** Note : Subject to final MEP drawings	12	Nos.	311.00	3,732.00
	WASHROOMS REFURBISHMENT				
6.15	Provision for the ceiling modification including the painting works including necessary shadow gap and bulkheads . Location : Male and Female toilets	1	Ls.	7,457.00	7,457.00
	Note : All finishes are subject to final sample approval.				
				SUB TOTAL CEILING FINISH :	**281,928.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR LEAN TECHNOLOGIES @ NASSIMA TOWER , DUBAI-UAE

Quote Ref No: VID/1057/25/CP/QTN_01/R1 **02-May-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
7.00	**DOORS**				
7.01	**AUTOMATIC SLIDING DOOR** Supply and fixing of 12 mm clear tempered double leaf frameless automatic glass sliding door with all around straight polish edges fixing by ASSA ABLLOY SL 500 sliding mechanism , bottom lock . Size : 3000 mm x 3000 mm **Location : Main Entrance**	1	Nos	27,457.00	27,457.00
7.02	**ACOUSTIC GLASS DOOR** Supply and fixing of 13.52mm clear acoustic laminated (6 mm clear tempered glass + 1.52 mm acoustic PVB + 6mm clear tempered glass) glass single leaf frameless glass doors with all around straight polished edges fixing by DORMA BTS 65 floor machine, OFFSET pivot hinges , bottom lock and 800*600 mm long H type handle including all around 50 mm wide overlapped UNICA door frame. Size: 900x2700mm **Location : Conference Room , All meeting rooms , Custom phone booths**	14	Nos	5,347.00	74,858.00
7.03	**SINGLE LEAF WOODEN DOOR - NON FR** Supply and installation of Semi solid wooden swing door NON FR in PU paint / veneer finish, with Frame, architrave, in PU paint finish with all necessary ironmongery and material for fixing. Size: 900 x 2400mm Ht **Location : Pantry** **PC Rate Ironmongeries : 500 / - Devon or equivalent**	1	No.	4,118.00	4,118.00
	WASHROOMS REFURBISHMENT				
7.04	Provision to paint the existing door to the washrooms .	9	Nos.	1,228.00	11,052.00
				SUB TOTAL DOORS :	**117,485.00**
8.00	**SIGNAGE WORKS - Provisional Sum**				
8.01	Supply and installation of aluminum 3D painted back lit signage in English and Arabic with logo as per the design. Size: L 1500 x H 600 mm **Location : Reception** Note : Subject to final design and sample approval. 	1	Item	9,393.00	9,393.00
	Note : 1. Any other signage excluded.				
				SUB TOTAL SIGNAGE WORKS :	**9,393.00**
9.00	**JOINERY WORKS**				
9.01	**RECEPTION DESK** Fabrication, Supply and installation of **Reception counter with MDF in PU paint finish** as per design including SS brushed finish beading along the edge and cladding at the base as per the design. **Overall Size : 1600 mm x 600 mm x 1100 mm** **Location : Reception** 	1	Item	8,497.00	8,497.00

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR LEAN TECHNOLOGIES @ NASSIMA TOWER , DUBAI-UAE

Quote Ref No: VID/1057/25/CP/QTN_01/R1 **02-May-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
9.02	**PANTRY LEDGE** Fabrication, supply and installation of wall mounted bar ledge counter with **MDF Unit in PU painted finish without foot rail .** Size: (2300+ 1500 + 2300) mm x 400 mm **Location : Pantry - around the column**	1	Item	8,815.00	8,815.00
9.03	**PANTRY UNIT + FULL HEIGHT CABINET** Fabrication, supply and installation of Wet pantry counter with MR **MDF Unit in veneer finish** with **2cm Marble counter top** and cabinets as per design with all necessary for fixing. **Location : Pantry** Overall Size: 3600 x 600mm x 2400 mm Note : Glass Backsplash Considered Separately **Marble PC Rate : 350 / -per sq.m.**	1	Item	19,769.00	19,769.00
9.04	**PLANTER BOX FOR NATURAL PLANT** Fabrication, supply and installation of planter box made with MR MDF in PU painted finish, including waterproofing on top necessary materials for installation. Size: 1200 x 360 x 1100mm **Location : Workstation area**	8	Item	3,754.00	30,032.00
9.05	**PLANTER BOX FOR NATURAL PLANT** Fabrication, supply and installation of planter box made with MR MDF in PU painted finish, including waterproofing on top necessary materials for installation. Size: 600 x 360 x 1100mm **Location : Workstation area**	2	Item	2,419.00	4,838.00
9.06	**SEATING UNIT - TYPE 1** Fabrication, supply and installation of seating unit with MDF in veneer finish . Overall Size - 2800 x 635 x 1000 mm **Location : Dining Area** 	1	Item	11,562.00	11,562.00
9.07	**SEATING UNIT - TYPE 2** Fabrication, supply and installation of seating unit with MR MDF in veneer finish and fabric upholstered seat and back rest , with planter box for live plants as per the requirement. Overall Size - 2650 x 620 x 1200 mm **Location : Dining Area**  Note : Plants and substrate excluded from scope , waterproofing included only in the area that will receive the plants .	1	Item	16,451.00	16,451.00
9.08	**TABLE WITH PLANTER BOX** Fabrication, supply and installation of seating unit with MDF in veneer finish and planter box made MR MDF in textured paint finish as per the design. Overall Size : 1800 x 600 x 1100mm **Location : Collaboration area**	1	Item	9,249.00	9,249.00

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR LEAN TECHNOLOGIES @ NASSIMA TOWER , DUBAI-UAE

Quote Ref No: VID/1057/25/CP/QTN_01/R1 **02-May-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
9.09	**OPEN HOT DESK** Fabrication, supply and installation of seating unit with MR MDF in veneer finish and fabric upholstered seat with desk in veneer finish , with planter box for live plants as per the requirement. Overall Size - 3600 x 1200 x 900 mm **Location : Suspended desk area** Note : Plants and substrate excluded from scope , waterproofing included only in the area that will receive the plants .	1	Item	24,494.00	24,494.00
9.10	**STORAGE CABINET** Fabrication, supply and installation of storage unit with MR MDF in veneer finish , with planter box for live plants as per the requirement. Overall Size - 3900 x 710 x 900 mm **Location : Conference room** Note : Plants and substrate excluded from scope , waterproofing included only in the area that will receive the plants .	1	Item	11,618.00	11,618.00
9.11	**SEATING UNIT - TYPE 4** Fabrication, supply and installation of seating unit with MDF fabric upholstered seat and back rest as per the requirement. Overall Size - 1150 x 500 x 900 mm **Location : Phone Booths** 	2	Item	4,736.00	9,472.00
9.12	**FULL HEIGHT CABINET** Fabrication, supply and installation of Full height cabinets made with MDF in PU paint finish including necessary materials for installation. Overall size : L3500 x D400 x H3000 mm **Location : Engineer's office**	1	Item	22,760.00	22,760.00
9.13	**PRINTER CABINET** Fabrication, supply and installation of Printer cabinet with MDF in veneer finish as below with all necessary for fixing. **Lower cabinet size : 2360 x 580 x 1100 mm** **Upper cabinet size : 2360 x 380 x 600 mm**	1	Item	9,364.00	9,364.00
9.14	**NICHE SEATING** Fabrication, supply and installation of Niche seating made with MDF upholstered with fabric as per the design . Size : 3000 mm x 900 mm x 900 mm **Location: Lift Lobby**	1	Item	10,621.00	Rate only
9.15	**DECORATIVE SHELVES** Fabrication, supply and installation of decorative shelf with colored acrylic as per the design . **Shelf size 1 : 1200 x 150 x 150 mm** **Shelf size 2 : 800 x 150 x 150 mm**	1	Item	2,890.00	2,890.00

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR LEAN TECHNOLOGIES @ NASSIMA TOWER , DUBAI-UAE

Quote Ref No: VID/1057/25/CP/QTN_01/R1 **02-May-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
	WASHROOMS REFURBISHMENT				
9.16	**VANITY COUNTER** Supply and installation of vanity counter with the provision of undercounter wash basin and 500 mm front fascia in MR MDF veneer finish . PC Rate Stone : 350/- Size : 1700 x 600 x 500 mm	2	Nos.	7,861.00	15,722.00
	Note : Stone ledge not considered for the washrooms behind the WC , full wall cladding without any niche considered				
				SUB TOTAL JOINERY WORKS :	**205,533.00**
10.00	**LIGHTING WORKS - NON DIMMABLE**				
	Supply of the following lights				
10.01	**GLOBE HANGING LIGHT - 12W** **Dia : 250 mm**	16	Nos	333.00	5,328.00
10.02	**RECESSED LINEAR LIGHT** **Size: 3600x50x75mm**	10	Nos	1,026.00	10,260.00
10.03	**LINEAR LIGHT - (40 W/m)** **Profile Size : 50 x 75 x 2400 mm**	10	Nos	684.00	6,840.00
10.04	**LINEAR LIGHT - (40 W/m)** **Profile Size : 50 x 75 x 1400 mm**	5	Nos	399.00	1,995.00
10.05	**LINEAR LIGHT - (40 W/m)** **Profile Size : 50 x 75 x 1200 mm**	4	Nos	342.00	1,368.00
10.06	**CYLINDER PENDANT LIGHT** **Wattage : 20W** **Size : 90 x 180 mm**	48	Nos	196.00	9,408.00
10.07	**DIRECTIONAL SPOT LIGHT - 7W**	6	Nos	172.00	1,032.00
10.08	**SPOT LIGHT - 11 W**	100	Nos	77.00	7,700.00
10.09	**DECORATIVE PENDANT LIGHT** **Size - 2000mm L** 	1	Nos	3,800.00	3,800.00
10.10	**MAGNETIC TRACK** **Size : 1000 mm** **Location : As per design**	13	LM	239.00	3,107.00

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR LEAN TECHNOLOGIES @ NASSIMA TOWER , DUBAI-UAE

Quote Ref No: VID/1057/25/CP/QTN_01/R1 **02-May-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
10.11	**MAGNETIC TRACK LIGHT** **Wattage : 3 x 2 W** **Size : 106 x 35 x 59 mm** **Location : Conference Room**	8	Nos	154.00	1,232.00
10.12	**DECORATIVE HANGING LIGHT** **Location : Reception** **Size : Ø500xH700x1800mm - 3 SET** **Watts: 45W**	1	Nos	1,722.00	1,722.00
10.13	**PANEL LIGHT** **Wattage : 16 W** **Size: 300 X 300 mm** **Location: Collaboration Area**	9	Nos	178.00	1,602.00
10.14	**DECORATIVE LIGHT** **Location : Collaboration Area** **Size: L1850mm** **Watts: 3x8W**	1	Nos	1,900.00	1,900.00
10.15	**TRACK SPOT LIGHT** **Watts: 15W**	3	Nos	172.00	516.00
10.16	**DECORATIVE LIGHT** **Location : Dining Area** **Size: Ø300mm** **Watts: 12W**	8	Nos	309.00	2,472.00
10.17	**DOUBLE SPOT LIGHT** **Finish : Black** **Location : Phone Booth** **Size: 196x104mm , 2x11W**	2	Nos	214.00	428.00
10.18	**DECORATIVE WALL LIGHT**	1	Nos	297.00	297.00
10.19	**DECORATIVE WALL LIGHT**	2	Nos	1,128.00	2,256.00
10.20	STRIP LIGHT including the driver and profile . IP20	55	r.m.	101.00	5,555.00

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR LEAN TECHNOLOGIES @ NASSIMA TOWER , DUBAI-UAE

Quote Ref No: VID/1057/25/CP/QTN_01/R1 **02-May-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
	WASHROOMS REFURBISHMENT				
10.21	**SPOT LIGHT - 11 W**	14	Nos	77.00	1,078.00
	Note : 1. Quantity subject to final RCP design and LUX calculations 2. Non dimmable lights				
				SUB TOTAL LIGHTS :	**69,896.00**
	MEP WORKS				
11.00	**HVAC WORKS**				
	AC MACHINES AND ACCESSORIES				
11.01	Performance testing of the existing FCU machines . Note : Assumed quantity - 11 nos.	11	Nos.	723.00	7,953.00
11.02	Supply and installation of 4TR FCU including the valve package . Note : Subject to availability of the chilled water supply by the building management Make : Mekar or equivalent	11	Nos.	6,534.00	Rate only
11.03	Relocation of existing Thermostat including the wiring . Make : Thermostat Note : BMS works excluded , existing FCU quantity assumed Note : Assumed the thermostats are in good working condition	11	Nos	361.00	3,971.00
	CHW PIPING AND ACCESSORIES				
11.04	Modification and extension of the existing chilled water piping as required	1	Ls	39,740.00	Rate only
11.05	Chemical flushing - Culligan	1	Ls	23,844.00	Rate only
	Note : BTU meter and related works excluded				
	DUCTING AND ACCESSORIES				
11.06	Supply and installation of new Phenolic ducting including all the accessories Note : To retain existing ducting and considered minor modifications only to accommodate the changes in the GA .	1	Ls.	41,667.00	41,667.00
11.07	Supply and installation of **12 mm rubber type Acoustic liner**				
11.08	Supply and installation of **Volume Control Damper.**				
11.09	Supply and Installation of flexible duct, plenum box and ring.				
11.10	Supply and installation of cross talk attenuator , Location: Meeting Rooms + Conference rooms only	12	Nos.	Ls.	12,121.00
11.11	Extension of duct for the fresh and extract air using phenolic ducting Note : To retain existing with very minor modifications .	1	Item	18,058.00	18,058.00
	GRILLS AND DIFFUSER				
11.12	Linear Slot grills/Diffuser	1	Item	19,074.00	19,074.00
	DRAIN PIPE				
11.13	Supply and Installation of **PVC Pipe** with insulation. - connecting to the existing line	1	Item	7,152.00	7,152.00
11.14	Testing and commissioning with air balancing (Verve)	1	Item	3,610.00	3,610.00
11.15	Third party testing with air balancing works	1	Item	7,948.00	7,948.00

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai.UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR LEAN TECHNOLOGIES @ NASSIMA TOWER , DUBAI-UAE

Quote Ref No: VID/1057/25/CP/QTN_01/R1 **02-May-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
	WASHROOMS REFURBISHMENT				
11.16	Modification to the existing extract system, to accommodate the new ceiling ,	1	Item	2,162.00	2,162.00
	Notes : 1. BTU Meter works and BMS Connection / cabling/ wiring excluded 2. Subject to final approval from the building management 3. Servicing and replacement of any parts of the FCU machines excluded from scope				
				SUB TOTAL HVAC WORKS :	**123,716.00**
12.00	**ELECTRICAL WORKS**				
12.01	PVC conduiting and wiring for light points including installation. Note: Light points are subject to revise upon final RCP Layout.	246	Nos	210.00	51,660.00
12.02	Supply and installation of **Single switches for lighting.** Including cabling works.(MK-Normal White)	24	Nos	260.00	6,240.00
12.03	Supply and installation of **Grid switch for lighting.** Including **PVC conduiting**. (Black Matt PVC finish Legrand / schneider) for Open workstation & corridor.	4	Nos	262.00	1,048.00
12.04	Supply and installation of **13A Single wall Power Socket,** in PVC finish including conduiting and wiring. (Schneider / Legrand)	25	Nos	318.00	7,950.00
12.05	Supply and installation of **13A Twin wall Power Socket,** in black PVC finish including conduiting and wiring. (Schneider / Legrand)	29	Nos	340.00	9,860.00
12.06	Supply and installation of **15A Single wall Power Socket,** in Black PVC finish including conduiting and wiring. (Schneider / Legrand)	4	Nos	470.00	1,880.00
12.07	Supply and installation of **Floor Box -Twin 13A+ Twin Data.** with cabling and conduiting and data and telephone plates provision only. Make : Obo or equivalent Note: 1 Nos Floor Box for 2 Person considered	56	Nos	650.00	36,400.00
12.08	50mm conduit and cabling provision for HDMI/VGI.	16	Nos.	650.00	10,400.00
12.09	Supply and installation of **PVC** containment for **WI-FI Points**. (Provisional qty)	6	Nos.	181.00	1,086.00
12.10	Supply and installation of PVC containment for **Access control** (Provisional qty)	2	Nos	181.00	362.00
12.11	Supply and installation of **PVC** containment for **CCTV Points**. (Provisional qty)	6	Nos.	181.00	1,086.00
12.12	Supply and installation of **PVC** containment for speakers system . (Provisional qty)	6	Nos.	181.00	1,086.00
12.13	Supply and installation of **PVC** containment for printers.	2	Nos.	181.00	362.00
12.14	Supply and installation of **PVC** containment for **AV Rack**	1	Nos.	181.00	181.00
12.15	Supply and installation of **PVC** containment for thermostat (Relocation of existing thermostat)	11	Nos.	181.00	1,991.00
12.16	Supply and installation of new power for the new FCU 20A SP Isolator including necessary wiring . Note : To retain existing power provision for the existing FCU , assumed 11 nos.	11	Nos.	795.00	Rate only
12.17	Power provision for **Signage** with timer switch	1	Nos.	939.00	939.00
12.18	Supply and installation of power for water heater as per the requirement.	1	Nos.	361.00	361.00
12.19	Supply and installation of **New SMDB** assembling, dressing, fixing as per DEWA standard.	1	Nos	7,081.00	7,081.00
12.20	Supply and installation of **MCC**	1	Nos	2,890.00	2,890.00
12.21	Supply and installation of Armored cable . (For SMDB)	1	LS	10,838.00	10,838.00

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR LEAN TECHNOLOGIES @ NASSIMA TOWER , DUBAI-UAE

Quote Ref No: VID/1057/25/CP/QTN_01/R1 **02-May-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
12.22	Supply and installation of new **DB** with all other accessories as per DEWA standards Note : Subject to load availability	2	Item	5,058.00	10,116.00
12.23	Supply & Installation of 100mm GI Cable Tray with necessary fittings & supports -For armored cable	1	LS	4,335.00	4,335.00
12.24	Supply & Installation of 150mm GI Cable Tray with necessary fittings & supports -For IT, AV, Light, Power	1	Lot	16,763.00	16,763.00
12.25	DEWA submission, inspection and approval. - 1 submission considered	1	No	5,058.00	5,058.00
12.26	Testing commissioning.	1	Item	2,168.00	2,168.00
12.27	Providing **PVC conduit for Data for workstations and cabins**	109	Nos	159.00	17,331.00
12.28	Allow Necessary charges for demerging and merging of existing DB	1	Ls	7,225.00	7,225.00
	WASHROOMS REFURBISHMENT				
12.29	Supply and installation of power for water heater as per the requirement.	2	Nos.	361.00	722.00
12.30	Supply and installation of power for urinal sensor	3	Nos.	361.00	1,083.00
12.31	PVC conduiting and wiring for light points including installation. Note: Light points are subject to revise upon final RCP Layout.	14	Nos	210.00	2,940.00
	Note: 1. We have assumed that the existing infrastructure's power has sufficient capacity to cater to the requirement of the project. 2. We have not allowed for upgrade of the capacity of any base building system. 3. All electrical conduits considered are of PVC type. 4. We have not allowed for any specific lighting control system in this offer. 5. Subject to final MEP drawings **Exclusions:** 1. Any BMS integration or related works. 2. DEWA Consultancy for power upgrade.				
				SUB TOTAL ELECTRICAL WORKS :	**221,442.00**
13.00	**CIVIL DEFENCE WORKS - PROVISIONAL SUM**				
13.01	**FIRE ALARM WORKS**				
a	Supply and installation of Fire Alarm Control Panel (GENT)	1	Nos		
b	Re-Installation of existing Smoke detector with New Piping & Cabling	10	Nos		
c	Supply and install New Smoke detector	17	Nos		
d	Supply and install New Heat detector	1	Nos		
e	Supply and installation of MCP WITH BACK BOX	2	Nos		
f	Supply and installation of Void smoke detector with LED indicator	5	Nos		
g	Supply and installation of Sounder with Flasher	5	Nos		
h	Building Interfacing	1	Item		
i	24x7/Access Control Interfacing	1	Item		
j	Fire Alarm Control Panel Programming	1	Item		
k	Dismantling of Existing Fire Alarm System	1	Item		
13.02	**FIRE FIGHTING WORKS**			LS	145,000.00
a	Supply and installation of Pendent Sprinkler(Q.R 68°C)	64	Nos		
b	Relocation of Existing sprinkler	34	Nos		
c	Supply and installation of Fire Blanket (FIREGUARD)	1	Item		

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR LEAN TECHNOLOGIES @ NASSIMA TOWER , DUBAI-UAE

Quote Ref No: VID/1057/25/CP/QTN_01/R1 **02-May-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
d	Supply and installation of new upright sprinkler	12	Item		
e	Sprinkler line Draining & Refilling	1	Item		
f	Supply, Warranty and installation Certificates	1	Item		
13.03	**EMERGENCY WORKS**				
a	Supply and installation of Self Contained Emergency Light Surface Mounted Type	23	Nos.		
b	Supply and installation of Self Contained Exit Light Hanging	8	Item		
c	Certification charges	1	Item		
	Notes / Exclusions: 1. Any additional charges/ fees for any third party shall be paid by the client. 3. Assumed existing sprinkler heads are as per the DCD standards 4. FM 200, central battery system works excluded 5. Existing Sprinkler main line Modification for other services excluded. 6. Any existing device found damaged/faulty on re-installation time will be charged accordingly. **7. Rates subject to base build contractor , Verve to charge 15% coordination charge on actual quote submitted by Base build contractor. Verve provided provisional sum**				
				SUB TOTAL CIVIL DEFENCE WORKS :	**145,000.00**
14.00	**PLUMBING WORKS AND SANITARY WARES**				
14.01	Modification to the existing plumbing lines (water supply and drainage) to accommodate the changes in the pantry area . Note : Water heater , Sani pump , core cutting excluded from scope	1	Item	12,283.00	12,283.00
14.02	**PANTRY SINK + Bottle trap + Waste** Undermounted Single Bowl Sink Size : 750 x 456 x 190 mm **Supply and installation**	1	Nos	1,645.00	1,645.00
14.03	**PANTRY SINK MIXER + Angle valve** Single Hole Kitchen Sink Mixer **Supply and installation**	1	Nos	680.00	680.00
14.04	Supply and installation of 100L water heater including all the cabling and wiring . Make : Ariston or equivalent . Location : Pantry	1	Nos.	1,228.00	1,228.00
	WASHROOMS REFURBISHMENT				
14.05	Modification to the existing plumbing lines (water supply and drainage) to accommodate the changes in the pantry area . Note : Water heater , Sani pump , core cutting excluded from scope Assumed sanitary wares will be installed in the current locations only .	1	Item	6,503.00	6,503.00
14.06	Supply and installation of 100L water heater including all the cabling and wiring . Make : Ariston or equivalent . Location : Toilets	2	Nos.	1,228.00	2,456.00

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR LEAN TECHNOLOGIES @ NASSIMA TOWER , DUBAI-UAE

Quote Ref No: VID/1057/25/CP/QTN_01/R1 **02-May-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
14.07	Supply and installation of sanitary wares : Make : RAK ceramics - Ceramic + Kludi RAK accessories - chrome				
a	**Wall mounted WC + Concealed cistern**	4	Sets	1,809.00	7,236.00
b	**Flush Plate**	4	Nos.		Included
c	**Shattaf (Bidet spray) + Angle valves**	4	Nos.	173.00	692.00
d	**Toilet paper holder**	4	Nos.	125.00	500.00
e	**Wash Basin + PVC bottle trap + Waste**	4	Sets	423.00	1,692.00
f	**Wash Basin Mixer**	4	Nos.	410.00	1,640.00
g	**Floor trap / drain**	7	Nos.	137.00	959.00
h	**Urinal + Sensor flush + Urinal partition** 	3	Sets	1,257.00	3,771.00
	Note : Subject to final requirement at site. Assumed stub out is present near the requirement at site.				
	SUB TOTAL PLUMBING WORKS AND SANITARY WARES :				**41,285.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai.UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR LEAN TECHNOLOGIES @ NASSIMA TOWER , DUBAI-UAE

Quote Ref No: VID/1057/25/CP/QTN_01/R1 — **May 2, 2025**

SR.NO	SAMPLE IMAGE	DESCRIPTION	QTY	UNIT	RATE	TOTAL (AED)
15.00	**WHITE GOODS**					
15.01		**FRIDGE** **Samsung - 420 L**	1	No.	1,425.00	1,425.00
15.02		**MICROWAVE** **LG - 42 L**	1	No.	932.00	932.00
15.03		**WATER DISPENSER** **Panasonic - Bottom Loading**	1	No.	904.00	904.00
15.04		**COFFEE MACHINE** **Make : Philips or equivalent**	1	No.	3,391.00	Rate only
15.05		**PRINTER** **Brother**	1	No.	1,308.00	Rate only
15.06		**TV SCREEN - 85 INCH** **Make : Hisense or equivalent - QLED** **Location : Conference Room**	1	No.	6,104.00	Rate only
15.07		**TV SCREEN - 65 INCH** **Make : Hisense or equivalent - QLED** **Location : Meeting Room 4 PAX**	1	No.	3,165.00	Rate only
					TOTAL WHITE GOODS :	**3,261.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR LEAN TECHNOLOGIES @ NASSIMA TOWER , DUBAI-UAE

Quote Ref No: VID/1057/25/CP/QTN_01/R1 — **May 2, 2025**

SR.NO	As per 3D	SAMPLE IMAGE	DESCRIPTION	QTY	UNIT	RATE	TOTAL (AED)
16.00	**LOOSE FURNITURE**						
			RECEPTION AREA				
16.01			**ARM CHAIR** Material: Fabric / PU Leather	2	Nos.	2,652.00	5,304.00
16.02			**COFFEE TABLE** Specification: Solid Plywood with ash wood pattern Tabletop with steel base in white color Dimension: 600mmW x 400mmD x 550mmH	1	Nos.	922.00	922.00
			PHONE BOOTH AREA				
16.03			**PHONE BOOTH POUF** Dimension: 600mm Diax520mmH Seating: Fabric	2	Nos.	720.00	1,440.00
			OPEN HOT DESK & CONFERENCE ROOM				
16.04			**MODULAR DESK** Specification : Foldable table with aluminum alloy legs in epoxy powder coated finish . Size : 1400 x 600 x 750 mm 5-year warranty	5	Nos.	1,257.00	6,285.00
16.05			**MEETING CHAIR** Fixed Aluminum Alloy armrest Synchronized-tilting (SAST) mechanism Recline lockable in three positions Polished Aluminum Alloy 5-star base Reinforced PU Mute Castors Chrome Class-3 Gas Lift Dimensions: 630 x 610, H935mm 5-year warranty	12	Nos.	992.00	11,904.00
16.06			**SIDE TABLE** Specification: Top on high density board with powder coated steel base Dimension: 450mm x 650mmH	2	Nos.	689.00	1,378.00
16.07			**SUSPENDED DESK CHAIRS**	5	Nos.	736.00	3,680.00
			COLLABORATION AREA				

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR LEAN TECHNOLOGIES @ NASSIMA TOWER , DUBAI-UAE

Quote Ref No: VID/1057/25/CP/QTN_01/R1 — **May 2, 2025**

SR.NO	As per 3D	SAMPLE IMAGE	DESCRIPTION	QTY	UNIT	RATE	TOTAL (AED)
16.08			**ROUND STOOL SEATING** Made: Wooden frame with foam and upholstery with Fabric finish. Base with plastic levelers Finish: Fabric - color form the chart catalogue	9	Nos.	657.00	5,913.00
16.09			**ROUND DISCUSSION TABLE** Table top: 25mmthk MDF melamine finish Understructure: Metal Pole leg Size: 800Dia x H750mm	2	Nos.	821.00	1,642.00
16.10			**HIGH CHAIR** Sofa Seat & Back in Fabric Finish with Metal Leg [white, black, pale pinkish grey, pea green, coral]. Dim: 510*500*990 Ht mm. Finish: Fabric.	6	Nos.	963.00	5,778.00
16.11			**MODULAR SEATING** Fully Upholstered with Beech Wood Leg Size : W 600 x D 800 x H 690 mm Material - Fabric Image is for reference , actual will be custom made	9	Nos.	2,210.00	19,890.00
			DINING AREA				
16.12			**DINING CHAIR** Material : Fabric/ Metal legs	13		523.00	6,799.00
16.13			**DINING HIGH CHAIR** Sofa Seat & Back in Fabric Finish with Metal Leg [white, black, pale pinkish grey, pea green, coral]. Dim: 510*500*990 Ht mm. Finish: Fabric.	7		963.00	6,741.00
16.14			**SQUARE DINING TABLE** Size: 700x700mm	8		1,061.00	8,488.00
			WORKSTATION AREAS				
16.15		 	**WORKSTATION** Desk Base workstation with melamine table top, loop legs, flip wire box and support ,without modesty panel including Privacy Screen . Dim: 1200*600*750 Ht mm. Finish : Melamine. Base / Leg : Steel [White].				
a			**CLUSTER OF 6 PAX - FACE TO FACE**	5	No.	7,542.00	37,710.00

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR LEAN TECHNOLOGIES @ NASSIMA TOWER , DUBAI-UAE

Quote Ref No: VID/1057/25/CP/QTN_01/R1 — **May 2, 2025**

SR.NO	As per 3D	SAMPLE IMAGE	DESCRIPTION	QTY	UNIT	RATE	TOTAL (AED)
b			**CLUSTER OF 2 PAX - FACE TO FACE - Height adjustable** **Location : Engineer office**	10	No.	4,352.00	43,520.00
c			**CLUSTER OF 4 PAX - FACE TO FACE**	4	No.	4,921.00	19,684.00
d			**CLUSTER OF 2 PAX - LINEAR**	3	No.	2,854.00	8,562.00
e			**SINGLE PAX** **Height adjustable** **Location : Engineer office**	7	No.	2,321.00	16,247.00
f			**CLUSTER OF 3 PAX - LINEAR** **2 PAX + SINGLE PAX**	2	No.	4,463.00	8,926.00
g			**CLUSTER OF 2 PAX - FACE TO FACE - Height adjustable including pedestal**	23	No.	5,398.00	Rate only
h			**SINGLE PAX - Height adjustable including pedestal**	12	No.	2,844.00	Rate only
16.16			**DRAWER PEDESTAL** 3 Drawer Steel filing and stationary mobile pedestal . Size : 400 x 460 x 560 mm Note : As per supplier it is not advisable to provide the hanging pedestal for the height adjustable desks .	27	No.	523.00	14,121.00
16.17			Cable Spain made ABS Plastic with Metal Base.	59	No.	57.00	3,363.00
16.18			**CABLE TRAY SPECIFICATION**: Cable tray made of 0.8mm Thick with white powder-coated perforated Finish DIM: 600mmW FINISH : Metal: White	59	No.	57.00	3,363.00
16.19			**PDU** Includes: 2 USB CHARGER (A+C) + 2 UK Power+ 2 CAT 6 Data and with Cable Starter: 2.2 meter UK Note : Provided as an option if required , we have considered grommet holes on the workstation tables .	86	No.	202.00	Rate only
16.20			**ROUND STOOL SEATING** Made: Wooden frame with foam and upholstery with Fabric finish. Base with plastic levelers Finish: Fabric - color form the chart catalogue	2	Nos.	657.00	1,314.00

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR LEAN TECHNOLOGIES @ NASSIMA TOWER , DUBAI-UAE							
Quote Ref No: VID/1057/25/CP/QTN_01/R1							May 2, 2025
SR.NO	As per 3D	SAMPLE IMAGE	DESCRIPTION	QTY	UNIT	RATE	TOTAL (AED)
16.21 OPT 1			**TASK CHAIR** TYPE : Medium Back Chair SPECIFICATION : Seat is made of Molded Foam upholstery with Fabric Finish ,with lumber support and Adjustable 3D armrest, with Four position locking and auto-weight mechanism with Seat Depth Adjustable and base Nylon with gas lift & PU black castor. FINISH : Frame : Black Backrest : Mesh Seat : Fabric Base : Nylon	86	No.	575.00	49,450.00
16.21 OPT 2			**TASK CHAIR** Medium Back Chair. Back: black back frame (Swing Function); Armrest: black adjustable armrest(2D up and down/armrest rotation); Mechanism: STG with 4 position locking; Base: black nylon five-star base with black PA castors. seat fabric: Elastic fabric Color: Dark sky grey Code: CM-PC27B	86	No.	1,149.00	Rate only

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR LEAN TECHNOLOGIES @ NASSIMA TOWER , DUBAI-UAE

Quote Ref No: VID/1057/25/CP/QTN_01/R1 — **May 2, 2025**

SR.NO	As per 3D	SAMPLE IMAGE	DESCRIPTION	QTY	UNIT	RATE	TOTAL (AED)
			MEETING OFFICE				
16.22			**MANAGER TABLE** L-shape executive desk with side cabinet. Material:E0-grade melamine, PVC edge banding, desktop thickness 25mm. Structure: 5-facet steel leg with powder-coated surface. Thickness is 1.8 mm. Cabling: From the bottom of side cabinet. Configured with flip-top cable box. Dim: 1800*1550*750 Ht mm Finish : Melamine	1	No.	3,068.00	3,068.00
16.23			**MEETING OFFICE CHAIR** High Back Chair. Finish: Black nylon and chrome frame with chrome aluminum alloy support, Arms: Adjustable armrest with PU leather pad Back & Seat: Half leather back with and half leather seat. Headrest: Half leather headrest Mechanism: Italy DONATI STG automatically tension control system with Four-Position locking and sliding function Cylinder: High quality gas-lift Base: Aluminum alloy Five-Star base with PA castors. Finish : Leather -ZP9817	1	No	2,614.00	2,614.00
16.24			**VISITOR CHAIR** Arm Chair in fabric with Polished four-star foot + PVC wheelDim:500*550*830*490 Ht mm.Finish: Seat leather	2	No	1,932.00	3,864.00
16.25			**CABINET** Low Height Configuration: Rectangle shape file cabinet with Translucent gray tempered glass in the middle of the door panel Structure: Melamine Base. Dim:2000*400*858 Ht mm. Finish: Melamine.	1	No	1,679.00	1,679.00
			MEETING ROOMS				
16.26			**MEETING TABLE** TOP: 18 / 25mmthk MDF melamine finish table top FINISH : Worktop : Melamine . [Light Oak / Dark Oak / Walnut / White] **Base / Leg : Chrome**				
a			Meeting room: 4 Pax Dimension: **L1200xW1200mmxH750mm**	5	No	2,237.00	11,185.00

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR LEAN TECHNOLOGIES @ NASSIMA TOWER , DUBAI-UAE

Quote Ref No: VID/1057/25/CP/QTN_01/R1 — **May 2, 2025**

SR.NO	As per 3D	SAMPLE IMAGE	DESCRIPTION	QTY	UNIT	RATE	TOTAL (AED)
b			Meeting Room: 4 Pax Dimension: **L1800xW1000mm**	2	No	2,767.00	5,534.00
c			Meeting Rom: 8 - 10 Pax Dimension: **L2400xW1200mmxH750mm**	1	No	3,234.00	3,234.00
d			Meeting Room: 4 Pax **Dimension: L1300xW800mm**	1	No	1,831.00	1,831.00
16.27			**MEETING CHAIR** Armchair - Linked seat sliding design with soft light grey fabric covered foam seat and back. White powder coated steel frame with nylon Pro-V base.	40	Nos.	633.00	25,320.00
16.28			**CABINET** Low Height Configuration: Rectangle shape file cabinet with Translucent gray tempered glass in the middle of the door panel Structure: Melamine Base. Dim:2000*400*858 Ht mm. Finish: Melamine.	3	No	1,679.00	5,037.00
						TOTAL LOOSE FURNITURE :	**355,790.00**
17.00	**ACOUSTIC PODS**						
17.01			**ACOUSTIC PODS** Dimension: W1080 X D1000 X H2326 mm	2	No.	23,947.00	47,894.00
17.02			**ACOUSTIC PODS** Dimension: W2300 X D1785 X H2326 mm	1	No.	41,116.00	41,116.00
						TOTAL ACOUSTIC PODS :	**89,010.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

Thank you,

© Verve Design, 2025

Verve Interior Decoration llc

Unit M04,
Al Reemas Building,
Sheikh Zayed Road, Al Quoz,
PO Box - 128279,
Dubai, UAE.

t : +971 4 240 0119
f : +971 4 240 8403
info@vervedesign.ae
www.vervedesign.ae