verve

space + design

PROPOSAL FOR INTERIOR FITOUT WORKS

INTERIOR FIT-OUT WORKS

FOR

AT

DUBAI-U.A.E

For
Electrolux Middle East

Prepared by:
Aparna Sinha
Verve Interior Decoration LLC
PO Box 128279, Dubai, UAE
Email: aparna@vervedesign.ae

Prepared on:
August 4, 2025

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedes gn.ae PO Box 128279 Dubai,UAE www.vervedes gn.ae

verve
space + design

CONTRACT AGREEMENT: General terms and conditions

Project Timeline: As per approved Project schedule

Payment Terms:

Advance Payment : 30% Advance payment against order confirmation.

Progress Payment : 20% upon approval of all the material samples and mobilization of materials to the site

Progress Payment : 45% as per site progress

Final Payment : 5% upon work completion at site and hand over.

Payment to be honored within 7 days from the date of receipt of Invoice

Note: Any change to the agreed scope of work—whether requested by the client or required due to site-related conditions—will be invoiced at 100% of its value, payable in full before the variation is carried out.

All products offered by us on this project carry a warranty against defective materials and/or workmanship as follows:

Fit Out Works : 12 Months from the date of Handover.

Air Conditioning System – FCUs Disclaimer

Verve has retained the existing Fan Coil Units (FCUs) as part of the final proposal, keeping in mind the client's budgetary constraints. Accordingly, Verve shall not be held liable for the performance of the existing FCUs. Any cooling inefficiencies or issues arising in the final fitout due to the existing AC system's limitations shall be addressed collaboratively between Verve and the Client. Verve cannot guarantee optimal performance of the current units and recommends replacement should performance issues be foreseen or experienced.

Insurances:

All our personnel working on the project will be covered under our Workmen Compensation

All works carried out at site will be covered by our Contractor's All Risk Policy

Validity.

Our offer is valid for a period of 30 days from hereof

Note: Bank guarantee or Retention Requirements TBC

Please sign below for acceptance of the offer. The BOQ will be treated as the final scope of work and contract will form the integral part of the project.

Signature: _____

on behalf of : Electrolux Middle East

Name:

Date:

Signature:_____

on behalf of : Verve Interior Decoration LLC

Name: **Syed Mehdi**

Date: **August 4, 2025**

Quote Ref No: VID/1104/24/CP/QTN_01/R0

T: +971 4 2400 119 F: +971 4 2408 403 E info@vervedos.gn.ae PO Box 128279 Dubai,UAE www.vervedos.gn.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR ELECTROLUX OFFICE @ DUBAI-UAE		
Quote Ref No: VID/1104/24/CP/QTN_01/R0		August 4, 2025
SR. NO	SUMMARY	TOTAL (AED)
1	PRELIMINARIES	38,399.00
2	DEMOLITION AND CIVIL WORKS	62,826.00
3	PARTITION WORKS	171,083.00
4	FLOOR WORKS	161,225.00
5	WALL FINISH	188,890.00
6	CEILING WORKS	117,141.00
7	DOORS	83,015.00
8	SIGNAGE WORKS	21,067.00
9	JOINERY WORKS	307,997.00
10	SANITARY FITTINGS	25,804.00
11	LIGHTING WORKS - NON DIMMABLE	65,600.00
12	HVAC WORKS	189,284.00
13	ELECTRICAL WORKS	150,408.00
14	CIVIL DEFENCE WORKS (PROVISIONAL SUM)	105,549.00
15	PLUMBING WORKS	31,724.00
16	IT WORKS	By Client
	TOTAL AMOUNT FOR FITOUT WORKS (AED):	1,720,012.00
17	LOOSE FURNITURE	205,654.00
	GRAND TOTAL AMOUNT FITOUT + FURNITURE WORKS (AED):	1,925,666.00
18	DECORATIVE ITEMS TO BE RELOCATED FROM EXISTING OFFICE	14,795.00
	GRAND TOTAL AMOUNT (AED):	1,940,461.00

Note: The above price is exclusive of Value Added Tax (VAT), 5% VAT shall be payable as an addition to the invoice value.

Note: **Any variation in terms of quantity that comes up during the course of work has to be paid by the client and hence client is liable for payment of Variation. Retention is not considered.**

Exclusions:

1) All fees and deposit for statutory authorities.
2) Any other items not mentioned in the attached BOQ.
3) LEED building consultancy and certification.

For Verve Interior Decoration LLC

Syed Medhi
Sales Director
+971 50 513 9878
syed@vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR ELECTROLUX OFFICE @ DUBAI-UAE

Quote Ref No: VID/1104/24/CP/QTN_01/R0 — **04-Aug-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
1.00	**PRELIMINARIES**				
1.01	General- Contractor's preliminaries for mobilization, site preparation, Provision for all temporary barricades, setting out transportations to/from site, material deliveries, small tools and equipment's, protection of finished products in on-going site, site attendance and call out attendance. PPE and other site requirements to be followed *Hoarding, Branding and posters are excluded.*	1	Item	8,387.00	**8,387.00**
1.02	All approval charges and security deposit towards any and all authorities (DMCC, DCD, DEWA, Building Management) to be paid by Client on Actual				**By Client On Actuals**
1.03	Co ordination Charges for obtaining approvals from the Landlord & the related authorities.	1	Item	2,578.00	**2,578.00**
1.04	Preparation of Technical drawings as required for submission to Relevant authorities. Detail drawings includes Architectural and MEP drawings.	1	Item	10,573.00	**10,573.00**
1.05	CAR Insurance for fit out work during the execution of works. ***Please Note: Insurance coverage is limited to CAR of Contract Value. If higher coverage limit is required by building management and any other authorities, the additional premium amount will be charged separately .Professional Indemnity Insurance excluded. If required will charge the client on actual.***	1	Item	2,578.00	**2,578.00**
1.06	Regular cleaning of site during construction period and after completion professional deep cleaning and made ready to occupy. Including carting away the debris to Municipal dumping area.	1	Item	9,767.00	**9,767.00**
1.07	Charges for site protection (protection of common area finishes, lift, corridor and the area near to the work space)	1	Item	1,935.00	**1,935.00**
1.08	Scaffolding Charges.	1	Item	2,581.00	**2,581.00**
	Please Note : Provision for mock up and samples submissions at site as per requirement included, however special items if any requested by Client, are chargeable and shall be billed to the client on actual.				
				SUB TOTAL PRELIMINARIES :	**38,399.00**
2.00	**DEMOLITION AND CIVIL WORKS**				
2.01	Carefully removal of existing gypsum partition and dispose from site in accordance to the building management rules and regulations and considering the environmental health and safety aspects and make good the surface.	1	Item	5,678.00	**5,678.00**
2.02	Carefully removal of existing gypsum / 60 x 60 ceiling and dispose from site in accordance to the building management rules and regulations and considering the environmental health and safety aspects and make good the surface.	1	Item	9,813.00	**9,813.00**
2.03	Carefully removal of existing tile flooring **from entrance area corridors to match the level with the external corridor flooring & existing washrooms & pantry only to match the level to the entire office** and dispose from site in accordance to the building management rules and regulations and considering the environmental health and safety aspects and make good the surface. ***Please Note : We have not considered removal of existing floor for the entire area. We propose to retain the existing flooring and have considered self leveling on top of it to fix the proposed floor finishes*** .	1	Item	3,721.00	**3,721.00**
2.04	Carefully removal of existing wall tiles and dispose from site in accordance to the building management rules and regulations and considering the environmental health and safety aspects and make good the surface.	1	Item	4,423.00	**4,423.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai.UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR ELECTROLUX OFFICE @ DUBAI-UAE

Quote Ref No: VID/1104/24/CP/QTN_01/R0 **04-Aug-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
2.05	Carefully removal of existing wooden / glass doors and dispose from site in accordance to the building management rules and regulations and considering the environmental health and safety aspects and make good the surface.	1	Item	3,355.00	**3,355.00**
2.06	Carefully removal of existing joinery items like (wooden cladding / ceiling/ pantry cabinets / vanity counters etc) and dispose from site in accordance to the building management rules and regulations and considering the environmental health and safety aspects and make good the surface.	1	Item	3,871.00	**3,871.00**
2.07	Carefully removal of existing MEP items like (lights /AC diffusers / ducts/ sanitary fittings etc) and dispose from site in accordance to the building management rules and regulations and considering the environmental health and safety aspects and make good the surface.	1	Item	6,452.00	**6,452.00**
2.08	Closing of existing plumbing points after removal of existing sanitary fittings as per site requirement.	1	Item	2,581.00	**2,581.00**
2.09	Chipping of existing floor tiles for laying the proposed self leveling to hold on it for the entire area as per the proposed floor finish	1	Item	15,190.00	**15,190.00**
2.10	Cutting & chasing of the flooring for the required MEP works and as per the proposed floor box locations	1	Item	7,742.00	**7,742.00**
	SUB TOTAL DEMOLITION AND CIVIL WORKS :				**62,826.00**
3.00	**PARTITION WORKS**				
A	**GYPSUM PARTITIONS**				
3.01	**CEMENT BOARD PARTITION (NON FR)** Supply and installation of **100 mm Thk Cement board Partition** with 12.5mm Thk cement board single layer on both sides with GI channels & studs, 50mm thick rockwool insulation inside rising up to the slab ceiling height, jointed taped with smooth leveling ready to receive final finish in the below mentioned areas including baffle above door. **Height up to 3170mm** **Location : Washrooms & Pantry With Wet Points**	83	Sq.m	206.00	**17,098.00**
3.02	**FR GYPSUM PARTITION SINGLE LAYER** Supply and installation of 100mm thk straight drywall partitions made of 72mm GI tracks, 70mm GI studs covered with 12.5mm thick fire resistant gypsum boards made to European standards on both faces with 50 mm mineral Rockwool insulation inside rising up to the slab ceiling height, jointed taped with smooth leveling ready to receive final finish in the below mentioned areas including baffle above door. **Height up to 3170 /770mm** **Brand - Knauf or Equivalent** **Location : Server Room**	35	Sq.m	154.00	**5,390.00**
3.03	**NORMAL GYPSUM PARTITION SINGLE LAYER (NON FR)** Supply and installation of 100mm thick straight drywall partitions, 72mm GI tracks, 70mm GI studs covered with 12.5mm thick normal gypsum boards on both faces made to European standards with 50 mm mineral rockwool insulation inside, jointed taped with smooth leveling ready to receive final finish in the below mentioned areas including baffles. **Height up to 3170 / 770mm** **Brand - Knauf or Equivalent**	190	Sq.m	136.00	**25,840.00**
a	**Location : Throughout As Per Proposed Layout**	170			
b	**Location : Focus Rooms**	20			

T: +971 4 2408 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai.UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR ELECTROLUX OFFICE @ DUBAI-UAE					
Quote Ref No: VID/1104/24/CP/QTN_01/R0					04-Aug-25
SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
3.04	**CEMENT BOARD CLADDING** Supply and installation of **Cement board wall cladding** with GI channels, frames / studs and other necessary material for fixing, smoothened and made ready to receive final finishes. **Height up to 2400mm** **Location : Washroom Area Existing Wall**	25	Sq.m	143.00	**3,575.00**
3.05	**FR GYPSUM CLADDING** Supply and installation of FR 12.5 mm thick fire resistant Gypsum board wall cladding with necessary material for fixing, smoothened and made ready to receive final finishes. **Height up to 3170mm** **Brand - Knauf or Equivalent** **Location : Server Room Existing Wall**	15	Sq.m	126.00	**1,890.00**
3.06	**NORMAL GYPSUM CLADDING** Supply and installation of standard gypsum cladding to be made with 12.5 mm thick normal Gypsum board wall cladding with GR channels & frames and all necessary material for fixing, smoothened and made ready to receive final finishes. **Height up to 3170mm** **Brand - Knauf or Equivalent** **Location : Existing & Columns To Have TV Points & Proposed Walls For Provision For TV**	57	Sq.m	99.00	**5,643.00**
B	**ACOUSTIC GLASS PARTITIONS**				
3.07	**ACCOUSTIC GLASS PARTITION SYSTEM** Kaprel System: Alpha 23 Type of Glass: 12mm Head Channel Dimension: 26mm x 23mm Bottom Channel Dimension: 26mm x 23mm Clarity of Glass: Clear Glass (Regular) Aluminium Profile Finish: RAL 9005 Comments: Including Abutments/Joints **Acoustic Rating: 33dB** **Height up to 2400mm** **Brand - Kaprel**	40	Sq.m	634.00	**25,360.00**
	Location : All Glass In Boardroom, Meeting Rooms & GM Office	34			
	Location : Focus Rooms	6			
C	**NON-STANDARD PARTITIONS**				
3.08	**MOVABLE PARTITIONS - GIBCA SOLID PARTITION** Supply and fix of full height, Sliding foldable door (Manually operated) as per the below specifications. Brand - Hufcor, Series 632 Acoustic rating : 51 STC Panel frames: Lamb's Wool / Gray / Brown (TBC) Track : Hufcor type - 40 Partition size -4400mm (W) x 2400mm (H) **Brand - Gibca** **Location - Proposed Meeting / Board Room**	1	LS	31,724.00	**31,724.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai.UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR ELECTROLUX OFFICE @ DUBAI-UAE

Quote Ref No: VID/1104/24/CP/QTN_01/R0 — **04-Aug-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
Option	**MOVABLE PARTITIONS - KAPREL GLASS PARTITION - OPTION 2** Supply and fix of Sliding foldable glass partition as per the below specifications. Composition: 8mm CF Glass + 8mm CF Glass Aluminium Profile Finish: RAL 9005 Size - 4400mm (W) x 2400mm (H) **Brand - Kaprel** **Model - Aqua MW - 49dB** **Location - Proposed Meeting / Board Room**	1	LS	142,345.00	**RATE ONLY**
3.09	**TOILET CUBICLES** Supply and installation of 25mm thk HPL toilet cubicle partition as per the below specifications & sizes **Male Washroom:** Overall Size - 3745mm X 2400mm H Door Size - 700mm x 2000mmH x 3Nos Divider Size : 1400mm X 2400Hx 2Nos **Female Washroom:** Overall Size - 2182mm X 2400mm H Door Size - 700mm x 2000mmH x 2Nos Divider Size : 1400mm X 2400Hx 1Nos **Location : Washrooms Internal Partition**	1	LS	30,549.00	**30,549.00**
D	**MISCELLANEOUS WORKS**				
3.10	Provision for MDF reinforcement for installation of TV screens and any wall mounted accessories / joinery items. ***Note : Supply of TV screens - By client***	15	Sq.m	554.00	**8,310.00**
3.11	Fabricate, supply and installation of MS support to receive the sliding foldable partition for smoother sliding of the panels and to avoid any sagging.	1	LS	5,162.00	**5,162.00**
3.12	**ACCOUSTIC SEALANT:** Supply and application of acoustic sealant and foam to close the gaps in the partitions, openings, penetrations etc to enhance the sound proofing with-in the enclosed spaces.	1	LS	5,297.00	**5,297.00**
3.13	**FIRE SEALANT:** Supply and application of fire stopping sealant for the openings on the fire rated gypsum walls / MEP services as per the Dubai Civil Defence regulations	1	LS	3,036.00	**3,036.00**
3.14	**WC BOX TYPE WALL CLADDING** Supply and installation of box type wall cladding for WC flush tank, to be constructed with cement boards with required supports and hardwares upto 1500mm height.	1	LS	2,209.00	**2,209.00**
				SUB TOTAL PARTITION WORKS :	**171,083.00**
4.00	**FLOOR WORKS**				
A	**FLOORING BASE WORKS**				
4.01	**ANTI - STATIC RAISED FLOOR** Supply and installation of 1.2 HPL Antistatic Raised Access Flooring with cementitious in filled panels - 600 x 600 x 35m with cross & border pedestals. Pedestal Height 150-200mm - as per the manufactures specifications and recommendation **Location : Server Room**	9	Sq.m	486.00	**4,374.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai.UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR ELECTROLUX OFFICE @ DUBAI-UAE

Quote Ref No: VID/1104/24/CP/QTN_01/R0 — **04-Aug-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
4.02	**SCREED LEVELLING** Leveling of existing screed (mximum upto 60mm) after removal of existing floor finishes and ready to receive new floor finish. All complete in accordence with the site requirement. **Location : After Removal Of Existing Flooring Near Entrances & Washrooms / Pantry Areas For Proposed New Flooring**	95	Sq.m	73.00	**6,935.00**
4.03	**SELF LEVELLING - 5-6mm** Supply and installation of **5 to 6 mm** self levelling compound to achieve same level as existing floor level of unit 2906 which is 3-4mm higher than office units 2904 & 2905, The same to be leveled for fixing new make the floor ready to receive the new flooring. **Location : To Match The Existing Floof Level Of Unit 2906**	230	Sq.m	67.00	**15,410.00**
4.04	**SELF LEVELLING** Supply and installation of **2 to 3** mm self levelling compound to make the floor ready to receive the new flooring. **Location : Remaining Area For Carpet & Vinyl Area Only**	190	Sq.m	46.00	**8,740.00**
4.05	**WATER PROOFING** Supply and installation of **Cementitious water proofing** 2 coats including protection screed. Area considered : Sqm **Location: Floor Area And Wall Upto 1200mm**	75	Sq.m	114.00	**8,550.00**
B	**FLOOR FINISHES**				
4.06	**CERAMIC TILE FLOORING** Supply and installation of **Ceramic Tile flooring to be fixed with required adhesive** with grouting including cutting and alignment. As per design and approved sample. Size : 60 x 60 cm **PC Rate : 60 AED per Sq.m** **Location : Washrooms** ***Note : Subject to sample approval.***	32	Sq.m	176.00	**5,632.00**
4.07	**CARPET FLOORING** Supply and installation of proposed carpet flooring as per the design requirement with necessary material for installation as per manufacturer's recommendation. **Brand: Mohwak or equivalent** **Location : Closed Rooms & Workstation**	330	Sq.m	140.00	**46,200.00**
4.08	**LVT FLOORING** Supply and installation of **LVT flooring** as per the design requirement with necessary material for installation as per manufacturer's recommendation. **Make : Amtico or equivalent** **Location : Corridor & Pantry**	145	Sq.m	134.00	**19,430.00**
4.09	**WOODEN STEPS SEATING** Supply and installation of wooden steps seating to be made with required framework to be finished in semisolid oak finish for thread and riser with 20mm thk nosing. Riser: Approx H175 **Location - Pantry**	1	Item	41,059.00	**41,059.00**
4.10	**TRANSITION STRIP** Supply and installation of Transition Strip in SS finish (ready available). **Location : Between different floor finishes, Door entrances.**	55	Lm	89.00	**4,895.00**
	Please Note: All finishes are subject to final sample approval.				
			SUB TOTAL FLOOR FINISH :		**161,225.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai.UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR ELECTROLUX OFFICE @ DUBAI-UAE

Quote Ref No: VID/1104/24/CP/QTN_01/R0 — **04-Aug-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
5.00	**WALL FINISH**				
5.01	**RECEPTION BACKWALL CLADDING WITH CURVED EDGES** Fabrication, supply and installation reception backwall cladding to be made with MDF in laminate finish with round edges at top & bottom. All complete as per the design with required adhesive and hardwares in the below mentioned area. **Size: 2220+1945L x 2400H mm** **Location : Reception**	10	Sq.m	1,375.00	**13,750.00**
5.02	**WOODEN SLATTED PANELS - LAMINATE FINISH** Supply and installation of **wooden slatted (Ribbed) panel** wall cladding. Cladding to be made with MDF in laminate finish including necessary fittings and accessories for installation. All complete as per the design in the below mentioned areas. **Height up to 2400 / 1000mm** **Location : Meeting Rooms & GM's Office**	22	Sq.m	1,174.00	**25,828.00**
5.03	**STRAIGHT WOODEN CLADDING - LAMINATE FINISH** Supply and installation of **wooden** wall cladding. Cladding to be made with MDF in lamiante finish including necessary fittings and accessories for installation. All complete as per the design in the below mentioned areas. **Height up to 1000mm** **Location : Pantry Step Seating Area & Window Cill Area in L-shape**	52	Sq.m	761.00	**39,572.00**
5.04	**MICRO TOPPING FINISH WINDOW SILL** Supply and application of microtopping finish to the existing tiles finish on the window periphery area. The same to be applied after chipping of the existing tiles, filling / leveling it up with putti to receive the final micrtopping finish. All complete as per the design in the below mentioned area. **Location : Window Periphery**	47	Sq.m	618.00	**29,046.00**
5.05	**BACK PAINTED GLASS (WRITABLE WALL)** Supply & Installation 6mm thk back painted glass with MDF backing as per the design requirement. Glass to be fixed on the proposed wall with required hardwares & adhesive in the below mentioned area. **Height Considered - 1400mm (above 1000mm from floorto the proposed false ceiling height of 2400mm).** **Location : GM Room** ***Note: Subject to sample approval.***	6	Sq.m	621.00	**3,726.00**
5.06	**ACOUSTIC WALL PANEL WITH GROOVES** Supply & Installation Acoustic Grooved Wall Panels - Polyester Fibre Panel • Product: AcouMAX- Grooved • Composition: 100% PET- Felt (60% Recycled) • Standard panel Size: 2400 mm x 1200 mm • Thickness: 12 mm • Density: 2400 gm/sqm • Type of Groove: V-Groove **Acoustic performance: 0.60 to 0.90 NRC** **Brand - AcouMAX** **Location : Focus Pods** ***Note: Subject to sample approval.*** 	35	Sq.m	388.00	**13,580.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai.UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR ELECTROLUX OFFICE @ DUBAI-UAE

Quote Ref No: VID/1104/24/CP/QTN_01/R0 — **04-Aug-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
5.07	**BACKSPLASH** Supply and installation of porcelian tiles backsplash. The same to be fixed with grouting and required hardwares and adhesive. All complete as per the design requirement in the below mentioned areas. **Size : 120 x 60 cm** **Height up to - 600mm** **Brand - RAK Ceramics or Equivalent** **PC Rate : 95 AED per Sq.m** **Location : Pantry & Display Areas**	10	Sq.m	228.00	**2,280.00**
5.08	**CERAMIC WALL TILES** Supply and installation of ceramic wall tiles. The same to be fixed with grouting and required hardwares and adhesive. All complete as per the design requirement in the below mentioned areas. **Size : 60 x 60 cm** **Height up to - 2400mm** **Brand - RAK Ceramics or Equivalent** **PC Rate : 60 AED per Sq.m** **Location : Washrooms**	86	Sq.m	166.00	**14,276.00**
5.09	**WALLPAPER** Supply and installation of **wallpaper** with necessary surface preparation and materials for application. All complete as per the design requirement in the below mentioned areas. **Height up to - 2400mm** **Brand - NGC or Equivalent** **PC Rate : 60 AED per Sq.m** **Location : Boardroom / Meeting Room** ***Please Note : We have considered the wall paper selection from standard range with is available cut to size. If any customisation or full roll wallpaper to be selected***	9	Sq.m	119.00	**1,071.00**
5.10	**TEXTURED WALL PAINT** Supply and application of **Textured paint finish.** The paint to be applied with base preparation after cleaning, leveling, putti and primer base with 2 coats of final texture paint finish. All complete as per the site requirement in the below mentioned areas. **Height up to 3170mm** **Brand - Locally sourced** **Location : Board Room On Ledge Seating Area Walls & Pantry Above Wooden Cladding On The Step Seating Area Wall**	42	Sq.m	135.00	**5,670.00**
5.11	**WALL PAINT** Supply and application of **fenomistic paint finish**. The paint to be applied with base preparation after cleaning, leveling, putti and primer base with 2 coats of final femonastic paint finish. All complete as per the site requirement in the below mentioned areas. **Height up to 3170 / 2400mm** **Brand - JOTUN or equivalent** **Location : Remaining Area Excluding Above Mentioned Finishes**	470	Sq.m	33.00	**15,510.00**
5.12	**MIRROR** Supply and installation of 6mm thick plain silver mirror with straight polished non bevelled edges including necessary MDF backing and materials for installation without any cut out, holes or illumination. **Height up to 1500mm** **Brand : Guardian** **Location : Above Vanity Counter In Washrooms**	7	Sq.m	481.00	**3,367.00**

T: +971 4 2408 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai.UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR ELECTROLUX OFFICE @ DUBAI-UAE

Quote Ref No: VID/1104/24/CP/QTN_01/R0 — **04-Aug-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
5.13	**ROLLER BLINDS - MANUAL** Supply and installation of standard **sunscreen manual roller blinds with** complete tracks and channels on single sided guide rail. The same to be fixed from mullion to mullion as per the design requirement in the below mentioned areas. **Height up to 2200mm** **Brand - Locally Sourced** **Location : Entire Window Periphery Area**	117	Sq.m	99.00	**11,583.00**
	SKIRTING WORKS				
5.14	**STRAIGHT SKIRTING - VENEER / PU** Supply and installation of 50 mm high straight skirting to be made with **MDF skirting in veneer / PU paint finish** with necessary fittings and accessories. All complete as per the design requirement in the beloiw mentioned areas. **Location - Throughtout On Straight Walls**	145	Lm	55.00	**7,975.00**
5.15	**CIRCULAR SKIRTING - VENEER / PU** upply and installation of 50 mm high circular skirting to be made with **MDF skirting in veneer / PU paint finish** with necessary fittings and accessories. All complete as per the design requirement in the beloiw mentioned areas. **Location - On Circular Columns**	3	Nos	552.00	**1,656.00**
	Please Note: ***1. All finishes are subject to final sample approval.*** ***2. All Artworks, decorative accessories and marketing works excluded.***				
			SUB TOTAL WALL FINISH :		**188,890.00**
6.00	**CEILING WORKS**				
	DECORATIVE CEILING				
6.01	**STRETCH CEILING** Supply and installation of Euroceil Premium Translucent PVC Membrane with Aluminium Channels and High Quality PVC Harpoon strengthening the periphery. PVC Membrane adhering to EN 14716 standards, Made in Germany customized at state of the art ISO 9001:2015 certified manufacturing facility in India, with following test certificates: * UL Classified * Fire: b-s1-d0 * No Heavy Metals * A+ Emission Code: EC2-TR-015 Nichia / Osram chip LED BAR/ module with wiring and looping. **Brand - Euroceil** **Location : Board / Meeting Rooms**	18	Sq.m	1,263.00	**22,734.00**

T: +971 4 2408 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai.UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR ELECTROLUX OFFICE @ DUBAI-UAE

Quote Ref No: VID/1104/24/CP/QTN_01/R0 — **04-Aug-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
6.02	**SUSPENDED ACOUSTIC CEILING** Supply & Installation of Acoustic Cloud Ceiling-Polyester Fibre • Product: AcouMAX-Cloud • Composition: 100% PET- Felt (60% Recycled) • Cloud Thickness: 12 mm • Edge Thickness: 40 mm • Cloud Size: 650 mm x 2400 mm • Color: To be selected • Density: 2400gm/m² • Acoustic performance: 0.60 to 0.90 NRC • Installation: Using hanging wires and Clips. **Brand - AcouMAX** **Location : Corridor Area**	52	Sq.m	673.00	**34,996.00**
6.03	**SUSPENDED ACOUSTIC PANELS** Supply & Installation of Suspended Acoustic Panels Boads Acoustic Cloud Ceiling-Polyester Fibre • Product: AcouMAX-Cloud • Composition: 100% PET- Felt (60% Recycled) • Thickness: 20 mm • Color: To be selected • Density: 2400gm/m² • Acoustic performance: 0.60 to 0.90 NRC • Installation: Using hanging wires and Clips. **Brand - AcouMAX** **Location : Pantry** 				
	Size : 800 x 800mm	2	Nos.	688.00	**1,376.00**
	Size : 500 x 500mm	2	Nos.	481.00	**962.00**
	GYPSUM CEILING				
6.04	**ALUMINUM PERFORATED CEILING** Supply and installation of **600 x 600mm aluminum perforated** ceiling tiles with complete suspension system. All complete as per the design requirement in the below mentioned areas. **Brand - Knauf or equivalent** **Location : Washrooms & Storeroom**	38	Sq.m	135.00	**5,130.00**
6.05	**PLAIN NORMAL GYPSUM CEILING** Supply and installation of Normal gypsum ceiling to be made with 12.5mm thk Normal Gypsum Board Plain ceiling with GI "C "channel, furring channels, studs and all necessary accessories. All complete with joining and tapping ready to receive final paint finish in the below mentioned areas. **Brand - Knauf or equivalent**	78	Sq.m	114.00	**8,892.00**
	Location - Closed Offices	70			
	Location - Focus Pods	8			
6.06	**GYPSUM DECORATIVE COVE** Supply and installation of gypsum decorative cove to be made with 12.5 mm normal gypsum boards with required supports as per the design requirements ready to receive final finish in the below mentioned areas. **Brand - Knauf or equivalent** **Location : Reception, GM's Office & Boardroom On Wall**	30	Lm	94.00	**2,820.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai.UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR ELECTROLUX OFFICE @ DUBAI-UAE

Quote Ref No: VID/1104/24/CP/QTN_01/R0 — **04-Aug-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
6.07	**GYPSUM BULKHEAD** Supply and installation of 150/250mm high gypsum bulkhead to be made with 12.5 mm normal gypsum boards with required supports as per the design requirements ready to receive final finish in the below mentioned areas. **Brand - Knauf or equivalent** **Location : Above Joinery Areas & Ceiling Level Difference**	65	Lm	94.00	**6,110.00**
6.08	**GYPSUM PELMET / WINDOW BULKHEAD** Supply and installation of 300mm high gypsum bulkhead to be made with 12.5 mm normal gypsum boards with required supports as per the design requirements ready to receive final finish in the below mentioned areas. **Brand - Knauf or equivalent** **Location: Window Periphery For Blinds** ***Please Note : The above rate is provided as rate only as we propose to retain the existing bulkhead. However if during demolition it is damaged, it will be charged as per the rate provided.***		Lm	161.00	**RATE ONLY**
6.09	**SHADOW GROOVE** Supply and installation of shadow groove with required channels as per the design requirements ready to receive final finish in the below mentioned areas. **Location: Closed Rooms Between Wall & False Ceiling.**	90	Lm	48.00	**4,320.00**
6.10	**OPEN CEILING PAINT** Supply and application of stucco paint finish for the open ceiling area. The paint to be applied with base preparation after cleaning, leveling, putti and primer base with 2 coats of final stucco paint finish. All complete as per the site requirement in the below mentioned areas including MEP services. **Location : Entire OPen Office Area Including Pantry**	350	Sq.m	62.00	**21,700.00**
6.11	**GYPSUM CEILING PAINT** Supply and application of fenomistic paint finish. The paint to be applied with base preparation after cleaning, leveling, putti and primer base with 2 coats of final standard femonastic paint finish. All complete as per the site requirement in the below mentioned areas. **Location : Above Mentioned Gypsum, Ceiling, Bulkheads & Coves**	115	Sq.m	31.00	**3,565.00**
	MISCELLANEOUS WORKS				
6.12	**GYPSUM ACCESS PANEL** Supply and installation of access panels fixed with hinges on the concealed frame for the future maintenance of MEP services above closed ceiling areas. Maximum size upto 600 x 600. **Location: Proposed Gypsum ceiling area** **Note : Subject to final MEP drawings**	12	Nos.	309.00	**3,708.00**
6.13	**FCU BOXING** Supply and installation of gypsum boxed cladding fixed with Rockwool insulations around the FCU units to absorb the sound as well as to reduce the noise of the unit. Necessary framing to be fixed around the unit with required access panels for easy operation and accessing of the units will be included. **Location: Proposed FCU's In Open Ceiling Area** ***Note : Subject to final HVAC design requirement***		Nos.	2,069.00	**RATE ONLY**
6.14	**SUPPORT FOR DECORATIVE LIGHTS** Supply and installation of additional soft wooden frame work built inside the gypsum ceiling to act as additional supports and to receive the light fittings.	1	Item	828.00	**828.00**
	Please Note : All finishes are subject to final sample approval.				
				SUB TOTAL CEILING FINISH :	**117,141.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai.UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR ELECTROLUX OFFICE @ DUBAI-UAE

Quote Ref No: VID/1104/24/CP/QTN_01/R0 — **04-Aug-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
7.00	**DOORS**				
	FR GLASS DOORS				
7.01	**SINGLE LEAF GLASS DOOR - FR 60 min** Supply and installation of **10 mm super-lite clear tempered fire rated (1 hour) single leaf glass door** with all around 40 x 60 mm MS frame along with powder coated aluminum cladding fixing by DORMA BTS 75 floor machine, accessories, bottom lock and 5 mm thick fire proof gasket. ***Note: All fittings are in powder coating or SS finish. Offset pivot excluded.*** Size: L 1000 mm X H 2800 mm **Location : Main Entrance** ***Please Noe : We have retained existing door as per building fitout guidelines. However have quoted RATE ONLY for the new door, incase building approves it beign FR door.***		No	10,345.00	**RATE ONLY**
	ACOUSTIC GLASS DOORS				
7.02	**ACOUSTIC GLASS SWING DOOR - SINGLE LEAF** **Kaprel System: Ultra DC - 34dB** Type of Glass: 12mm Locks: Excluded Ironmongery: Door Handle: Kaprel 1200mm H Type - Round Accessories: Pivots + Kaprel Floor Spring Acoustic Rating: 34dB Clarity of Glass: Clear Glass (Regular) Aluminium Profile Finish: RAL 9005 Comments: Including Door Stop Single leaf Width : 1074mm Height of Door: 2400 **Location : All Meeting Rooms, Boardroom, Focus Pods & GM's Office**	8	No	6,773.00	**54,184.00**
	WOODEN DOORS				
7.03	**WOODEN SWING DOOR - FR 60 min** Supply and installation of single leaf 60 mins-fire rated MDF flush single swing door with solid Meranti or Beech wood frame and architraves in approved matte or semi-gloss PU paint finish including all necessary standard ironmongeries. **Size : 1000 mm x 2400 mm** **Location - Server Room**	1	No	5,517.00	**5,517.00**
7.04	**SINGLE LEAF WOODEN DOOR - NON FR** Supply and installation of Semi solid wooden swing door NON FR in PU paint finish, with Frame, architrave, in PU paint finish with all necessary ironmongery and material for fixing. **Size: 900 x 2400mm** **Location : Storeroom & Washrooms Main Doors**	2	Nos	3,933.00	**7,866.00**
7.05	**CONCEALED SINGLE LEAF WOODEN DOOR - NON FR** Supply and installation of concealed wooden swing door NON FR. Door to be made with ready made doorcore in texture paint finish to match the wall finish, with concealed frame, with all necessary ironmongery and material as per the design in the below mentioned areas **Size: 900 x 2400mm Ht** **Location : Store Room & Boardroom For Sliding Folding Partition**	2	Nos	3,586.00	**7,172.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai.UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR ELECTROLUX OFFICE @ DUBAI-UAE

Quote Ref No: VID/1104/24/CP/QTN_01/R0 — **04-Aug-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
7.06	**CONCEALED DB SHUTTERS - JN09** Fabrication, supply and installation of concealed shutters for DB section along the corricor, to be made of MDF in paint finish concealed shutters to be fixed on concealed frame. All complete as per the design with required adhesive and hardwares in the below mentioned area. **Size : 2500L x 400D x 2400H mm** **Location : Corridor Near Entrance**	1	Nos	8,276.00	**8,276.00**
				SUB TOTAL DOORS :	**83,015.00**
8.00	**SIGNAGE WORKS**				
8.01	Supply and installation of Signage withlogo to be made with lasercut MDF in PU paint finish without illumination. All Complete as per the design in the below mentioned area. **Size: 1500 mm L x 600mm high** **Location : Reception & Waiting Area** ***Note : Subject to final design and sample approval.***	1	Item	9,322.00	**9,322.00**
8.02	Supply and installation of illuminated text works fixed on wall. All Complete as per the design in the below mentioned area. **Size: 2500 mm x 150mm** **Location : Pantry** ***Note : Subject to final design and sample approval.*** 	1	Item	6,207.00	**6,207.00**
8.03	**VINYL GRAPHICS** Supply and installation of vinyl graphics sticker as per the design to be fixed on glass partitions & walls. The same to be fixed with required adhesive in the below mentioned areas. **Sizes Varies** **Brand - Locally Sourced** **Location: Focus Pods, Boardroom & Display Counters**	6	Nos	362.00	**2,172.00**
8.04	**FROSTED / SANDBLASTING STICKER** Supply and installation of frosted / sandblasting sticker as per the design to be fixed above proposed glass partitions & doos. The same to be fixed with required adhesive in the below mentioned areas. **Height up to 1500mm** **Brand - Locally Sourced** **Location: All New Glass partition And Doors**	34	Sq.m	99.00	**3,366.00**
				SUB TOTAL SIGNAGE WORKS:	**21,067.00**
9.00	**JOINERY WORKS**				
9.01	**RECEPTION DESK WITH CURVED FRONT BOTTOM- JN01** Fabrication, Supply and installation of **Reception Counter** to be made of MDF in **combination of PU paint and marble** finish. The sides and top in PU paint finish and front elevation to be cladded with **Azul bahia marble** with slatted on **down curved front** bottom elevation. All complete with required adhesive and hardwares. **Size:2220Lx700Dx1100Hmm** **Location : Reception** 	1	Item	29,031.00	**29,031.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai.UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR ELECTROLUX OFFICE @ DUBAI-UAE

Quote Ref No: VID/1104/24/CP/QTN_01/R0 — **04-Aug-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
Option	**RECEPTION DESK WITH STRAIGH FRONT BOTTOM- JN01** Fabrication, Supply and installation of **Reception Counter** to be made of MDF in **combination of PU paint and marble** finish. The sides and top in PU paint finish and front elevation to be cladded with **Azul bahia marble** with slatted on **down straight front** elevation. All complete as per the design with required adhesive and hardwares in the below mentioned area. **Size:2220Lx700Dx1100Hmm** **Location : Reception**	1	Item	25,680.00	**RATE ONLY**
9.02	**WOODEN SLATS - JN02** Fabrication, supply and installation of wooden slats to be made of MDF in laminate finish. All complete as per the design with required adhesive and hardwares in the below mentioned area. **Size : 200L x 40D x 2400H mm** **Location : Near Entrance Display Area**	5	Nos	993.00	**4,965.00**
9.03	**RECEPTION SEATING - JN03** Fabrication, supply and installation of Lounge Seating, to be made of MDF in laminate finish. The front bottom to be finished with slatted panels including coushioned and upholstered seat abnd backrest covered in standard range of fabric. Item also includes planter box with GI sheet to accomodate Client supplied natural plants. All complete as per the design with required adhesive and hardwares in the below mentioned area. ***PC Rate of fabric considered as AED 150/- per Lm*** **Size seating : 2700L x 600D x 800H mm** **Size planter : 1575L x 300D x 400H mm** **Location : Reception** 	1	Item	18,322.00	**18,322.00**
9.04	**DISPLAY UNIT - JN04** Fabrication, supply and installation of Display unit in lounge area. Unit to be made of MDF laminate finish shutters and OH unit with provision for client supplied electronics. Counter top to be in corian finish. Inner carcass in white melamine finish. All complete as per the design with required adhesive and hardwares in the below mentioned area. **Size base : 1750L x 600D x 900H mm** **Size OH : 1750L x 600D x 600H mm** **Size Full height : 875L x 600D x 2400H mm** **Location : Reception Lounge Area** **Next To Meeting Room** 	1	Item	13,545.00	**13,545.00**

T: +971 4 2408 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai.UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR ELECTROLUX OFFICE @ DUBAI-UAE

Quote Ref No: VID/1104/24/CP/QTN_01/R0 — **04-Aug-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
9.05	**WALL MOUNT LEDGE - JN05** Fabrication, supply and installation of Ledge to be made with MDF in laminate finish to be fixed with required concealed support. All complete as per the design with required adhesive and hardwares in the below mentioned area. **Size : 1600L x 800D x 30Thick mm** **Location : Focus Pods** 	2	Nos	1,969.00	**3,938.00**
9.06	**PRINTER CABINET- JN06** Fabrication, supply and installation of printer cabinet with bottom unit with corian counter top and 2 nos of open shelves. Counter to be made of MDF in laminate finish for external surfaces & internal carcass to be made with white melamine. All complete as per the design with required adhesive and hardwares in the below mentioned area. **Size base : 2120L x 600D x 900H mm** **Size shelves : 2120L x 400D x 30Thick (2 nos)** **Location : Behind Reception**	1	Item	10,317.00	**10,317.00**
9.07	**NICHE SEATING - JN07** Fabrication, supply and installation of niche seating, to be made with MDF paint finish base, upholstered fabric seat & backrest. Including arch framing in laminate finish. All complete as per the design with required adhesive and hardwares in the below mentioned area. **Size seating : 3930L x 650D x 900H mm** **Size framing : 3930L x 650D x 2400H mm** ***PC Rate of fabric considered as AED 150/- Lm.*** **Location : Boardroom / Meeting Rooms** 	2	Nos	27,034.00	**54,068.00**
9.08	**HOT BAR DESK - JN08** Fabrication, supply and installation of curved hot bar ledge, to be made of MDF laminate finish top and round hollow base. All complete as per the design with required adhesive and hardwares in the below mentioned area. **Location : Near Window** 				

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai.UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR ELECTROLUX OFFICE @ DUBAI-UAE

Quote Ref No: VID/1104/24/CP/QTN_01/R0 — **04-Aug-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
a	**Size : 5100L x 500D x 1100H mm.**	1	Nos	14,516.00	**14,516.00**
b	**Size : 3425 x 500D x 1100H mm.**	1	Nos	9,740.00	**9,740.00**
9.09	**STORAGE CUM DISPLAY UNIT - JN09** Fabrication, supply and installation of storage cum display open shelves unit along the corricor. The top and bottom portion of the unit to have storage unit with shutters and centre portion with open display shelves. Unit to be of MDF in laminate finish shutters. Inner carcass in white melamine finish. All complete as per the design with required adhesive and hardwares in the below mentioned area. **Size : 6200L x 400D x 2400H mm** **Location : Corridor Next To DB** 	1	Nos	33,593.00	**33,593.00**
9.10	**DISPLAY UNIT - JN10** Fabrication, supply and installation of Display unit near pantry. Unit to be made of MDF laminate finish shutters and OH unit with provision for client supplied electronics. Counter top to be in corian finish. Inner carcass in white melamine finish. All complete as per the design with required adhesive and hardwares in the below mentioned area. **Size base : 1665L x 600D x 900H mm** **Size OH : 1665L x 600D x 600H mm** **Size Full height : 835L x 600D x 2400H mm** **Location : CorridorNear Pantry** 	1	Nos	14,582.00	**14,582.00**
9.11	**BOOK SHELF- JN11** Fabrication, supply and installation of open book shelf. Unit to be made of MDF laminate finish. All complete as per the design with required adhesive and hardwares in the below mentioned area. **Size : 1200L x 450D x 2400Hmm** **Location : Pantry Next To Server Room** 	1	Nos	6,323.00	**6,323.00**

T: +971 4 2408 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai.UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR ELECTROLUX OFFICE @ DUBAI-UAE

Quote Ref No: VID/1104/24/CP/QTN_01/R0 — **04-Aug-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
9.12	**BAR HEIGHT TABLE / LEDGE- JN12** Fabrication, supply and installation of bar height table / ledge. Same to be made of MDF laminate finish top and round hollow base. All complete as per the design with required adhesive and hardwares in the below mentioned area. **SIze : 5700L x 500D x 1100H mm** **Location : Pantry Near Window** 	1	Nos	14,840.00	**14,840.00**
9.13	**OPEN SHELVES - JN13** Fabrication, supply and installation of open shelves with L-angle metal supports at required distances. All complete as per the design with required adhesive and hardwares in the below mentioned area. **SIze : 3170+1250L x 650D x 25mm thk x 4Nos** **Location : Store Room**	1	Nos	14,086.00	**14,086.00**
9.14	**PANTRY UNIT - JN14** Fabrication, supply and installation of pantry unit to be comprised of bottom and overhead units. The counter to be made with MDF in laminate finish for the exterbal surface and inner carcass to be made with white melamine. Counter to be in corian finish. All complete as per the design with required adhesive and hardwares in the below mentioned area. **SIze base : 2745+1115L x 650D x 900H mm** **Size OH : 2745+1890L x 550D x 900H mm** **Location : Pantry** 	1	Nos	23,998.00	**23,998.00**
9.15	**VANITY COUNTER - JN15** Fabrication, supply and installation of vanity counter to be made of MDF structure cladded with corian. Inlcuding seating bench without backrest in uphosltered fabric finish. All complete as per the design with required adhesive and hardwares in the below mentioned area. ***PC Rate of fabric considered AED 100/- per Lm*** **Size vanity : 2600L x 700D x 900H mm** **Size bench : 1600L x 700D x 450H mm.** **Location : Female Washroom**	1	Nos	16,303.00	**16,303.00**

T: +971 4 2408 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai.UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR ELECTROLUX OFFICE @ DUBAI-UAE

Quote Ref No: VID/1104/24/CP/QTN_01/R0 — **04-Aug-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
9.16	**VANITY COUNTER - JN16** Fabrication, supply and installation of vanity counter to be made of MDF structure cladded with corian. Inlcuding seating bench without backrest in uphosltered fabric finish. All complete as per the design with required adhesive and hardwares in the below mentioned area. ***PC Rate of fabric considered AED 100/- per Lm*** **Size vanity : 1800L x 700D x 900H mm** **Size bench : 800L x 700D x 450H mm.** **Location : Male Washroom**	1	Nos	10,566.00	**10,566.00**
9.17	**JANITOR CABINET - JN17** Fabrication, supply and installation of janitor cabinet to be made of MDF in laminate finish for external surface and internal carcass to be made with melamine. All complete as per the design with required adhesive and hardwares in the below mentioned area. **Size : 1000L x 600D x 2400H mm** **Location : Near Washroom**	1	Nos	6,207.00	**6,207.00**
9.18	**LOW HEIGHT CABINET WITH PLANTER - JN18** Fabrication, supply and installation of low height cabinet with planter arrangement on the top portion. Cabinet to be made with MDF in laminate finish to match the desk. Planter box to have arrangement for live plants with waterproofing & GI sheet. All complete as per the design with required adhesive and hardwares in the below mentioned area. **Size : 750L x 400D x 900H mm** **Location : GM Cabin** 	1	Nos	2,157.00	**2,157.00**
9.19	Supply of 50mm dense, 600mm dia of loose cushions for the step seating area to be made with fibre and covered with standard range of fabric to match the 3D's, to be placed randomly. 	10	Nos	690.00	**6,900.00**
	Please Note: ***1. All carcass considered melamine finish, Shutter in laminate if not indicated above*** ***2. Standard Ironmongeries considered, Hevon or similar*** ***3. All drawers considered normal closing and shutter in finger goove finish only. Magnetic push to charge additinal if required*** ***4. All solid surface quoted considered solid color. Marble effect or with sparkles to charge additional if require. Propose Stark or similar*** ***5. DB wall cladding cosnidered FR MDF*** ***6. All Wet areas considered MR MDF, rest of areas are cosnidered standard MDF only*** ***7. All joinery with concealed lighting are considered with standard LED strip light quoted under light fittings*** ***8. All Plants & Electronics by Client***				
				SUB TOTAL JOINERY WORKS :	**307,997.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai.UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR ELECTROLUX OFFICE @ DUBAI-UAE

Quote Ref No: VID/1104/24/CP/QTN_01/R0 — **04-Aug-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
10.00	**SANITARY FITTINGS**				
10.01	**WC - WALL MOUNTED** Supply of Rimless wall hung water closet in glossy finish (Alpine white) and oval shape with complete kit including flush tank, flush plate and seat cover. Dimensions: 520 X 430 mm Color: Alpine White **Make : RAK ceramics** **Model Venice**	5	Nos	1,612.00	**8,060.00**
10.02	**BIDET SPARY KIT** Supply of bidet spray kit chrome finish. **Make : RAK Ceramics**	5	Nos	143.00	**715.00**
10.03	**URINALS** Supply of wall hung waterless urinals in glossy finish (Alpine white)with complete kit and urinal partitions Color: Alpine White **Make : RAK ceramics** **Model : Jazira**	3	Nos	873.00	**2,619.00**
10.04	**WASH BASIN - COUNTER TOP** Supply of countertop wash basin including fixing kit and bottle trap. Dimensions: 420 X 430 mm Color: Alpine White Shape : Round **Make : RAK ceramics** **Model - Feeling**	5	Nos	647.00	**3,235.00**
10.05	**BASIN MIXER** Supply of single lever deck high rise basin mixer in chrome finish Make : RAK ceramics Model - Prime	5	Nos	520.00	**2,600.00**
10.06	**TOILET ROLL HOLDER** Supply of wall mounted Toilet roll holder with single fixing point in chrome finish with screws and dowels including fixed guide plate. **Make : RAK Ceramics**	5	Nos	110.00	**550.00**
10.07	**PEDAL BIN** Supply of Pedal bin with 5 Liter capacity. Size : 200x 235 x 280 mm	8	Nos	197.00	**1,576.00**
10.08	**PAPER TOWEL DISPENSOR** Supply of chrome finish wall mounted manual paper tower dispensor Make : Sanipex	2	Nos	1,744.00	**3,488.00**
10.09	**FLOOR DRAIN** Supply of 150 x 150 mm floor drain in chrome finish.	9	Nos	181.00	**1,629.00**

T: +971 4 2408 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai.UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR ELECTROLUX OFFICE @ DUBAI-UAE

Quote Ref No: VID/1104/24/CP/QTN_01/R0 — **04-Aug-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
10.10	**SINK SET** Supply of Inset stainless steel sink with drainboard Colour : Stainless steel **Make : RAK Ceramics**	1	No	619.00	**619.00**
10.11	**SINK MIXER** Supply of deck mounted Single lever mixer tap in chrome finish with swivel spout. **Make - RAK Ceramics** **Model - Peak**	1	No	713.00	**713.00**
	Please Note : Above rates are subject to Client's final selection & approvals				
				SUB TOTAL SANITARY FITTINGS :	**25,804.00**
11.00	**LIGHTING WORKS - NON DIMMABLE**				
11.01	**SUSPENDED LED CURVED LINEAR LIGHT** Supply of Suspended LED Curved Linear Light Power: 20Watts/Mtr Output Lumen: 1600Lm/Mtr Size: L2400*W1400mm Profile Size: W40xH60mm Control Gear: Non Dimmable Protection: IP20 4000K & White Finish	1	Nos	4,090.00	**4,090.00**
11.02	**SUSPENDED LED LINEAR LIGHTS - 6.5** Supply of Suspended LED Linear Light Power: 114Watts Output Lumen: 9120Lm/Mtr. Size: L6500XW40XH70mm Control Gear: Non-Dimmable Protection: IP20 4000K & White Finish	3	Nos	2,197.00	**6,591.00**
11.03	**SUSPENDED LED LINEAR LIGHTS - 5.0** Supply of Suspended LED Linear Light Power: 114Watts Output Lumen: 9120Lm/Mtr. Size: L5000XW40XH70mm Control Gear: Non-Dimmable Protection: IP20 4000K & White Finish	1	Nos	2,018.00	**2,018.00**
11.04	**SUSPENDED LED LINEAR LIGHTS - 3.8** Supply of Suspended LED Linear Light Power: 114Watts Output Lumen: 9120Lm/Mtr. Size: L3800XW40XH70mm Control Gear: Non-Dimmable Protection: IP20 4000K & White Finish	3	Nos	1,284.00	**3,852.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai.UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR ELECTROLUX OFFICE @ DUBAI-UAE

Quote Ref No: VID/1104/24/CP/QTN_01/R0 — **04-Aug-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
11.05	**SUSPENDED LED LINEAR LIGHTS - 2.5** Supply of Suspended LED Linear Light Power: 114Watts Output Lumen: 9120Lm/Mtr. Size: L2500XW40XH70mm Control Gear: Non-Dimmable Protection: IP20 4000K & White Finish	1	Nos	844.00	**844.00**
11.06	**RECESSED LED LINEAR LIGHTS BETWEEN ACOUSTIC CEILING PANELS** Supply of Surface LED Linear Light Power: 30Watts/Mtr. Output Lumen: 2400Lm Size: W50XH75mm Control Gear: Non-Dimmable Protection: IP20 4000K & White Finish	35	Lm	342.00	**11,970.00**
11.07	**TRACKS LIGHTS** Supply of LED Track Spot Light with 4line 3phase power connector, end caps, internal caps and suspension kits Power: 20Watts Output Lumen: 1800Lm Size: D58XH155mm Control Gear: Non-Dimmable Protection: IP20 4000K & White Finish	45	Nos	401.00	**18,045.00**
11.08	**RECESSED DOWNLIGHT** Recessed LED Trimless Spot Light Power: 20Watts Output Lumen: 1800Lm Size: 145*87mm Control Gear: Non-Dimmable Protection: IP20 **4000K & White Finish**	60	Nos	184.00	**11,040.00**
11.09	**RECESSED DOWNLIGHT** Recessed LED Down Light Power: 20Watts Output Lumen: 1800Lm Size: φ103*H70mm Control Gear: Non-Dimmable Protection: IP65 **4000K & White Finish**	25	Nos	110.00	**2,750.00**

T: +971 4 2408 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai.UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR ELECTROLUX OFFICE @ DUBAI-UAE

Quote Ref No: VID/1104/24/CP/QTN_01/R0 — **04-Aug-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
11.10	**LED COVE LIGHT** LED Flexible Strip Light LUMILEDS Power: 9.6Watts/Mtr Output Lumen: 1203Lm/Mtr Protection: IP20 Aluminum Profile With Diffuser Size:17x15mm Constant Voltage Driver Control Type: Non Dimmable Output Voltage:24VDC Protection: IP20 **Location : Ceiling, Walls & Joinery**	80	Lm	55.00	**4,400.00**
	Note : **1. Quantity subject to final RCP design** **2. Non - dimmable lights considered.**				
				SUB TOTAL LIGHTS :	**65,600.00**
	MEP WORKS (PROVISIONAL SUM SUBJECT TO FINAL MEP DESIGN)				
12.00	**HVAC WORKS**				
12.01	Supply and installation of CHW FCUs (' Daikin / Mekar/ Trosten' Make) 3.2 TR ,1200 cfm,	2	Nos.	4,342.00	**8,684.00**
12.02	Relocation of existing FCU units from existing location to the proposed as per the new ceiling location. ***Please Note : We assume that the existing AC machines are in good working condition.***	6	Nos.	2,601.00	**15,606.00**
12.03	Performance test of existing FCU's - 6No's ***Please Note : Any modifications based on performance test to charged additional.***	1	Item	4,681.00	**4,681.00**
12.04	Supply and installation of PICV valves for the new FCU	2	Nos	2,483.00	**4,966.00**
12.05	Supply and installation on new VAV	3	Nos	3,448.00	**10,344.00**
12.06	Supply and installation of thermostat including wiring	2	Nos	623.00	**1,246.00**
12.07	Relocation of existing thermostat including wiring as per new peoposed layout	6	Nos	414.00	**2,484.00**
	DUCTING AND ACCESSORIES				
12.08	Supply and Installation of **PI Duct** with necessary support	1	LS	33,966.00	**33,966.00**
12.09	Supply and installation of **12 mm rubber type Acoustic liner**				
12.10	Supply and installation of **Volume Control Damper.**				
12.11	Supply and Installation of flexible duct, plenum box and ring.				
12.12	Supply and installation of cross talk attenuator ,	7	Nos.	1,277.00	**8,939.00**
12.13	Extension of existing supply air duct.	1	LS	10,213.00	**10,213.00**
12.14	Extension of existing supply extract ducting	1	LS	10,213.00	**10,213.00**
	GRILLS AND DIFFUSER				
12.15	Supply and Installation of **slot (2 Slot) grill** with necessary accessories and supports.	1	Item	39,716.00	**39,716.00**
12.16	Supply and Installation of **diffusers** with necessary accessories and supports.				
	DRAIN PIPE				
12.17	Supply and installation of condensate drain pipe for new FCU. ***Please Note : To be connected to the existing drain pipe.***	1	LS	1,418.00	**1,418.00**
12.18	Supply and installation of Chilled Water Pipe Line (ERW CH40) and fittings with thermal insulation, canvas cloth with foster, support and hangers for newly installed pipes for FCU's	1	LS	7,092.00	**7,092.00**
12.19	Supply and installation of fusable link FD	2	Nos	1,312.00	**2,624.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai.UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR ELECTROLUX OFFICE @ DUBAI-UAE

Quote Ref No: VID/1104/24/CP/QTN_01/R0 **04-Aug-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
12.20	Chemical Flushing - Make : Culligan	1	Item	13,617.00	**13,617.00**
12.21	Air & CWH balancing by the 3rd Party	1	Item	7,092.00	**7,092.00**
12.22	Testing commissioning	1	Item	6,383.00	**6,383.00**
	Exclusions: ***1. BTU Meter, BMS Connection.*** ***2. Maintenance platform*** ***3. We have considered reusing of existing FCU's with perfoming a test on it. If it is noticed that any of the existing FCU's are not in usable condition, we will have to propose for new FCU's and related works accordingly.***				
				SUB TOTAL HVAC WORKS :	**189,284.00**
13.00	**ELECTRICAL WORKS**				
13.01	PVC conduiting and wiring for the proposed light points ***Please Note: Light points are subject to revise upon final RCP Layout.***	162	Nos	166.00	**26,892.00**
13.02	installation of above mentioned light fittings	1	Item	5,745.00	**5,745.00**
13.03	Supply and installation of **Grid switch for lighting.** Including **PVC conduiting**. (Matt PVC finish Legrand / schneider) for Open workstation & corridor.	2	Nos	709.00	**1,418.00**
13.04	Supply and installation of **Single switch for lighting.** Including **PVC conduiting**. (Matt PVC finish Legrand / schneider) for closed offices	10	Nos	284.00	**2,840.00**
13.05	Supply and installation of **13A Single wall Power Socket,** in PVC finish including conduiting and wiring. (Schneider / Legrand)	16	Nos	319.00	**5,104.00**
13.06	Supply and installation of **13A Twin wall Power Socket,** in black PVC finish including conduiting and wiring. (Schneider / Legrand)	15	Nos	351.00	**5,265.00**
13.07	Supply and installation of **15A Single wall Power Socket,** in Black PVC finish including conduiting and wiring. (Schneider / Legrand)	2	Nos	638.00	**1,276.00**
13.08	Supply and installation of **16A industrial socket** including pvc conduiting and wiring. (Schneider / Legrand) for server racks	3	Nos	830.00	**2,490.00**
13.09	Supply and installation of **20A DP switch** and flex outlet for water heater including pvc conduiting and wiring.	3	Nos	702.00	**2,106.00**
13.10	Supply and installation of **Shared Floor Box -** 2 x Twin 13A with cabling and conduiting + provision for 2 x Twin Data with conduting and faceplates provision only. Make : Obo or equivalent	30	Nos	780.00	**23,400.00**
13.11	Supply and installation of **Single Floor Box -**1 x Twin 13A with cabling and conduiting + provision for 1 x twin data with conduting and faceplates provision only. Make : Obo or equivalent	7	Nos	638.00	**4,466.00**
13.12	Supply and installation of **13Amps fles outlet** with **PVC conduiting** and wiring (Considered for new FCU)	2	Nos	543.00	**1,086.00**
13.13	**50mm conduit** and cabling provision for **HDMI/VGI.**	8	Nos.	270.00	**2,160.00**
13.14	Supply and installation of **PVC** containment for **WI-FI Points**. (Provisional qty, considered for entrances & server room)	6	Nos.	135.00	**810.00**
13.15	Supply and installation of PVC containment for **Access control** (Provisional qty)	3	Nos	135.00	**405.00**
13.16	Supply and installation of **PVC** containment for **CCTV Points**. (Provisional qty, considered only near entrances & server room)	3	Nos.	135.00	**405.00**
13.17	Supply and installation of **PVC** containment for **AV Rack**	1	Nos.	135.00	**135.00**
13.18	Supply and installation of **13A flex outlet** for VAV including pvc conduiting and wiring	3	Nos.	532.00	**1,596.00**
13.19	Modification of existing **SMDB** with necessary ELCB, MCB , and all other accessories as per DEWA ***Please Note : Subject to load availability***	1	Item	5,106.00	**5,106.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai.UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR ELECTROLUX OFFICE @ DUBAI-UAE

Quote Ref No: VID/1104/24/CP/QTN_01/R0 — **04-Aug-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
13.20	Supply and installation of new DB ***Please Note : Subject to building management approval***	1	No	8,298.00	**8,298.00**
13.21	Supply and installation of 4C 35 sqmm xlpe/swa/pvc + 1C 16 sqmm Ecc cable from existing SMDB to DB.	1	Lot	7,340.00	**7,340.00**
13.22	Supply and installation of GI Trunking at high level for lighting circuits.	1	Lot	7,149.00	**7,149.00**
13.23	Supply and installation of GI Trunking at high level for power	1	Lot	7,596.00	**7,596.00**
13.24	Supply and installation of GI Trunking at high level for network	1	Lot	8,043.00	**8,043.00**
13.25	DEWA submission, inspection and approval.	1	No	4,965.00	**4,965.00**
13.26	Testing commissioning.	1	Item	2,837.00	**2,837.00**
13.27	Providing PVC conduit for Data/Voice	85	Nos	135.00	**11,475.00**
	Please Note: ***1. We have assumed that the existing infrastructure's power has sufficient capacity to cater to the requirement of the project.*** ***2. We have not allowed for upgrade of the capacity of any base building system.*** ***3. All electrical conduits considered are of PVC type.*** ***4. We have not allowed for any specific lighting control system in this offer.*** ***5. Subject to final MEP drawings*** ***Exclusions:*** ***1. Any BMS integration or related works.*** ***2. DEWA Consultancy for power upgrade.*** ***3. Metering Works Not considered***				
				SUB TOTAL ELECTRICAL WORKS :	**150,408.00**
14.00	**CIVIL DEFENCE WORKS (PROVISIONAL SUM)**				
A	**FIRE ALARM WORKS**				
14.01	Supply and installation of Smoke detector with base	4	Nos	LS	**42,581.00**
14.02	Relocation of existing smoke detector	21	Nos		
14.03	Relocation of existing heat detector	1	Nos		
14.04	Supply and installation of break glass	2	Nos		
14.05	Supply and installation of sounder	2	Nos		
14.06	Interfacing modules (FACP + Access control - 3 nos)	4	Nos.		
14.07	Isolation/ De-Isolation of fire alarm devices.	1	Lot		
14.08	Programming, Testing and commissioning charges for the fire alarm system.	1	Item		
14.09	Certification charges for the fire alarm devices.	1	Lot		
14.10	Supply and installation of Fire alarm control panel ***(If Required)***	1	Item	14,840.00	**RATE ONLY**
B	**FIRE FIGHTING WORKS**				
14.11	Supply and installation of pendent sprinkler	4	Nos	LS	**49,871.00**
14.12	Relocation of existing pendant sprinkler	13	Nos		
14.13	Relocation of existing pendent sprinkler with upright sprinkler.	25	Nos		
14.14	Supply and installation of CO2 and Dry Powder fire extinguishers set.	3	Sets		
14.15	Supply and installation fire blanket	1	No		
14.16	Shutdown and draining charges for the fire fighting system.	1	Item		
14.17	Pressure test and commissioning,	1	Item		
14.18	Certification charges	1	Item		
14.19	Supply & Installation of FM200 system for the server room ***(If required by DCD for more than 9 Sqm area)***	1	PS	64,517.00	**RATE ONLY**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai.UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR ELECTROLUX OFFICE @ DUBAI-UAE					
Quote Ref No: VID/1104/24/CP/QTN_01/R0					04-Aug-25
SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
C	EMERGENCY WORKS				
14.20	Supply and installation of emergency light.	2	Nos.	LS	13,097.00
14.21	Relocation of Emergency Light	16	Nos.		
14.22	Supply and installation of exit light.	5	Nos.		
14.23	Testing & commissioning charges	1	Item		
	Notes / Exclusions: ***1. Any additional charges/ fees for any third party shall be paid by the client.*** ***2. FM 200 works is quoted as provisional sum as rate only, will be charged if required by DCD during approvals*** ***3.We have considered our standard DCD approved supplier to carry out the above FLS works with 15% co-ordination charges. If there is any building approved Base build contractor for the same and the rates vary, Verve will charge on actuals to client with 15% co-ordination charges.***				
				SUB TOTAL CIVIL DEFENCE WORKS :	105,549.00
15.00	PLUMBING WORKS				
15.01	Supply and installation of **Water Supply PPR pipe** for Hot and Cold with socket, Elbow ,Threaded Road and other accessories as per standard	1	LS	31,724.00	31,724.00
15.02	Supply and installation of **UPVC drainage Pipe** for waste and Soil Pipe and connecting to existing line with ,fittings ,socket ,and other accessories as per Standard	1	LS		
15.03	Supply and Installation of **angle valve and gate valve.**	29	Nos.		
15.04	Pressure Test and Gravity Test	1	Item		
15.05	Installation of sanitary wares	1	LS		
15.06	Supply and installation of water heater - 80 litres	3	Nos.		
15.07	Corring and scanning works	15	Nos.	966.00	RATE ONLY
	Please Note : ***1. All terminations considered to the stub out present at site , connected to building system .*** ***2. Sanipump works excluded***				
				SUB TOTAL PLUMBING WORKS :	31,724.00

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai.UAE www.vervedesign.ae

verve
space + design

FURNITURE WORKS FOR ELECTROLUX OFFICE @ DUBAI-UAE

Quote Ref No: VID/1104/24/CP/QTN_01/R0 — **August 4, 2025**

SR.NO	SAMPLE IMAGE	CODE	DESCRIPTION	QTY	UNIT	RATE	TOTAL (AED)
17.00	**LOOSE FURNITURE**						
	PLEASE NOTE : ***LEAD TIME / DELIVERY - 10-12weeks** ***TASK CHAIRS - We have not considered any new task (user) chair, existing Herman Miller chairs to be reused for GM Desk, Reception & all workstations**						
	GM OFFICE						
17.01			**O Leg: Executive Table** Dimension: 1600W/750D x 1800L/500D x 750H a) MFC Rectangular TopLeg/Base b)O Leg c/w 1 Bracket c) Stack-on Metal Leg c/w 1_Bracket (75H) ~ L/R d) Support Beam (E-E) e) MFC Rectangular Modesty Panel c/w 2 Brackets (1450W)Storage f) MFC Stack on Cabinet c/w 1x Sliding Door, 1x Open Shelf & Pedestal 2D1F (1800W x 500D x 650H) ~Right / Left *1x Power Management Box (in Sliding Door Compartment) *1x Sliding Door (492W), 1x Open Shelf (900W), 1x 2D1F (408W) *Sliding Door c/w Aluminium Sliding Rail c/w Keylock w/ Handle *Pedestal Door c/w Handle & Keylock, Full Extension Slide for Drawer Boxes *Open Shelf c/w 1-Adjustable Shelf (25T)*18mmT Back Panel *c/w Aluminium flip-up w/ soft-closing (400W x 130D) ~ PC White	1	No.	2,996.00	**2,996.00**
17.02			**MOV- Meeting Table** Dimension: D90 x H72 Cm a) Mov Round Meeting Table, 4 Pax *MFC Top c/w Straight Edging Upholstered Base in fabric Finish:Top: MFC 25mm Thickness Top, Straight Edging Base: Tranquil Fabric	1	No.	1,914.00	**1,914.00**
17.03			**Tino (4-Star Base) - Visitor / Meeting Chairs** Swivel chair w/ 4-prong base; w/ Castor or Fixed Glide Fixed Armrest & Armrest Cover. Dimension: (630W x 630D x 820~880H; SH:450~510 (±10mm)) Upholstery: Fabric - TOMO Fabric - Harmony /Vinyl - Mori /Vinyl - Roma	4	No.	1,266.00	**5,064.00**
OPTION			**Grace lowback visitor chair** With armrest in White frame, Sled Base Finish & Upholstery: Frame: Grey PP Cushion: Berry Vinyl/ Tomo Fabric	1	No.	992.00	**RATE ONLY**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vorvodesign.ae PO Box: 128279, Dubai,UAE www.vorvodesign.ae

verve
space + design

FURNITURE WORKS FOR ELECTROLUX OFFICE @ DUBAI-UAE

Quote Ref No: VID/1104/24/CP/QTN_01/R0 — **August 4, 2025**

SR.NO	SAMPLE IMAGE	CODE	DESCRIPTION	QTY	UNIT	RATE	TOTAL (AED)
	MEETING ROOMS						
17.04	**Image for illustration purpose only**		**Meeting Room 12 Pax** Waltz: Meeting Table Dimension: 3200W x 1200D x 750H a) MFC Square Worktop c/w 1-Through hole for flip up.Cable Management b) Aluminium Flipper Cover c/w Soft-closing (400W x 130D) c) Metal Wire Tray c/w 4 Brackets (800W x 150D x 120H)Leg/Base d) Waltz Leg c/w 2 Brackets (1150W x 725H) e) Intermediate Leg c/w Wire Riser Box (1050/450W x 725H) f) Support Beam (E-1) g) Levelling Plate	1	No.	3,263.00	**3,263.00**
OPTION			**Meetin Room 12 Pax** Fabrication, supply & installtion of customised meeting table, to be made with MDF in laminate finish top and solid base in oval shape as per the design. All complete as per the design with required adhesive and hardwares in the below mentioned area. **Size : 2800L x 1350D x 750H mm** Location : Meeting Room Next To GM Office	1	No.	18,069.00	**RATE ONLY**
17.05	**Image for illustration purpose only**		**Meeting Room 8 Pax** Waltz: Meeting Table Dimension: 2800W x 1200D x 750H a) MFC Square Worktop c/w 1-Through hole for flip up.Cable Management b) Aluminium Flipper Cover c/w Soft-closing (400W x 130D) c) Metal Wire Tray c/w 4 Brackets (800W x 150D x 120H)Leg/Base d) Waltz Leg c/w 2 Brackets (1150W x 725H) e) Intermediate Leg c/w Wire Riser Box (1050/450W x 725H) f) Support Beam (E-1) g) Levelling Plate	1	No.	3,098.00	**3,098.00**
17.06	**Image for illustration purpose only**		**Meeting Room 6 Pax** Waltz: Meeting Table Dimension: 2400W x 1200D x 750H a) MFC Square Worktop c/w 1-Through hole for flip up.Cable Management b) Aluminium Flipper Cover c/w Soft-closing (400W x 130D) c) Metal Wire Tray c/w 4 Brackets (800W x 150D x 120H)Leg/Base d) Waltz Leg c/w 2 Brackets (1150W x 725H) e) Intermediate Leg c/w Wire Riser Box (1050/450W x 725H) f) Support Beam (E-1) g) Levelling Plate	1	No.	2,911.00	**2,911.00**
17.07			**Meeting Chairs** Posh - Meeting Chair Posh Midback Chair with upholstered Armrest Synchro Mechanism Aluminium Polish Base on Castors. Finish: Fabric - Viktor	26	Nos.	1,579.00	**41,054.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

FURNITURE WORKS FOR ELECTROLUX OFFICE @ DUBAI-UAE

Quote Ref No: VID/1104/24/CP/QTN_01/R0 — **August 4, 2025**

SR.NO	SAMPLE IMAGE	CODE	DESCRIPTION	QTY	UNIT	RATE	TOTAL (AED)
17.08			**Foldable Meeting Table** Forward foldable table with modesty panel Dimension - 1200 x 600 x 750 MFC table top & modesty panel with forward folding table frame **Without cable management**	4	Nos.	1,541.00	**6,164.00**
17.09			**Meetin Room 5 Pax** Grandeur: MFC Rectangular Freestanding Table Dimension: 1800W x 800D x 1070Ha) Grandeur MFC Rectangular Freestanding Table c/w 1-Grommet Cover *MFC Top (25mm Thk) *MFC Panel Leg (25mm Thk) *MFC Modesty Panel (450mm H)	1	Nos.	1,689.00	**1,689.00**
17.10			**SUNON DUCK High Chairs** High back chairs, Back in Fabric Finish with Metal Leg [white, black, pale pinkish grey, pea green, coral]. Dim: 520*560*1080*770 Ht mm. Finish: Fabric.	5	Nos.	1,212.00	**6,060.00**
	WORKSTATION AREA						
17.11			**DESKTOP MODIFICATION** Removal of existing worktop from the height adjustable / fixed workstations & replacing it with new desk top as per the new sizes Finish : Laminate. Dimension : 1400 x 700 x 18mm thk	60	Nos.	1,228.00	**73,680.00**
Option			**HARD BOARD PRIVACY PANELS** 18 mm thick fabric screen with holding brackets (Brackets in anodised finish only). DIM :- 1400mm(W) x 350mm (H) FINISH : Fabric: Colour From the chart catalogue		Nos.	515.00	**RATE ONLY**
Option			**HARD BOARD PRIVACY PANELS (For Height adjustable desks)** 18 mm thick fabric screen with holding brackets (Brackets in anodised finish only). DIM :- 1400mm(W) x 650mm (H) FINISH : Fabric: Colour From the chart catalogue		Nos.	773.00	**RATE ONLY**
Option			**CABLE MANAGEMENT** Snake Tube. Finish : White		Nos.	136.00	**RATE ONLY**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vorvodesign.ae PO Box: 128279, Dubai,UAE www.vorvodesign.ae

verve
space + design

FURNITURE WORKS FOR ELECTROLUX OFFICE @ DUBAI-UAE

Quote Ref No: VID/1104/24/CP/QTN_01/R0 — **August 4, 2025**

SR.NO	SAMPLE IMAGE	CODE	DESCRIPTION	QTY	UNIT	RATE	TOTAL (AED)
Option			**Cluster of 2 - Linear Workstation** Waltz: Double Desk - inline Dimension: (1400W x 700D x 750H) a) MFC Rectangular Worktop c/w 1-Grommet CoverCable Management b) Aluminium Flipper Cover c/w Soft-closing (400W x 130D) c) Metal Wire Tray c/w 3 Brackets (500W x 150D x 120H) d) Round Wire SnakeLeg/Base e) Waltz Leg c/w 1 Bracket (650W x 725H) f) Support Beam (E-E) g) MFC Rectangular Modesty Panel c/w 2 Brackets(1200W x 450H x 18T)Storage h) MFC Mobile Pedestal w/ 3 Drawers c/w Handle & Keylock(408W x 475D x 515H)	2	Nos.	3,674.00	**RATE ONLY**
Option			**Cluster of 4** Waltz: Double Desk - inline Dimension: (2800W x 1400D x 750H) a) MFC Rectangular Worktop c/w 1-Grommet CoverCable Management b) Aluminium Flipper Cover c/w Soft-closing (400W x 130D) c) Metal Wire Tray c/w 3 Brackets (500W x 150D x 120H) d) Round Wire SnakeLeg/Base e) Waltz Leg c/w 1 Bracket (650W x 725H) f) Support Beam (E-E) g) MFC Rectangular Modesty Panel c/w 2 Brackets(1200W x 450H x 18T)Storage h) MFC Mobile Pedestal w/ 3 Drawers c/w Handle & Keylock(408W x 475D x 515H)	5	Nos.	6,054.00	**RATE ONLY**
Option			**Cluster of 6** Waltz: Double Desk - inline Dimension: (4200W x 700D x 750H) a) MFC Rectangular Worktop c/w 1-Grommet CoverCable Management b) Aluminium Flipper Cover c/w Soft-closing (400W x 130D) c) Metal Wire Tray c/w 3 Brackets (500W x 150D x 120H) d) Round Wire SnakeLeg/Base e) Waltz Leg c/w 1 Bracket (650W x 725H) f) Support Beam (E-E) g) MFC Rectangular Modesty Panel c/w 2 Brackets(1200W x 450H x 18T)Storage h) MFC Mobile Pedestal w/ 3 Drawers c/w Handle & Keylock(408W x 475D x 515H)	6	Nos.	9,284.00	**RATE ONLY**
17.12		**Hot Desk**	**SUNON DUCK High Chairs - For Hot Desks / High Bar** High back chairs, Back in Fabric Finish with Metal Leg [white, black, pale pinkish grey, pea green, coral]. Dim: 520*560*1080*770 Ht mm. Finish: Fabric.	9	Nos.	1,212.00	**10,908.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vorvodesign.ae PO Box: 128279, Dubai,UAE www.vorvodesign.ae

verve
space + design

FURNITURE WORKS FOR ELECTROLUX OFFICE @ DUBAI-UAE							
Quote Ref No: VID/1104/24/CP/QTN_01/R0							August 4, 2025
SR.NO	SAMPLE IMAGE	CODE	DESCRIPTION	QTY	UNIT	RATE	TOTAL (AED)
17.13			**PANTRY HIGH BAR CHAIRS** Chat - Fixed Stool Polyurethane foam padding Shell in woodWhite Frame (BC) Upholstery:Cat F (fabric/PU Leather)	6	Nos.	669.00	**4,014.00**
17.14			**PANTRY TABLES** MFC Square Table w/ Round Base Dimension: 800W x 800D x 745H a) MFC Square Top(800W x 800D x 25T) b) Round Base (500Dia x 720H)	2	Nos.	2,183.00	**4,366.00**
17.15			**PANTRY CHAIRS** Keira - Dining Chair Armchair with metal painted frame,seat and backrest completely upholstered Upholstery: Group 2 (Fabric/ PU Leather)	4	Nos.	1,716.00	**6,864.00**
17.16			**POUF** SUNON D SERIES D2 Pouf Finish: High elastic Leather with a waterproof coating Structure: The aerospace steel frame inside backseat and solid wood frame shaping the sea tBase: The loop-shaped black wood leg. Dim: 650*550*430 Ht mm. Finish :EPU 81	4	Nos.	1,277.00	**5,108.00**
17.17			**SUNON MOGEE Coffee Table** Veneer Table top With Steel Base & Leg. Dim : 600 Dia *420 Ht mm. Finish : Veneer	1	Nos.	1,673.00	**1,673.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

FURNITURE WORKS FOR ELECTROLUX OFFICE @ DUBAI-UAE							
Quote Ref No: VID/1104/24/CP/QTN_01/R0							August 4, 2025
SR.NO	SAMPLE IMAGE	CODE	DESCRIPTION	QTY	UNIT	RATE	TOTAL (AED)
17.18			**S POD 3.0 Plus** • Laminated Desktop with Chamfered Edge(820W x 320D x 1020H) • Power Consumption: 0.18A • POD Weight: 266Kg • Heavy Castors for The Ease of Mobility • Motion Sensor For Energy Saving • Control Hub (Touch Screen) *Able to adjust: Light brightness, Fan speed, Sensor duration,Occupancy light mode, Intermittent air circulation duration. • LED Strip Light • Air Ventilation & Purifying System • AH Meyer Netbox Flush 1 Power Socket 110-240 VAC,Max. 20A & USB A+C Charging, Max 65W • 1 x CAT 6 Lan Outlet • High Stool not IncludedDimension:1000W x1000D x 2180H	2	Nos.	27,161.00	**RATE ONLY**
17.19	**EXISTING FURNITURE**		**SHIFTING OF EXISTING FURNITURE** 1. Dismantling of existing HM chairs, packing it properly, to be transported from existing office at Mazaya Tower to new office at Fortune tower, in JLT and re-installating the same for the users. 2. Dismantling of existing worktops of the workstations to replace it with new worktops (as quoted under item 17.11) and cart away the old worktops. Shifting of existing frames to the new office to fix the proposed new worktops.	1	Ls	24,828.00	**24,828.00**
						TOTAL LOOSE FURNITURE	**205,654.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vorvodesign.ae PO Box: 128279, Dubai,UAE www.vorvodesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR ELECTROLUX OFFICE @ DUBAI-UAE

Quote Ref No: VID/1104/24/CP/QTN_01/R0 — **August 4, 2025**

SR.NO	DESCRIPTION	QTY	UNIT	RATE	TOTAL (AED)
18.00	**DECORATIVE ITEMS TO BE RELOCATED FROM EXISTING OFFICE**				
18.01	Removal of existing of the decorative feature planters fixed on glass partition in Electrolux existing office at Mazaya BB1 and the same to be fixed on the proposed glass partition of the board room in new office.	5	Nos.	1,379.00	**6,895.00**
18.02	Replacement of damaged glass partition after removal of the above mentionbed decorative panels from the glass. Supply & installation of 10mm thk standard glass partition with powdercoated U-Channel (closest match to existing) as per the site requirement. ***Please note : The quantity is approximate for budget purpose only, same will be remeasured and charged as per actual site requirement based on per sqm rate.***	20	Sqm	395.00	**7,900.00**
	TOTAL FOR RELOCATION WORKS				**14,795.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

Thank you,

© Verve Design, 2025

Verve Interior Decoration llc

Unit M04,
Al Reemas Building,
Sheikh Zayed Road, Al Quoz,
PO Box - 128279,
Dubai, UAE.

t : +971 4 240 0119
f : +971 4 240 8403
info@vervedesign.ae
www.vervedesign.ae