verve

space + design

PROPOSAL FOR INTERIOR FITOUT WORKS

INTERIOR FIT-OUT WORKS

FOR

AT

DUBAI-U.A.E

For
Electrolux Middle East

Prepared by:
Aparna Sinha
Verve Interior Decoration LLC
PO Box 128279, Dubai, UAE
Email: aparna@vervedesign.ae

Prepared on:
August 20, 2025

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedes gn.ae PO Box 128279 Dubai,UAE www.vervedes gn.ae

verve
space + design

CONTRACT AGREEMENT: General terms and conditions

Project Timeline: As per approved Project schedule

Payment Terms:

Advance Payment : 30% Advance payment against order confirmation.
Progress Payment : 20% upon approval of all the material samples and mobilization of materials to the site
Progress Payment : 45% as per site progress
Final Payment : 5% upon work completion at site and hand over.

Please Note : All progress payments to be paid in 30days from the date of invoice, EXCLUDING advance payment

Note: Any change to the agreed scope of work—whether requested by the client or required due to site-related conditions—will be invoiced at 100% of its value, payable in full before the variation is carried out.

All products offered by us on this project carry a warranty against defective materials and/or workmanship as follows:

Fit Out Works : 12 Months from the date of Handover.

Air Conditioning System – FCUs Disclaimer

Verve has retained the existing Fan Coil Units (FCUs) as part of the final proposal, keeping in mind the client's budgetary constraints. Accordingly, Verve shall not be held liable for the performance of the existing FCUs. Any cooling inefficiencies or issues arising in the final fitout due to the existing AC system's limitations shall be addressed collaboratively between Verve and the Client. Verve cannot guarantee optimal performance of the current units and recommends replacement should performance issues be foreseen or experienced.

Insurances:

All our personnel working on the project will be covered under our Workmen Compensation
All works carried out at site will be covered by our Contractor's All Risk Policy

Validity.

Our offer is valid for a period of 30 days from hereof
Note: Bank guarantee or Retention Requirements TBC

Please sign below for acceptance of the offer. The BOQ will be treated as the final scope of work and contract will form the integral part of the project.

Signature: _____
on behalf of : Electrolux Middle East

Name:
Date:

Signature:_____
on behalf of : Verve Interior Decoration LLC

Name: Syed Mehdi
Date: August 20, 2025

Quote Ref No: VID/1104/24/CP/QTN_01/R2

T: +971 4 2400 119 F: +971 4 2408 403 E info@vervedes.gn.ae PO Box 128279 Dubai,UAE www.vervedes.gn.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR ELECTROLUX OFFICE @ DUBAI-UAE		
Quote Ref No: VID/1104/24/CP/QTN_01/R2		August 20, 2025
SR. NO	SUMMARY	TOTAL (AED)
1	PRELIMINARIES	34,875.00
2	DEMOLITION AND CIVIL WORKS	56,290.00
3	PARTITION WORKS	167,324.00
4	FLOOR WORKS	160,196.00
5	WALL FINISH	144,888.00
6	CEILING WORKS	120,428.00
7	DOORS	86,948.00
8	SIGNAGE WORKS	25,345.00
9	JOINERY WORKS	305,028.00
10	SANITARY FITTINGS	25,804.00
11	LIGHTING WORKS - NON DIMMABLE	62,911.00
12	HVAC WORKS	185,519.00
13	ELECTRICAL WORKS	146,796.00
14	CIVIL DEFENCE WORKS (PROVISIONAL SUM INCLUDING FM200)	157,164.00
15	PLUMBING WORKS	28,966.00
16	IT WORKS	By Client
	TOTAL AMOUNT FOR FITOUT WORKS (AED):	1,708,482.00
17	LOOSE FURNITURE	132,357.00
	GRAND TOTAL AMOUNT FITOUT + FURNITURE WORKS (AED):	1,840,839.00
18	DECORATIVE ITEMS TO BE RELOCATED FROM EXISTING OFFICE	14,795.00
	GRAND TOTAL AMOUNT (AED):	1,855,634.00

Note: The above price is exclusive of Value Added Tax (VAT), 5% VAT shall be payable as an addition to the invoice value.

Note: **Any variation in terms of quantity that comes up during the course of work has to be paid by the client and hence client is liable for payment of Variation. Retention is not considered.**

Notes:

1) We have considered shifiting of existing user / meeting chairs to be reused for all Meeting Rooms & Workstations as confirmed by Client.

2) We have tried adjusting 15 Nos of existing low height cabinets to be reused in the new office as per the space availiability

Exclusions:

1) All fees and deposit for statutory authorities.
2) Any other items not mentioned in the attached BOQ.
3) LEED building consultancy and certification.

For Verve Interior Decoration LLC
Syed Mehdi
Sales Director
+971 50 513 9878
syed@vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR ELECTROLUX OFFICE @ DUBAI-UAE

Quote Ref No: VID/1104/24/CP/QTN_01/R2 — **20-Aug-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
1.00	**PRELIMINARIES**				
1.01	General- Contractor's preliminaries for mobilization, site preparation, Provision for all temporary barricades, setting out transportations to/from site, material deliveries, small tools and equipment's, protection of finished products in on-going site, site attendance and call out attendance. PPE and other site requirements to be followed *Hoarding, Branding and posters are excluded.*	1	Item	8,387.00	**8,387.00**
1.02	All approval charges and security deposit towards any and all authorities (DMCC, DCD, DEWA, Building Management) to be paid by Client on Actual				**By Client On Actuals**
1.03	Co ordination Charges for obtaining approvals from the Landlord & the related authorities.	1	Item	2,578.00	**2,578.00**
1.04	Preparation of Technical drawings as required for submission to Relevant authorities. Detail drawings includes Architectural and MEP drawings.	1	Item	7,049.00	**7,049.00**
1.05	CAR Insurance for fit out work during the execution of works. ***Please Note: Insurance coverage is limited to CAR of Contract Value. If higher coverage limit is required by building management and any other authorities, the additional premium amount will be charged separately .Professional Indemnity Insurance excluded. If required will charge the client on actual.***	1	Item	2,578.00	**2,578.00**
1.06	Regular cleaning of site during construction period and after completion professional deep cleaning and made ready to occupy. Including carting away the debris to Municipal dumping area.	1	Item	9,767.00	**9,767.00**
1.07	Charges for site protection (protection of common area finishes, lift, corridor and the area near to the work space)	1	Item	1,935.00	**1,935.00**
1.08	Scaffolding Charges.	1	Item	2,581.00	**2,581.00**
	Please Note : Provision for mock up and samples submissions at site as per requirement included, however special items if any requested by Client, are chargeable and shall be billed to the client on actual.				
				SUB TOTAL PRELIMINARIES :	**34,875.00**
2.00	**DEMOLITION AND CIVIL WORKS**				
2.01	Carefully removal of existing gypsum partition and dispose from site in accordance to the building management rules and regulations and considering the environmental health and safety aspects and make good the surface.	1	Item	4,000.00	**4,000.00**
2.02	Carefully removal of existing gypsum / 60 x 60 ceiling and dispose from site in accordance to the building management rules and regulations and considering the environmental health and safety aspects and make good the surface.	1	Item	9,220.00	**9,220.00**
2.03	Carefully removal of existing tile flooring **from entrance area corridors to match the level with the external corridor flooring & existing washrooms & pantry only to match the level to the entire office** and dispose from site in accordance to the building management rules and regulations and considering the environmental health and safety aspects and make good the surface. ***Please Note : We have not considered removal of existing floor for the entire area. We propose to retain the existing flooring and have considered self leveling on top of it to fix the proposed floor finishes*** .	1	Item	3,495.00	**3,495.00**
2.04	Carefully removal of existing wall tiles and dispose from site in accordance to the building management rules and regulations and considering the environmental health and safety aspects and make good the surface.	1	Item	4,155.00	**4,155.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai.UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR ELECTROLUX OFFICE @ DUBAI-UAE

Quote Ref No: VID/1104/24/CP/QTN_01/R2 **20-Aug-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
2.05	Carefully removal of existing wooden / glass doors and dispose from site in accordance to the building management rules and regulations and considering the environmental health and safety aspects and make good the surface.	1	Item	2,365.00	**2,365.00**
2.06	Carefully removal of existing joinery items like (wooden cladding / ceiling/ pantry cabinets / vanity counters etc.) and dispose from site in accordance to the building management rules and regulations and considering the environmental health and safety aspects and make good the surface.	1	Item	3,635.00	**3,635.00**
2.07	Carefully removal of existing MEP items like (lights /AC diffusers / ducts/ sanitary fittings etc.) and dispose from site in accordance to the building management rules and regulations and considering the environmental health and safety aspects and make good the surface.	1	Item	6,060.00	**6,060.00**
2.08	Closing of existing plumbing points after removal of existing sanitary fittings as per site requirement.	1	Item	1,820.00	**1,820.00**
2.09	Chipping of existing floor tiles for laying the proposed self leveling to hold on it for the entire area as per the proposed floor finish	1	Item	14,270.00	**14,270.00**
2.10	Cutting & chasing of the flooring for the required MEP works and as per the proposed floor box locations	1	Item	7,270.00	**7,270.00**
	SUB TOTAL DEMOLITION AND CIVIL WORKS :				**56,290.00**
3.00	**PARTITION WORKS**				
A	**GYPSUM PARTITIONS**				
3.01	**CEMENT BOARD PARTITION (NON FR)** Supply and installation of **100 mm The Cement board Partition** with 12.5mm The cement board single layer on both sides with GI channels & studs, 50mm thick rockwool insulation inside rising up to the slab ceiling height, jointed taped with smooth leveling ready to receive final finish in the below mentioned areas including baffle above door. **Height up to 3170mm** **Location : Washrooms & Pantry With Wet Points**	83	Sq.m	206.00	**17,098.00**
3.02	**FR GYPSUM PARTITION SINGLE LAYER** Supply and installation of 100mm the straight drywall partitions made of 72mm GI tracks, 70mm GI studs covered with 12.5mm thick fire resistant gypsum boards made to European standards on both faces with 50 mm mineral Rockwool insulation inside rising up to the slab ceiling height, jointed taped with smooth leveling ready to receive final finish in the below mentioned areas including baffle above door. **Height up to 3170 /770mm** **Brand - Knauf or Equivalent** **Location : Server Room**	37	Sq.m	154.00	**5,698.00**
3.03	**NORMAL GYPSUM PARTITION SINGLE LAYER (NON FR)** Supply and installation of 100mm thick straight drywall partitions, 72mm GI tracks, 70mm GI studs covered with 12.5mm thick normal gypsum boards on both faces made to European standards with 50 mm mineral rockwool insulation inside, jointed taped with smooth leveling ready to receive final finish in the below mentioned areas including baffles. **Height up to 3170 / 770mm** **Brand - Knauf or Equivalent**	195	Sq.m	136.00	**26,520.00**
a	**Location : Throughout As Per Proposed Layout**	175			
b	**Location : Focus Rooms**	20			

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai.UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR ELECTROLUX OFFICE @ DUBAI-UAE					
Quote Ref No: VID/1104/24/CP/QTN_01/R2					20-Aug-25
SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
3.04	**CEMENT BOARD CLADDING** Supply and installation of **Cement board wall cladding** with GI channels, frames / studs and other necessary material for fixing, smoothened and made ready to receive final finishes. **Height up to 2400mm** **Location : Washroom Area Existing Wall**	25	Sq.m	143.00	**3,575.00**
3.05	**FR GYPSUM CLADDING** Supply and installation of FR 12.5 mm thick fire resistant Gypsum board wall cladding with necessary material for fixing, smoothened and made ready to receive final finishes. **Height up to 3170mm** **Brand - Knauf or Equivalent** **Location : Server Room Existing Wall**	17	Sq.m	126.00	**2,142.00**
3.06	**NORMAL GYPSUM CLADDING** Supply and installation of standard gypsum cladding to be made with 12.5 mm thick normal Gypsum board wall cladding with GR channels & frames and all necessary material for fixing, smoothened and made ready to receive final finishes. **Height up to 3170mm** **Brand - Knauf or Equivalent** **Location : Shaft Near Reception, Existing & Columns To Have TV Points & Proposed Walls For Provision For TV**	60	Sq.m	99.00	**5,940.00**
B	**ACOUSTIC GLASS PARTITIONS**				
3.07	**ACCOUSTIC GLASS PARTITION SYSTEM** Kaprel System: Alpha 23 Type of Glass: 12mm Head Channel Dimension: 26mm x 23mm Bottom Channel Dimension: 26mm x 23mm Clarity of Glass: Clear Glass (Regular) ALUMINIUM Profile Finish: RAL 9005 Comments: Including Abutments/Joints **Acoustic Rating: 33dB** **Height up to 2400mm** **Brand - Kaprel**	38	Sq.m	634.00	**24,092.00**
	Location : All Glass In Boardroom, Meeting Rooms & GM Office	32			
	Location : Focus Rooms	6			
3.08	**MOVABLE PARTITIONS - GIBCA SOLID PARTITION** Supply and fix of full height, Sliding foldable door (Manually operated) as per the below specifications. Brand - Hufcor, Series 632 Acoustic rating : 51 STC Panel frames: Lamb's Wool / Gray / Brown (TBC) Track : Hufcor type - 40 Partition size -4400mm (W) x 2400mm (H) **Brand - Gibca** **Location - Proposed Meeting / Board Room**	1	LS	31,724.00	**31,724.00**

T: +971 4 2408 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai.UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR ELECTROLUX OFFICE @ DUBAI-UAE

Quote Ref No: VID/1104/24/CP/QTN_01/R2 — **20-Aug-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
Option	**MOVABLE PARTITIONS - KAPREL GLASS PARTITION - OPTION 2** Supply and fix of Sliding foldable glass partition as per the below specifications. Composition: 8mm CF Glass + 8mm CF Glass ALUMINIUM Profile Finish: RAL 9005 Size - 4400mm (W) x 2400mm (H) **Brand - Kaprel** **Model - Aqua MW - 49dB** **Location - Proposed Meeting / Board Room**	1	LS	142,345.00	**RATE ONLY**
3.09	**TOILET CUBICLES** Supply and installation of 25mm the HPL toilet cubicle partition as per the below specifications & sizes **Male Washroom:** Overall Size - 3745mm X 2400mm H Door Size - 700mm x 2000mmH x 3Nos Divider Size : 1400mm X 2400Hx 2Nos **Female Washroom:** Overall Size - 2182mm X 2400mm H Door Size - 700mm x 2000mmH x 2Nos Divider Size : 1400mm X 2400Hx 1Nos **Location : Washrooms Internal Partition**	1	LS	28,580.00	**28,580.00**
D	**MISCELLANEOUS WORKS**				
3.10	Provision for MDF reinforcement for installation of TV screens and any wall mounted accessories / joinery items. ***Note : Supply of TV screens - By client***	15	Sq.m	485.00	**7,275.00**
3.11	Fabricate, supply and installation of MS support to receive the sliding foldable partition for smoother sliding of the panels and to avoid any sagging.	1	LS	5,160.00	**5,160.00**
3.12	**ACCOUSTIC SEALANT:** Supply and application of acoustic sealant and foam to close the gaps in the partitions, openings, penetrations etc. to enhance the sound proofing with-in the enclosed spaces.	1	LS	4,770.00	**4,770.00**
3.13	**FIRE SEALANT:** Supply and application of fire stopping sealant for the openings on the fire rated gypsum walls / MEP services as per the Dubai Civil Defense regulations	1	LS	2,760.00	**2,760.00**
3.14	**WC BOX TYPE WALL CLADDING** Supply and installation of box type wall cladding for WC flush tank, to be constructed with cement boards with required supports and hardwares up to 1500mm height.	1	LS	1,990.00	**1,990.00**
				SUB TOTAL PARTITION WORKS :	**167,324.00**
4.00	**FLOOR WORKS**				
A	**FLOORING BASE WORKS**				
4.01	**ANTI - STATIC RAISED FLOOR** Supply and installation of 1.2 HPL Antistatic Raised Access Flooring with cementitious in filled panels - 600 x 600 x 35m with cross & border pedestals. Pedestal Height 150-200mm - as per the manufactures specifications and recommendation **Location : Server Room**	11	Sq.m	486.00	**5,346.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai.UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR ELECTROLUX OFFICE @ DUBAI-UAE

Quote Ref No: VID/1104/24/CP/QTN_01/R2 — **20-Aug-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
4.02	**SCREED WORKS** Supply & application of new 100mm thk screed after removal of existing floor finishes to carry our the required new plumbing works and ready to receive new floor finish. All complete in accordance with the site requirement. **Location : Washrooms / Pantry Areas For Proposed Plumbing Works**	30	Sq.m	97.00	**2,910.00**
4.03	**SCREED LEVELLING** Leveling of existing screed (maximum up to 60mm) after removal of existing floor finishes and ready to receive new floor finish. All complete in accordance with the site requirement. **Location : After Removal Of Existing Flooring Near Entrances & Washrooms / Pantry Areas For Proposed New Flooring**	63	Sq.m	73.00	**4,599.00**
4.04	**SELF LEVELLING - 5-6mm** Supply and installation of **5 to 6 mm** self levelling compound to achieve same level as existing floor level of unit 2906 which is 3-4mm higher than office units 2904 & 2905, The same to be leveled for fixing new make the floor ready to receive the new flooring. **Location : To Match The Existing Floor Level Of Unit 2906**	230	Sq.m	67.00	**15,410.00**
4.05	**SELF LEVELLING** Supply and installation of **2 to 3** mm self levelling compound to make the floor ready to receive the new flooring. **Location : Remaining Area For Carpet & Vinyl Area Only**	190	Sq.m	46.00	**8,740.00**
4.06	**WATER PROOFING** Supply and installation of **Cementitious water proofing** 2 coats including protection screed. Area considered : Sqm **Location: Floor Area And Wall Upto 1200mm**	75	Sq.m	114.00	**8,550.00**
B	**FLOOR FINISHES**				
4.07	**CERAMIC TILE FLOORING** Supply and installation of **Ceramic Tile flooring to be fixed with required adhesive** with grouting including cutting and alignment. As per design and approved sample. Size : 60 x 60 cm **PC Rate : 60 AED per Sq.m** **Location : Washrooms Including Corridor In Washroom Area Only** ***Note : Subject to sample approval.***	46	Sq.m	166.00	**7,636.00**
4.08	**CARPET FLOORING** Supply and installation of proposed carpet flooring as per the design requirement with necessary material for installation as per manufacturer's recommendation. **Brand: Mohawk or equivalent** **Location : Closed Rooms, Workstation & Corridor Area**	415	Sq.m	140.00	**58,100.00**
4.09	**LVT FLOORING** Supply and installation of LVT flooring as per the design requirement with necessary material for installation as per manufacturer's recommendation. **Make : Amtico or equivalent** **Location : Pantry Only**	30	Sq.m	134.00	**4,020.00**
4.10	**WOODEN STEPS SEATING** Supply and installation of wooden steps seating **with some areas with storage below**. The same to be made with required framework to be finished in semisolid oak finish for thread and riser with 20mm thk nosing. Riser: Approx. H175 **Location - Pantry**	1	Item	43,550.00	**43,550.00**

T: +971 4 2408 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai.UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR ELECTROLUX OFFICE @ DUBAI-UAE

Quote Ref No: VID/1104/24/CP/QTN_01/R2 — **20-Aug-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
4.11	**TRANSITION STRIP** Supply and installation of Transition Strip in SS finish (ready available). **Location : Between different floor finishes, Door entrances.**	15	Lm	89.00	**1,335.00**
	Please Note: All finishes are subject to final sample approval.				
			SUB TOTAL FLOOR FINISH :		**160,196.00**
5.00	**WALL FINISH**				
5.01	**STRAIGHT WOODEN CLADDING - LAMINATE FINISH** Supply and installation of wooden wall cladding. Cladding to be made with MDF in laminate finish including necessary fittings and accessories for installation. All complete as per the design in the below mentioned areas. **Height -2400/ 1000mm** **Location : Reception Backwall, Meeting Room, GM Office & Pantry Step Seating Area & GM's Office Backwall**	45	Sq.m	761.00	**34,245.00**
5.02	**MICRO TOPPING FINISH WINDOW SILL** Supply and application of micro topping finish to the existing tiles finish on the window periphery area. The same to be applied after chipping of the existing tiles, filling / leveling it up with putti to receive the final micrtopping finish. All complete as per the design in the below mentioned area. **Location : Window Periphery**	47	Sq.m	565.00	**26,555.00**
5.03	**ACOUSTIC WALL PANEL WITH GROOVES** Supply & Installation Acoustic Grooved Wall Panels - Polyester Fiber Panel • Product: AcouMAX- Grooved • Composition: 100% PET- Felt (60% Recycled) • Standard panel Size: 2400 mm x 1200 mm • Thickness: 12 mm • Density: 2400 gm/sqm • Type of Groove: V-Groove **Acoustic performance: 0.60 to 0.90 NRC** **Brand - AcouMAX** **Location : Focus Pods & Small Meeting Room 1 Wall** ***Note: Subject to sample approval.***	42	Sq.m	388.00	**16,296.00**
5.04	**BACKSPLASH - BACKPAINTED GLASS** Supply & Installation 6mm thk back painted glass with MDF backing as per the design requirement. Glass to be fixed on the proposed wall with required hardwares & adhesive in the below mentioned area. **Height up to - 600mm** **Location : Pantry & Display Areas**	10	Sq.m	621.00	**6,210.00**
5.05	**CERAMIC WALL TILES** Supply and installation of ceramic wall tiles. The same to be fixed with grouting and required hardwares and adhesive. All complete as per the design requirement in the below mentioned areas. **Size : 60 x 60 cm** **Height up to - 2400mm** **Brand - RAK Ceramics or Equivalent** **PC Rate : 60 AED per Sq.m** **Location : Washrooms**	86	Sq.m	166.00	**14,276.00**

T: +971 4 2408 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai.UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR ELECTROLUX OFFICE @ DUBAI-UAE					
Quote Ref No: VID/1104/24/CP/QTN_01/R2					20-Aug-25
SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
5.06	**TEXTURED WALL PAINT** Supply and application of **Textured paint finish.** The paint to be applied with base preparation after cleaning, leveling, putti and primer base with 2 coats of final texture paint finish. All complete as per the site requirement in the below mentioned areas. **Height up to 3170mm** **Brand - Locally sourced** **Location : GM Office 1 Wall, Pantry Above Wooden Cladding On The Step Seating Area Wall & TV Wall**	40	Sq.m	135.00	**5,400.00**
5.07	**WALL PAINT** Supply and application of Fenomastic paint finish. The paint to be applied with base preparation after cleaning, leveling, putti and primer base with 2 coats of final Fenomastic paint finish. All complete as per the site requirement in the below mentioned areas. **Height up to 3170 / 2400mm** **Brand - JOTUN or equivalent** **Location : Remaining Area Excluding Above Mentioned Finishes**	525	Sq.m	33.00	**17,325.00**
5.08	**MIRROR** Supply and installation of 6mm thick plain silver mirror with straight polished non beveled edges including necessary MDF backing and materials for installation without any cut out, holes or illumination. **Height up to 1500mm** **Brand : Guardian** **Location : Above Vanity Counter In Washrooms**	7	Sq.m	481.00	**3,367.00**
5.09	**ROLLER BLINDS - MANUAL** Supply and installation of standard **sunscreen manual roller blinds with** complete tracks and channels on single sided guide rail. The same to be fixed from mullion to mullion as per the design requirement in the below mentioned areas. **Height up to 2200mm** **Brand - Locally Sourced** **Location : Entire Window Periphery Area**	117	Sq.m	99.00	**11,583.00**
	SKIRTING WORKS				
5.10	**STRAIGHT SKIRTING - VENEER / PU** Supply and installation of 50 mm high straight skirting to be made with **MDF skirting in veneer / PU paint finish** with necessary fittings and accessories. All complete as per the design requirement in the below mentioned areas. **Location - Throughout On Straight Walls**	145	Lm	55.00	**7,975.00**
5.11	**CIRCULAR SKIRTING - VENEER / PU** apply and installation of 50 mm high circular skirting to be made with **MDF skirting in veneer / PU paint finish** with necessary fittings and accessories. All complete as per the design requirement in the below mentioned areas. **Location - On Circular Columns**	3	Nos	552.00	**1,656.00**
	Please Note: ***1. All finishes are subject to final sample approval.*** ***2. All Artworks, decorative accessories and marketing works excluded.***				
			SUB TOTAL WALL FINISH :		**144,888.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai.UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR ELECTROLUX OFFICE @ DUBAI-UAE

Quote Ref No: VID/1104/24/CP/QTN_01/R2 — **20-Aug-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
6.00	**CEILING WORKS**				
	DECORATIVE CEILING				
6.01	**STRETCH CEILING** Supply and installation of Euroceil Premium Translucent PVC Membrane with Aluminium Channels and High Quality PVC Harpoon strengthening the periphery. PVC Membrane adhering to EN 14716 standards, Made in Germany customized at state of the art ISO 9001:2015 certified manufacturing facility in India, with following test certificates: * UL Classified * Fire: b-s1-d0 * No Heavy Metals * A+ Emission Code: EC2-TR-015 Nichia / Osram chip LED BAR/ module with wiring and looping. **Brand - Euroceil** **Location : Board / Meeting Rooms**	18	Sq.m	1,263.00	**22,734.00**
6.02	**SUSPENDED ACOUSTIC CEILING** Supply & Installation of Acoustic Cloud Ceiling-Polyester Fiber • Product: AcouMAX-Cloud • Composition: 100% PET- Felt (60% Recycled) • Cloud Thickness: 12 mm • Edge Thickness: 40 mm • Cloud Size: 650 mm x 2400 mm • Color: To be selected • Density: 2400gm/m² • Acoustic performance: 0.60 to 0.90 NRC • Installation: Using hanging wires and Clips. **Brand - AcouMAX** **Location : Corridor Area**	52	Sq.m	673.00	**34,996.00**
6.03	**SUSPENDED ACOUSTIC PANELS** Supply & Installation of Suspended Acoustic Panels Boards Acoustic Cloud Ceiling-Polyester Fiber • Product: AcouMAX-Cloud • Composition: 100% PET- Felt (60% Recycled) • Thickness: 20 mm • Color: To be selected • Density: 2400gm/m² • Acoustic performance: 0.60 to 0.90 NRC • Installation: Using hanging wires and Clips. Brand - AcouMAX Location : Pantry				
	Size : 800 x 800mm	2	Nos.	688.00	**1,376.00**
	Size : 500 x 500mm	2	Nos.	481.00	**962.00**
	GYPSUM CEILING				
6.04	**ALUMINUM GRID CEILING** Supply and installation of **600 x 600mm aluminum grid** ceiling tiles with complete suspension system. All complete as per the design requirement in the below mentioned areas. **Location : Washrooms & Storeroom**	38	Sq.m	135.00	**5,130.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai.UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR ELECTROLUX OFFICE @ DUBAI-UAE					
Quote Ref No: VID/1104/24/CP/QTN_01/R2					20-Aug-25
SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
6.05	**PLAIN NORMAL GYPSUM CEILING** Supply and installation of Normal gypsum ceiling to be made with 12.5mm thk Normal Gypsum Board Plain ceiling with GI "C "channel, furring channels, studs and all necessary accessories. All complete with joining and tapping ready to receive final paint finish in the below mentioned areas. **Brand - Knauf or equivalent**	86	Sq.m	114.00	**9,804.00**
	Location - Closed Offices	78			
	Location - Focus Pods	8			
6.06	**GYPSUM DECORATIVE COVE** Supply and installation of gypsum decorative cove to be made with 12.5 mm normal gypsum boards with required supports as per the design requirements ready to receive final finish in the below mentioned areas. **Brand - Knauf or equivalent** **Location : Reception, GM's Office & Boardroom On Wall**	30	Lm	94.00	**2,820.00**
6.07	**GYPSUM BULKHEAD** Supply and installation of 150/250mm high gypsum bulkhead to be made with 12.5 mm normal gypsum boards with required supports as per the design requirements ready to receive final finish in the below mentioned areas. **Brand - Knauf or equivalent** **Location : Above Joinery Areas & Ceiling Level Difference**	65	Lm	94.00	**6,110.00**
6.08	**GYPSUM PELMET / WINDOW BULKHEAD** Supply and installation of 300mm high gypsum bulkhead to be made with 12.5 mm normal gypsum boards with required supports as per the design requirements ready to receive final finish in the below mentioned areas. **Brand - Knauf or equivalent** **Location: Window Periphery For Blinds** ***Please Note : The above rate is provided as rate only as we propose to retain the existing bulkhead. However if during demolition it is damaged, it will be charged as per the rate provided.***		Lm	161.00	**RATE ONLY**
6.09	**SHADOW GROOVE** Supply and installation of shadow groove with required channels as per the design requirements ready to receive final finish in the below mentioned areas. **Location: Closed Rooms Between Wall & False Ceiling.**	90	Lm	48.00	**4,320.00**
6.10	**OPEN CEILING PAINT** Supply and application of stucco paint finish for the open ceiling area. The paint to be applied with base preparation after cleaning, leveling, putti and primer base with 2 coats of final stucco paint finish. All complete as per the site requirement in the below mentioned areas including MEP services. **Location : Entire Open Office Area Including Pantry**	350	Sq.m	62.00	**21,700.00**
6.11	**GYPSUM CEILING PAINT** Supply and application of Fenomastic paint finish. The paint to be applied with base preparation after cleaning, leveling, putti and primer base with 2 coats of final standard Fenomastic paint finish. All complete as per the site requirement in the below mentioned areas. **Location : Above Mentioned Gypsum, Ceiling, Bulkheads & Coves Including Existing Window Bulkhead**	180	Sq.m	33.00	**5,940.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai.UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR ELECTROLUX OFFICE @ DUBAI-UAE

Quote Ref No: VID/1104/24/CP/QTN_01/R2 — **20-Aug-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
	MISCELLANEOUS WORKS				
6.12	**GYPSUM ACCESS PANEL** Supply and installation of access panels fixed with hinges on the concealed frame for the future maintenance of MEP services above closed ceiling areas. Maximum size upto 600 x 600. **Location: Proposed Gypsum ceiling area** **Note : Subject to final MEP drawings**	12	Nos.	309.00	**3,708.00**
6.13	**FCU BOXING** Supply and installation of gypsum boxed cladding fixed with Rockwool insulations around the FCU units to absorb the sound as well as to reduce the noise of the unit. Necessary framing to be fixed around the unit with required access panels for easy operation and accessing of the units will be included. **Location: Proposed FCU's In Open Ceiling Area** ***Note : Subject to final HVAC design requirement***		Nos.	2,069.00	**RATE ONLY**
6.14	**SUPPORT FOR DECORATIVE LIGHTS** Supply and installation of additional soft wooden frame work built inside the gypsum ceiling to act as additional supports and to receive the light fittings.	1	Item	828.00	**828.00**
	Please Note : All finishes are subject to final sample approval.				
				SUB TOTAL CEILING FINISH :	**120,428.00**
7.00	**DOORS**				
	FR GLASS DOORS				
7.01	**SINGLE LEAF GLASS DOOR - FR 60 min** Supply and installation of **10 mm super-lite clear tempered fire rated (1 hour) single leaf glass door** with all around 40 x 60 mm MS frame along with powder coated aluminum cladding fixing by DORMA BTS 75 floor machine, accessories, bottom lock and 5 mm thick fire proof gasket. ***Note: All fittings are in powder coating or SS finish. Offset pivot excluded.*** Size: L 1000 mm X H 2800 mm **Location : Main Entrance** ***Please Noe : We have retained existing door as per building fit out guidelines. However have quoted RATE ONLY for the new door, incase building approves it being FR door.***		No	10,345.00	**RATE ONLY**
	ACOUSTIC GLASS DOORS				
7.02	**ACOUSTIC GLASS SWING DOOR - SINGLE LEAF** **Kaprel System: Ultra DC - 34dB** Type of Glass: 12mm Locks: Excluded Ironmongery: Door Handle: Kaprel 1200mm H Type - Round Accessories: Pivots + Kaprel Floor Spring Acoustic Rating: 34dB Clarity of Glass: Clear Glass (Regular) Aluminium Profile Finish: RAL 9005 Comments: Including Door Stop Single leaf Width : 1074mm Height of Door: 2400 **Location : All Meeting Rooms, Boardroom, Focus Pods & GM's Office**	8	No	6,773.00	**54,184.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai.UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR ELECTROLUX OFFICE @ DUBAI-UAE

Quote Ref No: VID/1104/24/CP/QTN_01/R2 — **20-Aug-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
	WOODEN DOORS				
7.03	**WOODEN SWING DOOR - FR 60 min** Supply and installation of single leaf 60 mins-fire rated MDF flush single swing door with solid Meranti or Beech wood frame and architraves in approved matte or semi-gloss PU paint finish including all necessary standard ironmongeries. **Size : 1000 mm x 2400 mm** **Location - Server Room**	1	No	5,517.00	**5,517.00**
7.04	**SINGLE LEAF WOODEN DOOR - NON FR** Supply and installation of Semi solid wooden swing door NON FR in PU paint finish, with Frame, architrave, in PU paint finish with all necessary ironmongery and material for fixing. **Size: 900 x 2400mm** **Location : Storeroom, Washrooms Main Doors & Door For Separating Washroom & Pantry**	3	Nos	3,933.00	**11,799.00**
7.05	**CONCEALED SINGLE LEAF WOODEN DOOR - NON FR** Supply and installation of concealed wooden swing door NON FR. Door to be made with ready made door core in texture paint finish to match the wall finish, with concealed frame, with all necessary ironmongery and material as per the design in the below mentioned areas **Size: 900 x 2400mm Ht** **Location : Store Room & Boardroom For Sliding Folding Partition**	2	Nos	3,586.00	**7,172.00**
7.06	**CONCEALED DB SHUTTERS - JN09** Fabrication, supply and installation of concealed shutters for DB section along the corridor, to be made of MDF in paint finish concealed shutters to be fixed on concealed frame. All complete as per the design with required adhesive and hardwares in the below mentioned area. **Size : 2500L x 400D x 2400H mm** **Location : Corridor Near Entrance**	1	Nos	8,276.00	**8,276.00**
				SUB TOTAL DOORS :	**86,948.00**
8.00	**SIGNAGE WORKS**				
8.01	Supply and installation of Signage with logo to be made with laser cut MDF in PU paint finish without illumination. All Complete as per the design in the below mentioned area. **Size: 1500 mm L x 600mm high** **Location : Reception & Waiting Area** ***Note : Subject to final design and sample approval.***	1	Nos	9,322.00	**9,322.00**
8.02	Supply and installation of illuminated text works fixed on wall. All Complete as per the design in the below mentioned area. **Size: 2500 mm x 150mm** **Location : Pantry** ***Note : Subject to final design and sample approval.***	1	Item	6,207.00	**6,207.00**
8.03	Supply and installation of backlit Signage with logo made with 6mm thk acrylic including Led light. All Complete as per the design in the be **Size: 1000 mm L x 400mm high** **Location : Display Area Near Reception** ***Note : Subject to final design and sample approval.***	1	Nos	6,450.00	**6,450.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai.UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR ELECTROLUX OFFICE @ DUBAI-UAE

Quote Ref No: VID/1104/24/CP/QTN_01/R2 — **20-Aug-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
8.04	**FROSTED / SANDBLASTING STICKER** Supply and installation of frosted / sandblasting sticker as per the design to be fixed above proposed glass partitions & doos. The same to be fixed with required adhesive in the below mentioned areas. **Height up to 1500mm** **Brand - Locally Sourced** **Location: All New Glass partition And Doors**	34	Sq.m	99.00	**3,366.00**
				SUB TOTAL SIGNAGE WORKS:	**25,345.00**
9.00	**JOINERY WORKS**				
9.01	**RECEPTION DESK - JN01** Fabrication, Supply and installation of **Reception Counter with curved edges. The counter** to be made of MDF in **combination of PU paint and laminate finish**. The sides and top in PU paint finish and front elevation to be cladded with straight elevation. All complete with required adhesive and hardwares. **Size:2220Lx700Dx1100Hmm** **Location : Reception**	1	Item	20,970.00	**20,970.00**
9.02	**WOODEN SLATS - JN02** Fabrication, supply and installation of wooden slats to be made of MDF in laminate finish. All complete as per the design with required adhesive and hardwares in the below mentioned area. **Size : 200L x 40D x 2400H mm** **Location : Near Entrance Display Area**	5	Nos	993.00	**4,965.00**
9.03	**RECEPTION SEATING - JN03** Fabrication, supply and installation of Lounge Seating, to be made of MDF in laminate finish. The front bottom to be finished with slatted panels including cushioned and upholstered seat abnd backrest covered in standard range of fabric. Item also includes planter box with GI sheet to accommodate Client supplied natural plants. All complete as per the design with required adhesive and hardwares in the below mentioned area. PC Rate of fabric considered as AED 150/- per Lm **Size seating : 2700L x 600D x 800H mm** **Size planter : 1575L x 300D x 400H mm** **Location : Reception**	1	Item	18,322.00	**18,322.00**
9.04	**DISPLAY UNIT - JN04** Fabrication, supply and installation of Display unit in lounge area. Unit to be made of MDF laminate finish shutters and OH unit with provision for client supplied electronics. Counter top to be in Corian finish and a top band for signage/logo in metallic laminate/Paint finish. Inner carcass in white melamine finish. All complete as per the design with required adhesive and hardwares in the below mentioned area. **Size base : 2650L x 600D x 900H mm** **Size OH : 2650L x 600D x 600H mm** **Location : Reception Lounge Area Next To Meeting Room**	1	Item	16,964.00	**16,964.00**
9.05	**WALL MOUNT LEDGE - JN05** Fabrication, supply and installation of Ledge to be made with MDF in laminate finish to be fixed with required concealed support. All complete as per the design with required adhesive and hardwares in the below mentioned area. **Size : 1600L x 800D x 30Thick mm** **Location : Focus Pods**	2	Nos	1,969.00	**3,938.00**

T: +971 4 2408 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai.UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR ELECTROLUX OFFICE @ DUBAI-UAE

Quote Ref No: VID/1104/24/CP/QTN_01/R2 — **20-Aug-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
9.06	**PRINTER CABINET- JN06** Fabrication, supply and installation of printer cabinet with bottom unit with Corian counter top and 2 no's of open shelves. Counter to be made of MDF in laminate finish for external surfaces & internal carcass to be made with white melamine. All complete as per the design with required adhesive and hardwares in the below mentioned area. **Size base : 2120L x 600D x 900H mm** **Size shelves : 2120L x 400D x 30Thick (2 nos)** **Location : Behind Reception**	1	Item	10,317.00	**10,317.00**
9.07	**NICHE SEATING - JN07** Fabrication, supply and installation of niche seating, to be made with MDF paint finish base, upholstered fabric seat & backrest. Including arch framing in laminate finish. All complete as per the design with required adhesive and hardwares in the below mentioned area. **Size seating : 3930L x 650D x 900H mm** **Size framing : 3930L x 650D x 2400H mm** ***PC Rate of fabric considered as AED 150/- Lm.*** **Location : Boardroom / Meeting Rooms**	2	Nos	27,034.00	**54,068.00**
9.08	**HOT BAR DESK - JN08** Fabrication, supply and installation of curved hot bar ledge, to be made of MDF laminate finish top and round hollow base. All complete as per the design with required adhesive and hardwares in the below mentioned area. **Location : Near Window**				
a	**Size : 5100L x 500D x 1100H mm.**	1	Nos	14,516.00	**14,516.00**
b	**Size : 3425 x 500D x 1100H mm.**	1	Nos	9,740.00	**9,740.00**
9.09	**FULL HEIGHT STORAGE UNIT - JN09** Fabrication, supply and installation of full height storage unit along the corridor. The unit to have storage unit with shutters and center portion with open display shelves. Unit to be of MDF in laminate finish shutters. Inner carcass in white melamine finish. All complete as per the design with required adhesive and hardwares in the below mentioned area. **Size : 6200L x 400D x 2400H mm** **Location : Corridor Next To DB**	1	Nos	29,936.00	**29,936.00**
9.10	**DISPLAY UNIT - JN10** Fabrication, supply and installation of Display unit near pantry. Unit to be made of MDF laminate finish shutters and OH unit with provision for client supplied electronics. Counter top to be in Corian finish. Inner carcass in white melamine finish. All complete as per the design with required adhesive and hardwares in the below mentioned area. **Size base : 1665L x 600D x 900H mm** **Size OH : 1665L x 600D x 600H mm** **Size Full height : 835L x 600D x 2400H mm** **Location : Corridor Near Pantry**	1	Nos	14,582.00	**14,582.00**
9.11	**BOOK SHELF- JN11** Fabrication, supply and installation of open book shelf. Unit to be made of MDF laminate finish. All complete as per the design with required adhesive and hardware's in the below mentioned area. **Size : 1200L x 450D x 2400Hmm** **Location : Pantry Next To Server Room**	1	Nos	6,323.00	**6,323.00**

T: +971 4 2408 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai.UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR ELECTROLUX OFFICE @ DUBAI-UAE					
Quote Ref No: VID/1104/24/CP/QTN_01/R2					20-Aug-25
SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
9.12	**WATER DISPENSER UNIT- JN12** Fabrication, supply and installation of open shelves unit with provision for water dispenser to be made with MDF in laminate finish. All complete as per the design with required adhesive and hardwares in the below mentioned area. **Size : 600L x 550D x 2400H mm** **Location : Pantry**	1	Nos	3,230.00	**3,230.00**
9.13	**BAR HEIGHT TABLE / LEDGE- JN13** Fabrication, supply and installation of bar height table / ledge. Same to be made of MDF laminate finish top and round hollow base. All complete as per the design with required adhesive and hardwares in the below mentioned area. **Size : 5700L x 500D x 1100H mm** **Location : Pantry Near Window**	1	Nos	14,840.00	**14,840.00**
9.14	**OPEN SHELVES - JN14** Fabrication, supply and installation of open shelves with L-angle metal supports at required distances. All complete as per the design with required adhesive and hardwares in the below mentioned area. **Size : 3170+1250L x 650D x 25mm thk x 4Nos** **Location : Store Room**	1	Nos	14,086.00	**14,086.00**
9.15	**PANTRY UNIT - JN15** Fabrication, supply and installation of pantry unit to be comprised of bottom and overhead units. The counter to be made with MDF in laminate finish for the external surface and inner carcass to be made with white melamine. Counter to be in Corian finish. All complete as per the design with required adhesive and hardwares in the below mentioned area. **Size base : 2745+1115L x 650D x 900H mm** **Size OH : 2745+1890L x 550D x 900H mm** **Location : Pantry**	1	Nos	23,998.00	**23,998.00**
9.16	**VANITY COUNTER - JN16** Fabrication, supply and installation of vanity counter to be made of MDF structure cladded with Corian. Including seating bench without backrest in upholstered fabric finish. All complete as per the design with required adhesive and hardwares in the below mentioned area. **PC Rate of fabric considered AED 100/- per Lm** **Size vanity : 2600L x 700D x 900H mm** **Size bench : 1600L x 700D x 450H mm.** **Location : Female Washroom**	1	Nos	16,303.00	**16,303.00**
9.17	**VANITY COUNTER - JN17** Fabrication, supply and installation of vanity counter to be made of MDF structure cladded with Corian. Including seating bench without backrest in upholstered fabric finish. All complete as per the design with required adhesive and hardwares in the below mentioned area. ***PC Rate of fabric considered AED 100/- per Lm*** **Size vanity : 1800L x 700D x 900H mm** **Size bench : 800L x 700D x 450H mm.** **Location : Male Washroom**	1	Nos	10,566.00	**10,566.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai.UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR ELECTROLUX OFFICE @ DUBAI-UAE

Quote Ref No: VID/1104/24/CP/QTN_01/R2 — **20-Aug-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
9.18	**JANITOR CABINET - JN18** Fabrication, supply and installation of janitor cabinet to be made of MDF in laminate finish for external surface and internal carcass to be made with melamine. All complete as per the design with required adhesive and hardwares in the below mentioned area. **Size : 1000L x 600D x 2400H mm** **Location : Near Washroom**	1	Nos	6,207.00	**6,207.00**
9.19	**LOW HEIGHT CABINET WITH PLANTER - JN19** Fabrication, supply and installation of low height cabinet with planter arrangement on the top portion. Cabinet to be made with MDF in laminate finish to match the desk. Planter box to have arrangement for live plants with waterproofing & GI sheet. All complete as per the design with required adhesive and hardwares in the below mentioned area. **Size : 750L x 400D x 900H mm** **Location : GM Cabin**	1	Nos	2,157.00	**2,157.00**
9.20	**LOW HEIGHT CLADDING WITH PLANTER PROVISION - JN20** Fabrication, supply and installation of low height planter box to have arrangement for live plants with waterproofing & GI sheet. All complete as per the design with required adhesive and hardwares in the below mentioned area. **Size : 1000L x 400D x 400H mm** **Location : Shaft At Reception**	1	Item	2,100.00	**2,100.00**
9.21	Supply of 50mm dense, 600mm dia of loose cushions for the step seating area to be made with fiber and covered with standard range of fabric to match the 3D's, to be placed randomly.	10	Nos	690.00	**6,900.00**
	Please Note: ***1. All carcass considered me*** ***inate if not indicated above*** ***2. Standard Ironmongeries c*** ***3. All drawers considered no inger groove finish only. Magnetic push to charge ad*** ***4. All solid surface quoted co e effect or with sparkles to charge additional if require. Propose Stark or similar*** ***5. DB wall cladding considered FR MDF*** ***6. All Wet areas considered MR MDF, rest of areas are considered standard MDF only*** ***7. All joinery with concealed lighting are considered with standard LED strip light quoted under light fittings*** ***8. All Plants & Electronics by Client***				
				SUB TOTAL JOINERY WORKS :	**305,028.00**

T: +971 4 2408 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai.UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR ELECTROLUX OFFICE @ DUBAI-UAE

Quote Ref No: VID/1104/24/CP/QTN_01/R2 — **20-Aug-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
10.00	**SANITARY FITTINGS**				
10.01	**WC - WALL MOUNTED** Supply of Rimless wall hung water closet in glossy finish (Alpine white) and oval shape with complete kit including flush tank, flush plate and seat cover. Dimensions: 520 X 430 mm Color: Alpine White **Make : RAK ceramics** **Model Venice**	5	Nos	1,612.00	**8,060.00**
10.02	**BIDET SPARY KIT** Supply of bidet spray kit chrome finish. **Make : RAK Ceramics**	5	Nos	143.00	**715.00**
10.03	**URINALS** Supply of wall hung waterless urinals in glossy finish (Alpine white)with c and urinal partitions Color: Alpine White **Make : RAK ceramics** **Model : Jazira**	3	Nos	873.00	**2,619.00**
10.04	**WASH BASIN - COUNTER TOP** Supply of countertop wash basin including fixing kit and bottle trap. Dimensions: 420 X 430 mm Color: Alpine White Shape : Round **Make : RAK ceramics** **Model - Feeling**	5	Nos	647.00	**3,235.00**
10.05	**BASIN MIXER** Supply of single lever deck high rise basin mixer in chrome finish Make : RAK ceramics Model - Prime	5	Nos	520.00	**2,600.00**
10.06	**TOILET ROLL HOLDER** Supply of wall mounted Toilet roll holder with single fixing point in chrome finish with screws and dowels including fixed guide plate. **Make : RAK Ceramics**	5	Nos	110.00	**550.00**
10.07	**PEDAL BIN** Supply of Pedal bin with 5 Liter capacity. Size : 200x 235 x 280 mm	8	Nos	197.00	**1,576.00**
10.08	**PAPER TOWEL DISPENSER** Supply of chrome finish wall mounted manual paper tower dispenser Make : Sanipex	2	Nos	1,744.00	**3,488.00**
10.09	**FLOOR DRAIN** Supply of 150 x 150 mm floor drain in chrome finish.	9	Nos	181.00	**1,629.00**
10.10	**SINK SET** Supply of Inset stainless steel sink with drainboard Color : Stainless steel **Make : RAK Ceramics**	1	No	619.00	**619.00**

T: +971 4 2408 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai.UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR ELECTROLUX OFFICE @ DUBAI-UAE

Quote Ref No: VID/1104/24/CP/QTN_01/R2 — **20-Aug-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
10.11	**SINK MIXER** Supply of deck mounted Single lever mixer tap in chrome finish with swivel spout. **Make - RAK Ceramics** **Model - Peak**	1	No	713.00	**713.00**
	Please Note : Above rates are subject to Client's final selection & app				
				SUB TOTAL SANITARY FITTINGS :	**25,804.00**
11.00	**LIGHTING WORKS - NON DIMMABLE**				
11.01	**SUSPENDED LED LINEAR LIGHTS - 6.5** Supply of Suspended LED Linear Light Power: 114Watts Output Lumen: 9120Lm/Mtr. Size: L6500XW40XH70mm Control Gear: Non-Dimmable Protection: IP20 4000K & White Finish	3	Nos	2,197.00	**6,591.00**
11.02	**SUSPENDED LED LINEAR LIGHTS - 5.0** Supply of Suspended LED Linear Light Power: 114Watts Output Lumen: 9120Lm/Mtr. Size: L5000XW40XH70mm Control Gear: Non-Dimmable Protection: IP20 4000K & White Finish	1	Nos	2,018.00	**2,018.00**
11.03	**SUSPENDED LED LINEAR LIGHTS - 3.8** Supply of Suspended LED Linear Light Power: 114Watts Output Lumen: 9120Lm/Mtr. Size: L3800XW40XH70mm Control Gear: Non-Dimmable Protection: IP20 4000K & White Finish	3	Nos	1,284.00	**3,852.00**
11.04	**SUSPENDED LED LINEAR LIGHTS - 2.0 - GM Office** Supply of Suspended LED Linear Light Power: 114Watts Output Lumen: 9120Lm/Mtr. Size: L2000XW40XH70mm Control Gear: Non-Dimmable Protection: IP20 4000K & White Finish	1	Nos	1,050.00	**1,050.00**

T: +971 4 2408 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai.UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR ELECTROLUX OFFICE @ DUBAI-UAE

Quote Ref No: VID/1104/24/CP/QTN_01/R2 — **20-Aug-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
11.05	**RECESSED LED LINEAR LIGHTS BETWEEN ACOUSTIC CEILING PANELS** Supply of Surface LED Linear Light Power: 30Watts/Mtr. Output Lumen: 2400Lm Size: W50XH75mm Control Gear: Non-Dimmable Protection: IP20 4000K & White Finish	35	Lm	342.00	**11,970.00**
11.06	**TRACKS LIGHTS** Supply of LED Track Spot Light with 4line 3phase power connector, end caps, internal caps and suspension kits Power: 20Watts Output Lumen: 1800Lm Size: D58XH155mm Control Gear: Non-Dimmable Protection: IP20 4000K & White Finish	45	Nos	401.00	**18,045.00**
11.07	**RECESSED DOWNLIGHT** Recessed LED Trimless Spot Light Power: 20Watts Output Lumen: 1800Lm Size: 145*87mm Control Gear: Non-Dimmable Protection: IP20 **4000K & White Finish** 	65	Nos	184.00	**11,960.00**
11.08	**RECESSED DOWNLIGHT** Recessed LED Down Light Power: 20Watts Output Lumen: 1800Lm Size: φ103*H70mm Control Gear: Non-Dimmable Protection: IP65 **4000K & White Finish** 	25	Nos	110.00	**2,750.00**
11.09	**LED COVE LIGHT** LED Flexible Strip Light LUMILEDS Power: 9.6Watts/Mtr Output Lumen: 1203Lm/Mtr Protection: IP20 Aluminum Profile With Diffuser Size:17x15mm Constant Voltage Driver Control Type: Non Dimmable Output Voltage:24VDC Protection: IP20 **Location : Ceiling, Walls & Joinery** 	85	Lm	55.00	**4,675.00**
	Note : **1. Quantity subject to final RCP design** **2. Non - dimmable lights considered.**				
				SUB TOTAL LIGHTS :	**62,911.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai.UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR ELECTROLUX OFFICE @ DUBAI-UAE

Quote Ref No: VID/1104/24/CP/QTN_01/R2 — **20-Aug-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
	MEP WORKS (PROVISIONAL SUM SUBJECT TO FINAL MEP DESIGN)				
12.00	**HVAC WORKS**				
12.01	Supply and installation of CHW FCUs (' Daikin / Mekar/ Trosten' Make) 3.2 TR ,1200 cfm,	2	Nos.	4,222.00	**8,444.00**
12.02	Relocation of existing FCU units from existing location to the proposed as per the new ceiling location. ***Please Note : We assume that the existing AC machines are in good working condition.***	6	Nos.	2,529.00	**15,174.00**
12.03	Performance test of existing FCU's - 6No's ***Please Note : Any modifications based on performance test to charged additional.***	1	Item	4,552.00	**4,552.00**
12.04	Supply and installation of PICV valves for the new FCU	2	Nos	2,483.00	**4,966.00**
12.05	Supply and installation on new VAV	3	Nos	3,448.00	**10,344.00**
12.06	Supply and installation of thermostat including wiring	2	Nos	623.00	**1,246.00**
12.07	Relocation of existing thermostat including wiring as per new proposed layout	6	Nos	414.00	**2,484.00**
	DUCTING AND ACCESSORIES				
12.08	Supply and Installation of **PI Duct** with necessary support	1	LS	33,966.00	**33,966.00**
12.09	Supply and installation of **12 mm rubber type Acoustic liner**				
12.10	Supply and installation of **Volume Control Damper.**				
12.11	Supply and Installation of flexible duct, plenum box and ring.				
12.12	Supply and installation of cross talk attenuator ,	7	Nos.	1,241.00	**8,687.00**
12.13	Extension of existing supply air duct.	1	LS	9,931.00	**9,931.00**
12.14	Extension of existing supply extract ducting	1	LS	9,931.00	**9,931.00**
	GRILLS AND DIFFUSER				
12.15	Supply and Installation of **slot (2 Slot) grill** with necessary accessories and supports.	1	Item	38,621.00	**38,621.00**
12.16	Supply and Installation of **diffusers** with necessary accessories and supports.				
	DRAIN PIPE				
12.17	Supply and installation of condensate drain pipe for new FCU. ***Please Note : To be connected to the existing drain pipe.***	1	LS	1,379.00	**1,379.00**
12.18	Supply and installation of Chilled Water Pipe Line (ERW CH40) and fittings with thermal insulation, canvas cloth with foster, support and hangers for newly installed pipes for FCU's	1	LS	6,897.00	**6,897.00**
12.19	Supply and installation of fusable link FD	2	Nos	1,276.00	**2,552.00**
12.20	Chemical Flushing - Make : Culligan	1	Item	13,241.00	**13,241.00**
12.21	Air & CWH balancing by the 3rd Party	1	Item	6,897.00	**6,897.00**
12.22	Testing commissioning	1	Item	6,207.00	**6,207.00**
	Exclusions: ***1. BTU Meter, BMS Connection.*** ***2. Maintenance platform*** ***3. We have considered reusing of existing FCU's with performing a test on it. If it is noticed that any of the existing FCU's are not in usable condition, we will have to propose for new FCU's and related works accordingly.***				
				SUB TOTAL HVAC WORKS :	**185,519.00**

T: +971 4 2408 119 F: +971 4 2408 403 E info@vervedesign.ae PO Box: 128279, Dubai.UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR ELECTROLUX OFFICE @ DUBAI-UAE

Quote Ref No: VID/1104/24/CP/QTN_01/R2 **20-Aug-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
13.00	**ELECTRICAL WORKS**				
13.01	PVC conduiting and wiring for the proposed light points ***Please Note: Light points are subject to revise upon final RCP Layout.***	167	Nos	161.00	**26,887.00**
13.02	Installation of above mentioned light fittings	1	Item	4,828.00	**4,828.00**
13.03	Supply & installation of dimmer controller with required wiring for the proposed stretch ceiling **Location : Meeting / Board Room**	2	No	830.00	**1,660.00**
13.04	Supply and installation of **Grid switch for lighting.** Including **PVC conduiting**. (Matt PVC finish Legrand / schneider) for Open workstation & corridor.	2	Nos	690.00	**1,380.00**
13.05	Supply and installation of **Single switch for lighting.** Including **PVC conduiting**. (Matt PVC finish Legrand / schneider) for closed offices	10	Nos	276.00	**2,760.00**
13.06	Supply and installation of **13A Single wall Power Socket,** in PVC finish including conduiting and wiring. (Schneider / Legrand)	16	Nos	310.00	**4,960.00**
13.07	Supply and installation of **13A Twin wall Power Socket,** in black PVC finish including conduiting and wiring. (Schneider / Legrand)	15	Nos	341.00	**5,115.00**
13.08	Supply and installation of **15A Single wall Power Socket,** in Black PVC finish including conduiting and wiring. (Schneider / Legrand)	2	Nos	621.00	**1,242.00**
13.09	Supply and installation of **16A industrial socket** including pvc conduiting and wiring. (Schneider / Legrand) for server racks	3	Nos	807.00	**2,421.00**
13.10	Supply and installation of **20A DP switch** and flex outlet for water heater including pvc conduiting and wiring.	3	Nos	683.00	**2,049.00**
13.11	Supply and installation of **Shared Floor Box -** 2 x Twin 13A with cabling and conduiting + provision for 2 x Twin Data with conduiting and faceplates provision only. Make : Obo or equivalent	30	Nos	759.00	**22,770.00**
13.12	Supply and installation of **Single Floor Box -**1 x Twin 13A with cabling and conduiting + provision for 1 x twin data with conduiting and faceplates provision only. Make : Obo or equivalent	7	Nos	621.00	**4,347.00**
13.13	Supply and installation of **13Amps fles outlet** with **PVC conduiting** and wiring (Considered for new FCU)	2	Nos	528.00	**1,056.00**
13.14	**50mm conduit** and cabling provision for **HDMI/VGI.**	8	Nos.	262.00	**2,096.00**
13.15	Supply and installation of **PVC** containment for **WI-FI Points**. (Provisional qty, considered for entrances & server room)	6	Nos.	124.00	**744.00**
13.16	Supply and installation of PVC containment for **Access control** (Provisional qty)	3	Nos	124.00	**372.00**
13.17	Supply and installation of **PVC** containment for **CCTV Points**. (Provisional qty, considered only near entrances & server room)	3	Nos.	124.00	**372.00**
13.18	Supply and installation of **PVC** containment for **AV Rack**	1	Nos.	124.00	**124.00**
13.19	Supply and installation of **13A flex outlet** for VAV including pvc conduiting and wiring.	3	Nos.	517.00	**1,551.00**
13.20	Modification of existing **SMDB** with necessary ELCB, MCB , and all other accessories as per DEWA ***Please Note : Subject to load availability***	1	Item	4,966.00	**4,966.00**
13.21	Supply and installation of new DB ***Please Note : Subject to building management approval***	1	No	8,069.00	**8,069.00**
13.22	Supply and installation of 4C 35 sqmm xlpe/swa/pvc + 1C 16 sqmm Ecc cable from existing SMDB to DB.	1	Lot	6,741.00	**6,741.00**
13.23	Supply and installation of GI Trunking at high level for lighting circuits.	1	Lot	6,952.00	**6,952.00**
13.24	Supply and installation of GI Trunking at high level for power	1	Lot	7,386.00	**7,386.00**
13.25	Supply and installation of GI Trunking at high level for network	1	Lot	7,821.00	**7,821.00**
13.26	DEWA submission, inspection and approval.	1	No	4,828.00	**4,828.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai.UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR ELECTROLUX OFFICE @ DUBAI-UAE

Quote Ref No: VID/1104/24/CP/QTN_01/R2 — **20-Aug-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
13.27	Testing commissioning.	1	Item	2,759.00	**2,759.00**
13.28	Providing PVC conduit for Data/Voice	85	Nos	124.00	**10,540.00**
	Please Note: ***1. We have assumed that the existing infrastructure's power has sufficient capacity to cater to the requirement of the project.*** ***2. We have not allowed for upgrade of the capacity of any base building system.*** ***3. All electrical conduits considered are of PVC type.*** ***4. We have not allowed for any specific lighting control system in this offer.*** ***5. Subject to final MEP drawings*** ***Exclusions:*** ***1. Any BMS integration or related works.*** ***2. DEWA Consultancy for power upgrade.*** ***3. Metering Works Not considered***				
				SUB TOTAL ELECTRICAL WORKS :	**146,796.00**
14.00	**CIVIL DEFENCE WORKS (PROVISIONAL SUM INCLUDING FM200)**				
A	**FIRE ALARM WORKS**				
14.01	Supply and installation of Smoke detector with base	4	Nos	LS	**42,581.00**
14.02	Relocation of existing smoke detector	21	Nos		
14.03	Relocation of existing heat detector	1	Nos		
14.04	Supply and installation of break glass	2	Nos		
14.05	Supply and installation of sounder	2	Nos		
14.06	Interfacing modules (FACP + Access control - 3 nos)	4	Nos.		
14.07	Isolation/ De-Isolation of fire alarm devices.	1	Lot		
14.08	Programming, Testing and commissioning charges for the fire alarm system.	1	Item		
14.09	Certification charges for the fire alarm devices.	1	Lot		
14.10	Supply and installation of Fire alarm control panel ***(If Required)***	1	Item	14,840.00	**RATE ONLY**
B	**FIRE FIGHTING WORKS**				
14.11	Supply and installation of pendent sprinkler	4	Nos	LS	**49,871.00**
14.12	Relocation of existing pendant sprinkler	13	Nos		
14.13	Relocation of existing pendent sprinkler with upright sprinkler.	25	Nos		
14.14	Supply and installation of CO2 and Dry Powder fire extinguishers set.	3	Sets		
14.15	Supply and installation fire blanket	1	No		
14.16	Shutdown and draining charges for the fire fighting system.	1	Item		
14.17	Pressure test and commissioning,	1	Item		
14.18	Certification charges	1	Item		
14.19	Supply & Installation of FM200 system for the server room ***Please Note : This amount has been added as per Electrolux standard requirement for the Server room. However the quoted amount is Provisional Sum & can be reworked / removed if the existing FM 200 is in usable condition and can be relocated. These charges will be revised for updation & relocation works***	1	PS	51,615.00	**51,615.00**
C	**EMERGENCY WORKS**				
14.20	Supply and installation of emergency light.	2	Nos.	LS	**13,097.00**
14.21	Relocation of Emergency Light	16	Nos.		
14.22	Supply and installation of exit light.	5	Nos.		
14.23	Testing & commissioning charges	1	Item		

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai.UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR ELECTROLUX OFFICE @ DUBAI-UAE					
Quote Ref No: VID/1104/24/CP/QTN_01/R2					20-Aug-25
SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
	Notes / Exclusions: ***1. Any additional charges/ fees for any third party shall be paid by the client.*** ***2. FM 200 works is quoted as provisional sum as rate only, will be charged if required by DCD during approvals*** ***3.We have considered our standard DCD approved supplier to carry out the above FLS works with 15% co-ordination charges. If there is any building approved Base build contractor for the same and the rates vary, Verve will charge on actuals to client with 15% co-ordination charges.***				
				SUB TOTAL CIVIL DEFENCE WORKS :	**157,164.00**
15.00	**PLUMBING WORKS**				
15.01	Supply and installation of **Water Supply PPR pipe** for Hot and Cold with socket, Elbow ,Threaded Road and other accessories as per standard	1	LS	28,966.00	**28,966.00**
15.02	Supply and installation of **UPVC drainage Pipe** for waste and Soil Pipe and connecting to existing line with ,fittings ,socket ,and other accessories as per Standard	1	LS		
15.03	Supply and Installation of **angle valve and gate valve.**	29	Nos.		
15.04	Pressure Test and Gravity Test	1	Item		
15.05	Installation of sanitary wares	1	LS		
15.06	Supply and installation of water heater - 80 litres	3	Nos.		
15.07	Coring and scanning works	15	Nos.	966.00	**RATE ONLY**
	Please Note : ***1. All terminations considered to the stub out present at site , connected to building system .*** ***2. Sani pump works excluded***				
				SUB TOTAL PLUMBING WORKS :	**28,966.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai.UAE www.vervedesign.ae

verve
space + design

FURNITURE WORKS FOR ELECTROLUX OFFICE @ DUBAI-UAE

Quote Ref No: VID/1104/24/CP/QTN_01/R2 — **August 20, 2025**

SR.NO	SAMPLE IMAGE	CODE	DESCRIPTION	QTY	UNIT	RATE	TOTAL (AED)
17.00	**LOOSE FURNITURE**						
	PLEASE NOTE : ***LEAD TIME / DELIVERY - 10-12weeks** ***CHAIRS - We have not considered any new task (user) / meeting chairs, existing Herman Miller chairs to be reused for all Meeting Rooms & Users as confirmed by Client.** ***CABINETS - We have reused 15 Nos of existing low height cabinets in the New Office**						
	GM OFFICE						
17.01			**O Leg: Executive Table** Dimension: 1600W/750D x 1800L/500D x 750H a) MFC Rectangular TopLeg/Base b)O Leg c/w 1 Bracket c) Stack-on Metal Leg c/w 1_Bracket (75H) ~ L/R d) Support Beam (E-E) e) MFC Rectangular Modesty Panel c/w 2 Brackets (1450W)Storage f) MFC Stack on Cabinet c/w 1x Sliding Door, 1x Open Shelf & Pedestal 2D1F (1800W x 500D x 650H) ~Right / Left *1x Power Management Box (in Sliding Door Compartment) *1x Sliding Door (492W), 1x Open Shelf (900W), 1x 2D1F (408W) *Sliding Door c/w Aluminium Sliding Rail c/w Keylock w/ Handle *Pedestal Door c/w Handle & Keylock, Full Extension Slide for Drawer Boxes *Open Shelf c/w 1-Adjustable Shelf (25T)*18mmT Back Panel *c/w Aluminium flip-up w/ soft-closing (400W x 130D) ~ PC White	1	No.	2,996.00	**2,996.00**
17.02			**MOV- Meeting Table** Dimension: D90 x H72 Cm a) Mov Round Meeting Table, 4 Pax *MFC Top c/w Straight Edging Upholstered Base in fabric Finish:Top: MFC 25mm Thickness Top, Straight Edging Base: Tranquil Fabric	1	No.	1,914.00	**1,914.00**
17.03			**Tino (4-Star Base) - Visitor / Meeting Chairs** Swivel chair w/ 4-prong base; w/ Castor or Fixed Glide Fixed Armrest & Armrest Cover. Dimension: (630W x 630D x 820~880H; SH:450~510 (±10mm)) Upholstery: Fabric - TOMO Fabric - Harmony /Vinyl - Mori /Vinyl - Roma	4	No.	1,266.00	**5,064.00**
OPTION			**Grace lowback visitor chair** With armrest in White frame, Sled Base Finish & Upholstery: Frame: Grey PP Cushion: Berry Vinyl/ Tomo Fabric	1	No.	992.00	**RATE ONLY**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

FURNITURE WORKS FOR ELECTROLUX OFFICE @ DUBAI-UAE

Quote Ref No: VID/1104/24/CP/QTN_01/R2 — **August 20, 2025**

SR.NO	SAMPLE IMAGE	CODE	DESCRIPTION	QTY	UNIT	RATE	TOTAL (AED)
	MEETING ROOMS						
17.04			**Foldable Meeting Table - Board Room** Forward foldable table with modesty panel **Dimension - 1400 x 700 x 750** MFC table top & modesty panel with forward folding table frame **Without cable management**	10	Nos.	1,675.00	**16,750.00**
17.05	**Image for illustration purpose only** 		**Meeting Room 12 Pax** Waltz: Meeting Table Dimension: 3200W x 1200D x 750H a) MFC Square Worktop c/w 1-Through hole for flip up.Cable Management b) Aluminium Flipper Cover c/w Soft-closing (400W x 130D) c) Metal Wire Tray c/w 4 Brackets (800W x 150D x 120H)Leg/Base d) Waltz Leg c/w 2 Brackets (1150W x 725H) e) Intermediate Leg c/w Wire Riser Box (1050/450W x 725H) f) Support Beam (E-1) g) Levelling Plate	1	No.	3,263.00	**RATE ONLY**
17.06	**Image for illustration purpose only** 		**Meeting Room 8 Pax** Waltz: Meeting Table Dimension: 2800W x 1200D x 750H a) MFC Square Worktop c/w 1-Through hole for flip up.Cable Management b) Aluminium Flipper Cover c/w Soft-closing (400W x 130D) c) Metal Wire Tray c/w 4 Brackets (800W x 150D x 120H)Leg/Base d) Waltz Leg c/w 2 Brackets (1150W x 725H) e) Intermediate Leg c/w Wire Riser Box (1050/450W x 725H) f) Support Beam (E-1) g) Levelling Plate	1	No.	3,098.00	**RATE ONLY**
17.07	**Image for illustration purpose only** 		**Meeting Room 6 Pax** Waltz: Meeting Table Dimension: 2400W x 1200D x 750H a) MFC Square Worktop c/w 1-Through hole for flip up.Cable Management b) Aluminium Flipper Cover c/w Soft-closing (400W x 130D) c) Metal Wire Tray c/w 4 Brackets (800W x 150D x 120H)Leg/Base d) Waltz Leg c/w 2 Brackets (1150W x 725H) e) Intermediate Leg c/w Wire Riser Box (1050/450W x 725H) f) Support Beam (E-1) g) Levelling Plate	1	No.	2,911.00	**RATE ONLY**
17.08			**Meeting Chairs** Posh - Meeting Chair Posh Midback Chair with upholstered Armrest Synchro Mechanism Aluminium Polish Base on Castors. Finish: Fabric - Viktor	26	Nos.	1,579.00	**RATE ONLY**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

FURNITURE WORKS FOR ELECTROLUX OFFICE @ DUBAI-UAE

Quote Ref No: VID/1104/24/CP/QTN_01/R2 — **August 20, 2025**

SR.NO	SAMPLE IMAGE	CODE	DESCRIPTION	QTY	UNIT	RATE	TOTAL (AED)
17.09			**Meetin Room 5 Pax** Grandeur: MFC Rectangular Freestanding Table Dimension: 1800W x 800D x 1070Ha) Grandeur MFC Rectangular Freestanding Table c/w 1-Grommet Cover *MFC Top (25mm Thk) *MFC Panel Leg (25mm Thk) *MFC Modesty Panel (450mm H)	1	Nos.	1,689.00	**1,689.00**
17.10			**SUNON DUCK High Chairs** High back chairs, Back in Fabric Finish with Metal Leg [white, black, pale pinkish grey, pea green, coral]. Dim: 520*560*1080*770 Ht mm. Finish: Fabric.	5	Nos.	1,212.00	**6,060.00**
	WORKSTATION AREA						
17.11			**DESKTOP MODIFICATION** Supply & installation of new worktops to be fixed on existing workstation frames as per the new sizes Finish : Laminate. Dimension : 1400 x 700 x 18mm thk	60	Nos.	690.00	**41,400.00**
Option			**HARD BOARD PRIVACY PANELS** 18 mm thick fabric screen with holding brackets (Brackets in anodised finish only). DIM :- 1400mm(W) x 350mm (H) FINISH : Fabric: Colour From the chart catalogue		Nos.	515.00	**RATE ONLY**
Option			**HARD BOARD PRIVACY PANELS (For Height adjustable desks)** 18 mm thick fabric screen with holding brackets (Brackets in anodised finish only). DIM :- 1400mm(W) x 650mm (H) FINISH : Fabric: Colour From the chart catalogue		Nos.	773.00	**RATE ONLY**
Option			**CABLE MANAGEMENT** Snake Tube. Finish : White		Nos.	136.00	**RATE ONLY**
Option			**Cluster of 2 - Linear Workstation** Waltz: Double Desk - inline Dimension: (1400W x 700D x 750H) a) MFC Rectangular Worktop c/w 1-Grommet CoverCable Management b) Aluminium Flipper Cover c/w Soft-closing (400W x 130D) c) Metal Wire Tray c/w 3 Brackets (500W x 150D x 120H) d) Round Wire SnakeLeg/Base e) Waltz Leg c/w 1 Bracket (650W x 725H) f) Support Beam (E-E) g) MFC Rectangular Modesty Panel c/w 2 Brackets(1200W x 450H x 18T)Storage h) MFC Mobile Pedestal w/ 3 Drawers c/w Handle & Keylock(408W x 475D x 515H)	2	Nos.	3,674.00	**RATE ONLY**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@verveDesign.ae PO Box: 128279, Dubai,UAE www.verveDesign.ae

verve
space + design

FURNITURE WORKS FOR ELECTROLUX OFFICE @ DUBAI-UAE

Quote Ref No: VID/1104/24/CP/QTN_01/R2 — **August 20, 2025**

SR.NO	SAMPLE IMAGE	CODE	DESCRIPTION	QTY	UNIT	RATE	TOTAL (AED)
Option			**Cluster of 4** Waltz: Double Desk - inline Dimension: (2800W x 1400D x 750H) a) MFC Rectangular Worktop c/w 1-Grommet CoverCable Management b) Aluminium Flipper Cover c/w Soft-closing (400W x 130D) c) Metal Wire Tray c/w 3 Brackets (500W x 150D x 120H) d) Round Wire SnakeLeg/Base e) Waltz Leg c/w 1 Bracket (650W x 725H) f) Support Beam (E-E) g) MFC Rectangular Modesty Panel c/w 2 Brackets(1200W x 450H x 18T)Storage h) MFC Mobile Pedestal w/ 3 Drawers c/w Handle & Keylock(408W x 475D x 515H)	5	Nos.	6,054.00	**RATE ONLY**
Option			**Cluster of 6** Waltz: Double Desk - inline Dimension: (4200W x 700D x 750H) a) MFC Rectangular Worktop c/w 1-Grommet CoverCable Management b) Aluminium Flipper Cover c/w Soft-closing (400W x 130D) c) Metal Wire Tray c/w 3 Brackets (500W x 150D x 120H) d) Round Wire SnakeLeg/Base e) Waltz Leg c/w 1 Bracket (650W x 725H) f) Support Beam (E-E) g) MFC Rectangular Modesty Panel c/w 2 Brackets(1200W x 450H x 18T)Storage h) MFC Mobile Pedestal w/ 3 Drawers c/w Handle & Keylock(408W x 475D x 515H)	6	Nos.	9,284.00	**RATE ONLY**
17.12		**Hot Desk**	**SUNON DUCK High Chairs - For Hot Desks / High Bar** High back chairs, Back in Fabric Finish with Metal Leg [white, black, pale pinkish grey, pea green, coral]. Dim: 520*560*1080*770 Ht mm. Finish: Fabric.	9	Nos.	1,212.00	**10,908.00**
17.13			**PANTRY HIGH BAR CHAIRS** Chat - Fixed Stool Polyurethane foam padding Shell in woodWhite Frame (BC) Upholstery:Cat F (fabric/PU Leather)	6	Nos.	669.00	**4,014.00**
17.14			**PANTRY TABLES** MFC Square Table w/ Round Base Dimension: 800W x 800D x 745H a) MFC Square Top(800W x 800D x 25T) b) Round Base (500Dia x 720H)	2	Nos.	2,183.00	**4,366.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vorvodesign.ae PO Box: 128279, Dubai,UAE www.vorvodesign.ae

verve
space + design

FURNITURE WORKS FOR ELECTROLUX OFFICE @ DUBAI-UAE

Quote Ref No: VID/1104/24/CP/QTN_01/R2 — **August 20, 2025**

SR.NO	SAMPLE IMAGE	CODE	DESCRIPTION	QTY	UNIT	RATE	TOTAL (AED)
17.15			**PANTRY CHAIRS** Keira - Dining Chair Armchair with metal painted frame,seat and backrest completely upholstered Upholstery: Group 2 (Fabric/ PU Leather)	4	Nos.	1,716.00	**6,864.00**
17.16			**POUF** SUNON D SERIES D2 Pouf Finish: High elastic Leather with a waterproof coating Structure: The aerospace steel frame inside backseat and solid wood frame shaping the sea tBase: The loop-shaped black wood leg. Dim: 650*550*430 Ht mm. Finish :EPU 81	3	Nos.	1,277.00	**3,831.00**
17.17			**SUNON MOGEE Coffee Table** Veneer Table top With Steel Base & Leg. Dim : 600 Dia *420 Ht mm. Finish : Veneer	1	Nos.	1,673.00	**1,673.00**
17.18			**S POD 3.0 Plus** • Laminated Desktop with Chamfered Edge(820W x 320D x 1020H) • Power Consumption: 0.18A • POD Weight: 266Kg • Heavy Castors for The Ease of Mobility • Motion Sensor For Energy Saving • Control Hub (Touch Screen) *Able to adjust: Light brightness, Fan speed, Sensor duration,Occupancy light mode, Intermittent air circulation duration. • LED Strip Light • Air Ventilation & Purifying System • AH Meyer Netbox Flush 1 Power Socket 110-240 VAC,Max. 20A & USB A+C Charging, Max 65W • 1 x CAT 6 Lan Outlet • High Stool not IncludedDimension:1000W x1000D x 2180H	2	Nos.	27,161.00	**RATE ONLY**
17.19	**EXISTING FURNITURE**		**SHIFTING OF EXISTING FURNITURE** 1. Dismantling of existing HM chairs, packing it properly, to be transported from existing office at Mazaya Tower to new office at Fortune tower, in JLT and re-installating the same for the users. 2. Dismantling of existing worktops of the workstations to replace it with new worktops (as quoted under item 17.11) and cart away the old worktops. Shifting of existing frames to the new office to fix the proposed new worktops. 3. Item also includes shifting of existing low height cabinets as per the proposed layout requirements	1	Ls	24,828.00	**24,828.00**
						TOTAL LOOSE FURNITURE	**132,357.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vorvodesign.ae PO Box: 128279, Dubai,UAE www.vorvodesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR ELECTROLUX OFFICE @ DUBAI-UAE

Quote Ref No: VID/1104/24/CP/QTN_01/R2 — **August 20, 2025**

SR.NO	DESCRIPTION	QTY	UNIT	RATE	TOTAL (AED)
18.00	**DECORATIVE ITEMS TO BE RELOCATED FROM EXISTING OFFICE**				
18.01	Removal of existing of the decorative feature planters fixed on glass partition in Electrolux existing office at Mazaya BB1 and the same to be fixed on the proposed glass partition of the board room in new office. (5 x 2 = 10Nos - as its on both sizes of partition)	5	Sets	1,379.00	**6,895.00**
18.02	Replacement of damaged glass partition after removal of the above mentionbed decorative panels from the glass. Supply & installation of 10mm thk standard glass partition with powdercoated U-Channel (closest match to existing) as per the site requirement. ***Please note : The quantity is approximate for budget purpose only, same will be remeasured and charged as per actual site requirement based on per sqm rate.***	20	Sqm	395.00	**7,900.00**
	TOTAL FOR RELOCATION WORKS				**14,795.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

Thank you,

© Verve Design, 2025

Verve Interior Decoration llc

Unit M04,
Al Reemas Building,
Sheikh Zayed Road, Al Quoz,
PO Box - 128279,
Dubai, UAE.

t : +971 4 240 0119
f : +971 4 240 8403
info@vervedesign.ae
www.vervedesign.ae