verve

space + design

Huspy™

PROPOSAL FOR INTERIOR FITOUT WORKS

verve
space + design

INTERIOR FIT-OUT WORKS

FOR

Huspy™

AT

PRODUCTION CITY DUBAI-U.A.E

For
HUSPY

Prepared by:
Marie Cayabyab
Verve Interior Decoration LLC
PO Box 128279, Dubai, UAE
Email: marie@vervedesign.ae

Prepared on:
December 17, 2025

verve
space + design

CONTRACT AGREEMENT: General terms and conditions

Project Timeline: As per approved Project schedule

Payment Terms:

Advance Payment : 30% Advance payment against order confirmation.
Progress Payment : 20% upon Authority approvals
Progress Payment : 45% as per site progress
Final Payment : 5% upon work completion at site and hand over.

Payment to be honored within 7 days from the date of receipt of Invoice

Note: Any change to the agreed scope of work—whether requested by the client or required due to site-related conditions—will be invoiced at 100% of its value, payable in full before the variation is carried out.

All products offered by us on this project carry a warranty against defective materials and/or workmanship as follows:

Fit Out Works : 12 Months from the date of Handover.

Air Conditioning System – FCUs Disclaimer

Verve has retained the existing Fan Coil Units (FCUs) as part of the final proposal. Accordingly, Verve shall not be held liable for the performance of the existing FCUs. Any cooling inefficiencies or issues arising in the final fitout due to the existing AC system's limitations shall be addressed collaboratively between Verve and the Client. Verve cannot guarantee optimal performance of the current units and recommends replacement should performance issues be foreseen or experienced.

Insurances:

All our personnel working on the project will be covered under our Workmen Compensation

All works carried out at site will be covered by our Contractor's All Risk Policy

Validity.

Our offer is valid for a period of 30 days from hereof

Note: Bank guarantee or Retention Requirements TBC

Please sign below for acceptance of the offer. The BOQ will be treated as the final scope of work and contract will form the integral part of the project.

Signature: _____

on behalf of: HUSPY

Name:

Date:

Signature:_____

on behalf of : Verve Interior Decoration LLC

Name: **Syed Mehdi**

Date: **December 17, 2025**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR HUSPY @ PRODUCTION CITY , DUBAI-UAE		
Quote Ref No: VID/1186/25/CP/QTN_01/R1		17-Dec-25
SR. NO	SUMMARY	TOTAL (AED)
1	PRELIMINARIES	54,038.00
2	DEMOLITION AND CIVIL WORKS	44,772.00
3	PARTITION WORKS	112,077.00
4	FLOOR WORKS	228,447.00
5	WALL FINISH	154,856.00
6	CEILING WORKS	112,471.00
7	DOORS	68,206.00
8	SIGNAGE WORKS - Provisional Sum	7,342.00
9	JOINERY WORKS	205,093.00
10	SANITARY FITTINGS	49,697.00
11	LIGHTING WORKS - NON DIMMABLE	53,914.00
12	HVAC WORKS (PROVISIONAL SUM)	77,239.00
13	ELECTRICAL WORKS (PROVISIONAL SUM)	195,796.00
14	CIVIL DEFENCE WORKS (PROVISIONAL SUM)	62,648.00
15	PLUMBING WORKS	90,382.00
16	RECEPTION AREA (PROVISIONAL SUM; SUBJECT TO BUILDING APPROVAL)	82,704.00
17	LOOSE FURNITURE	BY CLIENT
	GRAND TOTAL AMOUNT (AED):	1,599,682.00

Note: The above price is exclusive of Value Added Tax (VAT), 5% VAT shall be payable as an addition to the invoice value.

Note: **Any variation in terms of quantity that comes up during the course of work has to be paid by the client and hence client is liable for payment of Variation. Retention is not considered.**

Exclusions:

1) All fees and deposit for statutory authorities.
2) Any other items not mentioned in the attached BOQ.
3) LEED building consultancy and certification.

For Verve Interior Decoration LLC

Syed Mehdi
Sales Director
+971 50 513 9878
syed@vervedesign.ae

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR HUSPY @ PRODUCTION CITY, DUBAI-UAE

Quote Ref No: VID/1186/25/CP/QTN_01/R1 — **17-Dec-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
1.00	**PRELIMINARIES**				
1.01	General - Contractor's preliminaries for mobilization, site preparation, Provision for all temporary barricades, setting out transportations to/from site, material deliveries, small tools and equipment's, protection of finished products in on-going site, site attendance and call out attendance, PPE and other site requirements to be followed *Hoarding, Branding and posters are excluded.*	1	Item	4,405.00	**4,405.00**
1.02	Co ordination Charges for obtaining approvals from the Landlord & the related authorities.	1	Item	2,203.00	**2,203.00**
	Charges For Production of Shop Drawings				
1.03	Interior Fitout Drawings - Production of shop drawings for approvals. It includes Detail Design Drawings / Shop Drawings for Fit Out (Civil works)before work execution in order to aid in proper functioning of the Work Site .This is to reflect only the scope of works envisaged in the BOQ.	1	Item	29,075.00	**29,075.00**
1.04	MEP Drawings – Prepare complete set of Electrical, HVAC, Plumbing, Firefighting & Fire Alarm Design completion before work execution in order to aid in proper functioning of the Work Site. This is to reflect only the scope of works envisaged in the BOQ.				
1.05	CAR Insurance for fit out work during the execution of works. ***Please Note: Insurance coverage is limited to CAR of Contract Value. If higher coverage limit is required by building management and any other authorities, the additional premium amount will be charged separately . Professional Indemnity Insurance excluded. If required will charge the client on actual.***	1	Item	2,937.00	**2,937.00**
1.06	Regular cleaning of site during construction period and after completion professional deep cleaning and made ready to occupy. Including carting away the debris to Municipal dumping area.	1	Item	7,342.00	**7,342.00**
1.07	Charges for site protection (protection of common area finishes and the area near to the work space)	1	Item	4,405.00	**4,405.00**
1.08	Scaffolding Charges	1	Item	3,671.00	**3,671.00**
1.09	All approval charges and security deposit towards any and all authorities (DMCC, DCD, DEWA, Building Management) to be paid by client on actual				**By client on actual**
	Please Note : Provision for mock up and samples submissions at site as per requirement included, however special items are chargeable and shall be billed to the client on actual.				
				SUB TOTAL PRELIMINARIES :	**54,038.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

INTERIOR FIT-OUT WORKS FOR HUSPY @ PRODUCTION CITY, DUBAI-UAE

Quote Ref No: VID/1186/25/CP/QTN_01/R1 — **17-Dec-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
2.00	**DEMOLITION AND CIVIL WORKS**				
2.01	Carefully remove below mentioned items and dispose of all debris off-site in accordance with the building management's rules and regulations, and in compliance with all relevant environmental, health, and safety requirements. Upon removal, making good limited to areas directly impacted by the dismantling works.	1	Item	44,772.00	**44,772.00**
a	Existing gypsum or cement board partitions, glass partitions & doors, gypsum ceiling, floor finish, existing joinery items like (wooden cladding / ceiling/ pantry cabinets / vanity counters etc), MEP items like (lights /AC diffusers / ducts/ sanitary fittings etc)				
	Please note that any concealed services or unforeseen conditions encountered during removal are not included in our scope of works and will be brought to the client's attention for further instruction.				
	SUB TOTAL DEMOLITION AND CIVIL WORKS :				**44,772.00**
	ID WORKS				
3.00	**PARTITION WORKS**				
3.01	**GYPSUM PARTITION SINGLE LAYER (NON FR)** Supply and installation of **straight drywall partitions** made of 72mm GI tracks, 70mm GI studs covered with 12.5 mm thick normal gypsum boards made to European standards on both faces with 50 mm mineral Rockwool insulation inside rising up to the slab ceiling height, jointed taped with smooth leveling ready to receive final finish in the below mentioned areas. Height up to 3.5 m **Brand - Knauf or Equivalent** **Location: To Open Workstation Partitions**	52	Sq.m	125.00	**6,500.00**
3.02	**CURVED GYPSUM PARTITION SINGLE LAYER (NON FR)** Supply and installation of 100 mm Thk Non-FR gypsum partition with 12.5 mm Thk Non-FR gypsum board (Knauf or equivalent) single layer on both sides with studs, 50mm thick rockwool insulation and necessary frames and accessories. Height up to 3.5 m **Location : Along Vestibule area**	9	Sq.m	132.00	**1,188.00**
3.03	**GYPSUM PARTITION SINGLE LAYER (FR)** Supply and installation of **100mm Thk FR gypsum partition** with 12.5mm Thk FR gypsum board (Knauf or equivalent) Single layer on both sides with studs, 50mm thick rockwool insulation and necessary frames and accessories. Height up to 3.5 m **Location : Server room**	27	Sq.m	162.00	**4,374.00**
3.04	**GYPSUM PARTITION DOUBLE LAYER (NON FR)** Supply and installation of 125 mm Thk Non-FR gypsum partition with 2 x 12.5 mm Thk Non-FR gypsum board (Knauf or equivalent) double layer on both sides with studs, 50mm thick rockwool insulation and necessary frames and accessories. Height up to 3.5 m **Location : Meeting Rooms**	142	Sq.m	184.00	**26,128.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR HUSPY @ PRODUCTION CITY, DUBAI-UAE

Quote Ref No: VID/1186/25/CP/QTN_01/R1 **17-Dec-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
3.05	**GLASS PARTITION - NON FR** Supply and installation of **single glazed 40 x 40 mm powder coated aluminum framed single layered partition (around the partitions)** utilizing 12 mm thick glass with all around straight polished edges including glass to glass clear joints. Height up to 2.7 m **Location : Workstation Entrance**	3	Sq.m	514.00	**1,542.00**
3.06	**ACOUSTIC GLASS PARTITION - NON FR** Supply and fixing of 25 x 25 mm aluminium framed QIC partition utilizing 13.52mm clear acoustic laminated (6 mm clear tempered glass + 1.52 mm acoustic PVB + 6mm clear tempered glass) with all around straight polished edges fixing by clip profiles with rubber gasket , including glass to glass beading joints . Height up to 2.7 m **Location : Meeting rooms and Entrance to Offices**	43	Sq.m	808.00	**34,744.00**
3.07	**DOUBLE LAYER GYPSUM BAFFLE (NON-FR)** Supply and installation of **Non-FR gypsum baffle wall** with 12.5mm Thk Non-FR gypsum board (Knauf or equivalent) single layer on both sides with 50mm thick rockwool insulation, necessary frames and accessories . Height up to 0.8 m **Location : Above glass partitions**	26	Lm	184.00	**4,784.00**
3.08	**GYPSUM CLADDING - NFR** Supply and installation of **NFR 12.5 mm thick Gypsum board (Knauf or equivalent) wall cladding** with necessary material for fixing, smoothened and made ready to receive final finishes. Height up to 2.7 m **Location : Meeting Room TV Niche**	60	Sq.m	103.00	**6,180.00**
3.09	**CEMENT BOARD PARTITION (NON FR)** Supply and installation of **100 mm Thk Cement board Partition** with 12.5mm Thk cement board single layer on both sides with studs, 50mm thick rockwool insulation and necessary frames and accessories. Height up to 3.5m **Location : Washroom Area**	86	Sq.m	235.00	**20,210.00**
3.10	**CEMENT BOARD CLADDING** Supply and installation of **Cement board wall cladding** with necessary material for fixing, smoothened and made ready to receive final finishes. Height up to 3m **Location : Washroom (window side)**	15	Sq.m	162.00	**2,430.00**
3.11	Supply and installation of **MDF support** to install the TV	16	Sq.m	103.00	**1,648.00**
3.12	**WC BOX TYPE WALL CLADDING** Supply and installation of box type wall cladding for WC flush tank, to be constructed with cement boards with required supports and hardwares.	1	Item	2,349.00	**2,349.00**
		SUB TOTAL PARTITION WORKS :			**112,077.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR HUSPY @ PRODUCTION CITY, DUBAI-UAE

Quote Ref No: VID/1186/25/CP/QTN_01/R1 **17-Dec-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
4.00	**FLOORING WORKS**				
4.01	**SCREED LEVELLING** Leveling of existing screed after removal of existing floor finishes and ready to receive new floor finish. All complete in acordence with the site requirement. **Location : To Tile Finish**	106	Sq.m	73.00	**7,738.00**
4.02	**SELF LEVELLING** Supply and installation of 2 to 3 mm self levelling compound to make the floor ready to receive the new flooring. **Location : To carpet and LVT flooring**	897	Sq.m	51.00	**45,747.00**
4.03	Allowance for cutting and chasing of existing floor screed to accommodate the new floor boxes	1	Item	11,358.00	**11,358.00**
4.04	**WATER PROOFING** Supply and installation of **Cementitious water proofing** 2 coats including protection screed. Area considered : Sqm **Location: Floor area and wall up to 300 mm, up to 1.2 m behind WC/ wash basin**	56	Sq.m	125.00	**7,000.00**
4.05	Supply and installation of **RF-01** anti static raised floor (HPL) finish. Max Height - 200mm Area - 6 m2 **Location : Server room**	1	Item	4,038.00	**4,038.00**
4.06	**CERAMIC TILE FLOORING** Supply and installation of Ceramic Tile flooring with grouting including cutting and alignment. As per design and approved sample. Size : 60 x 120 cm PC Rate : 125 AED per Sq.m Location :Dinign Area Note : Subject to sample approval.	75	Sq.m	279.00	**20,925.00**
4.07	**CERAMIC TILE FLOORING** Supply and installation of Ceramic Tile flooring with grouting including cutting and alignment. As per design and approved sample. Size : 30 x 60 cm concrete grey matte finish PC Rate : 60 AED per Sq.m Location : Washroom Area Note : Subject to sample approval.	32	Sq.m	187.00	**5,984.00**
4.08	**CP 01 CARPET FLOORING** Supply and Installation of Carpet tile flooring including adhesives and all necessary material for fixing. Made: Eros Carpet Tile: 501 Drak Grey Location : As per Design	712	Sq.m	106.00	**75,472.00**
4.09	**LVT FLOORING** Supply and installation of **Luxury Vinyl Tile flooring** with necessary material for installation. Size: 30x60 x 4mm thk Make : Taiga **Location : Pathwalk / Corridor area**	179	Sq.m	155.00	**27,745.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR HUSPY @ PRODUCTION CITY, DUBAI-UAE

Quote Ref No: VID/1186/25/CP/QTN_01/R1 — **17-Dec-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
4.10	**TRANSITION STRIP** Supply and installation of Transition Strip in SS finish (ready available). **Location : Between different floor finishes**	204	Lm	110.00	**22,440.00**
	Note: All finishes are subject to final sample approval.				
		SUB TOTAL FLOORING WORKS :			**228,447.00**
5.00	**WALL FINISHES**				
5.01	**WALL PAINT** Supply and application of **Jotun Fenomastic Paint Finish (white)** with all cleaning and levelling. Closed Ceiling Height up to 2.7 m Open Ceiling Height up to 3.5 m	941	Sq.m	35.00	**32,935.00**
5.02	**WASHABLE PAINT** Supply and application of **Jotun Washable Paint Finish (Color)** with all cleaning and levelling. Height Up to H1.5m Location: Washrooms	53	Sq.m	44.00	**2,332.00**
5.03	**TEXTURE PAINT** Supply and application of Texture paint as per the design Height up to 2.7 m **Location: Reception Seating Wall, Collab Lounge and Dining/Breakout Area**	115	Sq.m	132.00	**15,180.00**
5.04	**MDF WALL CLADDING** Supply and installation of **plain MDF wall cladding in wood veneer finish** including necessary fittings and accessories for installation. Height up to H2700mm **Location: Multi Purpose Wall**	17	Sq.m	954.00	**16,218.00**
5.05	**ACOUSTIC WALL PANEL** Supply and installation of Acoustic wall (PET/ felt) panel as per design and approved sample with v-groove Height up to 1.2 m **Location : 4Pax Meeting rooms**	18	Sq.m	576.00	**10,368.00**
5.06	**BACKPAINTED GLASS - (WRITABLE WALL)** Supply and installation of Back painted crystal clear glass with necessary material for fixing including MDF backing. Maxi Height - 1.2m **Location: 12Pax Meeting room**	9	Sq.m	734.00	**6,606.00**
5.07	**CERAMIC WALL TILE** Supply and installation of Ceramic Tile flooring with grouting including cutting and alignment. As per design and approved sample. Size : 30 x 60 cm up to H1.2m PC Rate : 60 AED per Sq.m Location : Washrooms Note : Subject to sample approval.	43	Sq.m	187.00	**8,041.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR HUSPY @ PRODUCTION CITY, DUBAI-UAE

Quote Ref No: VID/1186/25/CP/QTN_01/R1 — **17-Dec-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
5.08	**BACKSPLASH WALL TILE** Supply and installation of wall tiles including necessary materials for fixing. PC Rate : 80AED/Sq.m Brand: RAK / Equivalent Height up to H1.8m only Location: Coffee Counter	10	Sq.m	290.00	**2,900.00**
5.09	Supply and installation of plain **Frosted sticker .** Height upto 1200 mm Location : New glass partition and doors	32	Sq.m	103.00	**3,296.00**
5.10	**SKIRTING** Supply and installation of (up to 50 mm high) **MDF skirting in PU paint finish** with necessary fittings and accessories. **Note : Non concealed**	406	Lm	66.00	**26,796.00**
5.11	**ROLLER BLINDS - MANUAL** Supply and installation of **sunscreen blinds** Height: Upto 3500mm **Location : External glazing**	343	Sq.m	88.00	**30,184.00**
	Note: 1. All finishes are subject to final drawing and sample approvals.				
			SUB TOTAL WALL FINISH :		**154,856.00**
6.00	**CEILING WORKS**				
6.01	**PLAIN GYPSUM CEILING** Supply and installation of **Gypsum Board Plain ceiling** (Knauf or equivalent) with necessary hanging systems including wall angle "C "channel, furring channel with 12.5mm gypsum boards joined taped smoothened finish. **Location : As per design**	117	Sq.m	110.00	**12,870.00**
6.02	**60 X 60 CM VINYL FACED GYPSUM CEILING.** Supply and installation of 60x60cm vinyl faced ceiling tile. **Location : Server room**	6	Sq.m	117.00	**702.00**
6.03	**60 X 60 GRID GYPSUM CEILING.** Supply and installation of 60x60cm grid ceiling tile **Location : Wash Room and Utility**	30	Sq.m	88.00	**2,640.00**
6.04	**GYPSUM BULKHEAD - COVELIGHT** Supply and installation of 100/200 mm high Gypsum Bulkhead with curve edges 12.5 mm gypsum boards with paint finish. **Location: To Waiting Lounge and 12 Pax Meeting room**	30	Lm	135.00	**4,050.00**
6.05	**GYPSUM PELMET** Supply and installation of **Gypsum Pelmet** with necessary fittings with paint finish. **Location : For blinds**	93	LM	135.00	**12,555.00**
6.06	**SHADOW GAP** Supply and installation of shadow gap as per the design.	104	LM	37.00	**3,848.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

INTERIOR FIT-OUT WORKS FOR HUSPY @ PRODUCTION CITY, DUBAI-UAE

Quote Ref No: VID/1186/25/CP/QTN_01/R1 **17-Dec-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
6.07	**GYPSUM ACCESS PANEL** Supply and installation of **Gypsum access panel (Max 60 x 60 cm)** with frame and hinges. **Location: Proposed Gypsum ceiling area** Note : Subject to final MEP drawings	7	Nos.	316.00	**2,212.00**
6.08	**GYPSUM CEILING PAINT** Supply and application of **Jotun Fenomastic WHITE paint** including all cleaning and levelling. As per design and approved sample. (2 coats including sanding). **Location : Proposed Gypsum ceiling areas**	117	Sq.m	35.00	**4,095.00**
6.09	**OPEN CEILING NEW PAINT** Supply and application of new Stucco Paint finish to Open Ceiling in white color. Scope includes cleaning, scraping and removal of any loose, flaking/deteriorated existing paint on site and repaint complete includig the MEP services **Location: Open Ceiling**.	811	Sq.m	81.00	**65,691.00**
6.09 OPT	**OPEN CEILING BLACK PAINT (REPAINT)** Supply and application of one coat of black **Jotun Fenomastic paint on the existing open ceiling including** MEP Services.	0	Item	35,720.00	**Rate Only**
6.10	**BAFFLE CEILING** Supply and installation of circular baffle ceiling complete with required support and necessary accessories for installation Approx Size considered Dia1.2m Location: Collab Loung Area	4	Nos.	952.00	**3,808.00**
	Note : All finishes are subject to final sample approval.				
				SUB TOTAL CEILING WORKS :	**112,471.00**
7.00	**DOORS**				
7.01	**ACOUSTIC GLASS DOOR SWING DOOR - SINGLE LEAF** Supply and fixing of 13.52mm clear acoustic laminated (6 mm clear tempered glass + 1.52 mm acoustic PVB + 6mm clear tempered glass) glass single leaf frameless glass doors with all around straight polished edges fixing by DORMA BTS 65 floor machine, OFFSET pivot hinges , bottom lock and 800*600 mm long H type handle including all around 50 mm wide overlapped UNICA door frame. Size: 1000x2700mm **Location : Meeting rooms and Entrances to Office**	6	Nos	5,433.00	**32,598.00**
7.02	Supply and fixing of 12 mm clear tempered glass single leaf 76 * 42 mm powder coated beading type aluminium framed pivot door with all around straight polish edges fixing with DORMA BTS 65 floor machine, top and bottom pivot, bottom lock and 800 * 600 mm long H type round straight handle. Size:- 1000x2700mm **Location : Main Entrance**	3	Nos	3,524.00	**10,572.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR HUSPY @ PRODUCTION CITY, DUBAI-UAE

Quote Ref No: VID/1186/25/CP/QTN_01/R1 — **17-Dec-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
7.03	**SINGLE LEAF WOODEN DOOR - NON FR** Supply and installation of Semi solid wooden swing door NON FR in PU paint finish, with Frame, architrave, in PU paint finish with all necessary ironmongery and material for fixing. Size: 900 x 2200mm Ht **Location : Washroom and Utility** Note : Concealed door	3	Nos	4,919.00	**14,757.00**
7.04	**WOODEN SWING DOOR - FR 60 min** Supply and installation of single leaf 60 mins-fire rated MDF flush single swing door with solid Meranti or Beech wood frame and architraves in approved matte or semi-gloss PU paint finish including all necessary standard ironmongeries. Size : 900 mm x H 2200 mm **Location : Server room**	1	Nos	6,755.00	**6,755.00**
7.05	Allowance for the wrapping inside only panel of existing secondary doors. Note: No existing fittings to replace. Any modification required aside on wrapping will be subject for approval and wll be treared as a work variation. Building corridor side finish same as it is Location: Secondary Doors (2 nos)	1	Item	3,524.00	**3,524.00**
	Note: **a. All fittings are in powder coating or SS finish. Offset pivot excluded.** **b. All existing secondary entrances to retain as is. Any substantial issues with the existing said doors that require additional work will be treated as a work variation. The scope and cost of any variation will be assessed based on the actual site conditions, determined after demolition, and may result in adjustments to the cost proposal.**				
				SUB TOTAL DOORS :	**68,206.00**
8.00	**SIGNAGE WORKS - Provisional Sum**				
6.02	Supply and installation of 3D wordings as per the approved design Approx Size: H1000 x Propotionate Length **Location: Coffee Bar Column** 	1	Nos	7,342.00	**7,342.00**
	Note : 1. Any other signage excluded.				
				SUB TOTAL SIGNAGE WORKS :	**7,342.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

INTERIOR FIT-OUT WORKS FOR HUSPY @ PRODUCTION CITY, DUBAI-UAE

Quote Ref No: VID/1186/25/CP/QTN_01/R1 **17-Dec-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
9.00	**JOINERY WORKS**				
9.01	**MDF TV WALL UNIT** Supply and installation of MDF TV wall unit in veneer finish inclduing necessary fittings and accessories for installation Size: L2500xH2700mm **Location: 12Pax Meeting room**	8	Sq.m	954.00	**7,632.00**
9.02	**UPHOLSTERED SEATING** Fabrication, supply and installation of seating unit with MDF in veneer finish and fabric upholstered cushion, subject to final designa and approval Seating Size: 2360mm x 500 x 500/750mm **Location: 12 Pax Meeting room**	1	Item	12,129.00	**12,129.00**
9.03	**PLANTER BOX** Fabrication, supply and installation of planter box made MDF in veneer finish as per the design. Planter Box: 1750 x 600 x 750mm **Location: 12 Pax Meeting room** Note: Planter box considered for artificial plants and to suply by Client	1	Item	3,855.00	**3,855.00**
9.04	**PLANTER BOX** Fabrication, supply and installation of planter box made with MDF in veneer finish, necessary materials for installation. Size: 1400 x 500 x 1100mm **Location : Along Vestibule** **Note: Plants excluded**	1	Item	3,084.00	**3,084.00**
9.05	Supply and installation of platform to be constructed with access raise floor complete with Edge made MDF finished by veneer finish. Top finish of carpet is priced under floor finish scope	1	Item	1,639.00	**Rate Only**
9.06	**HOT DESK** Fabrication, supply and installation of Hot desk in MDF veneer top finish as per design including necessary materials for installation. Size : : L2500xW600xH1100mm **Location : Open Area Workstation**	2	Item	7,636.00	**15,272.00**
9.07	**HOT DESK** Fabrication, supply and installation of Hot desk in veneer top and leg finish complete with round planter box provision for plant as per design including necessary materials for installation. Planter to be supplied by Client Size : : L4200xW450xH1100mm **Location : Open Area Workstation**	1	Item	9,178.00	**9,178.00**
9.08	**DINING/LOUNGE COUNTER DESK** Fabrication, supply and installation of Hot desk in veneer top and leg finish complete with round planter box provision for plant as per design including necessary materials for installation. Planter to be supplied by Client Size : : L3150xW500mm **Location : Dining Area Along Column**	1	Item	11,564.00	**11,564.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

INTERIOR FIT-OUT WORKS FOR HUSPY @ PRODUCTION CITY, DUBAI-UAE

Quote Ref No: VID/1186/25/CP/QTN_01/R1 **17-Dec-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
9.09	**HIGH BAR COUNTER DESK** Fabrication, supply and installation of Hot desk in veneer top and leg finish complete with round planter box provision for plant as per design including necessary materials for installation. Planter to be supplied by Client Size : : L6000xW600mm **Location : Dining/Breakout Area Along Columns**	1	Item	22,026.00	**22,026.00**
9.10	**COLLAB LOUNGE COUNTER DESK** Fabrication, supply and installation of counter desk with round legs in MDF veneer finish, including all necessary materials for installation. Subject to final approval and design Size : : L2200xW600mm **Location : Collab Lounges**	2	Item	9,046.00	**18,092.00**
9.11	**MDF WALL BATTENS** Supply and installation of fixed MDF batten divider to be made with MDF in veneer finish. All complete with required support to slab ceiling Size: 100x50x3500Hx 22nos **Location: Breakout Area**	1	LS	25,441.00	**25,441.00**
9.12	**BREAKOUT LOUNGE SEATING** Fabrication, supply and installation of Breakout Lounge in MDF veneer finish complete with fabric seating and back rest. Subject to final approval and design Dimension: L4100xW600mm Location: At Dining/Breakout Area	1	Item	6,167.00	**6,167.00**
9.13	**COFFEE COUNTER** Fabrication, supply and installation of Dry Coffee counter with MDF Unit in veneer finish with 2cm Tundra grey Marble counter top and shelves made MDF in veneer finish as per design with all necessary for fixing. **Location : Entrance Coffee bar Area** Lower cabinet size : 4400 x 700 x 900 mm Shelves size : 2400 x 300 mm x 2nos Note : Tile Backsplash Considered Separately **Marble PC Rate : 350 / -per sq.m.**	1	Item	22,265.00	**22,265.00**
9.14	**PRINTER CABINET** Fabrication, supply and installation of Printer cabinet with MDF in veneer finish as below with all necessary for fixing. **Lower cabinet size : 2000 x 600 x 1100 mm** **Upper cabinet size : 2000 x 500 x 600 mm**	1	Item	5,874.00	**5,874.00**
9.15	**PRINTER CABINET** Fabrication, supply and installation of Printer cabinet with MDF in veneer finish as below with all necessary for fixing. **Lower cabinet size : 2500 x 600 x 1100 mm** **Upper cabinet size : 2500 x 500 x 600 mm**	1	Item	7,342.00	**7,342.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

INTERIOR FIT-OUT WORKS FOR HUSPY @ PRODUCTION CITY, DUBAI-UAE

Quote Ref No: VID/1186/25/CP/QTN_01/R1 **17-Dec-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
9.16	**STORAGE CABINETS** Fabrication, supply and installation of MDF in veneer finish facia and melamine finish inside carcase complete with shelf, shutter and required standard necessary fittings Size: L2000xW600xH2700mm Location: Waiting Lounge	1	Item	11,894.00	**11,894.00**
9.17	**STORAGE CABINETS** Fabrication, supply and installation of MDF in veneer finish facia and melamine finish inside carcase complete with shelf, shutter and required standard necessary fittings Size: L1350xW600xH2700mm Location: Waiting Lounge	1	Item	8,029.00	**8,029.00**
9.18	**VANITY COUNTER** Fabrication, supply and installation of vanity counter with **MDF Unit in laminate finish** with **quartz counter top finish** as per design with all necessary for fixing. **Location : Female Washroom** Size: L1670xW600mmm **Marble PC Rate : 350 / -per sq.m.**	1	Item	5,697.00	**5,697.00**
9.19	**VANITY COUNTER** Fabrication, supply and installation of vanity counter with **MDF Unit in laminate finish** with **quartz counter top finish** as per design with all necessary for fixing. **Location : Male Washroom** Size: L2800xW600mmm **Marble PC Rate : 350 / -per sq.m.**	1	Item	9,552.00	**9,552.00**
	Please Note: ***1. All carcasses to be finished in melamine; shutters to be finished in laminate unless otherwise specified.*** ***2. Standard Ironmongeries considered, Brand : Devon or similar*** ***3. Drawers to have standard closing mechanisms; shutters to have finger groove finishes. Magnetic push-to-open fittings are additional if required.*** ***4. Joinery in wet areas to be constructed using Moisture-Resistant (MR) MDF. Fire-Retardant (FR) MDF to be used only where specifically indicated (e.g., DB wall cladding).*** ***5. Joinery incorporating concealed lighting to include standard LED strip lights only.***				
				SUB TOTAL JOINERY WORKS :	**205,093.00**
10.00	**SANITARY FITTINGS**				
	Supply of sanitary fittings as per verve design **Finish : White or chrome** **Make : RAK ceramics or equivalent**				
10.01	**COUNTERTOP WASH BASIN** Finish : Ceramic white Size : 515 x 400 x 135 mm **Make : REMO ROUND UNDERCOUNTER WASH BASIN DIAMETER 400X185 MM WHITE**	5	Nos	839.00	**4,195.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR HUSPY @ PRODUCTION CITY, DUBAI-UAE

Quote Ref No: VID/1186/25/CP/QTN_01/R1 — **17-Dec-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
10.02	**BASIN MIXER** Supply of Single lever deck mounted Mono Basin mixer in chrome finish with minimum operating pressure of 0.2 BAR LP including wall mounted Angle valve with flange 1/2" X 1/2" CP.	5	Nos	365.00	**1,825.00**
10.03	**FLOOR MOUNT WC + TANK** Flush plate finish - matt chrome RAK KARLA **Make : RAK ceramics**	6	Nos	1,667.00	**10,002.00**
10.03 Opt	**WALL MOUNT WC + CONCEALED CISTERN + PLUSH PLATE** Flush plate finish - matt chrome RAK ORIGIN 50Cm **Make : RAK ceramics**	0	Nos	3,585.00	**Rate Only**
10.04	**SHATTAF** Finish : chrome **Make : KLUDI**	6	Nos	90.00	**540.00**
10.05	**TOILET ROLL HOLDER** Finish : Chrome **Make : RAK ceramics**	6	Nos	122.00	**732.00**
10.06	**URINAL BOWL + FLUSH PUSH TYPE** Finish : White **Make : RAK ceramics**	3	Nos	576.00	**1,728.00**
10.07	**URINAL PARTITION** Finish : White **Make : RAK ceramics**	3	Nos	250.00	**750.00**
10.08	**MIRROR** Supply and installation of 6mm thick plain silver mirror with straight polished non bevelled edges including necessary MDF backing and materials for installation without any cut out and holes, without light Make : Guardian	6	Sq.m	624.00	**3,744.00**
10.09	**FLOOR DRAIN** Size 150 x 150 mm	9	Nos	109.00	**981.00**
10.10	**CUBICLE PARTITIONS** Supply and installation of cubicle partition finished with HPL including door Height : 1800 mm Panel Thickness : 12mm Hardware : Stainless Steel - 304 Grade **Make : Solera or equivalent** **Location : Male & female washrooms**	6	Nos	4,200.00	**25,200.00**
				SUB TOTAL SANITARY FITTINGS :	**49,697.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR HUSPY @ PRODUCTION CITY, DUBAI-UAE

Quote Ref No: VID/1186/25/CP/QTN_01/R1 — **17-Dec-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
11.00	**LIGHTING WORKS**				
	Supply of non - dimmable lights as per verve design **Make : Hegron UK or equivalent**				
11.01	**WALL MOUNTED LIGHT - 3x8W** Location: At Stage Platform	4	Nos	527.00	**2,108.00**
11.02	**ROUND DOWN LIGHT** Location: To Gypsum ceiling	41	Nos	116.00	**4,756.00**
11.03	**LED STRIP LIGHT including driver** Location: To all Joinery and covelight	45	Lm	118.00	**5,310.00**
11.04	**PENDANT LIGHT - (20 W)** Overall Size : 95 mm dia x 150 mm Location: At Open Office Area	160	Nos	157.00	**25,120.00**
11.05	**60x60cm Ceiling Panel Light** Location: Washroom and Utility Area	1	Item	1,488.00	**1,488.00**
11.06	**SUSPENDED OVAL LIGHT** Oblong Size Up to: L4000xW800mm Location: At Big Meeting room	1	Nos	5,513.00	**5,513.00**
11.07	**SUSPENDED CIRCULAR LIGHT** Size: 900mm Dia Location: To Meeting Room 4Pax	3	Nos	1,395.00	**4,185.00**
11.08	**SUSPENDED CIRCULAR LIGHT** Size up to: 1200mm Dia Location: To Collab Area	2	Nos	1,897.00	**3,794.00**
11.09	PENDANT DECORATIVE LIGHT Approx Size: Dia 320mm	2	Nos	410.00	**820.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

INTERIOR FIT-OUT WORKS FOR HUSPY @ PRODUCTION CITY, DUBAI-UAE

Quote Ref No: VID/1186/25/CP/QTN_01/R1 — **17-Dec-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
11.10	**SUSPENDED LINEAR LIGHT** Oblong Size Up to: L1200mm Location: At 4pax Meeting Room	2	Nos	410.00	**820.00**
	Note : 1. Consider existing Pendant LineaLights are in good conditiona nd to re-use for the Open Ceiling Area 2. Quantity subject to final RCP design and LUX calculations 3. Non dimmable lights				
				SUB TOTAL LIGHT FITTINGS :	**53,914.00**
	MEP WORKS				
	MEP WORKS				
12.00	**HVAC WORKS (PROVISIONAL SUM)**				
	AC MACHINES AND ACCESSORIES				
	Modification of existing HVAC system including ducting works as per proposed plan, circular and slot supply and return diffusers, plenum box, flexible ducts and air balancing. Subject to final requirements				
12.01	Relocation of existing FCU from existing office based on new design Note : Considering existing AC machines are in good working condition.	0	Nos.	1,468.00	**Rate Only. If required as per site condition**
12.02	Relocation of existing thermostat. Provisional Qty	0	Nos	367.00	**Rate Only. If required as per site condition**
12.03	Performance test of existing FCU - Provisional Qty as existing as-built is not available and the same to be confirmed during execution (+/-) Note : Any modifications based on performance test to charged additional.	10	PS	734.00	**7,340.00**
	CHW PIPING AND ACCESSORIES				
12.03	Modification and extension of the existing chilled water piping as required	1	Ls	-	**TBC**
12.04	Chemical flushing for relocated FCU- Culligan	1	Ls	-	
	DUCTING AND ACCESSORIES				
	Modification of existing ducting to accommodate new closed ceiling. Subject to final MEP requirements				
12.05	Supply and installation of new Phenolic ducting including all the accessories	1	Ls.	29,369.00	**29,369.00**
12.06	Supply and installation of **12 mm rubber type Acoustic liner**				
12.07	Supply and installation of **Volume Control Damper.**				
12.08	Supply and Installation of flexible duct, plenum box and ring.				

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR HUSPY @ PRODUCTION CITY, DUBAI-UAE

Quote Ref No: VID/1186/25/CP/QTN_01/R1 **17-Dec-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
12.09	Supply and installation of cross talk attenuator , Location: Meeting Room, Conference. Qty provided as provisional. Subject to final location	4	Nos	1,322.00	**5,288.00**
12.10	Supply and installation of Extract duct (GI/PI) along with necessary NRD from the exhaust fan.	1	Item	13,216.00	**13,216.00**
12.11	Supply and installation of inline ducted fan including the ducting and related accessories				
	GRILLS AND DIFFUSER				
12.12	Linear Slot grills/Diffuser. Considered for new gypsum ceiling areas only	1	Item	11,747.00	**11,747.00**
	DRAIN PIPE				
12.13	Supply and Installation of **PVC Pipe** with insulation. - connecting to the existing line. Subject to actual Site requirements	1	Item	-	**TBC**
12.14	Testing and commissioning with air balancing (Verve)	1	Item	5,874.00	**5,874.00**
12.15	Third party testing with air balancing works	1	Item	4,405.00	**4,405.00**
	Notes : 1. BTU Meter works and BMS Connection / cabling/ wiring excluded 2. We have assumed existing FCU are in good condition; only relocation of 2 Nos considered. . Due to non availability of As-built drawings, relocation of FCU to be confirmed as per site condition upon commencement of work				
				SUB TOTAL HVAC WORKS :	**77,239.00**
13.00	**ELECTRICAL WORKS (PROVISIONAL SUM)**				
13.01	PVC conduiting and wiring for light points including installation. Qty provided for new closed gypsum ceiling Note: Light points are subject to revise upon final RCP Layout.	104	Nos	213.00	**22,152.00**
13.02	Removal, relocation and reinstallation of existing Pendant Linear Light complete with required rewiring Note: Existing Linear Pendant light considered in good condition	1	LS	13,532.00	**13,532.00**
13.03	Supply and installation of **Single switches for lighting.** Including cabling works.(MK-Normal White)	9	Nos	264.00	**2,376.00**
13.04	Supply and installation of **Grid switch for lighting.** Including **PVC conduiting**. (Black Matt PVC finish Legrand / schneider) for Open workstation & corridor.	6	Nos	587.00	**3,522.00**
13.05	Supply and installation of **13A Single wall Power Socket,** in PVC finish including conduiting and wiring. (Schneider / Legrand) *Note: Assumed not required power point at existing columns*	15	Nos	323.00	**4,845.00**
13.06	Supply and installation of **13A Twin wall Power Socket,** in black PVC finish including conduiting and wiring. (Schneider / Legrand) *Note: Assumed not required power point at existing columns*	25	Nos	345.00	**8,625.00**
13.07	Supply and installation of **15A Single wall Power Socket,** in Black PVC finish including conduiting and wiring. (Schneider / Legrand)	5	Nos	477.00	**2,385.00**
13.08	Supply and installation of **Floor Box -Twin 13A+ Twin Data.** with cabling and conduiting and data and telephone plates provision only. Make : Obo or equivalent	88	Nos	661.00	**58,168.00**
13.09	50mm conduit and cabling provision for HDMI/VGI.	7	Nos.	661.00	**4,627.00**
13.10	Supply and installation of **PVC** containment for **WI-FI Points**. (Provisional qty)	10	Nos.	184.00	**1,840.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR HUSPY @ PRODUCTION CITY, DUBAI-UAE

Quote Ref No: VID/1186/25/CP/QTN_01/R1 **17-Dec-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
13.11	Supply and installation of PVC containment for **Access control** (Provisional qty)	2	Nos	184.00	**368.00**
13.12	Supply and installation of **PVC** containment for **CCTV Points**. (Provisional qty)	8	Nos.	184.00	**1,472.00**
13.13	Supply and installation of **PVC** containment for speakers system . (Provisional qty)	8	Nos.	184.00	**1,472.00**
13.14	Supply and installation of **PVC** containment for printers.	4	Nos.	184.00	**736.00**
13.15	Supply and installation of **PVC** containment for **AV Rack**	1	Nos.	184.00	**184.00**
13.16	Supply and installation of **PVC** containment for thermostat (Replacement of existing thermostat)	0	Nos.	184.00	**Rate Only**
13.17	Power provision for **Signage**	1	Nos.	954.00	**954.00**
13.18	Modification of existing **SMDB** with necessary ELCB, MCB , and all other accessories as per DEWA ***Please Note : Subject to load availability***	1	Nos	6,608.00	**6,608.00**
13.19	Modification of existing **DB** with necessary ELCB, MCB , and all other accessories as per DEWA Note : No relocation of existing DB	2	Item	3,671.00	**7,342.00**
13.20	Supply & Installation of 100mm GI Cable Tray with necessary fittings & supports -For armoured cable	1	LS	6,975.00	**6,975.00**
13.21	Supply & Installation of 150mm GI Cable Tray with necessary fittings & supports -For IT, AV, Light, Power	1	Lot	13,216.00	**13,216.00**
13.22	DEWA submission, inspection and approval. - 1 submission considered	1	No	5,140.00	**5,140.00**
13.23	Testing commissioning.	1	Item	2,203.00	**2,203.00**
13.24	Providing PVC conduit for Data for workstations, Meeting room and Recetion Note : Not considered for workstations and meeting rooms	167	Nos	162.00	**27,054.00**
	Note: 1. We have assumed that the existing infrastructure's power has sufficient capacity to cater to the requirement of the project. 2. We have not allowed for upgrade of the capacity of any base building system. 3. All electrical conduits considered are of PVC type. 4. We have not allowed for any specific lighting control system in this offer. 5. Subject to final MEP drawings **Exclusions:** 1. Any BMS integration or related works. 2. DEWA Consultancy for power upgrade.				
				SUB TOTAL ELECTRICAL WORKS :	**195,796.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve

space + design

INTERIOR FIT-OUT WORKS FOR HUSPY @ PRODUCTION CITY, DUBAI-UAE

Quote Ref No: VID/1186/25/CP/QTN_01/R1 — **17-Dec-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
14.00	**CIVIL DEFENCE WORKS (PROVISIONAL SUM)**				
	As per the revised design, majority remained as open ceiling therefore we have considered that existing services to reamin as is and only minor modification if affected due to new closed rooms. Supply and installation of new devices below are considered for new closed ceiling areas only.				
14.01	**FIRE ALARM WORKS**				
a	Allow for supply and installation of Smoke detector with base	9.00	Nos		
b	Relocation of existing smoke detector affected due to new closed rooms	5.00	Nos		
c	Supply and installation of Heat detector	2.00	Nos		
d	Relocation of existing voice alarm	1.00	Nos		
e	Supply and installation of break glass	1.00	Nos		
f	Supply and installation of sounder	4.00	Nos.		
g	Fire Resistance Cable G.I conduit and necessary accessories	1.00	Item		
h	Programming , testing and commissioning	1.00	Lot		
i	Installation Charges	1.00	Item	PS	62,648.00
14.02	**FIRE FIGHTING WORKS**				
a	Supply and installation of recessed pendent sprinkler 68°C (QR)	15.00	Nos		
b	Relocation of existing sprinkler affected due to new closed rooms	25.00	Nos		
c	Supply & Installation of 6 KG DCP Fire Extinguisher	4.00	Nos		
d	Supply & Installation of 5 KG CO2 Fire Extinguisher	4.00	Nos		
e	Draining and Recharging of sprinkler system By BMTS	1.00	Item		
f	Pressure test and commissioning, Certification charges	1.00	Item		
14.03	**EMERGENCY WORKS**				
a	Supply of Self - contained Emergency Light - Denko-Round	9.00	Nos.		
b	Relocation of Emergency Light	9.00	Nos.		
c	Supply of Self - contained Exit light - Denko	9.00	Lot		
d	Fire Resistance Cable G.I conduit and necessary accessories	1.00	Item		
e	Installation Charges	1.00	Item		
	Notes / Exclusions: 1. Any additional charges/ fees for any third party shall be paid by the client. 3. Assumed existing sprinkler heads are as per the DCD standards 4. FM 200, central battery system works excluded 5. Any building interface excluded. Subject to actual requirement 6. Any existing device found damaged/faulty on re-installation time will be charged accordingly. 7. No new Fire alarm control panel considered to this proposal 8. Rates subject to base build contractor , Verve to charge 15% coordination charge on actual quote submitted by Base build contractor. Verve provided provisional sum				
				SUB TOTAL CIVIL DEFENCE WORKS :	**62,648.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve

space + design

INTERIOR FIT-OUT WORKS FOR HUSPY @ PRODUCTION CITY, DUBAI-UAE

Quote Ref No: VID/1186/25/CP/QTN_01/R1 — **17-Dec-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
15.00	**PLUMBING WORKS (PROVISIONAL SUM)**				
15.01	Supply and installation of PPR pipe for Cold piping with necessary fittings and accessories	15	Nos	PS	**90,382.00**
15.02	Supply and installation of PPR pipe for hot piping with necessary fittings and accessories	11	Nos		
15.03	Supply and Installation of angle valve	15	Nos		
15.04	Supply and Installation of gate valve	15	Nos		
15.05	Supply and Installation of water hammer arrestor	2	Nos		
15.06	Supply and installation of 50L water heater with necessary fittings and accessories, as per drawing	1	Nos		
15.07	Supply and installation of UPVC drainage Pipe for waste Pipe and connecting to line with ,fittings ,socket ,and other accessories as per Standard	1	Item		
15.08	Supply and installation of Soil waste pipe with necessary fttings and accessories 110 mm for toilet	1	Item		
15.09	Supply and installation of Vent pipe with necessary fittings and accessories	1	Item		
15.10	Allow cost for required coring and scanning works for the new plumbing points	1	Item		
15.11	Supply and installation of floor trap with necessary fittings and accessories	1	Item		
15.12	Supply and installation of clean out with necessary fittings and accessories	1	Item		
15.13	Installation of sanitary fixtures	1	Item		
15.14	Supply and installation of Sani Pump with over flow alarm	1	Item		
15.15	Supply and Installation of High Pressure Pipe from saini pump to existing nearest taping with all fittings and support	1	Item		
15.16	Pressure testing & Gravity testing related to plumbing installation	1	Item		
	Note:Assumed stub-out avaialble to nearest location as per proposed layout				
				SUB TOTAL PLUMBING WORKS :	**90,382.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR HUSPY @ PRODUCTION CITY, DUBAI-UAE

Quote Ref No: VID/1186/25/CP/QTN_01/R1					17-Dec-25
	RECEPTION AREA				
SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
	ID WORKS				
1.00	DEMOLITION AND CIVIL WORKS				
1.01	Carefully remove existing floor finish and gypsum ceiling works including any affected lightings and dispose of all debris off-site in accordance with the building management's rules and regulations, and in compliance with all relevant environmental, health, and safety requirements. Upon removal, making good limited to areas directly impacted by the dismantling works.	1	Item	1,316.00	**1,316.00**
	Please note that any concealed services or unforeseen conditions encountered during removal are not included in our scope of works and will be brought to the client's attention for further instruction.				
				SUB TOTAL DEMOLITION AND CIVIL WORKS :	1,316.00
2.00	PARTITION WORKS				
2.01	**GYPSUM CLADDING - NFR** Supply and installation of **NFR 12.5 mm thick Gypsum board (Knauf or equivalent) curve wall cladding** with necessary material for fixing, smoothened and made ready to receive final finishes. Height up to 2.7 m **Location : To Existing Wall**	36	Sq.m	117.00	**4,212.00**
				SUB TOTAL PARTITION WORKS :	4,212.00
3.00	FLOORING WORKS				
3.01	**SCREED LEVELLING** Leveling of existing screed after removal of existing floor finishes and ready to receive new floor finish. All complete in acordence with the site requirement. **Location : To Tile Finish**	15	Sq.m	73.00	**1,095.00**
3.02	**CERAMIC TILE FLOORING** Supply and installation of Ceramic Tile flooring with grouting including cutting and alignment. As per design and approved sample. Size : 60 x 120 cm PC Rate : 125 AED per Sq.m Location :Dinign Area Note : Subject to sample approval.	15	Sq.m	279.00	**4,185.00**
3.03	**TRANSITION STRIP** Supply and installation of Transition Strip in SS finish (ready available). **Location : Between different floor finishes**	3	Lm	110.00	**330.00**
	Note: All finishes are subject to final sample approval.				
				SUB TOTAL FLOORING WORKS :	5,610.00

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

INTERIOR FIT-OUT WORKS FOR HUSPY @ PRODUCTION CITY, DUBAI-UAE

Quote Ref No: VID/1186/25/CP/QTN_01/R1 — **17-Dec-25**

RECEPTION AREA

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
4.00	**WALL FINISHES**				
4.01	**WALL PAINT** Supply and application of **Jotun Fenomastic Paint Finish (white)** with all cleaning and levelling. Closed Ceiling Height up to 2.7 m Note: Wall paint considered only from the new cladded wall only	51	Sq.m	35.00	**1,785.00**
4.02	**MDF WALL CLADDING** Supply and installation of **plain/slatted MDF wall cladding in wood veneer finish** including necessary fittings and accessories for installation. Height up to 2.7 mm **Location: Reception back wall**	11	Sq.m	808.00	**8,888.00**
4.03	**SKIRTING** Supply and installation of (up to 50 mm high) **MDF skirting in PU paint finish** with necessary fittings and accessories. **Note : Non concealed**	14	Lm	66.00	**924.00**
	Note: 1. All finishes are subject to final sample approval.				
			SUB TOTAL WALL FINISH :		**11,597.00**
5.00	**CEILING WORKS**				
5.01	**PLAIN GYPSUM CEILING** Supply and installation of **Gypsum Board Plain ceiling** (Knauf or equivalent) with necessary hanging systems including wall angle "C "channel, furring channel with 12.5mm gypsum boards joined taped smoothened finish. **Location : As per design**	14	Sq.m	110.00	**1,540.00**
5.02	**ROUND GYPSUM BULKHEAD - COVELIGHT** Supply and installation of 100/200 mm high Gypsum Bulkhead with curve edges 12.5 mm gypsum boards with paint finish.	13	Lm	172.00	**2,236.00**
5.03	**SHADOW GAP** Supply and installation of shadow gap as per the design.	11	LM	37.00	**407.00**
5.04	Huspy **S PANEL** allation of **Gypsum access panel (Max 60 x 60 cm)** with frame and hinges. **Location: Proposed Gypsum ceiling area** Note : Subject to final MEP drawings	1	LS	514.00	**514.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

INTERIOR FIT-OUT WORKS FOR HUSPY @ PRODUCTION CITY, DUBAI-UAE

Quote Ref No: VID/1186/25/CP/QTN_01/R1 — **17-Dec-25**

RECEPTION AREA

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
5.05	**GYPSUM CEILING PAINT** Supply and application of **Jotun Fenomastic WHITE paint** including all cleaning and levelling. As per design and approved sample. (2 coats including sanding).	111	Sq.m	35.00	**3,885.00**
a	*Location : Proposed Gypsum ceiling areas*	*14*	*Sq.m*		
b	*Location : Existing gypsym ceiling from reception to lift area*	*97*	*Sq.m*		
	Note : All finishes are subject to final sample approval.				
				SUB TOTAL CEILING WORKS :	**8,582.00**
6.00	**SIGNAGE WORKS - Provisional Sum**				
6.01	Supply and installatin of 3D signage to read "HUSPY" in 25mmthk embossed aluminium black powder coated finsih complete with backlit **Location: Main Reception** 	1	Nos	7,048.00	**7,048.00**
6.02	Supply and installatin of 3D signage to read "HUSPY" in 25mmthk embossed aluminium black powder coated finsih complete with backlit 	1	Nos	8,811.00	**8,811.00**
6.03	Supply and installation of graphics as per the approved design Approx Size: H1000 x Propotionate Length	1	Nos	1,500.00	**1,500.00**
	Note : 1. Any other signage excluded.				
				SUB TOTAL SIGNAGE WORKS :	**17,359.00**
7.00	**JOINERY WORKS**				
7.01	**RECEPTION DESK** Fabrication, Supply and installation of **Reception counter with MDF in veneer/ PU paint finish** as per design. **Overall Size : 2500 mm x 900 mm x 1100 mm** **Location : Reception** 	1	Item	13,216.00	**13,216.00**
				SUB TOTAL JOINERY WORKS :	**13,216.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR HUSPY @ PRODUCTION CITY, DUBAI-UAE

Quote Ref No: VID/1186/25/CP/QTN_01/R1 — **17-Dec-25**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
	RECEPTION AREA				
8.00	**LIGHTING WORKS**				
	Supply of non - dimmable lights as per verve design **Make : Hegron UK or equivalent**				
8.01	**DECORATIVE LIGHT** Location : Reception Size : 1000 mm Wattage : 5x5W Location: At Reception	1	Nos	2,120.00	**2,120.00**
8.02	**ROUND DOWN LIGHT** Location: To Gypsum ceiling	6	Nos	108.00	**648.00**
	Note : 1. Consider existing Pendant LineaLights are in good conditiona nd to re-use for the Open Ceiling Area 2. Quantity subject to final RCP design and LUX calculations 3. Non dimmable lights				
				SUB TOTAL LIGHT FITTINGS :	**2,768.00**
	MEP WORKS				
	MEP WORKS (PROVISIONAL SUM. SUBJECT TO BUILDING APPROVAL)				
9.00	**HVAC WORKS (PROVISIONAL SUM)**				
9.01	Modification of existing HVAC system including supply and return diffusers, and any ducting works to accomdate the new design. Subject to final design and approval and requirement	1	LS	5,480.00	**5,480.00**
10.00	**ELECTRICAL WORKS (PROVISIONAL SUM)**				
10.01	Allowance to provide electrical points including all requirements for new light fittings, new power point along wall such 1no each of 13A single & double wall powerpoint, 1no floor box, 2nosxSignage powerpoint including cable and conduiting works. Subject to final design and approval	1	LS	8,013.00	**8,013.00**
11.00	**CIVIL DEFENCE WORKS (PROVISIONAL SUM)**				
11.01	Allowance for minor modification of existing sprinkler and emergency light including any affected pipings due to new proposed design.	1	LS	4,551.00	**4,551.00**
				SUB TOTAL HVAC WORKS :	**18,044.00**
				GRAND TOTAL WORKS FOR RECEPTION AREA	**82,704.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

PROJECT NAME: INTERIOR FIT OUT WORKS FOR HUSPY @ PRODUCTION CITY, DUBAI-UAE

PROJECT CODE: 1186_25

Quote Ref No: VID/1186/25/CP/QTN 01/R0

General Notes

1. The price is exclusive of Value Added Tax (VAT); 5% VAT shall be payable as an addition to the invoice value.
2. Any variation in terms of quantity that comes up during the course of work has to be paid by the client and hence client is liable for payment of Variation.
3. Insurance coverage is limited to CAR of Contract Value. If higher coverage limit is required by building management and any other authorities, the additional premium amount will be charged separately
4. LEED building consultancy and certification is excluded.
5. Hoarding, Branding and posters is excluded.
6. Professional indemnity insurance is excluded.
7. Performance & retention bank Bonds not considered.
8. Security deposit, Authority Fees, entry and exit pass for vehicles and labors, night work permit fee, Building/ Mall management fees (If required) has to be paid by the client on actuals
9. Provision for mock up and samples submissions at site as per requirement included, however special items are chargeable and shall be billed to the client on actual.

NOTES & EXCLUSIONS

Internal finishes:

1. All finishes are subject final sample approval.

MEP Works:

1. All MEP works are subject final MEP design and authority approval.
2. Assuming existing cooling capacity is sufficient.
3. Ducting PI; Square or rectangular ducting for any modification required.
4. We have assumed that the existing infrastructure's power has sufficient capacity to cater to the requirement of the project.
5. We have not allowed for upgrading the capacity of any base building system.
6. All electrical conduits considered are of PVC type.
7. We have not allowed for any specific lighting control system in this offer.
8. All terminations considered to the stub out present at site, connected to building system.

Civil Defense works

1. To be claimed on actual based on invoice submitted by AMC contractor (Verve to charge 15% of the value as coordination charges) Verve provided provisional sum.
2. Any additional charges/ fees for any third party shall be paid by the client.
3. FM 200, central battery system works excluded.
4. We have assumed existing Emergency control panel to have sufficient capacity to accommodate the new exit and emergency light. New Emergency control panel excluded from scope.

MEP works – Exclusions

1. BTU Meter, any BMS integration or related works.
2. DEWA Consultancy for power upgrade
3. New DB
4. IT cabling, CCTV camera, Access control, Speakers, Wi-Fi AP, BMS works, Occupancy sensor.

Exclusions

1. Any other items not mentioned in the attached BOQ.
2. Furniture, Workstations, Task Chairs, White Goods, Music System
3. TV, LED Screen, Projector, Kitchen/ Pantry Equipment, Electronic devices.
4. All Artworks, Rugs, Accessories and marketing works.
5. Etisalat/Du works.
6. Planters.

Thank you,

© **Verve Design, 2023**

Verve Interior Decoration llc

Unit M04,
Al Reemas Building,
Sheikh Zayed Road, Al Quoz,
PO Box - 128279,
Dubai, UAE.

t : +971 4 240 0119
f : +971 4 240 8403
info@vervedesign.ae
www.vervedesign.ae