verve

space + design

AMALGAMA OFFICE @ JLT

PROPOSAL FOR INTERIOR FITOUT WORKS

OPTION - 02

INTERIOR FIT-OUT WORKS

FOR

AMALGAMA OFFICE
OPTION - 02

AT

UNIT 3604, JBC 4 ,DUBAI -U.A.E

For
AMALGAMA

Prepared by:
Suvidha Kamath
Verve Interior Decoration LLC
PO Box 128279, Dubai, UAE
Email: suvidha@vervedesign.ae

Prepared on:

December 16, 2024

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

CONTRACT AGREEMENT: General terms and conditions

Project Timeline: As per approved Project schedule

Payment Terms:

Advance Payment : 30% Advance payment against order confirmation.
Progress Payment : 20% upon approval of all the material samples and mobilization of materials to the site
Progress Payment : 45% as per site progress
Final Payment : 5% upon work completion at site and hand over.

Payment to be honored within 7 days from the date of receipt of Invoice

All products offered by us on this project carry a warranty against defective materials and/or workmanship as follows:
Fit Out Works : 12 Months from the date of Handover.

Insurances:
All our personnel working on the project will be covered under our Workmen Compensation
All works carried out at site will be covered by our Contractor's All Risk Policy

Validity.
Our offer is valid for a period of 30 days from hereof
Note: Bank guarantee or Retention Requirements TBC

Please sign below for acceptance of the offer. The BOQ will be treated as the final scope of work and contract will form the integral part of the project.

Signature: _____
on behalf of: AMALGAMA

Name:
Date:

Signature:_____
on behalf of : Verve Interior Decoration LLC

Name: Syed Mehdi
Date: December 16, 2024

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR AMALGAMA OFFICE @ JBC 4 , DUBAI-UAE		
Quote Ref No: VID/1243/24/CP/QTN_01/R0/Opt - 02		16-Dec-24
SR. NO	SUMMARY	TOTAL (AED)
1	PRELIMINARIES	30,000.00
2	DEMOLITION AND CIVIL WORKS	2,000.00
3	PARTITION WORKS	45,065.00
4	FLOOR FINISH	87,230.00
5	WALL FINISH	83,536.00
6	CEILING FINISH	67,902.00
7	DOORS	40,800.00
8	SIGNAGE WORKS - Provisional Sum	0.00
9	JOINERY WORKS	64,085.00
10	LIGHTING WORKS - NON DIMMABLE	56,405.00
11	SANITARY FITTINGS	2,030.00
12	HVAC WORKS	96,475.00
13	ELECTRICAL WORKS	85,275.00
14	CIVIL DEFENCE WORKS	107,900.00
15	IT WORKS	33,895.00
	TOTAL AMOUNT (AED):	802,598.00
16	LOOSE FURNITURE	169,615.00
17	WHITE GOODS	20,025.00
	GRAND TOTAL AMOUNT (AED):	992,238.00

18	ADDITIONAL CHARGES TO REFURBISH THE EXISTING TOILETS	56,054.00

Note: **Any variation in terms of quantity that comes up during the course of work has to be paid by the client and hence client is liable for payment of Variation. Retention is not considered.**

Exclusions:

1) All fees and deposit for statutory authorities.
2) Any other items not mentioned in the attached BOQ.

For Verve Interior Decoration LLC

Syed Mehdi
Sales Director
+971 50 513 9878
syed@vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR AMALGAMA OFFICE @ JBC 4 , DUBAI-UAE

Quote Ref No: VID/1243/24/CP/QTN_01/R0/Opt - 02 **16-Dec-24**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
1.00	**PRELIMINARIES**				
1.01	General- Contractor's preliminaries for mobilization, site preparation, Provision for all temporary barricades, setting out transportations to/from site, material deliveries, small tools and equipment's, protection of finished products in on-going site, site attendance and call out attendance, electricity & water charges including charges for scaffolding. PPE and other site requirements to be followed	1	Item	5,000.00	5,000.00
1.02	Co ordination Charges for obtaining approvals from the Landlord & the related authorities.	1	Item	2,000.00	2,000.00
1.03	Preparation of Technical drawings as required for submission to Relevant authorities. Detail drawings includes Architectural and MEP drawings. Subject to receipt of current approved as built drawings	1	Item	5,700.00	5,700.00
1.04	CAR Insurance for fit out work during the execution of works. (includes third party liability) *Note: Insurance coverage is limited to CAR of Contract Value. If higher coverage limit is required by building management and any other authorities, the additional premium amount will be charged separately* .	1	Item	3,300.00	3,300.00
1.05	Professional indemnity insurance	1	Item	6,000.00	6,000.00
1.06	Regular cleaning of site during construction period and after completion professional deep cleaning and made ready to occupy. Including carting away the debris to Municipal dumping area.	1	Item	2,500.00	2,500.00
1.07	Charges for site protection (protection of common area finishes and the area near to the work space)	1	Item	3,000.00	3,000.00
1.08	Supply and installation of hoarding with relevant branding as per the building regulation . Size : 2100 x 2700 mm	1	Item	2,500.00	2,500.00
1.09	Security deposit (Area > 2000 sq.ft)(to JBC Properties DMCC)	1	Item	25,000.00	By client
1.10	Fee schedules as per Fit-out Manual				
a.	Submission Administration fee (to JBC Management DMCC)	1	Item	500.00	On actual
b.	Technical review fee (to JBC Properties DMCC)	1	Item	1,500.00	On actual
c.	Drawing approval fee (to JBC Properties DMCC)	1	Item	5,000.00	On actual
d.	Electrical consumption in absence of permanent DEWA connection **0.75 AED PER SQ.FT.**	1	Item	2,050.00	On actual
	Note: Security deposit, Authority Fees, entry and exit pass for vehicles and labors, night work permit fee, Mall management fees(If required) has to be paid by the client on actuals				
	Note : Provision for mock up and samples submissions at site as per requirement included, however special items are chargeable and shall be billed to the client on actual.				
				SUB TOTAL PRELIMINARIES :	**30,000.00**
2.00	**DEMOLITION AND CIVIL WORKS**				
2.01	Builders works to accommodate MEP works	1	Ls.	2,000.00	2,000.00
				SUB TOTAL DEMOLITION AND CIVIL WORKS :	**2,000.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR AMALGAMA OFFICE @ JBC 4 , DUBAI-UAE

Quote Ref No: VID/1243/24/CP/QTN_01/R0/Opt - 02 **16-Dec-24**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
3.00	**PARTITION WORKS**				
3.01	**GYPSUM CLADDING - FR 60 min** Supply and installation of **FR 12.5 mm thick Gypsum board (Knauf or equivalent) wall cladding** with necessary material for fixing, smoothened and made ready to receive final finishes. Height up to 2.5 m **Location : To existing walls to receive the sockets (workstation areas only)**	23	Sq.m	115.00	2,645.00
3.02	**GYPSUM PARTITION SINGLE LAYER (NON FR)** Supply and installation of **100mm Thk Non-FR gypsum partition** with 2 x 12.5mm Thk Non-FR gypsum board (Knauf or equivalent) layer on both sides with studs, 50mm thick rockwool insulation and necessary frames and accessories. Height up to 3 m **Location : As per layout**	84	Sq.m	190.00	15,960.00
3.03	**GYPSUM PARTITION SINGLE LAYER (FR)** Supply and installation of **100mm Thk FR gypsum partition** with 2 x 12.5mm Thk FR gypsum board (Knauf or equivalent) layer on both sides with studs, 50mm thick rockwool insulation and necessary frames and accessories. Height up to 3 m **Location : Server room**	18	Sq.m	265.00	4,770.00
3.04	**GLASS PARTITION - NON FR** Supply and installation of **single glazed 40 x 40 mm powder coated aluminum framed single layered partition (around the partitions)** utilizing 12 mm thick glass with all around straight polished edges including glass to glass clear joints. Height up to 2.5 m **Location : All glass partitions inside the unit**	28	Sq.m	585.00	16,380.00
3.05	**GYPSUM BAFFLE (NON-FR)** Supply and installation of **Non-FR gypsum baffle wall** with 12.5mm Thk Non-FR gypsum board (Knauf or equivalent) single layer on both sides with 50mm thick rockwool insulation, necessary frames and accessories . Height up to 2.7 m **Location : Above proposed glass partitions,**	18	LM	145.00	2,610.00
3.06	**Provision for MDF support below proposed glass partitions / raised floor**	18	LM	150.00	2,700.00
				SUB TOTAL PARTITION WORKS :	**45,065.00**
4.00	**FLOOR FINISH**				
4.01	Supply and installation of **Raised access floor FS-800 cementitious** 600 x 600 x 33 mm steel top, steel bottom fully encapsulated bare finish panel with up to 20cm ffh flat pedestal & stringer . **Make : AFT**	238	Sq.m	175.00	41,650.00
4.02	Supply and installation of anti static raised floor (HPL) finish , upto height of 200 mm **Location : Server room**	6	Sq.m	470.00	2,820.00
4.03	**SELF LEVELLING ON RAISED FLOOR** Supply and installation of 2 to 3 mm self levelling compound to make the floor ready to receive the new flooring. **Location : Proposed LVT flooring**	54	Sq.m	105.00	5,670.00

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR AMALGAMA OFFICE @ JBC 4 , DUBAI-UAE

Quote Ref No: VID/1243/24/CP/QTN_01/R0/Opt - 02 — **16-Dec-24**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
4.04	**CP 01 CARPET FLOORING** Supply and Installation of Carpet tile flooring including adhesives and all necessary material for fixing. Make : Tegola or equivalent **Location : Meeting rooms + workstation area + Meeting booth + Cabins** Note : To be installed directly on the raised floor 	166	Sq.m	125.00	20,750.00
4.05	**LV 01 LVT FLOORING** Supply and installation of **Luxury Vinyl Tile flooring** with necessary material for installation. Make : Nox **Location : Corridor, waiting area**	12	Sq.m	175.00	2,100.00
4.06	**LV 02 LVT FLOORING** Supply and installation of **Luxury Vinyl Tile flooring** with necessary material for installation. Make : Amtico **Location : Corridor, waiting area**	42	Sq.m	160.00	6,720.00
4.07	**LV 03 LVT FLOORING** Supply and installation of **Luxury Vinyl Tile flooring** with necessary material for installation. Make : Amtico **Location : 12 PAX meeting room** **Herringbone pattern**	16	Sq.m	250.00	Rate only option
4.07 opt	**CP 01 CARPET FLOORING** Supply and Installation of Carpet tile flooring including adhesives and all necessary material for fixing. Make : Tegola or equivalent **Location : Meeting rooms + workstation area + Meeting booth + Cabins** Note : To be installed directly on the raised floor	16	Sq.m	125.00	2,000.00
4.08	**TRANSITION STRIP** Supply and installation of Transition Strip in SS finish (ready available). **Location : Between different floor finishes, Door entrances.**	48	LM	115.00	5,520.00
	Note: All finishes are subject to final sample approval.				
				SUB TOTAL FLOOR FINISH :	**87,230.00**
5.00	**WALL FINISH**				
5.01	**WALL PAINT** Supply and application of **Jotun Fenomastic Paint Finish (white)** with all cleaning and levelling. Height up to 2.5 m	262	Sq.m	33.00	8,646.00
5.02	**TRAVERTINE LOOK WALL CLADDING** **Location : Reception**				
a	**WALL TILE** Supply and installation of wall tiles including necessary materials for fixing. Height upto 2.5 m PC Rate : 350 AED per Sq.m Size : 120 x 280 cm - cut to size 100 x 240 cm due to the capacity of the service lift **Note : Only 3 tiles considered**	11	Sq.m	685.00	Rate only option

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR AMALGAMA OFFICE @ JBC 4 , DUBAI-UAE

Quote Ref No: VID/1243/24/CP/QTN_01/R0/Opt - 02 **16-Dec-24**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
5.02 opt	Supply and installation of textured paint as per the requirement including the wall preparations and all required base coats . Make : MAS Height : 2500 mm	11	Sq.m	225.00	2,475.00
5.03	**FABRIC / PET PANEL WALL CLADDING** Supply and installation of **fabric / pet wall cladding** including necessary materials for installation. Height up to 2.5 m **Location : Meeting room + Meeting booth**	25	Sq.m	530.00	13,250.00
5.04	**MDF WALL CLADDING - type 1** Supply and installation of **plain MDF wall cladding in wood veneer finish** including necessary fittings and accessories for installation. Height up to 2.5 mm	15	Sq.m	680.00	10,200.00
5.05	**MDF WALL CLADDING - type 2** Supply and installation of **slatted MDF wall cladding in wood veneer finish** including necessary fittings and accessories for installation. Height up to 2.5 mm	25	Sq.m	985.00	24,625.00
5.06	**BACK PAINTED GLASS** Supply and installation of back painted glass including necessary fittings and accessories for installation. Height up to 1.5 mm	6	Sq.m	680.00	4,080.00
5.07	**SKIRTING** Supply and installation of (up to 50 mm high) **MDF skirting in PU paint finish** with necessary fittings and accessories. **Note : Non concealed**	117	LM	60.00	7,020.00
5.08	**FROSTED STICKER** Supply and installation of gradient effect Frosted sticker . Height upto 1500 mm **Location : All glass partition and doors**	23	Sq.m	225.00	Rate only option
5.08 opt 1	Supply and installation of fluted effect sticker as per the design. **Location : All glass partitions and doors .** **Height : 2500 mm**	38	Sq.m	755.00	Rate only option
5.08 opt 2	Supply and installation of plain Frosted sticker . Height upto 1500 mm Location : All glass partition and doors	23	Sq.m	110.00	2,530.00
5.09	**ROLLER BLINDS - MANUAL** Supply and installation of **sunscreen blinds** Height upto 2.5m **Location : External glazing**	119	Sq.m	90.00	10,710.00
5.09.a	**Additional charges for motorized curtains for the 12 PAX meeting room .**				
i	**Motors** **Make : Somfy**	5	Nos.	1,440.00	Rate only option
ii	**16 channel remote control**	1	Nos.	610.00	Rate only option
	Note: 1. All finishes are subject to final sample approval.				
				SUB TOTAL WALL FINISH :	**83,536.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR AMALGAMA OFFICE @ JBC 4 , DUBAI-UAE

Quote Ref No: VID/1243/24/CP/QTN_01/R0/Opt - 02 **16-Dec-24**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
6.00	**CEILING FINISH**				
6.01	**PLAIN GYPSUM CEILING** Supply and installation of **Gypsum Board Plain ceiling** (Knauf or equivalent) with necessary hanging systems including wall angle "C "channel, furring channel with 12.5mm gypsum boards joined taped smoothened finish. **Location : All areas**	148	Sq.m	115.00	17,020.00
6.02	**PLAIN GYPSUM CEILING - FR** Supply and installation of **FR Gypsum Board Plain ceiling** (Knauf or equivalent) with necessary hanging systems including wall angle "C "channel, furring channel with 12.5mm gypsum boards joined taped smoothened finish. **Location : Server room**	6	Sq.m	140.00	840.00
6.03	**GYPSUM CEILING PAINT** Supply and application of **Jotun Fenomastic WHITE paint** including all cleaning and levelling. As per design and approved sample. (2 coats including sanding). **Location : Proposed Gypsum ceiling areas**	154	Sq.m	33.00	5,082.00
6.04	Supply and installation of 600 x 1200 x 19 mm acoustic tiles including all the necessary fixing materials . **Make : AMF thermatex** Location : Workstation area + MD cabin	90	Sq.m	175.00	15,750.00
6.05	**GYPSUM BULKHEAD - COVE LIGHT** Supply and installation of 100 mm high Gypsum Bulkhead for cove with 12.5 mm gypsum boards with paint finish.	21	Sq.m	145.00	3,045.00
6.06	**GYPSUM BULKHEAD - U BULKHEAD** Supply and installation of 100 mm high Gypsum Bulkhead with 12.5 mm gypsum boards with black paint finish.	59	Sq.m	155.00	9,145.00
6.07	**GYPSUM BULKHEAD** Supply and installation of 100 mm high Gypsum Bulkhead with 12.5 mm gypsum boards with paint finish.	26	Sq.m	135.00	3,510.00
6.08	**GYPSUM PELMET** Supply and installation of **Gypsum Pelmet** with necessary fittings with paint finish. Height up to 150 mm **Location : For blinds**	44	LM	150.00	6,600.00
6.09	**SHADOW GAP** Supply and installation of shadow gap as per the design.	115	LM	40.00	4,600.00
6.10	**GYPSUM ACCESS PANEL** Supply and installation of **Gypsum access panel (Max 60 x 60 cm)** with frame and hinges. **Location: Proposed Gypsum ceiling area** Note : Subject to final MEP drawings	7	Nos.	330.00	2,310.00
	Note : All finishes are subject to final sample approval.				
				SUB TOTAL CEILING FINISH :	**67,902.00**
7.00	**DOORS**				
7.01	**ACOUSTIC GLASS DOOR - NON FR** Supply and installation of **12 mm thick glass single leaf frameless glass doors** with all around straight polished edges fixing by OFFSET pivot hinges , bottom lock and 1000 mm long H type straight round handle including all around 50 mm wide overlapped UNICA door frame. Note: All fittings are in powder coating or SS finish. Size: L 900 mm X H 2500 mm **Location : Meeting rooms, closed cabins**	5	Nos	5,640.00	28,200.00

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR AMALGAMA OFFICE @ JBC 4 , DUBAI-UAE

Quote Ref No: VID/1243/24/CP/QTN_01/R0/Opt - 02 — **16-Dec-24**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
7.02	**ACOUSTIC GLASS DOOR - NON FR** Supply and installation of 12 mm thick glass single leaf frameless glass doors with all around straight polished edges fixing by OFFSET pivot hinges , bottom lock and 1000mm long H type straight round handle including all around 50 mm wide overlapped UNICA door frame. Note: All fittings are in powder coating or SS finish. Size: L 750 mm X H 2500 mm **Location : Meeting booth**	1	Nos	5,600.00	5,600.00
7.03	Provision to wrap the existing main double leaf entrance door (Only on the internal side) , including the frames . Note : Subject to building management approval	1	Nos	1,305.00	Rate only Option
7.04	**SINGLE LEAF WOODEN DOOR - FR 60 min** Supply and installation of Semi solid Timber swing door in veneer finish, with Frame, architrave, in PU paint finish with all necessary ironmongery and material for fixing. Size: 910 x 2500mm Ht **Location : Server room** **Note : Concealed door**	1	Nos	7,000.00	7,000.00
				SUB TOTAL DOORS :	**40,800.00**
8.00	**SIGNAGE WORKS - Provisional Sum**				
8.01	Supply and installation of aluminum 3D painted back lit signage as per the design. Size: L 1800 x H 600 mm **Location : Reception** Note : Subject to final design and sample approval.	1	Item	8,400.00	Rate only Excluded
	Note : 1. Any other signage excluded. 2. Signages in other units - By respective tenants				
				SUB TOTAL SIGNAGE WORKS :	**-**
9.00	**JOINERY WORKS**				
9.01	**RECEPTION DESK** Fabrication, Supply and installation of **Reception counter with MDF in veneer/ PU paint finish** as per design with marble fascia ((1960 + 1255) mm x 900 mm) . **Marble PC Rate : 350/-** **Overall Size : 2850 mm x 900 mm x 1100 mm** **Location : Reception** **Note : Marble changed to textured paint**	1	Item	10,200.00	10,200.00
9.02	**PANTRY UNIT** Fabrication, supply and installation of Wet pantry counter with **MR MDF Unit in veneer finish** with **2cm Marble counter top** and cabinets as below with all necessary for fixing. Including the back splash on 2 sides . **Location : Pantry area** Note : Backsplash included **Marble PC Rate : 350 / -per sq.m.**	1	Item	12,400.00	12,400.00

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR AMALGAMA OFFICE @ JBC 4 , DUBAI-UAE

Quote Ref No: VID/1243/24/CP/QTN_01/R0/Opt - 02 **16-Dec-24**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
9.03	**PRINTER CABINET** Fabrication, supply and installation of Printer cabinet with MDF in veneer finish (over head cabinet and storage counter top) and cabin (in PU painted shutters) as below with all necessary for fixing. **Lower cabinet size : 2950 x 600 x 1100 mm** **Upper cabinet size : 2950 x 500 x 600 mm** 	1	Item	8,540.00	8,540.00
9.04	**DISPLAY WALL** Fabrication, supply and installation of display wall with wooden cladding and open shelves made with MDF in wood veneer/ PU paint finish including necessary materials for installation. **Location : Reception** **Size : 1900 x 2500 mm** 	1	Item	10,000.00	10,000.00
9.05	**BAR TABLE** Fabrication, supply and installation of wall mounted bar table MDF in wood veneer finish including necessary materials for installation. Size : : L 2000 x D 400 x H 40 mm **Location : Pantry area** **Note : Price includes the leg support metal bar made with aluminum in powder coated finish .**	1	Item	6,300.00	6,300.00
9.06.a	**CONSOLE UNIT WITH PLANTER BOX** Fabrication, supply and installation of Storage cabinet made with MDF in veneer/ PU paint finish, with planter box including waterproofing on top necessary materials for installation. **Location : Open workstation area**	1	Item	10,780.00	10,780.00
9.06.b	Plants including soil, gravel, pebbles, etc - **Provisional sum**	1	Item	1,800.00	1,800.00
9.07	Modification to the existing wet pantry counter (Replace the counter top to marble to accommodate new sink and mixer , Marble PC Rate : 350/- , including wrapping the existing shutters with vinyl (subject to sample approval)	1	Item	2,735.00	2,735.00
9.08	Supply and installation of bracket made with PU painted MDF finish , to hold the markers and erasers on the back painted glass . Location : 12 PAX meeting room	1	Item	1,330.00	1,330.00
				SUB TOTAL JOINERY WORKS :	**64,085.00**
10.00	**LIGHTING WORKS - NON DIMMABLE**				
	Supply of the following lights				
10.01	**DECORATIVE LIGHT** **Location : Reception** **Size : 1500 mm** **Wattage : 3 x 12 W**	1	Nos	4,340.00	4,340.00

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR AMALGAMA OFFICE @ JBC 4 , DUBAI-UAE

Quote Ref No: VID/1243/24/CP/QTN_01/R0/Opt - 02 **16-Dec-24**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
10.02	**DECORATIVE WALL LIGHT** **Location : Reception waiting area** **Dia : 200 mm** **Wattage : 5 W** 	1	Nos	590.00	590.00
10.03	**DECORATIVE LIGHT** **Location : Meeting rooms + MD cabin** **Dia : 380 mm** **Wattage : 10W** 	4	Nos	275.00	1,100.00
10.04.a	**MAGNETIC TRACK** **Size : 1000 mm** **Location : Meeting rooms + workstation area + MD cabin** 	60	LM	260.00	15,600.00
10.04.b	**MAGNETIC TRACK LIGHT** **Wattage : 3 x 2 W** **Size : 106 x 35 x 59 mm** **Location : Meeting rooms + workstation area + MD cabin** 	42	Nos	170.00	7,140.00
10.05	**PENDANT LIGHT** **Finish : Black** **Location : Pantry** **Dia : 200 mm , 10 W** 	3	Nos	380.00	1,140.00
10.06	**RECESSED LINEAR LIGHT** **L 5000 mm** **Location : Workstation areas** **Wattage : 40/ m** 	6	Nos	1,575.00	9,450.00
10.07	**RECESSED LINEAR LIGHT** **L 4000 mm** **Location : MD cabin** **Wattage : 40/ m** 	3	Nos	1,260.00	3,780.00
10.08	**DECORATIVE LIGHT - 1** **Dia : 250 mm** **Location : Meeting booth** **Wattage : 12 W x 3** 	1	Set	985.00	985.00
10.09	**DECORATIVE LIGHT - 2** **Location : Closed cabins** 	2	Nos	1,110.00	2,220.00

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR AMALGAMA OFFICE @ JBC 4 , DUBAI-UAE

Quote Ref No: VID/1243/24/CP/QTN_01/R0/Opt - 02 **16-Dec-24**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
10.10	**SPOT LIGHT - 11 W**	71	Nos	85.00	6,035.00
10.11	**LED STRIP LIGHT including driver** **Make : Osram**	35	LM	115.00	4,025.00
	Note : 1. Quantity subject to final RCP design and LUX calculations 2. Non dimmable lights				
				SUB TOTAL LIGHTS :	**56,405.00**
11.00	**SANITARY FITTINGS**				
11.01	**PANTRY SINK + Bottle trap + Waste** Undermounted Single Bowl Sink Size : 380 x 440 x 190 mm **Supply and installation**	1	Nos	1,285.00	1,285.00
11.02	**PANTRY SINK MIXER + Angle valve** Single Hole Kitchen Sink Mixer **Supply and installation**	1	Nos	745.00	745.00
				SUB TOTAL SANITARY FITTINGS :	**2,030.00**
	MEP WORKS				
12.00	**HVAC WORKS**				
	<u>AC MACHINES AND ACCESSORIES</u>				
12.01	Supply of 4 TR DX unit for additional cooling as per the heat load requirement . Make : Carrier (inverter)	1	Nos	8,330.00	8,330.00
12.02	Installation of DX unit including refrigerant piping and control wiring between the indoor and outdoor unit .	1	Nos	4,160.00	4,160.00
12.03	Supply and installation of new thermostat for new DX unit and to replace existing thermostat.	4	Nos	680.00	2,720.00
12.04	Relocation of existing FCU including the chilled water piping works . Location : Proposed 12 PAX meeting room + MD room - relocated to the open areas	2	Nos.	2,955.00	Rate only
12.05	Supply and installation of new VAV including the thermostat as per the requirement . Location : Cabins 1 & 2 + MD cabin Note : Excluded for the meeting rooms	3	Nos.	4,015.00	12,045.00
	<u>DUCTING AND ACCESSORIES</u>				
12.06	Supply and installation of new GI / Phenolic ducting including all the accessories VCD , etc.	1	Item	33,330.00	33,330.00
12.07	Supply and installation of inline ducted fan including the ducting and related accessories . Location : New Pantry Note : To retain existing extract ducting in the existing toilets and pantry	1	Item	1,810.00	1,810.00

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR AMALGAMA OFFICE @ JBC 4 , DUBAI-UAE

Quote Ref No: VID/1243/24/CP/QTN_01/R0/Opt - 02 **16-Dec-24**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
12.08	Extension of duct for the fresh and extract air using GI / phenolic ducting Note : Stub out present at site	1	Item	13,630.00	13,630.00
12.09	Chemical flushing - Culligan considered	1	Item	6,660.00	Rate only
12.10	Supply and installation of cross talk attenuators in the meeting rooms and the cabins	5	set	985.00	4,925.00
	GRILLS AND DIFFUSER				
12.10	Linear Slot grills (3-Slot)	1	Item	9,090.00	9,090.00
	DRAIN PIPE				
12.11	Supply and Installation of **PVC Pipe** with insulation. - connecting to the existing line	1	Item	1,135.00	1,135.00
12.12	Testing and commissioning with air balancing (Verve)	1	Item	2,270.00	2,270.00
12.13	Third party testing with air balancing works	1	Item	3,030.00	3,030.00
	Notes : 1. BTU Meter works and BMS Connection / cabling/ wiring excluded 2. Considered to install the outdoor machine in the balcony , subject to building management approval . 3. Performance testing of existing FCU machines				
				SUB TOTAL HVAC WORKS :	**96,475.00**
13.00	**ELECTRICAL WORKS**				
13.01	PVC conduiting and wiring for light points including installation. Note: Light points are subject to revise upon final RCP Layout.	122	Nos	220.00	26,840.00
13.02	Supply and installation of **Single switches for lighting.** Including cabling works.(MK-Normal White)	14	Nos	275.00	3,850.00
13.03	Supply and installation of **Grid switch for lighting.** Including **PVC conduiting**. (Black Matt PVC finish Legrand / schneider) for Open workstation & corridor.	1	Nos	275.00	275.00
13.04	Supply and installation of **13A Single wall Power Socket,** in PVC finish including conduiting and wiring. (Schneider / Legrand)	22	Nos	335.00	7,370.00
13.05	Supply and installation of **13A Twin wall Power Socket,** in black PVC finish including conduiting and wiring. (Schneider / Legrand)	10	Nos	360.00	3,600.00
13.06	Supply and installation of **15A Single wall Power Socket,** in Black PVC finish including conduiting and wiring. (Schneider / Legrand)	2	Nos	495.00	990.00
13.07	Supply and installation of **Floor Box -Twin 13A+ Twin Data.** with cabling and conduiting and data and telephone plates provision only. Make : Obo or equivalent	18	Nos	680.00	12,240.00
13.08	Supply and installation of **20A SP isolator power for the DX unit (indoor and outdoor machines)**	2	Nos	835.00	1,670.00
13.09	Supply and installation of DP switch for the new VAV	3	Nos	530.00	1,590.00
13.10	**50mm conduit** and cabling provision for **HDMI/VGI including the connections for the conferencing systems**	4	Nos.	615.00	2,460.00
13.11	Supply and installation of **PVC** containment for **WI-FI Points**. (Provisional qty)	3	Nos.	190.00	570.00
13.12	Supply and installation of PVC containment for **Access control** (Provisional qty)	1	Nos	190.00	190.00
13.13	Supply and installation of **PVC** containment for **CCTV Points**. (Provisional qty)	3	Nos.	190.00	Rate only Option
13.14	Supply and installation of **PVC** containment for speakers system . (Provisional qty)	3	Nos.	190.00	Rate only Option
13.15	Supply and installation of **PVC** containment for printers.	2	Nos.	190.00	380.00
13.14	Supply and installation of **PVC** containment for **AV Rack**	1	Nos.	190.00	190.00
13.15	Supply and installation of **PVC** containment for thermostat (new DX machine + new VAV + replacement of existing thermostat)	7	Nos.	190.00	1,330.00

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR AMALGAMA OFFICE @ JBC 4 , DUBAI-UAE

Quote Ref No: VID/1243/24/CP/QTN_01/R0/Opt - 02 **16-Dec-24**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
13.16	Power provision for **Signage** with timer switch Note : Signage not considered for unit 2 and 3	1	Nos.	985.00	985.00
13.17	Modification of existing **DB** with all other accessories as per DEWA standards Note : Subject to load availability	1	Item	2,275.00	2,275.00
13.18	Supply & Installation of 150mm GI Cable Tray with necessary fittings & supports -For IT, AV, Light, Power	1	Lot	10,900.00	10,900.00
13.19	DEWA submission, inspection and approval. - 1 submission considered	1	No	5,300.00	5,300.00
13.20	Testing commissioning.	1	Item	2,270.00	2,270.00
13.21	Providing **PVC conduit for Data/Voice for workstations and cabins** Note : Not considered for workstations	53	Nos	190.00	Rate only
	Note: 1. We have assumed that the existing infrastructure's power has sufficient capacity to cater to the requirement of the project. 2. We have not allowed for upgrade of the capacity of any base building system. 3. All electrical conduits considered are of PVC type. 4. We have not allowed for any specific lighting control system in this offer. 5. Subject to final MEP drawings 6. We have assumed only 1 DB with single bill for the main tenant only , we have not considered 3 separate DB for the 3 units **Exclusions:** 1. Any BMS integration or related works. 2. DEWA Consultancy for power upgrade.				
				SUB TOTAL ELECTRICAL WORKS :	**85,275.00**
14.00	**CIVIL DEFENCE WORKS**				
14.01	**FIRE ALARM WORKS**				
a	Supply & Installation of Fire Alarm Addressable Control Panel 1 Loop With Battery	1	Nos.		
b	Supply and installation of smoke detector with base	11	Nos.		
c	Relocation of existing smoke detector	3	Nos.		
d	Relocation of existing smoke detector with sounder base	1	Nos.		
e	Supply and installation of heat detector with base	1	Nos.		
f	Supply of break glass unit with back box	3	Nos.		
g	Supply of sounder unit	4	Nos.		
h	Supply of interface modules	5	Nos.		
i	Programming , Testing & Commissioning	1	Item		
j	Supply Certificate, Installation Certificate, Warranty Certificate	1	Item		
14.02	**FIRE FIGHTING WORKS**				
a	Supply & installation of new sprinkler with pipes & accessories including upright	6	Nos	LS	107,900.00
b	Relocation of existing sprinklers with pipes & accessories	25	Nos		
c	Supply & installation of fire extinguisher set (4KG CO2 + 5 KG DCP)	4	Set		
d	Pressure test	1	Item		
e	Draining & recharging of FFS	1	Item		
f	Certification charges	1	Item		
g	Supply and installation of automatic fire extinguisher **(FM 200 excluded as the area is less than 9 sq.m.)**	1	Item		
14.03	**EMERGENCY WORKS**				
a	Supply and installation of Emergency Light (Self contained)	13	Nos.		

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR AMALGAMA OFFICE @ JBC 4 , DUBAI-UAE

Quote Ref No: VID/1243/24/CP/QTN_01/R0/Opt - 02 **16-Dec-24**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
b	Supply and installation of existing exit light	4	Nos.		
c	DCD Certificates Fire Proof Cable 1.5 Sqmm Accessories Device Installation	1	Item		
	Notes / Exclusions: 1. Any additional charges/ fees for any third party shall be paid by the client. 3. Assumed existing sprinkler heads are as per the DCD standards 4. FM 200 , central battery system works excluded 5.**Rates subject to base build contractor , Verve to charge 15% coordination charge on actual quote submitted by Base build contractor. Verve provided provisional sum**				
		SUB TOTAL CIVIL DEFENCE WORKS :			**107,900.00**
15.00	**IT WORKS**				
	STRUCTURED CABLING WORKS - D Link				
15.01	Supply and Installation of Cat 6 Cable , include cable pulling ,termination both end with Keystone , Face Plate and labeling (For User)	53	Nos.	29,920.00	Rate only (option)
15.02	Supply of Cat 6 Patch Code 2 M	53	Nos.		
15.03	Supply of Cat 6 Patch Code 3 M	53	Nos.		
15.04	Supply of 24P Patch Panel	3	Nos.		
15.05	Supply of Cable Manager	3	Nos.		
15.06	Supply of 6 Way PDU	3	Nos.		
15.07	Supply of 42U Cabinet 800X1000	1	Nos.		
15.08	Supply DGS-F1500-52MP- D-Link	3	Nos.		
15.09	Supply and Installation of Cat 6 Cable , include cable pulling ,termination both end with Keystone , Face Plate and labeling	6	Nos.	305.00	1,830.00
	Note : Data points for workstations provided as option				
	FIBRE OPTIC CABLE				
15.09	FOC Cable 4 Core - in Meter	5	Nos.	LS	3,110.00
15.10	Fiber Pulling	1	Nos.		
15.11	FOC Pigtail	2	Nos.		
15.12	Supply and Installation of Cat 6 Cable , include cable pulling ,termination both end with Keystone , Face Plate and labeling	2	Nos.		
15.13	FOC Adaptor	4	Nos.		
15.14	FOC Splicing Both End	1	Nos.		
	CCTV WORKS				
15.15	Supply of 8 CH NVR-POE Built	1	Nos.	1,274.00	Rate only (option)
15.16	Supply of 4MP Dome Camera	2	Nos.	276.00	
15.17	Supply of 8 TB HDD	1	Nos.	1,166.00	
15.18	Supply of 22" Monitor	1	Nos.	379.00	
15.18	Supply and Installation Cat 6 Cable	2	Nos.	302.00	
15.19	Supply of PVC Bk Box	2	Nos.	26.00	
15.20	Supply of Camera Pole	2	Nos.	189.00	
15.21	Camera Installation and Focusing	2	Nos.	77.00	
15.22	NVR Installation and IP Configuration	1	Nos.	1,212.00	

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR AMALGAMA OFFICE @ JBC 4 , DUBAI-UAE

Quote Ref No: VID/1243/24/CP/QTN_01/R0/Opt - 02 **16-Dec-24**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
15.23	Supply of Mounting Bracket and HDMI Cable	1	Nos.	235.00	
	SPEAKERS				
15.24	Ceiling speakers (set of 2) Make : BOSE	2	sets	1,274.00	Rate only (option)
15.25	Zone amplifier	1	Nos.	8,285.00	
15.26	Control center	2	Nos.	491.00	
15.27	Supply of pre mixer	1	Nos.	982.00	
15.28	Supply of Cable	1	Nos.	1,514.00	
15.29	Cable pulling	1	Nos.	1,514.00	
15.30	Speaker fixing	4	Nos.	77.00	
15.31	AMP installation and commissioning	1	Nos.	1,212.00	
15.32	Supply of Mounting Bracket and HDMI Cable	1	Nos.	225.00	
	ACCESS CONTROL WORKS				
15.33	Supply of ZK Biopro SA40 with Wi-Fi	1	Nos.	LS	7,380.00
15.34	Supply of LZ Bracket	1	Nos.		
15.35	Supply of Magnetic	1	Nos.		
15.36	Supply of Non Touch Exit Button	1	Nos.		
15.37	Remote Key	1	Nos.		
15.38	ZK Biotime 9.5 software devices: 5, users: 1000	1	Nos.		
15.39	Supply of RFID Card	25	Nos.		
15.40	Supply and Installation Cat 6 Cable from Bio to Switch ,for Three Bio +Intercom Door lock to Bio etc	1	LS		
15.41	Installation and Commissioning	1	Nos.		
	ACCESS POINT				
15.42	Supply of Unifi - U7	3	Nos.	LS	6,265.00
15.43	Supply and Installation Cat 6 Cable	3	Nos.		
15.44	WAP Installation	3	Nos.		
15.45	Configuration and Commissioning	1	Nos.		
	POLYCOM Note : Considered only for the 12 PAX meeting room				
15.46	Polycom Studio- 842D4AA#ABU - Audio/Video USB Soundbar with 4K Camera- 7200-85830-102	1	Nos.	LS	15,310.00
15.47	Poly Studio X50/X52/X70/USB Table Microphone 875M6AA	1	Nos.		
15.48	Beelink SEi12 Mini PC, 12th Gen Intel® Core™ i5 Processors 12450H, 16GB+500GB SSD, Navy blue, 8 core up to 4.40 Ghz,Intel® UHD Graphics,	1	Nos.		
15.49	HDMI Cable 10M	2	Nos.		
15.50	Configuration and Commissioning	1	Nos.		
15.51	Device , TV and HDMI Cable Installation	2	Nos.		
	Note : 1. Etisalat/ DU works, Occupancy sensor excluded 2. UPS excluded				
				SUB TOTAL IT WORKS :	**33,895.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR AMALGAMA OFFICE @ JBC 4 , DUBAI-UAE

Quote Ref No: VID/1243/24/CP/QTN_01/R0/Opt - 02 — **December 16, 2024**

SR.NO	SAMPLE IMAGE	DESCRIPTION	QTY	UNIT	RATE	TOTAL (AED)
16.00	**LOOSE FURNITURE**					
16.01		**WORKSTATION (NORMAL)** Description: WORKSTATION TABLE TOP: 18mm thick MDF melamine finish table top. UNDERSTRUCTURE: Metal powder-coated O Series Leg with powder-coated beams to support the tabletop. WIRE MANAGEMENT: Flip up on the tabletop side for wire management FRONT SCREEN : 18 (9+9)mm Fabric hardboard				
a.1		**6 PAX FACE TO FACE (NORMAL)** **Each Desk - 1400mm(W) * 700mm(D) * 750mm(H)**	2	No.	9,090.00	18,180.00
a.2		**4 PAX FACE TO FACE (NORMAL)** **Each Desk - 1400mm(W) * 700mm(D) * 750mm(H)**	2	Nos.	6,140.00	12,280.00
a.3		**MOBILE PEDESTAL** **Description:** **3 Drawers Metal mobile pedestal with key-lock is included.**	22	No.		Included
a.4		**PDU + cable management (cable snakes)** **Note : Excluded for the reception counter**	20	No.	685.00	13,700.00
16.02		**L SHAPE EXECUTIVE DESK WITH RETURN**				
a		**L SHAPE EXECUTIVE DESK WITH RETURN (NORMAL)** **Description:** **Tabletop:** 18mm MFC. **Base frame and legs:** Powder coated aluminum. **Glides:** Height adjustable plastic pingo glides. **Cable management:** Table grommet, cable tray, socket box and vertebra are included. Side cabinet included. **Dimension:** **W 2000 x D 1850 x H 720 mm**	2	No.	3,210.00	6,420.00
b		**L SHAPE EXECUTIVE DESK WITH RETURN (NORMAL)** **Description:** **Tabletop:** 18mm MFC. **Base frame and legs:** Powder coated aluminum. **Glides:** Height adjustable plastic pingo glides. **Cable management:** Table grommet, cable tray, socket box and vertebra are included. Side cabinet included. **Dimension:** **W 2000 x D 1850 x H 720 mm** **Location : MD cabin**	1	No.	5,100.00	5,100.00
c		**PDU + cable management**	3	No.	685.00	2,055.00

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR AMALGAMA OFFICE @ JBC 4 , DUBAI-UAE

Quote Ref No: VID/1243/24/CP/QTN_01/R0/Opt - 02 — **December 16, 2024**

SR.NO	SAMPLE IMAGE	DESCRIPTION	QTY	UNIT	RATE	TOTAL (AED)
16.03		**EXECUTIVE CHAIR** Finish: Black nylon and chrome frame with chrome aluminum alloy support, Arms: Adjustable armrest with PU leather pad Back & Seat: Half leather back with and half leather seat. Headrest: Half leather headrest Mechanism: Italy DONATI STG automatically tension control system with Four-Position locking and sliding function Cylinder: High quality gas-lift Base: Aluminum alloy Five-Star base with PA castors. 3-year warranty Make : Sunon	3	No.	3,135.00	Rate only Optional
16.03 opt		**EXECUTIVE CHAIR** Seat cushion with Dark Grey fabric upholstery (MA) Black PP frame with adjustable soft lumbar support Advanced synchro-tilting (AST) mechanism for smooth movement Recline lockable in 3 positions Adjustable headrest with cushion in matching mesh 3D-adjustable armrest with PU armpads Black nylon frame and star base Reinforced nylon castors for easy mobility Dimensions: 670 x 700, H1170mm 5-year warranty Make : Kano / Bafco	3	No.	1,430.00	4,290.00
16.04		**VISITOR CHAIR** Arm Chair in Leather with Polished four-star foot + PVC wheel Finish: EPU	6	No.	1,890.00	Rate only Optional
16.04 opt		**VISITOR CHAIR** Matte PP plastic body and seat in Black, White, Red or Green Chrome electroplated 5-star Base 5-year warranty Make : Kano / Bafco	6	No.	700.00	4,200.00
16.05		**TASK CHAIR** Back: black back frame (Swing Function); Armrest: black adjustable armrest(2D up and down/armrest rotation); Mechanism: STG with 4 position locking; Base: black nylon five-star base with black PA castors.	22	No.	1,200.00	Rate only Optional
16.05 opt		**TASK CHAIR** Make : Kano / Bafco Warranty - 3 years	20	No.	975.00	19,500.00

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR AMALGAMA OFFICE @ JBC 4 , DUBAI-UAE

Quote Ref No: VID/1243/24/CP/QTN_01/R0/Opt - 02 — **December 16, 2024**

SR.NO	SAMPLE IMAGE	DESCRIPTION	QTY	UNIT	RATE	TOTAL (AED)
16.06		**2 SEATER SOFA** **Description:** Custom made. Structure in wood and plywood. Fully upholstered in fabric. **Dimension: 1620 x 800 x 480 mm**	1	No.	5,115.00	5,115.00
16.07		**LOUNGE CHAIR (WAITING AREA)** **Description:** Custom made.Frame and legs in beech wood. Back and seat upholstered in fabric. **Dimension: W 600 x D 700 x H 650 mm**	4	No.	2,980.00	Rate only Optional
16.07 opt		**LOUNGE CHAIR (WAITING AREA)** Steel reinforced internal molded foam frame Class-3 height adjustable gas lift Pivoting Aluminum Alloy 4-spoke base Fully upholstered curving armrest 5-year warranty Make : Kano / Bafco	4	No.	2,100.00	8,400.00
16.08		**ARM CHAIR** **Description:** Custom made.Frame and legs in beech wood. Back and seat upholstered in fabric. **Location : MD room**	1	No.	3,890.00	Rate only Optional
16.08 opt		**ARM CHAIR** **Description:** Leather lounge chair **Location : MD room**	1	No.	2,285.00	2,285.00
16.09		**COFFEE TABLE** Dia : 500 x 600 mm	2	No.	560.00	1,120.00
16.10		**COFFEE TABLE** **Description:** Custom made.Base and top in glass. **Dimension: Dia 600 x H 450 mm**	1	No.	2,450.00	2,450.00
16.11		**COFFEE TABLE** **Description:** Custom made.Base and top in glass. **Dimension: Dia 800 x H 450 mm**	1	No.	3,060.00	3,060.00
16.12.a		**MEETING TABLE - 1** **Dimension: W 3500 x D 1200 x H 740 mm** **Custom**	1	No.	13,890.00	13,890.00

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR AMALGAMA OFFICE @ JBC 4 , DUBAI-UAE

Quote Ref No: VID/1243/24/CP/QTN_01/R0/Opt - 02 — December 16, 2024

SR.NO	SAMPLE IMAGE	DESCRIPTION	QTY	UNIT	RATE	TOTAL (AED)
16.12.b		**MEETING TABLE - 2** **Dimension: W 1200 x D 1200 x H 750 mm**	1	No.	2,465.00	2,465.00
16.12.c		**PDU + cable management**	3	No.	685.00	2,055.00
16.13		**MEETING CHAIR**	16	No.	1,120.00	Rate only Optional
16.13 opt		**MEETING CHAIR**	16	No.	605.00	9,680.00
16.14		**POUF** **Size : 430 x 360 x 460 mm** **Fabric / PU**	3	No.	800.00	2,400.00
16.15		**BAR STOOL** Sofa Seat & Back in Fabric Finish with MetalLeg [white, black, pale pinkish grey, pea green, coral]. Dim: 520*560*1080*770 Ht mm. Finish: Fabric.	3	No.	1,235.00	3,705.00
16.16		**STORAGE WITH PLANTERBOX** **Size : 1500 x 350 x 1220 mm** **Note : Considered for artificial plants**	4	No.	2,230.00	8,920.00
16.17		**STORAGE** **Size : 2000 x 400 x 1150 mm**	3	No.	1,755.00	5,265.00

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR AMALGAMA OFFICE @ JBC 4 , DUBAI-UAE						
Quote Ref No: VID/1243/24/CP/QTN_01/R0/Opt - 02						December 16, 2024
SR.NO	SAMPLE IMAGE	DESCRIPTION	QTY	UNIT	RATE	TOTAL (AED)
16.18		**MEETING BOOTH TABLE** **Custom made : Size : 1050 mm x 820 mm x 750 mm**	1	No.	3,200.00	3,200.00
16.19		**MEETING BOOTH SEATING** **Custom made : Size : 1650 mm x 600 mm**	2	No.	4,940.00	9,880.00
	Lead time	**12 - 14 weeks**				
	Note : Images are for indicative purposes , actual product may vary slightly , subject to material specifications					
					TOTAL LOOSE FURNITURE :	**169,615.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR AMALGAMA OFFICE @ JBC 4 , DUBAI-UAE

Quote Ref No: VID/1243/24/CP/QTN_01/R0/Opt - 02 | December 16, 2024

SR.NO	SAMPLE IMAGE	DESCRIPTION	QTY	UNIT	RATE	TOTAL (AED)
17.00	**WHITE GOODS**					
17.01		**FRIDGE** **Samsung - 420 L**	1	No.	1,480.00	1,480.00
17.02		**MICROWAVE** **LG - 42 L**	1	No.	970.00	970.00
17.03		**COFFEE MACHINE** **Make : Philips or equivalent**	1	No.	3,525.00	3,525.00
17.04		**PRINTER** **Brother**	1	No.	1,360.00	1,360.00
17.05		**TV SCREEN - 85 INCH** **Make : Hisense or equivalent - QLED** **Location : Meeting rooms**	2	No.	6,345.00	12,690.00
17.06		**TV SCREEN - 65 INCH** **Make : Hisense or equivalent - QLED** **Location : Manager rooms**	3	No.	3,290.00	Rate only
					TOTAL WHITE GOODS :	**20,025.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR AMALGAMA OFFICE @ JBC 4 , DUBAI-UAE

Quote Ref No: VID/1243/24/CP/QTN_01/R0/Opt - 02 **16-Dec-24**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
	ADDITIONAL CHARGES TO REFURBISH THE EXISTING TOILETS				
1.00	**DEMOLITION AND CIVIL WORKS**				
1.01	Demolition of the existing flooring , walls and ceiling as per site condition including carting away to DM approved yard .	1	Item	4,800.00	4,800.00
1.02	Builders works to accommodate MEP works				
	SUB TOTAL DEMOLITION AND CIVIL WORKS :				**4,800.00**
2.00	**PARTITION WORKS**				
2.01	**CEMENT BOARD CLADDING (NON FR)** Supply and installation of **100mm Thk Cement board Cladding** with 12.5mm Thk cement board single layer on both sides with studs, 50mm thick with necessary frames and accessories. Height up to 3 m **Location : Behind WC**	10	Sq.m	165.00	1,650.00
	SUB TOTAL PARTITION WORKS :				**1,650.00**
3.00	**FLOOR FINISH**				
3.01	Modification to the existing screed after demolition of the existing floor tiles.	8	Sq.m	55.00	440.00
3.02	**TILES** Supply and installation of 600 x 600 mm floor tiles including all the fixing material. PC Rate : 60/- Make : RAK ceramics or equivalent	8	Sq.m	175.00	1,400.00
3.03	**THRESHOLD** Supply and installation of stone threshold , 150 mm width x 900 mm **Location : Toilet doors**	2	Nos.	300.00	600.00
3.04	**WATER PROOFING** Supply and installation of **Bituminous sheet water proofing** 2 coats including protection screed. Area considered : 30 Sqm **Location : Floor area and wall upto 1200 mm**	1	LS	4,180.00	4,180.00
	Note: All finishes are subject to final sample approval.				
	SUB TOTAL FLOOR FINISH :				**6,620.00**
4.00	**WALL FINISH**				
4.01	**CERAMIC WALL TILES** Supply and installation of **Ceramic Wall tiles** with necessary materials for fixing. Height up to 2500 mm PC Rate : 60 AED per Sq.m Size : 600 x 600 mm **Location : Toilets**	38	Sq.m	180.00	6,840.00
4.02	Modification to the existing plaster to receive the new wall tiles after demolition.	38	Sq.m	40.00	1,520.00
	Note: 1. All finishes are subject to final sample approval.				
	SUB TOTAL WALL FINISH :				**8,360.00**
6.00	**CEILING FINISH**				
6.01	**PLAIN GYPSUM CEILING** Supply and installation of **Gypsum Board Plain ceiling** (Knauf or equivalent) with necessary hanging systems including wall angle "C "channel, furring channel with 12.5mm gypsum boards joined taped smoothened finish. **Location : All areas**	8	Sq.m	115.00	920.00

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR AMALGAMA OFFICE @ JBC 4 , DUBAI-UAE

Quote Ref No: VID/1243/24/CP/QTN_01/R0/Opt - 02 — **16-Dec-24**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
6.02	**GYPSUM CEILING PAINT** Supply and application of **Jotun Fenomastic WHITE paint** including all cleaning and levelling. As per design and approved sample. (2 coats including sanding). **Location : Proposed Gypsum ceiling areas**	8	Sq.m	33.00	264.00
6.03	**SHADOW GAP** Supply and installation of shadow gap as per the design.	16	LM	40.00	640.00
6.04	**GYPSUM ACCESS PANEL** Supply and installation of **Gypsum access panel (Max 60 x 60 cm)** with frame and hinges. **Location: Proposed Gypsum ceiling area** Note : Subject to final MEP drawings	2	Nos.	330.00	660.00
	Note : All finishes are subject to final sample approval.				
				SUB TOTAL CEILING FINISH :	**2,484.00**
7.00	**DOORS**				
7.01	**Wrapping the existing toilet doors (new ironmongeries)**	2	Nos.	1,800.00	3,600.00
	Note : Third party certificate available for fire-rated glass, not DCD. Fire rated certificate available only for glass, not for frames and fittings				
				SUB TOTAL DOORS :	**3,600.00**
9.00	**JOINERY WORKS**				
9.01	**Supply and installation of vanity counter with granite top and fascia upto 300 mm .** **Size : 800 mm**	2	Nos.	2,600.00	5,200.00
				SUB TOTAL JOINERY WORKS :	**5,200.00**
10.00	**SANITARY FITTINGS**				
	Supply and installation of below sanitary wares				
10.01	**WC (including cistern and flush plate)** 	2	Nos	2,270.00	4,540.00
10.02	**Wash basin + Bottle trap + waste** 	2	Nos	1,305.00	2,610.00
10.03	**Wash basin mixer + Angle valve** 	2	Nos	1,055.00	2,110.00

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR AMALGAMA OFFICE @ JBC 4 , DUBAI-UAE

Quote Ref No: VID/1243/24/CP/QTN_01/R0/Opt - 02 **16-Dec-24**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
10.04	**Toilet roll holder**	2	Nos	220.00	440.00
10.05	**Shattaf + angle valve**	2	Nos	310.00	620.00
10.06	**Floor trap**	2	Nos	200.00	400.00
10.07	**Robe hook**	2	Nos	115.00	230.00
10.08	**Vanity mirror without backlight , with frame (powder coated)** **Size : 800 x 1500 mm**	2	Nos	790.00	1,580.00
				SUB TOTAL SANITARY FITTINGS :	**12,530.00**
11.00	**LIGHTING WORKS - NON DIMMABLE**				
	Supply of the following lights				
11.01	**SPOT LIGHT - 20 W**	4	Nos	95.00	380.00
	Note : 1. Quantity subject to final RCP design 2. Non dimmable lights				
				SUB TOTAL LIGHTS :	**380.00**
	MEP WORKS				
12.00	**HVAC WORKS**				
12.01	Minor modification of the existing extract and fresh air ducting .	1	Item	3,700.00	3,700.00
	Notes : 1. BTU Meter works and BMS Connection / cabling/ wiring excluded 2. Considered to install the outdoor machine in the balcony , subject to building management approval .				
				SUB TOTAL HVAC WORKS :	**3,700.00**
13.00	**ELECTRICAL WORKS**				
13.01	PVC conduiting and wiring for light points including installation. Note: Light points are subject to revise upon final RCP Layout.	4	Nos	220.00	880.00
13.02	Supply and installation of **Single switches for lighting.** Including cabling works.(MK-Normal White)	2	Nos	275.00	550.00

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

verve
space + design

INTERIOR FIT-OUT WORKS FOR AMALGAMA OFFICE @ JBC 4 , DUBAI-UAE

Quote Ref No: VID/1243/24/CP/QTN_01/R0/Opt - 02 — **16-Dec-24**

SR.NO	DESCRIPTION	QTY	UNIT	UNIT RATE	TOTAL (AED)
	Note: 1. We have assumed that the existing infrastructure's power has sufficient capacity to cater to the requirement of the project. 2. We have not allowed for upgrade of the capacity of any base building system. 3. All electrical conduits considered are of PVC type. 4. We have not allowed for any specific lighting control system in this offer. 5. Subject to final MEP drawings 6. We have assumed only 1 DB with single bill for the main tenant only , we have not considered 3 separate DB for the 3 units **Exclusions:** 1. Any BMS integration or related works. 2. DEWA Consultancy for power upgrade.				
				SUB TOTAL ELECTRICAL WORKS :	**1,430.00**
14.00	**CIVIL DEFENCE WORKS**				
14.01	**FIRE ALARM WORKS**			**N/A**	
14.02	**FIRE FIGHTING WORKS**				
14.03	**EMERGENCY WORKS**				
	Notes / Exclusions: *1. Any additional charges/ fees for any third party shall be paid by the client.* *3. Assumed existing sprinkler heads are as per the DCD standards* *4. FM 200 , central battery system works excluded* *5* ***.Rates subject to base build contractor , Verve to charge 15% coordination charge on actual quote submitted by Base build contractor. Verve provided provisional sum***				
				SUB TOTAL CIVIL DEFENCE WORKS :	**-**
15.00	**PLUMBING WORKS**				
15.01	Supply and installation of **Water Supply PPR pipe** for Hot and Cold with socket, Elbow ,Threaded Road and other accessories as per standard	1	LS	5,300.00	5,300.00
15.02	Supply and installation of **UPVC drainage Pipe** for waste and Soil Pipe and connecting to existing line with ,fittings ,socket ,and other accessories as per Standard				
15.03	Pressure Test and Gravity Test				
15.04	Installation of sanitary wares				
	Note : 1. All terminations considered to the stub out present at site , connected to building system . 2. Any slab core cutting works excluded.				
				SUB TOTAL PLUMBING WORKS :	**5,300.00**
	GRAND TOTAL AMOUNT (AED):				**56,054.00**

T: +971 4 2400 119 F: +971 4 2408 403 E: info@vervedesign.ae PO Box: 128279, Dubai,UAE www.vervedesign.ae

Thank you,

© **Verve Design, 2024**

Verve Interior Decoration llc

Unit M04,
Al Reemas Building,
Sheikh Zayed Road, Al Quoz,
PO Box - 128279,
Dubai, UAE.

t : +971 4 240 0119
f : +971 4 240 8403
info@vervedesign.ae
www.vervedesign.ae